

Schedule A

(See Clause 2.1 and 8.1)

SITE OF THE PROJECT

1 The Site

- 1.1 Site of the Four-Lane Project Highway shall include the land, buildings, structures and road works as described in Annex-I of this Schedule-A.The site is a balance work site with partially/fully completed Road Works, between Jhanji-Demow section of NH-37 (Old).
- 1.2 The dates of handing over the Right of Way to the Contractor are specified in Annex-II of this Schedule-A.
- 1.3 An inventory of the Site including the land, buildings, structures, road works, trees and any other immovable property on, or attached to, the site shall be prepared jointly by the Authority Representative and the Contractor, and such inventory shall form part of the memorandum referred to in Clause 8.2 (i) of this Agreement.
- 1.4 The alignment plans of the project Highway are specified in Annex-III. In the case of sections where no modification in the existing alignment of the Project Highway is contemplated, the alignment plan has not been provided. Alignment plans have only been given for sections where the existing alignment is proposed to be upgraded. The proposed profile of the Project Highways shall be followed by the Contractor with minimum FRL as indicated in the alignment plan. The contractor, however, improve/upgrade the Road Profile as indicated in Annexure-III based on site/design requirement. In no case the FRL of the new road to be less than the FRL of the existing road.
- 1.5 The status of the environment clearances obtained or awaited is given in Annex-IV.
- 1.6 The instant work is a balance work of Road Works, along with construction of approaches to the structures coming in the stretch (as per details in Para 2.1 of Schedule-A) and laying of Wearing Coat on these structures. Being a Balance Work, at several locations work has been carried out which may be partially/fully complete. Further, some of the partially/fully completed works might have been deteriorated. The EPC Contractor shall have to assess the level of deterioration of such works, carry out the required remedial measures/rectification works as per the satisfaction of the AE and then proceed for the next stage of work. It is being stipulated that in case any partially/completed work has failed or deteriorated and rectification work is to be carried out and the same is not discretely mentioned in the schedules, the same shall not qualify for Change of Scope as per the Article 13 of the EPC CA.

- 1.7 It is clarified that the works which requires fresh construction either due to substantial damages of the completed/partially completed works or in case the previous contractor did not start the work, they have not been indicated in completed/partially completed works in Schedule A and the same shall fall in the scope of the EPC Contractor.
- 1.8 The instant project is a balance work. The process of termination of the present EPC Contractor is in progress and works are also being executed by the EPC Contractor. Accordingly, the prospective bidders are strongly advised to visit the site and get themselves acquainted with the ground situation during the bidding. The actual scope of work for this project will be decided based on the Joint Inspection of the executed works by the AE, newly appointed EPC Contractor and present EPC Contractor (which will be terminated before appointment of the new EPC Contractor), as on Appointed Date. In case, any work is required to be deleted/added from/in the scope of the newly appointed Contractor on account of the newly executed works beyond the Schedule A or non-existent works due to any discrepancy/error in the Schedule A in the completed works specified in Schedule A, as verified during Joint inventory, the same shall be added/deleted and the corresponding amount will be deducted/added based on the Schedule-H rates of the newly appointed EPC Contractor. In case of any disagreement between the parties, the decision of the AE shall prevail and will be binding on the parties.
- 1.9 The Jhanji-Demow Section of NH-37 (Old) is 44.00 Km long. Earlier, the 4-laning work was being carried out in the entire length. Now, with a sole intention to carry out the work in multiple fronts and complete the balance work in 12 months, the stretch has been fragmented into 4 parts. 3 parts consists of Road Works (along with construction of approaches to all the structures and laying of wearing coat on all the structures and carry out Road Furniture work on these structures) and the 4th part consists of Structures (VUP/PUP/Minor Bridges/Major Bridges/Grade Separator) & Toll Plaza. All 4 EPC Contractors are required to coordinate with each other and are required to execute the works keeping in mind the Work Program of each other to provide requisite base to execute the work.

Annex-I

(Schedule-A)

Site

1. Site

1.1 The Site of the 4 lane Project Highway comprises the section of National Highway 37 (old) commencing from Km 501.800 to Km 514.800 (Design Chainage) in the state of Assam. The land, carriageway and structures comprising the site are described below.

2. Land

The Site of the Project Highway comprises the land (sum total of land already in possession and land to be possessed) as described below:

Design Ch	nainage (Km)	Total PROW (inm)	Remarks
From To			
501+800	514+290	60	
514+290	514+800	40	

2.1 In this stretch of 11 Km, there are Structures, as per details below, which are under construction by a separate EPC Contractor. The EPC Contractor, appointed through the instant bid is required to construct the approaches to these structures and lay wearing course alongwith Road Furniture on these Structures:

Sl. No.	Design Chainage	Structure	RoW	
1	513+345	VUP	60	
2	513+708	VUP	60	
3	505+085	VUP	60	
4	502+550	PUP	60	
5	502+270	MNB	60	
6	508+454	MJB	60	

3. Carriageway

The existing carriageway of the Project Highway (4 lane/2 lane). The type of the existing pavement is flexible. The carriageway consists of the following which are complete/incomplete/partially complete/damaged and are to be completed in all respect.

(a) Main Carriage Way (Widening Portion of existing 2-lane)

		Subgrad	le Widening	g portion	
Sl.	Chainage	Side	Length	Status	Remarks

No.	From	То		(m)		
1	505+725	507+695	LHS	1970	Subgrade Completed	
2	508+740	508+900	RHS	160	Subgrade Completed	
3	508+900	511+830	RHS	2930	Subgrade Completed	
4	511+830	512+500	RHS	670	Subgrade Completed	
5	512+500	512+880	RHS	380	Subgrade Completed	
6	514+360	514+375	RHS	15	Subgrade Completed	
7	514+375	514+800	RHS	425	Subgrade Completed	
	Total Sub	grade Comp	leted, m	6550.00		
1	502+810	503+285	LHS	475	Subgrade Partially Completed	
2	503+415	504+480	LHS	1065	Subgrade Partially Completed	
		ubgrade par ompleted, m	•	1540		

	GSB Widening portion								
Sl. No.	Chainage		Side	Side Length	Status	Remarks			
	From	To		(m)					
1	505+725	507+695	LHS	1970	GSB Completed				
2	508+740	508+900	RHS	160	GSB Completed				
3	508+900	511+830	RHS	2930	GSB Completed				
4	511+830	512+500	RHS	670	GSB Completed				
5	512+500	512+880	RHS	380	GSB Completed				
6	514+360	514+375	RHS	15	GSB Completed				
7	514+375	514+800	RHS	425	GSB Completed				
	Total G	SB Complet	ed, m	6550.00					

	WMM Widening Portion									
Sl.	Chainange		Side	Length	Status	D 1				
No.	From	To	Side	9	Status	Remarks				
1	505+725	507+695	LHS	1970	WMM Completed					
2	508+900	511+830	RHS	2930	WMM Completed					
3	511+830	512+500	RHS	670	WMM Completed					
4	512+500	512+880	RHS	380	WMM Completed					
5	514+375	514+800	RHS	425	WMM Completed					
	Total W	MM Comple	eted, m	6375.00						
1	508+740	508+900	RHS	160	WMM Partially completed					
2	514+360	514+375	RHS	15	WMM Partially completed					
		WMM parti ompleted, m	•	175.00						

	DBM Widening Portion							
Sl.	Chair	nange	C:J.	T on oth	Status	Damanla		
No.	From	To	Side	Length	Status	Remarks		

1	505+725	507+695	LHS	1970	DBM Completed	
2	511+830	512+500	RHS	670	DBM Completed	Shoulder filling balance
3	512+500	512+880	RHS	380	DBM Completed	
4	514+375	514+800	RHS	425	DBM Completed	
5	508+900	511+830	RHS	2930	DBM Completed	
	Total D	BM Comple	ted, m	6375.00		

	BC Widening Portion								
Sl.	Chai	inage	C! I.	Longth	Status	Domonka			
No.	From	To	Side	e Length	Status	Remarks			
1	505+725	507+695	LHS	1970	BC Completed	Median filling balance			
2	508+900	511+830	RHS	2930	BC Completed	Shoulder filling			
3	512+500	512+880	RHS	380	BC Completed	balance			
4	514+375	514+800	RHS	425	BC Completed				
	Total	BC Comple	ted	5705.00					

(b) <u>Main Carriage Way (New 2-Lane Construction/4-LaneinRealignment)</u>

Subgrade:

Sl No	Chai	nage	Side	length	Status	Remarks
31 110	From	То	Side	in (m)	Status	Kemarks
1	502+020	502+180	LHS	160	Subgrade Completed	
2	508+740	508+980	LHS	240	Subgrade Completed	
3	508+980	509+000	LHS	20	Subgrade Completed	
5	512+880	512+930	LHS	50	Subgrade Completed	
6	514+180	514+300	LHS	120	Subgrade Completed	
7	514+355	514+375	LHS	20	Subgrade Completed	
8	514+375	514+800	LHS	425	Subgrade Completed	
9	502+020	502+180	RHS	160	Subgrade Completed	
10	502+810	503+155	RHS	345	Subgrade Completed	
11	505+460	505+665	RHS	205	Subgrade Completed	
12	507+700	507+740	RHS	40	Subgrade Completed	
_	Total lea	ngth Compl	eted, m	1785.00		

Sl No	Chai	inage		langth in (m)	Status	Domoniza
SINO	From	To	To Side length in	lengui in (m)	Status	Remarks
1	502+180	502+200	LHS	20	Subgrade partially completed	

2	509+000	512+880	LHS	3880	Subgrade partially completed	
3	512+930	512+960	LHS	30	Subgrade partially completed	
5	513+860	514+100	LHS	240	Subgrade partially completed	
6	514+100	514+180	LHS	80	Subgrade partially completed	
7	514+300	514+355	LHS	55	Subgrade partially completed	
8	502+180	502+200	RHS	20	Subgrade partially completed	
9	503+155	504+700	RHS	1545	Subgrade partially completed	
10	505+665	507+700	RHS	2035	Subgrade partially completed	
11	513+860	514+100	RHS	240	Subgrade partially completed	
12	514+100	514+210	RHS	110	Subgrade partially completed	
	Total Length, partially completed in m			8255		

	GSB New 2-lane / Realignment Portion								
Sl.	Chainage	Side	Length	Status	Status	Remarks			
No.	From	To	(m)	Status	Status	Kemarks			
1	502+020	502+180	LHS	160	GSB Completed				
2	508+740	508+980	LHS	240	GSB Completed				
3	508+980	509+000	LHS	20	GSB Completed				
5	512+880	512+930	LHS	50	GSB Completed				
6	514+180	514+300	LHS	120	GSB Completed				
7	514+355	514+375	LHS	20	GSB Completed				
8	514+375	514+800	LHS	425	GSB Completed				
9	502+020	502+180	RHS	160	GSB Completed				
10	502+810	503+155	RHS	345	GSB Completed				
12	505+460	505+665	RHS	205	GSB Completed				
13	507+700	507+740	RHS	40	GSB Completed				
	Total length Complet		eted, m	1785					
1	509+000	512+880	LHS	3880	GSB Partially Completed				
2	503+155	504+700	RHS	1545	GSB Partially				

					Completed	
3	505+665	507+700	RHS	2035	GSB Partially Completed	
		length part ompleted, m	•	7460		

		W	MM New 2-	lane/ 4-lane Re	ealignment	
Sl. No.	Chai From	nage To	Side	Length (m)	Status	Remarks
1	508+980	509+000	LHS	20	WMM Completed	
_					WMM Completed	
2	514+375	514+800	LHS	425	WMM Completed	
		MM Comp	leted, m	445.00		
SI		nage	Side	length in	Status	Remarks
No	From	To	Side	(m)	Status	Remarks
1	502+020	502+180	LHS	160	WMM (rectification required)	
2	508+740	508+980	LHS	240	WMM(rectification required)	
3	509+000	512+880	LHS	3880	WMM(rectification required)	
4	512+880	512+930	LHS	50	WMM(rectification required)	
5	514+180	514+300	LHS	120	WMM(rectification required)	
6	514+355	514+375	LHS	20	WMM(rectification required)	
7	502+020	502+180	RHS	160	WMM(rectification required)	
8	502+810	503+155	RHS	345	WMM(rectification required)	
9	503+155	504+700	RHS	1545	WMM(rectification required)	
10	505+460	505+665	RHS	205	WMM(rectification required)	
11	505+665	507+700	RHS	2035	WMM(rectification required)	
12	507+700	507+740	RHS	40	WMM(rectification required)	
		l length par Completed, 1	-	8800		

	DBM New 2-lane / 4-lane Realignment Portion								
Sl.	Cha	ainage	Side	Length	Status	Domontra			
No.	From	To	Side	(m)	Status	Remarks			
1	508+980	509+000	LHS	20	DBM Completed	Median filling balance			
2	514+375	514+800	LHS	425	DBM Completed				
	Total l	DBM Complete	ed, m	445.00					

1	509+000	512+880	LHS	3880	DBM damaged	
2	503+155	504+700	RHS	1545	DBM damaged	
3	505+665	507+700	RHS	2035	DBM damaged	
	Total DBM partially done, m		7460.00			

	BC New 2-lane / Realignment Portion								
Sl.	Chainage (Km)		Side	Length	Status	Remarks			
No.	From	To	Side	(Km)	Status	Kemarks			
1	514+375	514+800	LHS	425	BC Completed				
2	508+900	511+830	RHS	2930	BC Completed				
	Total	BC Complete	d, m	3355.00					
1	509+000	512+880	LHS	3880	BC damaged				
2	503+155	504+700	RHS	1545	BC damaged				
3	505+665	507+700	RHS	2035	BC damaged				
Total BC Partially Completed,									
		m		7460.00					

Note: Kerb in al length of about 825 m is pending to be completed besides the above-mentioned length

(c) Service Road:

Sl.	Chain	age (Km)	Longth (m)	Side	
No.	From	To	Length (m)	Side	
		Subgrade Cor	npleted		
	501+870	501+900	30.00	RHS	
	502+000 502+150		150.00	RHS	
		Sub-Total	180.00		

4. Major Bridges

(a) The site includes the following existing 2-lane Major Bridges:

Sl.	Design	Тур	e of Structu	res	No. of Spans with span	Width
No.	Chainage (km)	Foundation	Sub Structure	Super Structure	length in m	(m)

NIL

(b) New 2-lane Major Bridge Partially completed:

Sl. No.	Design Chainage (km)	Туре	Type of Structure& Status						
		Foundation	Foundation Sub structure Super structure						
	NIL								

5. Road over-bridges (ROB)/ Road under-bridge(RUB)

The Site includes the following ROB (road over railway line)/RUB (road under railway line):

Sl.	Chainage	Type of St	ructures	No. of Spans			
No.	(km)	Foundation	Super Structure	with span length (m)	Total Width (m)	ROB/RUB	
	NIL						

6. Grade Separators

The Site includes the following grade separators.

	Chainage	Type of St	ructures	No. of Spans	
Sl.No.	(km)	Foundation	Super Structure	with span length (m)	Total Width (m)
			NIL		

7. Minor bridges

The Site includes the following minor bridges in existing 2-lane:

Sl.	Design	•	Type of Structures	8	No. of Spans	Width	
No.	Chainage (km)	Foundation	Sub Structure	Super Structure	with span length in m	(m)	

NIL

Minor Bridge(Partially completed)

New Minor Bridge (Partially completed):

CI	Design	,	Гуре of Structu	res	No. of Spans	
Sl. No.	Chainage (km)	Foundati on	Sub Structure	Super Structure	with span length in m	Status
			NI	L		

Widening of Minor Bridge (Partially completed):

Sl.	Design	Widt	Span	Type of structure			Details of	
	Chainage	h (m)	Arrange ment	Found- ation	Sub structure	Super Structure	widening	
				Nil				
				INII				

8. Railway level crossings

The Site includes the following railway level crossings:

Sl. No.	Location (Km)	Remarks
	NIL	

9. Underpasses (vehicular, non-vehicular)

The Site includes the following underpasses.

Underpasses (Partially Completed):

Sl. No.	Design Chainage (Km)	Type of Structures	No. of Spans with span length (m)	Status

Note: 03 VUP at Km 513+345, 513+701, 505+085 & 01 PUP at Km 502+550are in the project whose structure is complete/partially complete (In the scope of other EPC

Contractor) and the Contractor needs to complete the work of RE Walls erection & earth filling therein including the friction slab. Besides, approaches to the structures falling in the package shall also be completed within the available RoW with/without retaining structures.

Details of RE Wall in approaches of VUP/PUP:

Custody of the RE Panels, available within the ROW of the Site RE Panels having an approximate area of 9482.082Sqm is available within the ROW of the Site. Thesame are proposed to be jointly verified at site on the date ofdeclaration of the Appointed Date of the Civil Work Packages and $1/3^{rd}$ of the panels will be handed over to each of the Road Work's Contractors.

10. Culverts

The Site includes the following culverts,

List of Existing Box Culverts, in 4-lane width. Pending items & Protection works are to be done.

Sl. No.	Design Chainage	Type of Structure	Span Arrangement	Present Status
1	505+455	Box Culvert	1x4.1x2.538 m	Completed up to Deck Slab
2	505+886	Box Culvert	1x2.1x2.205 m	Completed up to Deck Slab
3	506+257	Box Culvert	1x2.0x2.916 m	Completed up to Deck Slab
4	507+537	Box Culvert	1x4.5x3.137 m	Completed up to Deck Slab
5	509+240	Box Culvert	1x3.7x2.497 m	Completed up to Deck Slab
6	509+691	Box Culvert	2x3.7x2.484 m	Completed up to Deck Slab
7	509+922	Box Culvert	1x5.0x2.465 m	Completed up to Deck Slab
8	510+943	Box Culvert	1x2.0x2.272 m	Completed up to Deck Slab
9	511+387	Box Culvert	1x2.0x2.1 m	Completed up to Deck Slab
10	511+892	Box Culvert	1x1.7x1.928 m	Completed up to Deck Slab
11	513+051	Box Culvert	1x1.8x1.815 m	Completed up to Deck Slab
12	513+670	Box Culvert	1x2.1x2.167 m	To be dismantled.
13	514+345	Box Culvert	1x3.0x3.296 m	Only 2-lane Culvert on existing carriageway

Pipe Culvert (partially completed)

Sl.	Design	Existing Type of	Existing (m) span	Existing	Status		
No.	Chainage	Structure	Arrangement	Width (m)			
	NIL						

11. Bus Bays

The details of existing bus bays on the site are as follows:-

Sl. No.	Chainage (Km)	Length (m)	LHS	RHS
		As per Schedule	C	

12. Truck Lay Byes

The details of truck lay byes are as follows:

Sl. No.	Chainage (Km)	Length (m)	LHS	RHS
		As per Schedule	e C	

13. Road side drains

The details of road side drains completed/partially completed and to be completed:

LHS Side:

Sl No	Chainag	ge	I amoth in Van	Ctatus
S1 N0	From	To	Length in Km	Status
1	502.040	502.150	0.110	Completed
2	502.669	502.790	0.121	Completed
3	502.905	502.940	0.035	Completed
4	502.947	502.971	0.024	Completed
5	503.019	503.046	0.027	Completed
6	504.717	504.915	0.198	Completed
7	504.956	504.974	0.018	Completed
8	504.992	505.007	0.015	Completed
9	513.388	513.415	0.027	Completed
10	513.490	513.586	0.096	Completed
11	513.590	513.601	0.011	Completed
12	513.607	513.622	0.015	Completed
13	513.636	513.656	0.020	Completed
14	513.790	513.820	0.030	Completed
15	513.862	513.896	0.034	Completed
16	513.904	513.927	0.023	Completed
17	513.933	513.951	0.018	Completed
18	513.963	514.002	0.039	Completed
19	514.006	514.034	0.028	Completed
20	514.040	514.095	0.055	Completed
	Total length comp	leted in Km	0.944	

RHS:

Sl No Chainage Length in Km Status

	From	To		
1	501.800	501.830	0.040	Completed
2	501.842	501.852	0.010	Completed
3	501.855	501.862	0.007	Completed
4	501.865	501.877	0.012	Completed
5	501.882	501.898	0.016	Completed
6	501.904	501.937	0.033	Completed
7	502.080	502.235	0.155	Completed
8	504.675	504.797	0.122	Completed
9	504.835	504.912	0.077	Completed
10	504.925	504.958	0.033	Completed
11	504.958	504.960	0.002	Completed
12	505.003	505.047	0.044	Completed
13	513.647	513.665	0.018	Completed
14	513.851	513.865	0.014	Completed
15	513.870	513.880	0.010	Completed
16	513.909	513.934	0.025	Completed
17	513.955	514.096	0.141	Completed
	Total length comp	leted in Km	0.749	

Note: Existing Drain which are partially complete/deteriorated to be completed in all respect.

14. Major Junctions

The details of major junctions are as follows: -

Sl. No	Loca	ation	At Grade	Separated	Ca	tegory of	Cross Ro	oad
	From Km	To Km			NH	SH	MDR	Others
	NIL							

15. Minor Junctions

The details of minor junctions are noted below: -

CL No.	Design	Side	Carriageway	Width in m
Sl. No.	Chainage	(Left/Right)	Left	Right
1	502+550	Left	4.00	-
2	504+500	Left	4.00	-
3	505+040	Right	-	5.50
4	506+770	Left	4.25	-
5	506+800	Right	-	4.00
6	507+150	Left	5.00	-
7	508+500	Both Side	3.75	3.75
8	509+670	Left	5.25	-

9	511+560	Right	-	4.00
10	513+300	Both Side	4.25	4.25
11	513+655	Both Side	3.50	3.50

16. Bypasses

The details of bypasses are as follows:-

Sl. No.	Name of	Chainage (km)	Length	C	arriageway
	Bypass (town)	from to	in Km	Width (m)	Type
As per the Alignment Plan					

17. Other Structures

NIL

Annex-II

(Schedule-A)

Dates for Providing Right of Way

The dates on which the Authority shall provide Right to Way to the Contractor on different stretches of the Site are stated below.

Sl. No.		From Km	To Km	HindranceFreeLength(Km)	Width (m)	Date of Providing ROW
1		2	3	4	5	6
	1	501.800	502.520	0.720	60.000	
	2	502.570	502.860	0.290	60.000	On
	3	502.910	505.000	2.090	60.000	Appointed
	4	505.080	513.700	8.620	60.000	date
Right of Way	5	513.760	514.800	1.040	60.000	
	1	502.520	502.570	0.050	60.000	Within
	2	502.860	502.910	0.050	60.000	150 Days
	3	505.000	505.080	0.080	60.000	of Appointed
	4	513.700	513.760	0.060	60.000	Date

Annex-III

(Schedule-A)

Alignment Plans

The existing alignment of the Project Highway shall be modified in the following sections as per the alignment plan indicated below:

- (i) The alignment of the Project Highway is enclosed in alignment plan. Finished road level indicated in the alignment plan shall be followed by the Contractor as minimum FRL. In any case, the finished road level of the project highway shall not be less than those indicated in the alignment plan. The contractor shall, however, improve/upgrade the Road profile as indicated in Annex-III based on site/design requirement and the same shall not qualify for Change in Scope as per the Article 13 of the EPC Contract Agreement.
- (ii) Traffic signages in the Project Highway shall be provided as per relevant specifications/IRC Codes/Manual to the satisfaction of the Authority's Engineer.

Annex-IV (Schedule-A) Environment Clearances

The following environment clearance have been obtained: Not Applicable

The following environment clearance are awaited: NIL

(Schedule-B)

(See Clause 2.1)

Development of the Project Highway

1. Development of The Project Highway

- 1.1 Development of the Project Highway shall include design and construction of the Project Highway as described in this Schedule-B and in Schedule-C. The alignment plan of the Project Highway is specified in Annexure-III of Schedule A. The proposed profile of the Project Highway as indicated in the Annexure-III of Schedule-A shall be treated as an approximate assessment. Contractor shall design the alignment plans and profiles of the Project Highway based on site / design requirement mentioned in Schedule-D with approval from Authority's Engineer within the available Right of Way.
- 1.2 The majority of the designs and drawings have already been approved by the AE and are available and have been also made part of this Bid Document. However, the EPC Contractor is at a liberty of minor modifications, so as to save time. Further, the EPC Contractor will have a freedom to propose any upgraded design/alternate design/new technology design which will not make the already executed work at site, infructuous. The balance designs and drawings shall be prepared and get approved by the EPC Contractor from AE, in accordance with the EPC Contract Agreement.
- 1.3 The instant project is a balance work. The process of termination of the present EPC Contractor is in progress and works are also being executed by the EPC Contractor. Accordingly, the prospective bidders are strongly advised to visit the site and get themselves acquainted with the ground situation during the bidding. The actual scope of work for this project will be decided based on the Joint Inspection of the executed works by the AE, newly appointed EPC Contractor and present EPC Contractor (which will be terminated before appointment of the new EPC Contractor), as on Appointed Date. In case, any work is required to be deleted/added from/in the scope of the newly appointed Contractor on account of the newly executed works beyond the Schedule A or non-existent works due to any discrepancy/error in the Schedule A in the completed works specified in Schedule A, as verified during Joint inventory, the same shall be added/deleted and the corresponding amount will be deducted/added based on the Schedule-H rates of the newly appointed EPC Contractor. In case of any disagreement between the parties, the decision of the AE shall prevail and will be binding on the parties.

2 Rehabilitation and Augmentation

Rehabilitation and augmentation shall include Four- laning and strengthening of the Project Highway as described in Schedule A, Schedule-B and in Schedule-C.

3 Specification and Standards

The Project Highway shall be designed and constructed in conformity with the Specifications and Standards specified in Annex-I of Schedule-D.

Annex-I

(Schedule-B)

Description of Four Lanning and strengthening

1. Widening of the Existing Highway

1.1 The Project Highway shall follow the existing alignment unless otherwise specified by the Authority and shown in the alignment plans specified in Annex III of Schedule-A. Notwithstanding anything to the contrary contained in this Agreement or IRC:SP:84-2014, the proposed profile of the Project Highway as indicated in the Annexure-III of Schedule-A shall be treated as an approximate assessment. Contractor shall design the alignment plan and profile of the Project Highway based on site / design requirement mentioned in Schedule-D with approval from Authority's Engineer within the available Right of Way. Geometric deficiencies, if any, in the existing horizontal and vertical profiles shall be corrected as per the prescribed standards for plain terrain to the extent land is available. The same shall not constitute a change of scope, save and except any variations arising out of a change of scope expressly undertaken in accordance with the provision of Article 13.

1.2 Width of carriageway

- 1.2.1 The paved carriageway shall be as per IRC: SP: 84-2014.
- 1.2.2 Provided that in following Built-up/urban stretches, the service road shall be provided with the main carriageway as per IRC: SP: 84-2014.

Sl. No.	Name of Township	Design Chainage (km)		
SI. NO.		From	To	
1	Namdang,Gaurisagar	501+800	502+796	
2	BaliaGhat	502+800	503+150	
3	Bhatiapar	504+700	505+500	
4	Jengani-Katia Pragati	513+460	513+860	

1.2.3 Except as otherwise provided in this Agreement, the width of the paved carriageway and Cross-Sectional features shall conform to paragraph 1.2.1 above.

2. Geometric Design and General Features

2.1 General

GeometricdesignandgeneralfeaturesoftheProjectHighwayshallbeinaccordance with Section 2 of the Manual IRC SP 84-2014.

2.2 Design Speed

The design speed shall be the minimum design speed of 80 Km per hour except the locations having RoW constraints. (Constrained Locations should be Accepted by

the Authority/AE).

2.3 Improvement of the existing Road Geometrics

In the following sections, where improvement of the existing road geometrics to the prescribed standards is not possible, the existing road geometrics shall be improved to the extent possible within the given right of way and proper road signs and safety measures shall be provided.

Design Chair	Design Chainage in km		Type of Deficiency	Remarks
From	То		Deficiency	
501+800	502+400	600	Historical Bridge on Namdang	
301+000	302± 4 00		river	
508+540	508+810	270	To follow existing alignment	Major Bridge
509+480	510+000	520	Curve Improvement	

2.4 Right of Way

Details of the Right of Way are given in Annex-II of Schedule-A.

2.5 Type of Shoulders

(a) In built-up sections, footpaths/fully paved shoulders shall be provided in the following stretches:

Sl.No.	Design Chainage (Km)		Reference	Remarks
	From	То	to cross	
			section	
1	501+800	502+796	Figure	Namdang,Gaurisagar
			2.5/2.6	
2	502+800	503+150	Figure	Balia Ghat
			2.5/2.6	
3	504+700	505+500	Figure	Bhatiapar
			2.5/2.6	
4	513+460	513+860	Figure	Jengani-Katia
			2.5/2.6	Pragati

Note: Figure 2.5 and Figure 2.6 refer Manual IRC: SP:84-2014 of Clause 2.16

Sl. No.	Stretch (from km to km)	Fully paved shoulders/footpath	Reference to cross section			
	As per TCS reviewedby Engineer in conformity with the Manual					

- (b) In open country, PavedShouldersof1.50mwidth and Earthen Shoulders for a width of 2.00 m will be provided.
- (c) Design and specifications of paved shoulders and granular material shall conform to the requirements specified in paragraphs 5.10, 5.11 and 5.12 of the manual.

2.6 Lateral and Vertical Clearances at Underpasses

- 2.6.1 Lateral and vertical clearances at underpasses and provision of guardrails/crash barriers shall be as per the paragraph 2.11 of the Manual.
- 2.6.2 Lateral clearance: The width/size of the opening at the underpasses shall be as follows:

Sl. No.	Design Chainage	Span (No. x length) in m	Minimum Length of RE wall(m)	Remarks	
NIL					

2.7 Lateral and vertical clearance at overpasses

2.7.1 Lateral and vertical clearances at over passes shall be as per paragraph 2.12 of the Manual.

NIL

2.7.2 Lateral clearances: The size of the opening at the overpasses shall be as follows:

Sl. No.	Location	Number and length	Remarks		
	(chainage)	of spans			
	From km to km	_			
NIL					

Details of RE Wall in approaches of VUP/PUP:

Custody of the RE Panels, available within the ROW of the Site RE Panels having an approximate area of 9482.082Sqm is available within the ROW of the Site. The same are proposed to be jointly verified at site on the date of declaration of the Appointed Date of the Civil Work Packages and $1/3^{\rm rd}$ of the panels will be handed over to each of the Road Work's Contractors.

2.8 Service roads/Slip Road

Service roads shall be constructed at the locations and for the lengths indicated below:

Sl. No.	Design	Chainage	Length	Width (m)	Side	
	From	To	(m)	Width (III)	Siuc	
1	512+960	513+860	900	7.0	LHS & RHS	
2	501+800	503+150	1350	7.0	LHS & RHS	
3	504+700	505+500	800	7.0	LHS & RHS	
4	508+720	508+900	180	7.0	LHS	
5	508+260	508+370	110	7.0	LHS	
6	502+300	502+600	300	7.0	LHS	
	Total length, m		6690 m			

2.9 Grade separated structures

2.9.1 Grade separated structures shall be provided as per paragraph 2.13 of the Manual. The requisite particulars are given below:

Sl.No.	Location of Structure	Design Chainage	Length (m)	Number and length of spans	Approach gradient	Remarks
NIL						

2.9.2 In the case of Grade separated structures, the type of structure and the level of the Project Highway and the cross roads shall be as follow:

		Type of	Cross road at			Remarks	
Sl. No.	Location	Structure	Existing	Raised	Lowered		
		Length(m)	level	Level	Level		
NIL							

2.10 Cattle and Pedestrian Underpass/Overpass

Pedestrian Underpass (PUP) shall be constructed as follows:

Sl. No.	Design	Chainage	Proposed span arrangement
		NIL	

2.10.1 Vehicular Underpasses (VUP) shall be constructed as follows:

Sl. No.	Design Chainage	Span (No. x length) in m	Minimum Length of RE wall(m)	Remarks		
NIL						

2.11 Typical cross-sections of the Project Highway

Type of cross sections for different segments of Four lane stretch shall be developed as provided in' Manual of Specifications & Standard for Four Laning of Highways as per IRC:SP:84-2014 referred in schedule-D.

Sl No	Chai	nage	Side	length in	Remarks
51110	From	To	Side	(m)	Kemarks
1	502+200	502+290	LHS	90	Widening Existing road
2	502+810	503+150	LHS	340	Widening Existing road
3	503+150	503+285	LHS	135	Widening Existing road
4	503+285	503+415	LHS	130	Widening Existing road
5	503+415	504+480	LHS	1065	Widening Existing road
6	504+480	504+720	LHS	240	Widening Existing road
7	505+460	505+725	LHS	265	Widening Existing road
8	505+725	507+695	LHS	1970	Widening Existing road
9	507+695	508+700	LHS	1005	Widening Existing road
10	507+800	508+740	RHS	940	Widening Existing road
11	508+740	508+900	RHS	160	Widening Existing road
12	508+900	511+830	RHS	2930	Widening Existing road
13	511+830	512+500	RHS	670	Widening Existing road
14	512+500	512+880	RHS	380	Widening Existing road
15	512+880	512+960	RHS	80	Widening Existing road
16	514+300	514+360	RHS	60	Widening Existing road
17	514+360	514+375	RHS	15	Widening Existing road
18	514+375	514+800	RHS	425	Widening Existing road
	Total length in M			10900	
			<u></u>		

Sl No	Chai	nage	Side	length in	Remarks
31110	From	To	Side	(m)	Remarks
1	501+800	502+020	LHS	220	New Alignment
2	502+020	502+180	LHS	160	New Alignment
3	502+180	502+200	LHS	20	New Alignment
4	502+290	502+810	LHS	520	PUP Approach
5	504+720	505+460	LHS	740	VUP Approach
6	508+700	508+740	LHS	40	New Alignment
7	508+740	508+980	LHS	240	New Alignment
8	508+980	509+000	LHS	20	New Alignment
9	509+000	512+880	LHS	3880	New Alignment
10	512+880	512+930	LHS	50	New Alignment
11	512+930	512+960	LHS	30	New Alignment
12	512+960	513+860	LHS	900	VUP Approach
13	513+860	514+100	LHS	240	New Alignment
14	514+100	514+180	LHS	80	New Alignment
15	514+180	514+300	LHS	120	New Alignment
16	514+300	514+355	LHS	55	New Alignment
17	514+355	514+375	LHS	20	New Alignment
18	514+375	514+800	LHS	425	New Alignment

	Tot	al length in	M	15100	
36	514+210	514+300	RHS	90	New Alignment
35	514+100	514+210	RHS	110	New Alignment
34	513+860	514+100	RHS	240	New Alignment
33	512+960	513+860	RHS	900	VUP Approach
32	507+740	507+800	RHS	60	New Alignment
31	507+700	507+740	RHS	40	New Alignment
30	505+665	507+700	RHS	2035	New Alignment
29	505+460	505+665	RHS	205	New Alignment
28	504+720	505+460	RHS	740	VUP Approach
27	504+700	504+720	RHS	20	New Alignment
26	503+155	504+700	RHS	1545	New Alignment
25	503+110	503+155	RHS	45	New Alignment
24	502+810	503+110	RHS	300	New Alignment
23	502+290	502+810	RHS	520	PUP Approach
22	502+200	502+290	RHS	90	New Alignment
21	502+180	502+200	RHS	20	New Alignment
20	502+020	502+180	RHS	160	New Alignment
19	501+800	502+020	RHS	220	New Alignment

Note:

- 1. In some locations, where DBM/BC are already done, Median Kerb, Earthen Shoulder & Median fillings is pending & are to be done by the Contractor to the satisfaction of the Engineer & this shall not constitute a Change of Scope as per Article 13 of the Contract Agreement.
- **2.** Road side Toe wall to be provided for a minimum length of 2000m with slope protection by turfing with sod. The locations to be finalized by site verification with the Engineer.

3.0 Intersections and grade separators

All intersections and grade separators shall be as per Section 3 of the Manual. Existing intersections which are deficient shall be improved to the prescribed standards.

Properly designed intersections shall be provided at the locations and of types and features given in the tables below:

(a) At-grade intersections

i) Major Junction

Sl.no	Design Chainage	Category of Road	Type of Junction	Remarks
		NIL		

ii) Minor Junctions

The details of minor junctions are noted below: -

Sl.	Design Chainege	Side	Carriageway	Width in m
No.	Design Chainage	(Left/Right)	Left	Right
1	502+550	Left	4.00	-
2	504+500	Left	4.00	-
3	505+040	Right	-	5.50
4	506+770	Left	4.25	-
5	506+800	Right	-	4.00
6	507+150	Left	5.00	-
7	508+500	Both Side	3.75	3.75
8	509+670	Left	5.25	-
9	511+560	Right	-	4.00
10	513+300	Both Side	4.25	4.25
11	513+655	Both Side	3.50	3.50

(b) Grade separated intersection without ramps

Sl. No.	Location	Salient features	Minimum length of viaduct to be provided	Road to carried over/under the structure			
NIL							

4. Road embankment and cut section

4.1 Widening and improvement of the existing road embankment/cuttings and constructions of new road embankment/cuttings shall conform to the specifications and standards given in Section 4 of the Manual and the specified cross-sectional details. Notwithstanding anything to the contrary contained in this Agreement or IRC: SP:84-2014, the proposed profile of the Project Highway as indicated in the Annexure-III of Schedule-A shall be deemed to be part of this Schedule-B and shall be treated as an approximate assessment. The contractor may design the alignment plan & profile of the Project Highway based on site / design requirement specified in Schedule-D, with approval from Authority's Engineer within the available Right of Way. However, the EPC Contractor shall have to abide by the already reviewed Plan & Profile (Annexure-III of Schedule-A) as the basis/guiding document and the minimum FRL is to be maintained as per it. Deficiencies in the plan and profile of the existing road shall be corrected within the available ROW. In case there is any change/modification/improvement in the geometrics proposed by the EPC Contractor, with in the ROW, the same shall not qualify for Change of Scope as per Article 13.

5.0 Pavement Design

5.1 Pavement design shall be carried out in accordance with Section-5 of IRC: SP:84-2014, IRC:37-2018.

5.2 Type of pavement

The type of the pavement for the entire stretch shall be of flexible type pavement except the following location, where the pavement shall be rigid.

Sl. No.	Design Chainage (Km)		Length	Location	
2201100	From	То	(m)		
		NIL			

5.3 Design requirements

5.3.1 Design Period and Strategy

Flexible pavement for new pavement and for widening and strengthening of the existing pavement shall be designed for a minimum design period of 15 years. Stage constructions shall not be permitted.

5.3.2Design Traffic

Notwithstanding anything to the contrary contained in this Agreement of the Manual, the contractor shall design the pavement for design traffic of not less than 60 million standard axles (MSA).

5.4Reconstruction of stretches – As per TCS

6. Roadside drainage

6.1. Drainage system including surface drains for the Project Highway shall be provided as per section 6 of the Manual. Covered RCC Drains shall be provided in the following stretches.

Design Cha	Design Chainage in km		Side	
From	To	<u> </u>		
501+800	503+150	1350	Both Side	
504+700	505+500	800	Both side	
513+050	513+860	810	Both Side	
Total Le	ength, m	5920 m		

In addition to the above, the road side drain should also be providein the following locatons:

Design Chainage in km		Length in	Side	
From	To	- m		
512+960	513+050	90	Both Side	

513+860	514+510	650	Both side
		1480 m	

Status of RCC drain completed/Partially completed as per Schedule A

RCC drain (Covered) partially completed to be completed in all respect.

- 6.2. Unlined Drain is to be constructed at all other locations as per Manual.
- 6.3. Median Drain is also to be provided as per Manual and Site Requirement.

7. Design of Structures

7.1 General

- 7.1.1 The majority of the designs and drawings have already been approved by the AE and are available and have been also made part of this Bid Document. However, the EPC Contractor is at a liberty of minor modifications, so as to save time. Further, the EPC Contractor will have a freedom to propose any upgraded design/alternate design/new technology design which will not make the already executed work at site, infructuous. The balance designs and drawings shall be prepared as per Manual and get approved by the EPC Contractor from AE, in accordance with the EPC Contract Agreement.
- 7.1.2 Width of the carriageway of new bridges and structures shall be as follows: -

All new structures shall be minimum carriageway as per Manual Fig. 7.2 and fig. 7.3

7.1.3 The following structures shall be provided with footpaths:

Sl. No	Bridge at Km	Utility service to be	Remarks	
		carried		
All new bridges/Bridges proposed to be widened shall have provisions for footpath				

- 7.1.4 All bridges shall be high-level bridges
- 7.1.5 Utility services to be carried over the structures

The following structures shall be designed to carry utility services specified in the table below: -

Sl. No	Bridge at Km	Utility service to be carried	Remarks		
All new bridges/Bridges proposed to be widened shall have provisions for utility services					
to be carried over					

7.1.6 Cross - section of the new culverts and bridges at deck level for the Project Highway shall

Conform to the typical cross-sections given in section 7 of the Manual.

7.2 Culverts

- 7.2.1 Overall width of all culverts shall be equal to the roadway width of the approaches.
- 7.2.2 Reconstruction of existing culverts.

The existing culverts at the following locations shall be re-constructed as new culverts: -

Sl. No.	Existing Chainage	Design Chainage	Proposed Type of Structure	Recommend ation	Proposed span Arrangement (m)	Over all Width in (m)	
NIL							

Status of Culvert (Reconstruction) completed/Partially completed as per Schedule A

Culvert (Reconstruction) Work partially completed and to be completed up to final stage including the Protection works, Parapet wall etc.

Sl. No.	Design Chainage	Existing Type of Structure	Existing (m) span Arrangement	Present Status
1	505+455	Box Culvert	1x4.1x2.538 m	Completed up to Deck Slab
2	505+886	Box Culvert	1x2.1x2.205 m	Completed up to Deck Slab
3	506+257	Box Culvert	1x2.0x2.916 m	Completed up to Deck Slab
4	507+537	Box Culvert	1x4.5x3.137 m	Completed up to Deck Slab
5	509+240	Box Culvert	1x3.7x2.497 m	Completed up to Deck Slab
6	509+691	Box Culvert	2x3.7x2.484 m	Completed up to Deck Slab
7	509+922	Box Culvert	1x5.0x2.465 m	Completed up to Deck Slab
8	510+943	Box Culvert	1x2.0x2.272 m	Completed up to Deck Slab
9	511+387	Box Culvert	1x2.0x2.1 m	Completed up to Deck Slab
10	511+892	Box Culvert	1x1.7x1.928 m	Completed up to Deck Slab

Sl. No.	Design Chainage	Existing Type of Structure	Existing (m) span Arrangement	Present Status
11	513+051	Box Culvert	1x1.8x1.815 m	Completed up to Deck Slab
12	513+670	Box Culvert	1x2.1x2.167 m	To be dismantled
13	514+345	Box Culvert	1x3.0x3.296 m	Completed in service road width in RHS

7.2.3 Widening of Existing Culverts

All existing culverts which are not to be reconstructed shall be widened to the roadway width of the Project Highway as per the typical cross section given in section 7 of the Manual. Repairs and strengthening of existing structures where required shall be carried out.

Sl. No.	Design Chainage	Proposed Type of Structure	Recommendati on	Proposed (m) span Arrangement	Overall Width in m	Status
			New		4-Lane	Completed in
1	514+345	Box	Construction to	1x3.0x3.296 m	including	service road
		Culvert	be Done		service road	width in RHS

7.2.4 Additional new culverts shall be constructed as per particulars given in the table below:

Sl. No.	Design Chainage (km)	Proposed Type of culvert	Span Arrangement No. x Length /No. x Día(m)	Overall Width
1	501+890	Box Culvert	2.0x2.0 m	4-lane width including Service road
2	513+675	Box Culvert	2.167x2.1 m	4-lane width

7.2.5 Repairs/replacement of railing/parapets, flooring and protection works of the existing culverts shall be undertaken as follows:

As per site condition, Repairs/replacement of railing/parapets and any other defects noticed at the time of construction shall be undertaken by the contractor for all the retained culverts along with repair/construction of flooring and protection works to the satisfaction of the Engineer.

- 7.2.6 Floor protection works shall be as specified in the relevant IRC Codes and Specification.
- 7.2.7 In case of culverts proposed for widening / repair as per details in Clause 7.2.3 above, the same shall be re-constructed if the design shows that these are unsafe for design loads. No change of scope shall be considered in such cases.

Note:

- 7.3 Bridges
- 7.3.1 Existing bridges to be re-construction/widened/Repairs
- i) The existing bridges at the following locations shall be re-constructed as new structures.
 - a) Major Bridges

Sl.No.	Bridge Location (Km)	Salient details of existing Bridge	Adequacy or otherwise of the existing waterway, vertical clearance, etc	Remarks		
NIL						

The following narrow bridges shall be widened

Sl.No	Location (Km)	Existing width (m)	Extent of widening (m)	Cross-section at deck level for widening @		
NIL						

b) Minor Bridges

Sl. No.	Design Chainage	Proposed Structure configuration	Proposed span arrangement (No. x L)		
NIL					

- (ii) The following existing bridges shall be Repaired and Strengthened:
- a) Major Bridges

Sl.	Chainage	Width	Span	Т	Type of struc	ture	Details of
No ·	(km)	(m)	Arrangement	Found ation	Sub structure	Super structure	Repair
	Nil						

b) Minor Bridges: Already widened however, have to be completed in all respect:

Sl.	Design	Width	Span	T	Type of struct	ture	Details of
	Chainages	(m)	Arrange ment	Found- ation	Sub structure	Super Structure	widening

Sl.	Design	n Width Span		Type of structure			Details of
	Chainages	(m)	Arrange ment	Found- ation	Sub structure	Super Structure	widening
				NIL			

7.3.2 Additional new bridges

New bridges at the following location on the Project Highway shall be constructed.

Sl.No.	Location (Km)	Total Length (m)	Remarks, if any		
NIL					

7.3.3 The railing of existing bridges shall be replaced by crash barriers at the following locations:

Sl. No.	Location at km	Remarks		
	NIL			

7.3.4 Repairs/replacements of railing/parapets of the existing bridges shall be undertaken as follow:

Sl. No.	Location at km	Remarks		
	NIL			

7.3.5 Drainage system for bridges decks

An effective drainage system for bridge decks shall be provided as specified in paragraph 7.21 of the Manual.

7.3.6 Structure in marine environment

NIL

7.4 Rail-road bridges

- 7.4.1. Design, construction and detailing of ROB/RUB shall be as specified in section 7 of theManual.
- 7.4.2 Road over bridges(road over rail) shall be provided at the following crossing, as per GAD drawing attached:

Sl.No.	Location of Level Crossing (Km)	Length of Bridge (m)
--------	---------------------------------	----------------------

-	
NIL	

7.4.3 Road under bridges (road under railway line)shall be provided at the following level crossings, as per GAD drawing attached:

Road under bridges

Sl. No.	Location of level crossing	Number and length of span			
Nil					

7.5 Grade separated structure

The grade separated structures shall be provided at the locations at the locations and of the type and length specified in paragraphs 2.9 and 3 of this Annex-I of Sch-B.

7.6 Repairs and strengthening of Structures

The existing structures to be repaired/strengthened, and the nature and extent of repairs/strengthening required are given below:

A-Bridges

Sl.No.	Design Chainage	Nature & Extent of Repairs/Strengthening to be carried out		
	NIL			

B-ROB/RUB

Sl. No.	Location of structure (km)	Nature and extent of repair/strengthening to be carried out
	NIL	

C- Overpasses/ Underpasses and other structures

Sl. No.	Location of structure (Km)	Nature and extent of repair/strengthening to be carried out		
NIL				

D- The following is the list of the New Major Bridges and Structures: -

Sl.No.	Location		
NIL			

Note:

- 1. Wearing coat (40mm BC) over Bridge Decks for a minimum length of 449m to be provided. The locations to be finalized by site verification with the Engineer.
- **2.** Existing Culverts cleaning, provision of required Protection works/Concrete Crash Barriers for new/existing culverts are to be done by the Contractor to the satisfaction of the AE.

8. Traffic control devices and road safety works

- 8.1 Traffic control devices and road safety works shall be provided in accordance with section 9 of the manual.
- 8.2 Specifications of the reflecting sheeting: As per the clause 9.3 of the Manual of specifications and standards.

9. Roadside furniture

Roadside Furniture shall be provided in accordance with the provision of section 11 of the Manual.

9.1 Overhead traffic signs: locations and size

Minimum 5 No's overhead shall be provided excluding toll-Plaza locations. The locations are to be decided by the Authority's Engineer.

10. Compulsory Afforestation

Compulsory / Compensatory afforestation to be carried out at locations as directed by the Authority

11. Hazardous locations

The safety barriers shall also be provided at the following hazardous locations:

Sl No.	Location stretches from	LHS/RHS		
	(km) to (km)			
This shall be provided at high embankment and at sharp curve locations for a				
minimum length of 2000 m in linear length, as per locations finalized by the EPC				
Contractor with the approval of AE.				

12. Special requirements for hill roads

NIL

13. Change of Scope

The length of structures and bridges specified herein above shall be treated as an approximate assessment. The proposed span arrangement of above structures may be changed (keeping

overall length same) based on innovative design of structure, latest construction techniques and aesthetics of structures and the actual lengths as required on the basis of detailed investigations shall be determined by the Contractor in accordance with the Specifications and Standards. Any increase in the lengths specified in this Schedule B shall not constitute a change of scope, save and except any variations in the length arising out of a change expressly undertaken in accordance with the provisions of Article 13.

Schedule-C

(See Clause 2.1)

PROJECT FACILITIES

1 Project Facilities

The Contractor shall construct the Project Facilities in accordance with the provisions of the Agreement. Such Project Facilities shall include:

- a) Toll plaza[s];
- b) Roadside furnitures;
- c) Pedestrian facilities;
- d) Tree plantation;
- e) Truck lay-byes;
- f) Bus-bays and bus shelters;
- g) Rest areas; and
- h) Other to be specified

2 Description of Project Facilities

Each of the Project Facilities is described below showing:

a) Toll Plaza:

NIL

b) Road side Furniture

(i) Traffic Signs and Pavement Markings

Traffic signs and pavement marking shall include road side, overhead signs, curve mounted signs and road marking along the project highway. The locations for these provisions shall be finalised as per manual.

- (ii) Concrete Crash Barrier, Metal beam crash barrier (Minimum length 2000m), Separators (MS railings). Locations to be finalized with the AE.
- (iii) Traffic Safety Devices wherever required.
- (iv) Boundary Stones.
- (v) Hectometre/Kilometre Stones.

- (vi) Traffic Blinker Signal (L.E.D) shall be provided at all At-grade junctions, median opening, schools, hospitals, police station, places of worship and institutional buildings etc.
- (vii) Overhead signs: Minimum 1 Nos.(Excluding overhead signs at Toll Plaza location which are as given in Schedule D) shall be provided.
- (viii) Delineators and Studs(100mmx 100mm) with reflective panels of dual prismatic cube capable of providing total reflection of light entering the lens face for lane marking and delineators for night time visibility shall be provided for the entire project Highway.

c) Pedestrian Facilities

The additional pedestrian facilities in the form of pedestrian guard rails (length 1780 m), footpath, lighting (length 6100m) etc.It shall be provided wherever required.

d) Landscaping and Tree Plantation

Landscaping of the highway shall be done on, but not limited to the following:

- Median& Road side
- Grade Separated intersections
- Entry and Exit ramp
- At grade islands of intersection locations
- Toll Plaza Area
- Tree Plantation shall be done in Median & Road side as per the Standard throughout the Project length.
- e) **Truck Lay-byes:**Truck Lay-byes shall be provided at following locations:

Sl. No.	Design Chainage	Side
	NIL	

e)Bus-bays and Bus Shelter:Bus-bays shall be provided locations:

Locations of Bus bays

Sl. No.	Chainage (km)	Side	Location
1	512+600	BHS	Konwarpur

Note: The locations are tentative and shall be decided by the Authority's Engineer. Further, any addition in the number of Bus-Bays will not be considered as a Change of Scope.

f) Others

1. Highway Lighting (length 6100m) shall be provided as per schedule D(Manual of Specifications and Standard for 4-Laning of Highway) (IRC:SP:84-2014).

2. Highway Patrol

The Contractor shall provide Highway Patrol vehicles in adequate number as per manual and this agreement.

3. **Medical Aid Post:** As per Article 21.

4. Cranes

The Contractor shall provide one mobile Cranes having the capacity to left a truck with a gross vehicle weight of 30,000(thirty thousand) kilogram and such posts shall be located at the toll plaza location in consultation with the IC/Authority.

5. Traffic Aid Post

As per the Manual.

Schedule-D

(See Clause 2.1)

SPECIFICATIONS AND STANDARDS

1. Construction

The Contractor shall comply with the Specifications and Standards set forth in Annex-I of this Schedule-D for construction of the Project Highway:

2. Design Standards

The Project Highway including Project Facilities shall conform to design requirements set out in the following documents:

Manual of Standards and Specifications for Four Laning manual published by the Indian Road Congress-IRC: SP:84-2014.

Annex-I

(Schedule-D)

Specifications and Standards for Construction

1. Specifications and Standards

All Materials, works and construction operations shall conform to the Manual of Specifications and Standards for four laning of Highways (IRC: SP-84: -2014) referred to as the Manual for four laning of Highways published by IRC and MORTH Specifications for Road and Bridge Works. Where the specification for a work is not given, Good Industry Practice shall be adopted to the satisfaction of the Authority's Engineer. As this is being a balance work, the approved designs & drawings are available for some locations/structures/pavements. Rest required Designs & Drawings are to be submitted by the Contractor and get approved from the Authority's Engineer.

2. Deviations from the Specifications and Standards

- 2.1 The term "Concessionaire", "Independent Engineer" and "Concession Agreement" used in the Manual shall be deemed to be substituted by the terms "Contractor", "Authority's Engineer" and "Agreement respectively".
- 2.2 Notwithstanding anything to the contrary contained in para 1 above, the following specifications and standards shall apply to the Project Highway and/or purposes of this Agreement, the aforesaid specifications and standards shall be deemed to be amended to the extent set forth below.

Sl. No.	Item	Clause referred in Manual		Provision as per Manual	Modified Provision
1	Typical Cross section	IRC: SP: 2014	84-	Typical Cross Section	Typical Cross section shall be as per Manual

Schedule - E

(See Clauses 2.1 and 14.2)

Maintenance Requirements

1. Maintenance Requirements

- 1.1 The Contractor shall, at all times maintain the Project Highway in accordance with the provisions of this Agreement, Applicable Laws and Applicable Permits.
- 1.2 The Contractor shall repair or rectify any Defect or deficiency set forth in Paragraph 2 of this Schedule-E within the time limit specified therein and any failure in this behalf shall constitute non-fulfilment of the Maintenance obligations by the Contractor. Upon occurrence of any breach hereunder, the Authority shall be entitled to effect reduction in monthly lump sum payment as set forth in Clause 14.6 of this Agreement, without prejudice to the rights of the Authority under this Agreement, including Termination thereof.
- 1.3 All Materials, works and construction operations shall conform to the MORTH Specifications for Road and Bridge Works, and the relevant IRC publications. Where the specifications for a work are not given, Good Industry Practice shall be adopted.

2. Repair / rectification of Defects and deficiencies

The obligations of the Contractor in respect of Maintenance Requirements shall include repair and rectification of the Defects and deficiencies specified in Annex - I of this Schedule-E within the time limit set forth therein.

3. Other Defects and deficiencies

In respect of any Defect or deficiency not specified in Annex - I of this Schedule-E, the Authority's Engineer may, in conformity with Good Industry Practice, specify the permissible limit of deviation or deterioration with reference to the Specifications and Standards, and any deviation or deterioration beyond the permissible limit shall be repaired or rectified by the Contractor within the time limit specified by the Authority's Engineer.

4. Extension of time limit

Notwithstanding anything to the contrary specified in this Schedule-E, if the nature and extent of any Defect or deficiency justifies more time for its repair or rectification than the time specified herein, the Contractor shall be entitled to additional time in conformity with Good Industry Practice. Such additional time shall be determined by

the Authority's Engineer and conveyed to the Contractor and the Authority with reasons thereof.

5. Emergency repairs / restoration

Notwithstanding anything to the contrary contained in this Schedule-E, if any Defect, deficiency or deterioration in the Project Highway poses a hazard to safety or risk of damage to property, the Contractor shall promptly take all reasonable measures for eliminating or minimizing such danger.

6. Daily inspection by the Contractor

The Contractor shall, through its engineer, undertake a daily visual inspection of the Project Highway and maintain a record thereof in a register to be kept in such form and manner as the Authority's Engineer may specify. Such record shall be kept in safe custody of the Contractor and shall be open to inspection by the Authority and the Authority's Engineer at any time during office hours.

7. Pre-monsoon inspection / post-monsoon inspection

The Contractor shall carry out a detailed pre-monsoon inspection of all bridges, culverts and drainage system before [1st June] every year in accordance with the guidelines contained in IRC: SP35. Report of this inspection together with details of proposed maintenance works as required on the basis of this inspection shall be sent to the Authority's Engineer before the [10thJune] every year. The Contractor shall complete the required repairs before the onset of the monsoon and send to the Authority's Engineer a compliance report. Post monsoon inspection shall be done by the [30thSeptember] and the inspection report together with details of any damages observed and proposed action to remedy the same shall be sent to the Authority's Engineer.

8. Repairs on account of natural calamities

All damages occurring to the Project Highway on account of a Force Majeure Event or wilful default, or neglect of the Authority shall be undertaken by the Authority at its own cost. The Authority may instruct the Contractor to undertake the repairs at the rates agreed between the Parties.

Annex – I

(Schedule-E)

Repair / rectification of Defects and deficiencies

The Contractor shall repair and rectify the Defects and deficiencies specified in this Annex-I of Schedule-E within the time limit set forth in the table below.

Table -1: Maintenance Criteria for Pavements:

Asset Type	Performance	Level o	f Service (LOS)	Frequency	Tools / Equipment	Standards and References	Time limit for	Maintenance
	Parameter	Desirable	Acceptable	of		for Inspection and Data	Rectification /	Specifications
				Inspection		Analysis	Repair	
Flexible	Potholes	Nil	< 0.1 % of area and	Daily	Length	IRC 82: 2015 and Distress	24-48 hours	MORT&H
Pavement			subject to limit of		Measurement Unit	Identification Manual for		Specification
(Pavement of			10 mm in depth		like Scale, Tape,	Long Term Pavement		3004.2
MCW, Service					odometer etc.	Performance Program,		
Road,	Cracking	Nil	< 5 % subject to	Daily		FHWA 2003 reports / 03031 /	7-15 days	MORT&H
approaches of			limit of 0.5 sqm for)		Specification
Grade structure,			any 50 m length					3004.3
approaches of	Rutting	Nil	< 5 mm	Daily	Straight Edge		15 -30 days	MORT&H
connecting roads,								Specification
slip roads, lay								3004.2
byes etc. as	Corrugations	Nil	< 0.1 % of area	Daily	Length		2-7 days	IRC:82-2015
applicable)	and Shoving				Measurement Unit			

				like			
Bleeding	Nil	< 1 % of area	Daily	Scale, Tape,		3-7 days	MORT&H
				odometer etc.			Specification
							3004.4
Ravelling /	Nil	< 1 % of area	Daily			7-15 days	IRC:82-2015
Stripping							read with IRC
							SP81
Edge	Nil	< 1 m for any 100	Daily			7- 15 days	IRC:82-2015
Deformation /		m section and width					
Breaking		<0.1 m at any					
		location, restricted					
		to 30cm from the					
		edge					
Roughness BI	2000 mm /	2400 mm / km	Bi-	Class I Profilometer	Class I Profilometer : ASTM	180 days	IRC:82-2015
	km		Annually	SCRIM (Sideway-	E950 (98):2004 –Standard		
Skid Number	60SN	50SN	Bi-	force Coefficient	Test Method for measuring	180 days	BS: 7941-1:2006
			Annually	Routine	Longitudinal Profile of		
Pavement	3	2.1	Bi-	Investigation	Travelled Surfaces with	180 days	IRC:82-2015
Condition			Annually	Machine or	Accelerometer Established		
Index				equivalent)	Inertial Profiling Reference		
Other					ASTM E1656 -94: 2000-	2-7 days	IRC:82-2015
Pavement					Standard Guide for		
Distresses					Classification of Automatic		
					Pavement Condition Survey		
					Equipment		

	Deflection /			Annually	Falling Weight	IRC 115: 2014	180 days	IRC:115-2014
	Remaining Life				Deflectometer			
Rigid Pavement	Roughness BI	2200m m /	2400mm / km	Bi-	Class I	ASTM E950	180 days	IRC:SP:83-2008
(Pavement of		km		Annually	Profilometer	(98) :2004		
MCW, Service						and ASTM		
Road, Grade						E1656 -94:		
structure,						2000		
approaches of	Skid	Skid Resist	ance no. at different	Bi-	SCRIM (Sideway-	IRC:SP:83-2008	180 days	IRC:SP:83-
connecting roads,			ed of vehicles	Annually	force Coefficient			2008
slip roads, lay		Minimum	Traffic Speed (Km /		Routine			
byes etc. as		SN	h)		Investigation			
applicable)		36	50		Machine or			
		33	65		equivalent)			
		32	80					
		31	95					
		31	110					
Embankment /	Edge drop at	Nil	40mm	Daily	Length	IRC	7-15 days	MORT&H
Slope	shoulders				Measurement Unit			Specification
					like Scale, Tape,			408.4
	Slope of	Nil	<2% variation in	Daily	odometer etc.		7-15 days	MORT&H
	camber / cross		prescribed slope of					Specification
	fall		camber / cross fall					408.4
	Embankment	Nil	<15 % variation in	Daily			7-15 days	MORT&H
	Slopes		prescribed side					Specification
			slope					408.4

Embankment	Nil	Nil	Daily	7-15 days	MORT&H
Protection					Specification
Rain Cuts /	Nil	Nil	Daily	7-15 days	MORT&H
Gullies in			Specially		Specification
slope			During		
			Rainy		
			Season		

[Note: Where necessary, the Authority may modify the time limit for repair / rectification, or add to the nature of Defect or deficiency before issuing the bidding document, with the approval of the competent authority.]

In addition to the above performance criterion, the contractor shall strictly maintain the rigid pavements as per requirements in the following table

Table -2: Maintenance Criteria for Rigid Pavements:

Sl. No.	Type of Distress	Measured	Degree of	Assessment Rating	Repair A	Action
		Parameter	Severity		For the case $d < D/2$	For the case $d > D$
						2
				CRACKING		
1	Single Discrete	w = width of crack	0	Nil, not discernible	No Action	Not applicable
	Cracks Not	L = length of crack	1	w < 0.2 mm. hair cracks		
	intersecting with any	d = depth of crack	2	w = 0.2 - 0.5 mm, discernible from	Seal without delay	Seal, and stitch if L
	joint	D = depth of slab		slow-moving car		>lm. Within 7days
			3	w = 0.5 - 1.5 mm, discernible from		
				fast-moving car		
			4	w = 1.5 - 3.0 mm	Seal, and stitch if $L > 1$	Staple or Dowel Bar

Sl. No.	Type of Distress	Measured	Degree of	Assessment Rating	Repair A	Action
		Parameter	Severity		For the case $d < D/2$	For the case d > D /
						2
			5	w > 3 mm.	m. Within 7 days	Retrofit, FDR for
						affected portion.
						Within 15days
2	Single Transverse (or	w = width of crack	0	Nil, not discernible	No Action	
	Diagonal) Crack	L = length of crack	1	w < 0.2 mm, hair cracks	Route and seal with	Staple or Dowel Bar
	intersecting with one	d = depth of crack	2	w = 0.2 - 0.5 mm, discernible from	epoxy. Within 7 days	Retrofit. Within
	or more joints	D = depth of slab		slow vehicle		15days
			3	w = 0.5 - 3.0 mm, discernible from	Route, seal and stitch, if	
				fast vehicle	L > 1 m. Within 7 days	
			4	w = 3.0 - 6.0 mm	Dowel Bar Retrofit.	Full Depth Repair
					Within 15 days	Dismantle and
			5	w > 6 mm, usually associated with	Not Applicable, as it	reconstruct affected.
				spalling, and / or slab rocking	may be full depth	Portion with norms
				under traffic		and specifications -
						See Para 5.5 &
						9.2Within 15days
3	Single Longitudinal	w = width of crack	0	Nil, not discernible	No Action	
	Crack intersecting	L = length of crack	1	w < 0.5 mm, discernable from	Seal with epoxy, if $L > 1$	Staple or dowel bar
	with one or more	d = depth of crack		slow moving vehicle	m. Within 7 days	retrofit. Within
	joints	$D = depth \ of \ slab$				15days
			2	w = 0.5 - 3.0 mm, discernible from	Route seal and stitch, if	-
				fast vehicle	L>1 m. Within 15 days	

Sl. No.	Type of Distress	Measured	Degree of	Assessment Rating	Repair A	Action
		Parameter	Severity		For the case $d < D/2$	For the case d > D /
						2
			3	w = 3.0 - 6.0 mm	Staple, if $L > 1$ m.	Partial Depth Repair
					Within 15 days	with stapling. Within
						15 days
			4	w = 6.0 - 12.0 mm, usually	Not Applicable, as it	
				associated with spalling	may be full depth	
			5	w > 12 mm, usually associated		Full Depth Repair
				with spalling, and / or slab rocking		Dismantle and
				under traffic		reconstruct affected
						portion as per norms
						and specifications -
	Multiple Cracks	w = width of crack	0	Nil, not discernible	No Action	-
	intersecting with one			,	Seal, and stitch if $L > 1$	
	or more joints		2	w = 0.2 - 0.5 mm. discernible from	m. Within 15 days	
				slow vehicle		
			3	w = 0.5 - 3.0 mm, discernible from		Dismantle, Reinstate
				fast vehicle	within15 days	subbase, Reconstruct
			4	w = 3.0 - 6.0 mm panel broken		whole slab as per
				into2 or 3 pieces		specifications
				w > 6 mm and / or panel broken		within30 days
				into more than 4 pieces		
5	Corner Break	w = width of crack		,	No Action	-
		L = length of crack	1	w < 0.5 mm; only 1 corner broken	Seal with low viscosity	Seal with epoxy seal

Sl. No.	Type of Distress	Measured	Degree of	Assessment Rating	Repair A	Action
		Parameter	Severity		For the case $d < D/2$	For the case d > D /
						2
			2	w < 1.5 mm; L < 0.6 m, only one	epoxy to secure broken	with epoxy Within
				corner broken	parts Within 7 days	7days
			3	w < 1.5 mm; L < 0.6 m, two	Partial Depth (Refer	Full depth repair
				corners broken	Figure 8.3 of IRC:SP:	
			4	w > 1.5 mm; $L > 0.6$ m or three	83-2008) Within 15	
				corners broken	days	
			5	ree or four corners broken		Reinstate sub-base,
						and reconstruct the
						slab as per norms and
						specifications within
						30days
6	Punchout(Applicable	w = width of crackL	0	Nil, not discernible		No Action
	to Continuous	= length (m / m2)	1	w < 0.5 mm; L < 3 m / m2	Not Applicable, as it	Seal with low
	Reinforced Concrete		2	either $w > 0.5$ mm or $L < 3$ m / m ²	may be full depth	viscosity epoxy to
	Pavement (CRCP)		3	w > 1.5 mm and L < 3 m / m2		secure broken parts.
	only)					Within 15days
			4	w > 3 mm, L < 3 m / m2 and		Full depth repair -
				deformation		Cut out and replace
			5	w > 3 mm, L > 3 m / m2 and		damaged area taking
				deformation		care not to damage
						reinforcement.
						Within 30days

Sl. No.	Type of Distress	Measured	Degree of	Assessment Rating	Repair A	Action
		Parameter	Severity		For the case $d < D/2$	For the case d > D /
						2
				Surface Defects		
7	Ravelling or	r = area damaged	0	Nil, not discernible	Short Term	Long Term
	Honeycomb type	surface / total			No action.	Not Applicable
	surface	surface of slab (%)	1	r < 2 %	Local repair of areas	
		h = maximum depth	2	r = 2 - 10 %	damaged and liable to	
		of damage			be damaged. Within 15	
					days	
			3	r = 10-25%	Bonded Inlay, 2 or 3	
			4	r = 25 - 50 %	slabs if affecting.	
					Within 30 days	
			5	r > 50% and h > 25 mm	Reconstruct slabs, 4 or	
					more slabs if affecting.	
					Within 30 days	
8	Scaling	r = damaged surface	0	Nil, not discernible	Short Term	Long Term
		/ total surface of			No action.	Not Applicable
		slab (%) h =	1	r < 2 %	Local repair of areas	
		maximum depth of	2	r = 2 - 10 %	damaged and liable to	
		damage			be damaged. Within	
					7days	
			3	r = 10 - 20%	Bonded Inlay within 15	
			4	r = 20 - 30 %	days	
			5	r > 30 % and h > 25 mm	Reconstruct slab	1

Sl. No.	Type of Distress	Measured	Degree of	Assessment Rating	Repair A	Action
		Parameter	Severity		For the case $d < D/2$	For the case d > D /
						2
					within30 days	
9	Polished Surface /	t = texture depth,	0		No action.	Not Applicable
	Glazing	sand patch test	1	t > 1 mm		
			2 '	t = 1 - 0.6 mm	Monitor rate of	
			3	t = 0.6 - 0.3 mm	deterioration	
			4	t = 0.3 - 0.1 mm		
			5	t < 0.1 mm	Diamond Grinding if	
					affecting50% or more	
					slabs in a continuous	
					stretch ofminimum5 km.	
					Within 30 days	
10	Popout (Small Hole),		0	d < 50 mm; $h < 25 mm$; $n < 1 per$	No action.	Not Applicable
	Pothole Refer Para8.4	= diameter h =		5 m2		
		maximum depth	1	d = 50 - 100 mm; h < 50 mm; n <	Partial depth repair 65	
				1 per 5 m2	mm deep. Within 15	
			2	d = 50 - 100 mm; h > 50 mm; n <	days	
				1 per 5 m2		
			3	d = 100 - 300 mm; h < 100 mm n	Partial depth	
				<1 per 5 m2	repair110mmi.e.10 mm	
			4	d = 100 - 300 mm; h > 100 mm; n	more than the depth of	
				<1 per 5 m2	the hole. Within 30 days	
			5	d > 300 mm; h > 100 mm: n > 1	Full depth repair. Within	

Sl. No.	Type of Distress	Measured	Degree of	Assessment Rating	Repair A	Action
		Parameter	Severity		For the case $d < D/2$	For the case d > D /
						2
				per5 m2	30 days	
Joint De	fects					
11	Joint Seal Defects	loss or damage L =	0	Difficult to discern.	Short Term	Long Term
		Length as % total			No action.	Not Applicable
		joint length	1	Discernible, L< 25% but of little	Clean joint, inspect	
				immediate consequence with	later.	
				regard to ingress of water or		
				trapping incompressible material.		
			3	Notable. L > 25% insufficient	Clean and reapply	
				protection against ingress of water	sealant in selected	
				and trapping incompressible	locations. Within 7 days	
				material.		
			5		Clean, widen and reseal	
				protection against ingress of water	the joint. Within 7 days	
				and trapping in compressible		
				material		
12	Spalling of Joints	w = width on either	0	Nil, not discernible	No action.	Not Applicable
		side of the joint L =		w < 10 mm	Apply low viscosity	
		length of spalled	2	w = 10 - 20 mm, L < 25%	epoxy resin / mortar in	
		portion (as % joint			cracked portion. Within	
		length)			7 days	
			3	w = 20 - 40 mm, L > 25%	Partial Depth Repair.	

Sl. No.	Type of Distress	Measured	Degree of	Assessment Rating	Repair A	Action
		Parameter	Severity		For the case $d < D/2$	For the case d > D /
						2
					Within 15 days	
			4	w = 40 - 80 mm, L > 25%	30 - 50 mm deep, h = w	
					+ 20% of w, within 30	
					days	
			5	w > 80 mm, and L > 25%	50 - 100 mm deep	
					repair. $H = w + 20\%$ of	
					w. Within 30 days	
13	Faulting (or	f = difference of	0	not discernible, < 1 mm	No action.	No action.
	Stepping)	level				
	in Cracks or Joints		1	f < 3 mm		
			2	f = 3 - 6 mm	Determine cause and	Replace the slab as
					observe, take action for	appropriate. Within
					diamond grinding	30days
			3	f = 6 - 12 mm	Diamond Grinding	
			4	f= 12 - 18 mm	Raise sunken slab.	Replace the slab as
			5	f> 18 mm	Strengthen subgrade and	appropriate. Within
					sub-base by grouting	30days
					and raising sunken slab	
14	Blowup or Buckling	h = vertical	0	Nil, not discernible	Short Term	Long Term
		displacement from			No Action	
		normal profile				
			1	h < 6 mm		

Sl. No.	Type of Distress	Measured	Degree of	Assessment Rating	Repair A	Action
		Parameter	Severity		For the case $d < D/2$	For the case $d > D$ /
						2
			2	h = 6 - 12 mm	Install Signs to Warn	
					Traffic	
			3	h = 12 - 25 mm	within 7 days	
			4	h > 25 mm	Full Depth Repair.	
					Within 30 days	
			5	shattered slabs, ie 4 or more pieces	Replace broken slabs.	
					Within 30 days	
15	Depression	h = negative vertical	0	Not discernible, h < 5 mm	No action.	Not Applicable
		displacement from	1	h = 5 - 15 mm		
		normal profile	2	h = 15-30 mm, Nos <20% joints	Install Signs to Warn	
		L=length	3	h = 30 - 50 mm	Traffic within 7 days	
			4	h > 50 mm or > 20% joints	Strengthen subgrade.	
					Reinstate pavement at	
					normal level	
			5	h > 100 mm	if L < 20 m. Within 30	
					days	
16	Heave	h = positive vertical	0	Not discernible. $h < 5 \text{ mm}$	Short Term	Long Term
		displacement from			No action.	scrabble
		normal profile.L =	1	h = 5 - 15 mm	Follow up.	
		length	2	h = 15 - 30 mm, Nos<20% joints	Install Signs to Warn	
			3	h = 30 - 50 mm	Traffic within 7 days	
			4	h > 50 mm or > 20% joints	Stabilise subgrade.	

Sl. No.	Type of Distress	Measured	Degree of	Assessment Rating	Repair	Action
		Parameter	Severity		For the case $d < D/2$	For the case d > D /
						2
			5	h > 100 mm	Reinstate pavement at	
					normal level if length<	
					20 m. Within 30 days	
17	Bump	h = vertical	0	h < 4 mm	No action	
		displacement	1	h = 4 - 7 mm	Grind, in case of new	Construction Limit
		fromnormal profile			construction within 7	for New
					days	Construction.
			3	h = 7 - 15 mm	Grind, in case of	Replace in case of
					ongoing Maintenance	new construction.
					within 15 days	Within 30days
			5	h > 15 mm	Full Depth Repair.	Full Depth Repair.
					Within 30 days	Within 30days
18	Lane to Shoulder	f = difference of	0	Nil, not discernible< 3mm	Short Term	Long Term
	Dropoff	level			No action.	
			1	f = 3 - 10 mm	Spot repair of shoulder	
			2	f = 10 - 25 mm	within 7 days	
			3	f = 25 - 50 mm	Fill up shoulder	
			4	f = 50 - 75 mm	within 7 days	For any 100 m stretch
			5	f > 75 mm		Reconstruct shoulder,
						if affecting 25% or
						more of stretch.
						Within 30days

Sl. No.	Type of Distress	Measured	Degree of	Assessment Rating	Repair A	Action
		Parameter	Severity		For the case $d < D/2$	For the case d > D /
						2
				Drainage		
19	Pumping	quantity of fines	0	not discernible	No Action	
		and water expelled	1 to 2	slight / occasional Nos <10%	Repair cracks and joints	Inspect and repair
		through open joints			Without delay.	sub-drainage at
		and cracks Nos	3 to 4	appreciable / Frequent10 - 25%	Lift or jack slab within	distressed sections
					30 days.	and upstream.
		Nos / 100 m stretch	5	abundant, crack development >	Repair distressed	
				25%	pavement sections.	
					Strengthen subgrade and	
					subbase. Replace slab.	
					Within 30 days	
20	Ponding	Ponding on slabs	0-2	No discernible problem	No action.	
		due to blockage of	3 to 4	Blockages observed in drains, but	Clean drains etc within	Action required to
		drains		water flowing	7 days, Follow up	stop water damaging
			5	Ponding, accumulation of water	-do-	foundation within 30
				observed		days.

Table -3: Maintenance Criteria for Safety Related Items and Other Furniture Items:

Asset Type	Performanc	Level of Service (LOS)	Frequency of	Testing Method	Recommended	Time limit	Specification
	e Parameter		Measurement		Remedial measures	for	s and
						Rectification	Standards
Highway	Availability	As per IRC SP:84-2014, a	Monthly	Manual	Removal of obstructi	on within 24	IRC:SP84-

Asset Type	Performanc	Leve	l of Servi	ice (LOS)	Frequency of	Testing Method	Recommended	Time limit	Specification
	e Parameter				Measurement		Remedial measures	for	s and
								Rectification	Standards
	of Safe Sight	minimur	n of safe	stopping		Measurement s with	hours, in case of sight l	ine affected by	2014
	Distance	sight dis	tance sha	ll be		Odometer along	temporary objects su	ich as trees,	
			e through			with video / image	temporary encroachme	nts. In case of	
		Design	Desirabl	Safe		backup	permanent structure	or design	
		Speed,	e	Stopping			deficiency: Removal o	1	
		kmph	Minimu	Sight			improvement of defi-		
			m Sight	Distance (m)			earliest Speed Restricti	ion boards and	
			Distance				suitable traffic calm	•	
			(m)				such as transverse	bar marking,	
		100	360	180			blinkers, etc. shall be	11	
		80	260	130			the period of rectification	on.	
Pavement	Wear	<70% of	f marking	remaining	Bi- Annually	Visual Assessment	Re - painting	Cat-1 Defect	IRC:35-2015
Marking						as per Annexure-F		–within 24	
						of IRC:35-2015		hoursCat-2	
								Defect -	
								within 2	
								months	
	Day time	During e	expected l	ife Service	Monthly	As per Annexure-D	Re - painting	Cat-1 Defect	IRC:35-2015
	Visibility	Time Ce	ement Roa	ad -130mcd /		of IRC:35-2015		– within 24	
		m2 / lux	Bitumino	ous Road -				hours Cat-2	
		100mcd	/ m2 / lux	Κ				Defect –	

Asset Type	Performanc	Lev	el of Serv	ice (LOS)	Frequency of	Testing Method	Recommended	Time limit	Specification
	e Parameter				Measurement		Remedial measures	for	s and
								Rectification	Standards
								within 2	
								months	
	Night Time	Initial a	and Minim	<u>um</u>	Bi-Annually	As per Annexure-E	Re - painting	Cat-1 Defect	IRC:35-2015
	Visibility	Perforn	nancefor D	Ory Retro		of IRC:35-2015		– within 24	
		reflecti	vity during	gnight time:				hours Cat-2	
		Design	(RL) Retro	o Reflectivity				Defect –	
		Speed	(mcd / m2	/lux)				within 2	
			Initial (7	Minimum				months	
			days)	Threshold					
				level (TL) &					
				warranty					
				period					
				required up					
				to 2 years					
		Up to	200	80					
		65							
		65 -	250	120					
		100							
		Above	350	150					
		100							
		Initial a	nd Minim	<u>um</u>					
		Perforn	nance forN	<u>light</u>					

Asset Type Per	erformanc	Level of Service (LOS)	Frequency of	Testing Method	Recommended	Time limit	Specification
e P	Parameter		Measurement		Remedial measures	for	s and
						Rectification	Standards
		Visibility under wet					
		condition(Retro reflectivity):					
		Initial 7 days Retro					
		reflectivity: 100 mcd / m2 /					
		lux Minimum Threshold					
		Level: 50mcd / m2 / lux					
Ski	id	Initial and Minimum	Bi-Annually	As per Annexure-G		Within 24	IRC:35-2015
Res	esistance	performance for Skid		of IRC:35-2015		hours	
		Resistance: Initial (7days):					
		55BPNMin. Threshold:					
		44BPN*Note: shall be					
		considered under urban / city					
		traffic condition					
		encompassing the locations					
		like pedestrian crossings, bus					
		bay, bus stop, cycle track					
		intersection delineation,					
		transverse bar markings etc					
Road Signs Sha	ape and	Shape and Position as per	Daily	Visual with video /	Improvement of shape,	48 hours in	IRC:67-2012
Pos	sition	IRC:67-2012.Signboard		image backup	in case if shape is	case of	
		should be clearly visible for			damaged. Relocation	Mandatory	
		the design speed of the			as per requirement	Signs,	
		section.				Cautionary	

Asset Type	Performanc	Level of Service (LOS)	Frequency of	Testing Method	Recommended	Time limit	Specification
	e Parameter		Measurement		Remedial measures	for	s and
						Rectification	Standards
						and	
						Informatory	
						Signs (Single	
						and Dual post	
						signs)15 Days	
						in case of	
						Gantry /	
						Cantilever	
						Sign boards	
	Retro	As per specifications in	Bi-Annually	Testing of each	change of signboard	48 hours in	RC:67-2012
	reflectivity	IRC:67-2012				case of	
						Mandatory	
				signboard using		Signs,	
				Retro Reflectivity		Cautionary	
				Measuring Device.		and	
				In accordance with		Informatory	
				ASTM D4956-09.		Signs (Single	
						and Dual post	
						signs)1 Month	
						in case of	
						Gantry /	
						Cantilever	
						Sign boards	

Asset Type	Performanc	Level of Service (LOS)	Frequency of	Testing Method	Recommended	Time limit	Specification
	e Parameter		Measurement		Remedial measures	for	s and
						Rectification	Standards
Kerb	Kerb Height	As per IRC 86:1983	Bi-Annually m	Use of distance	raising Kerb eight	Within 1	RC 86:1983
		depending upon type of Kerb		Reassuring tape H		Month	
	Kerb	Functionality: Functioning of	Daily	Visual with video /	Kerb Repainting	Within 7-days	RC 35:2015
	Painting	Kerb painting as intended		image K backup			
Other Road	Reflective	Numbers and Functionality as	Daily	Counting	New Installation	Within 2	IRC:SP:84-
Furniture	Pavement	per specifications in				months	2014,
	Markers	IRC:SP:84-2014 and IRC:35-					IRC:35-2015
	(Road Studs)	2015, unless specified in					
		Schedule-B.					
	Pedestrian	Functionality: Functioning of	Daily	Visual with video /	Rectification	Within 15	IRC:SP:84-
	Guardrail	guardrail as intended		image backup		days	2014
	Traffic	Functionality: Functioning of	Daily	Visual with video /	Rectification	Within 7 days	IRC:SP:84-
	Safety	Safety Barriers as intended		image backup			2014,
	Barriers						IRC:119-
							2015
	End	Functionality: Functioning of	Daily	Visual with video /	Rectification	Within 7 days	IRC:SP:84-
	Treatment of	End Treatment as intended		image			2014,
	Traffic			backup			IRC:119-
	Safety						2015
	Barriers						
	Attenuators	Functionality: Functioning of	Daily	Visual with video /	Rectification	Within 7 days	IRC:SP-
		Attenuators as intended		image backup			2014,

Asset Type	Performanc	Level of Service (LOS)	Frequency of	Testing Method	Recommended	Time limit	Specification
	e Parameter		Measurement		Remedial measures	for	s and
						Rectification	Standards
							IRC:119-
							2015
	Guard Posts	Functionality: Functioning of	Daily	Visual with video /	Rectification	Within 15	IRC: 79 -
	and	Guard Posts and Delineators		image backup		days	1981
	Delineators	as intended					
	Overhead	Overhead sign structure shall	Daily	Visual with video /	Rectification	Within 15	IRC:67-2012
	Sign	be structurally adequate		image backup		days	
	Structure						
	Traffic	Functionality: Functioning of	Daily	Visual with video /	Rectification	Within 7 days	IRC:SP:84-
	Blinkers	Traffic Blinkers as intended		image backup			2014
Highway	Highway	Illumination: Minimum 40	Daily	The illumination	Improvement in	24 hours	IRC:SP:84-
Lighting	Lights	Lux illumination on the road		level shall be	Lighting System		2014
System		surface		measured with			
				luxmeter			
		No major failure in the	Daily	-	Rectification of failure	24 hours	IRC:SP:84-
		lighting system					2014
		No minor failure in the	Monthly	-	Rectification of failure	8 hours	IRC:SP:84-
		lighting system					2014
	Toll Plaza	Minimum 40 Lux illumination	Daily	The illumination	Improvement in	24 hours	IRC:SP:84-
	Canopy	on the road surface		level shall be	Lighting System		2014
	Lights			measured with			
				luxmeter			

Asset Type	Performanc	Level of Service (LOS)	Frequency of	Testing Method	Recommended	Time limit	Specification
	e Parameter		Measurement		Remedial measures	for	s and
						Rectification	Standards
		No major / minor failure in the	Daily	-	Rectification of failure	8 hours	IRC:SP:84-
		lighting system					2014
Trees and	Obstruction	No obstruction due to trees	Monthly	Visual with video /	Removal of trees	Immediate	IRC:SP:84-
Plantation	in a			image backup			2014
including	minimum						
median	headroom						
plantation	of5.5 m						
	above						
	carriageway						
	or						
	obstruction						
	in visibility						
	of road signs						
		Health of plantation shall be	Daily	Visual with video /	Timely watering and	Within 90	IRC:SP:84-
		as per requirement of		image backup	treatment. Or	days	2014
		specifications & instructions			Replacement of Trees		
		issued by Authority from time			and Bushes.		
		to time					
	Vegetation	Sight line shall be free from	Daily	Visual with video /	Removal of Trees	Immediate	IRC:SP 84-
	· ·	obstruction by vegetation		image backup			2014
	sight line						
	and road						
	structures						

Asset Type	Performanc	Level of Service (LOS)	Frequency of	Testing Method	Recommended	Time limit	Specification
	e Parameter		Measurement		Remedial measures	for	s and
						Rectification	Standards
Rest Areas	Cleaning of	-	Daily	-	-	Every 4 hours	
	toilets						
	Defects in	-	Daily	-	Rectification	24 hours	
	electrical,						
	water and						
	sanitary						
	installations						
Other	Damage or de	eterioration in Approach	Daily	-	Rectification	15 days	IRC:SP 84-
Project	Roads, pedes	trian facilities, truck lay-bys,					2014
Facilities	bus-bays, bus	- shelters, cattle crossings,					
and	Traffic Aid P	osts, Medical Aid Posts and					
Approach	other works						
roads							

Table 4: Maintenance Criteria for Structures and Culverts:

Asset Type	Performanc	Level of Service (LOS)	Frequency of	Testing Method	Recommended	Time limit	Specification
	e Parameter		Measurement		Remedial measures	for	s and
						Rectification	Standards
Pipe / box /	Free	85% of culvert normal flow	2 times in a	Inspection by	Cleaning silt up soils	15 days	IRC 5-2015,
slab	waterway /	area to available	year (before	Bridge Engineer as	and debris in culvert	before onset	IRC SP:40-
culverts	unobstructed		and after rainy	per IRC SP: 35-	barrel after rainy	of monsoon	1993 and
	flow section		season)	1990 and recording	season, removal of	and within 30	IRC SP:13-

Asset Type	Performanc	Level of Service (LOS)	Frequency of	Testing Method	Recommended	Time limit	Specification
	e Parameter		Measurement		Remedial measures	for	s and
						Rectification	Standards
				of depth of silting	bushes and vegetation,	days after end	2004
				and area of	U / s of barrel, under	of rainy	
				vegetation.	barrel and D / s of	season.	
					barrel before rainy		
					season.		
	Leak-proof	No leakage through expansion	Bi-Annually	Physical inspection	Fixing with sealant	30 days or	IRC SP:40-
	expansion	joints		of expansion joints	suitably	before onset	1993 and
	joints if any			as per IRC SP: 35-		of rains	IRC SP:69-
				1990 if any, for		whichever	2011
				leakage strains on		comes earlier	
				walls at joints.			
	Structurally	Spalling of concrete not more	Bi-Annually	Detailed inspection	Repairs to spalling,	15 days	IRC SP 40-
	sound	than 0.25 sqm		of all components	cracking,		1993 and
		Delamination of concrete not		of culvert as per	delamination, rusting		MORTH
		more than 0.25 sq.m.		IRC SP:35-1990	shall be followed as		Specification
		Cracks wider than 0.3 mm not		and recording the	per IRC:SP:40-1993.		s clause 2800
		more than 1m aggregate		defects			
		length					
	Protection	Damaged of rough stone	2 times in a	Condition survey as	Repairs to damaged	30 days after	IRC: SP 40-
	works in	apron or bank revetment not	year (before	per IRC SP:35-1990	aprons and pitching	defect	1993 and
	good	more than 3 sqm, damage to	and after rainy			observation or	IRC:SP:13-
	condition	solid apron (concrete apron)	season)			2 weeks	2004.

Asset Type	Performanc	Level of Service (LOS)	Frequency of	Testing Method	Recommended	Time limit	Specification
	e Parameter		Measurement		Remedial measures	for	s and
						Rectification	Standards
		not more than 1 sqm				before onset	
						of rainy	
						season	
						whichever is	
						earlier.	
Bridges	Riding	No pothole in wearing coat on	Daily	Visual inspection as	Repairs to BC or	15 days	MORT&H
including	quality or	bridge deck		per IRC SP:35-1990	wearing coat		Specification
ROBs	user comfort						2811
Flyover etc.							
as							
applicable							
Bridge -	Bumps	No bump at expansion joint	Daily	Visual inspection as	Repairs to BC on	15 days	MORT&H
Super				per IRC SP:35-1990	either side of		Specification
Structure					expansion joints,		3004.2 &
					profile correction		2811.
					course on approach		
					slab in case of		
					settlement to approach		
					embankment		
	User safety	No damaged or missing	Daily	Visual inspection	Repairs and	3days	IRC: 5-1998,
	(condition of	stretch of crash barrier or		and detailed	replacement of safety		IRC SP: 84-
	crash barrier	pedestrian hand railing		condition survey as	barriers as the case		2014 and
	and guard			per IRC SP: 35-	may be		IRC SP: 40-

Asset Type	Performanc	Level of Service (LOS)	Frequency of	Testing Method	Recommended	Time limit	Specification
	e Parameter		Measurement		Remedial measures	for	s and
						Rectification	Standards
	rail)			1990.			1993.
	Rusted	Not more than 0.25 sq.m	Bi-Annually	Detailed condition	All the corroded	15 days	IRC SP: 40-
	reinforceme			survey as per IRC	reinforcement shall		1993 and
	nt			SP: 35-1990 using	need to be thoroughly		MORTH
	Spalling of	Not more than 0.50 sq.m		Mobile Bridge	cleaned from rusting		Specification
	concrete			Inspection Unit	and applied with anti-		1600.
	Delaminatio	Not more than 0.50 sq.m			corrosive coating		
	n				before carrying out the		
					repairs to affected		
					concrete portion with		
					epoxy mortar /		
					concrete		
	Cracks	Not more than 1m total length	Bi-Annually	Detailed condition	Grouting with epoxy	48 hours	IRC SP: 40-
	wider than			survey as per IRC	mortar, investigating		1993 and
	0.30 mm			SP: 35-1990 using	causes for cracks		MORTH
				Mobile Bridge	development and carry		Specification
				Inspection Unit	out necessary		2800.
					rehabilitation.		
	Rainwater	Leakage – nil	Quarterly	Detailed condition	Grouting of deck slab	1 months	MORTH
	seepage			survey as per IRC	at leakage areas,		specifications
	through deck			SP: 35-1990 using	waterproofing, repairs		2600 & 2700
	slab			Mobile Bridge	to drainage spouts		
				Inspection Unit			

Asset Type	Performanc	Level of Service (LOS)	Frequency of	Testing Method	Recommended	Time limit	Specification
	e Parameter		Measurement		Remedial measures	for	s and
						Rectification	Standards
	Deflection	Within design limits.	Once in every	Load Test Method	Carry out major	6 months	IRC SP: 51-
	due to		10 years for		rehabilitation works on		1999.
	permanent		spans more		bridge to retain		
	loads and		than 40m		original design loads		
	live loads				capacity		
	Vibrations in	Frequency of vibrations shall	Once in every 5	Laser displacement	Strengthening of super	4 months	AASHTO
	bridge deck	not be more than 5 Hz	years for spans	sensors or laser	structure		LRFD
	due to		more than 30m	vibro-meters			specifications
	moving		and every 10				
	trucks		years for spans				
			between 15 to				
			30m				
	Leakage in	No damage to elastomeric	Bi-Annually	Detailed condition	Replace of seal in	15 days	MORTHspec
	Expansion	sealant compound in strip seal		survey as per IRC	expansion joint		ifications260
	joints	expansion joint, no leakage of		SP:35-1990 using			0 and IRC
		rain water through expansion		Mobile Bridge			SP: 40-1993.
		joint in case of buried and		Inspection Unit			
		asphalt plug and copper strip					
		joint.					
	Debris and	No dust or debris in expansion	Monthly	Detailed condition	Cleaning of expansion	3 days	MORTH
	dust in strip	joint gap		survey as per IRC	joint gaps thoroughly		specifications
	seal			SP:35-1990 using			2600 and
	Expansion			Mobile Bridge			IRC SP: 40-

Asset Type	Performanc	Level of Service (LOS)	Frequency of	Testing Method	Recommended	Time limit	Specification
	e Parameter		Measurement		Remedial measures	for	s and
						Rectification	Standards
	joint			Inspection Unit			1993.
	Drainage	No down take pipe missing /	Monthly	Detailed condition	Cleaning of drainage	3 days	MORTHspec
	spouts	broken below soffit of the		survey as per IRC	spouts thoroughly.		ification2700
		deck slab. No silt, debris,		SP: 35-1990 using	Replacement of		
		clogging of drainage spout		Mobile Bridge	missing / broken down		
		collection chamber.		Inspection Unit	take pipes with a		
					minimum pipe		
					extension of 500mm		
					below soffit of slab.		
					Providing sealant		
					around the drainage		
					spout if any leakages		
					observed.		
Bridge-	Cracks /	No cracks, spalling of	Bi-Annually	Detailed condition	All the corroded	30 days	IRC SP: 40-
substructur	spalling of	concrete and rusted steel		survey as per IRC	reinforcement shall		1993 and
e	concrete /			SP: 35-1990 using	need to be thoroughly		MORTH
	rusted steel			Mobile Bridge	cleaned from rusting		specification
				Inspection Unit	and applied with anti-		2800.
					corrosive coating		
					before carrying out		
					repairs to substructure		
					by grouting / guniting		
					and micro concreting		

Asset Type	Performanc	Level of Service (LOS)	Frequency of	Testing Method	Recommended	Time limit	Specification
	e Parameter		Measurement		Remedial measures	for	s and
						Rectification	Standards
					depending on type of		
					defect noticed		
	Bearings	Delamination of bearing	Bi-Annually	Detailed condition	In case of failure of	3 months	MORTH
		reinforcement not more		survey as per IRC	even one bearing on		specification
		than5%, cracking or tearing of		SP: 35-1990 using	any pier / abutment, all		2810 and
		rubber not more than 2		Mobile Bridge	the bearings on that		IRC SP: 40-
		locations per side, no rupture		Inspection Unit	pier / abutment shall be		199.
		of reinforcement or rubber			replaced, in order to		
					get uniform load		
					transfer on to bearings.		
Bridge	Scouring	Scouring shall not be lower	Bi-Annually	Condition survey	Suitable protection	1 month	IRC SP: 40-
Foundation	around	than maximum scour level for		and visual	works around pier /		1993, IRC83-
S	foundations	the bridge		inspection as per	abutment		2014,
				IRC SP:35-1990			MORTH
				using Mobile			specification
				Bridge Inspection			2500
				Unit. In case of			
				doubt, use			
				Underwater camera			
				for inspection of			
				deep wells in major			
				Rivers.			

Asset Type	Performanc	Level of Service (LOS)	Frequency of	Testing Method	Recommended	Time limit	Specification
	e Parameter		Measurement		Remedial measures	for	s and
						Rectification	Standards
	Protection	Damaged of rough stone	2 times in a	Condition survey as	Repairs to damaged	30 days after	IRC: SP 40-
	works in	apron or bank revetment not	year (before	per IRC SP:35-1990	aprons and pitching.	defect	1993 and
	good	more than 3	and after rainy			observation or	IRC:SP:13-
	condition	sq.m, damage to solid	season)			2	2004.
		apron(concrete apron) not				Weeks before	
		more than 1 sq.m				onset of rainy	
						season	
						whichever is	
						earlier.	

Note: Any Structure during the entire contract period which is found that does not comply with all requirements of this Table will be prepared, rehabilitated or even reconstructed under the scope of the contractor.

Table 5: Maintenance Criteria for Hill Roads

In addition to above, for hill roads the following provisions for maintenance is also to done.

	Hill Roads							
(i)	(i) Damage to Retaining wall / Breast wall 7 (Seven) days							
(ii)	Landslides requiring clearance	12 (Twelve) hours						
(iii)	Snow requiring clearance	24 (Twenty-Four) hours						

Note: For all tables 1 to 5 above, latest BIS & IRC standards (even those not indicated herewith) along with MoRTH specifications shall be binding for all maintenance activities.

A. Flexible Pavement

	Nature of Defect or deficiency	Time limit for repair / rectification
(b) G	Franular earth shoulders, side slopes, drains and cu	llverts
(i)	Variation by more than 1 % in the prescribed slope	7 (seven) days
	of camber / cross fall (shall not be less than the	
	camber on the main carriageway)	
(ii)	Edge drop at shoulders exceeding 40 mm	7 (seven) days
(iii)	Variation by more than 15% in the prescribed	30 (thirty) days
	side(embankment) slopes	
(iv)	Rain cuts / gullies in slope	7 (seven) days
(v)	Damage to or silting of culverts and side drains	7 (seven) days
(vi)	Desilting of drains in urban / semi- urban areas	24 (twenty four) hours
(vii)	Railing, parapets, crash barriers	7 (seven) days (Restore
		immediately if causing safety
		hazard)
(c) R	oad side furniture including road sign and paveme	nt marking
(i)	Damage to shape or position, poor visibility or loss	48 (forty eight) hours
	of retro- reflectivity	
(ii)	Painting of km stone, railing, parapets, crash barriers	As and when required / Once
		every year
(iii)	Damaged / missing signs road requiring replacement	7 (seven) days
(iv)	Damage to road mark ups	7 (seven) days

	Nature of Defect or deficiency	Time limit for repair / rectification
(d) R	Road lighting	
(i)	Any major failure of the system	24 (twenty-four) hours
(ii)	Faults and minor failures	8 (eight) hours
(e) T	rees and plantation	
(i)	Obstruction in a minimum head-room of 5 m above	24 (twenty-four)hours
	carriageway or obstruction in visibility of road signs	
(ii)	Removal of fallen trees from carriageway	4 (four) hours
(iii)	Deterioration in health of trees and bushes	Timely watering and treatment
(iv)	Trees and bushes requiring replacement	30 (thirty) days
(v)	Removal of vegetation affecting sight line and road	15 (fifteen) days
	structures	
(f) R	est area	
(i)	Cleaning of toilets	Every 4 (four) hours
(ii)	Defects in electrical, water and sanitary installations	24 (twenty-four) hours
(g) [7	Foll Plaza]	
(h)	Other Project Facilities and Approach roads	
(i)	Damage in approach roads, pedestrian facilities,	15 (fifteen) days
	truck lay- byes, bus-bays, bus-shelters, cattle	
	crossings, [Traffic Aid Posts, Medical Aid Posts]	
	and service roads	
(ii)	Damaged vehicles or debris on the road	4 (four) hours
(iii)	Malfunctioning of the mobile crane	4 (four) hours
Brid	ges	

	Nature of Defect or deficiency	Time limit for repair / rectification
(a) S	uperstructure	
(i)	Any damage, cracks, spalling / scaling Temporary	within 48 (forty-eight) hours
	measures Permanent measures	within 15 (fifteen) days or as
		specified by the Authority's
		Engineer
(b) F	oundations	
(i)	Scouring and / or cavitation	15 (fifteen) days
(c) P	iers, abutments, return walls and wing walls	
(i)	Cracks and damages including settlement and tilting,	30 (thirty) days
	spalling, scaling	
(d) B	Bearings (metallic) of bridges	
(i)	Deformation, damages, tilting or shifting of bearings	15 (fifteen) days Greasing of
		metallic bearings once in a year
(e) J	oints	
(i)	Malfunctioning of joints	15 (fifteen) days
(f) O	ther items	
(i)	Deforming of pads in elastomeric bearings	7 (seven) days
(ii)	Gathering of dirt in bearings and joints; or clogging	3 (three) days
	of spouts, weep holes and vent-holes	
(iii)	Damage or deterioration in kerbs, parapets, handrails	3 (three) days (immediately
	and crash barriers	within 24 hours if posing danger
		to safety)
(iv)	Rain-cuts or erosion of banks of the side slopes of	7 (seven) days

	Nature of Defect or deficiency	Time limit for repair /	
		rectification	
	approaches		
(v)	Damage to wearing coat	15 (fifteen) days	
(vi)	Damage or deterioration in approach slabs, pitching,	30 (thirty) days	
	apron, toes, floor or guide bunds		
(vii)	Growth of vegetation affecting the structure or	15 (fifteen) days	
	obstructing the waterway		
(g) H	ill Roads		
(i)	Damage to retaining wall / breast wall	7 (seven) days	
(ii)	Landslides requiring clearance	12 (twelve) hours	
(iii)	Snow requiring clearance	24 (twenty four) hours	

[Note: Where necessary, the Authority may modify the time limit for repair / rectification or add to the nature of Defect or deficiency before issuing the bidding document, with the approval of the competent authority.]

Schedule - F

(See Clause 4.1 (vii)(a))

Applicable Permits

1. Applicable Permits

- 1.1 The Contractor shall obtain, as required under the Applicable Laws, the following Applicable Permits:
 - (a) Permission of the State Government for extraction of boulders from quarry;
 - (b) Permission of Village Panchayats and Pollution Control Board for installation of crushers;
 - (c) License for use of explosives;
 - (d) Permission of the State Government for drawing water from river / reservoir;
 - (e) License from inspector of factories or other competent Authority for setting up batching plant;
 - (f) Clearance of Pollution Control Board for setting up batching plant;
 - (g) Clearance of Village Panchayats and Pollution Control Board for setting up asphalt plant;
 - (h) Permission of Village Panchayats and State Government for borrow earth; and
 - (i) Any other permits or clearances required under Applicable Laws.
- 1.2 Applicable Permits, as required, relating to environmental protection and conservation shall have been procured by the Authority in accordance with the provisions of this Agreement.

Schedule - G

(See Clauses 7.1 and 19.2)

Annex-I

(See Clause 7.1)

Form of Bank Guarantee

[Performance Security / Additional Performance Security]

To National Highway & Highway Development Corporation Ltd. PTI Building, 3rd Floor, 4, Parliament Street, NewDelhi-110001

WHEREAS:

- [name and address of contractor] (hereinafter called the "Contractor") and [name and address of the authority] (hereinafter called the "Authority") have entered into an agreement (hereinafter called the "Agreement") for "Construction of Balance Work of the 4-laning of the Section from Jhanji to Demow of NH-37 (Old): Pkg-II: Road Works from Km 501+800 to Km 514+800 (13.000 Km), under SARDP- NE, under EPC Mode" subject to and in accordance with the provisions of the Agreement
- (b) The Agreement requires the Contractor to furnish a Performance Security for due and faithful performance of its obligations, under and in accordance with the Agreement, during the {Construction Period / Defects Liability Period and Maintenance Period} (as defined in the Agreement) in a sum of Rs.... cr. (Rupees crore) (the "Guarantee Amount").

NOW, THEREFORE, the Bank hereby, unconditionally and irrevocably, guarantees and affirms as follows:

1. The Bank hereby unconditionally and irrevocably guarantees the due and faithful performance of the Contractor's obligations during the {Construction Period / Defects Liability Period and Maintenance Period} under and in accordance with the Agreement, and agrees and undertakes to pay to the Authority, upon its mere first written demand, and without any demur, reservation, recourse, contest or protest, and without any reference to the Contractor, such sum or sums up to an aggregate sum of

the Guarantee Amount as the Authority shall claim, without the Authority being required to prove or to show grounds or reasons for its demand and / or for the sum specified therein.

- 2. A letter from the Authority, under the hand of an officer not below the rank of [General Manager in the National Highways Authority of India], that the Contractor has committed default in the due and faithful performance of all or any of its obligations under and in accordance with the Agreement shall be conclusive, final and binding on the Bank. The Bank further agrees that the Authority shall be the sole judge as to whether the Contractor is in default in due and faithful performance of its obligations during and under the Agreement and its decision that the Contractor is in default shall be final and binding on the Bank, notwithstanding any differences between the Authority and the Contractor, or any dispute between them pending before any court, tribunal, arbitrators or any other authority or body, or by the discharge of the Contractor for any reason whatsoever.
- 3. In order to give effect to this Guarantee, the Authority shall be entitled to act as if the Bank were the principal debtor and any change in the constitution of the Contractor and / or the Bank, whether by their absorption with any other body or corporation or otherwise, shall not in any way or manner affect the liability or obligation of the Bank under this Guarantee.
- 4. It shall not be necessary, and the Bank hereby waives any necessity, for the Authority to proceed against the Contractor before presenting to the Bank its demand under this Guarantee.
- 5. The Authority shall have the liberty, without affecting in any manner the liability of the Bank under this Guarantee, to vary at any time, the terms and conditions of the Agreement or to extend the time or period for the compliance with, fulfillment and / or performance of all or any of the obligations of the Contractor contained in the Agreement or to postpone for any time, and from time to time, any of the rights and powers exercisable by the Authority against the Contractor, and either to enforce or forbear from enforcing any of the terms and conditions contained in the Agreement and / or the securities available to the Authority, and the Bank shall not be released from its liability and obligation under these presents by any exercise by the Authority of the liberty with reference to the matters aforesaid or by reason of time being given to the Contractor or any other forbearance, indulgence, act or omission on the part of the Authority or of any other matter or thing whatsoever which under any law relating to sureties and guarantors would but for this provision have the effect of releasing the Bank from its liability and obligation under this Guarantee and the Bank hereby waives all of its rights under any such law.

- 6. This Guarantee is in addition to and not in substitution of any other guarantee or security now or which may hereafter be held by the Authority in respect of or relating to the Agreement or for the fulfillment, compliance and / or performance of all or any of the obligations of the Contractor under the Agreement.
- 7. Notwithstanding anything contained hereinbefore, the liability of the Bank under this Guarantee is restricted to the Guarantee Amount and this Guarantee will remain in force for the period specified in paragraph 8 below and unless a demand or claim in writing is made by the Authority on the Bank under this Guarantee all rights of the Authority under this Guarantee shall be forfeited and the Bank shall be relieved from its liabilities hereunder.
- 8. The Guarantee shall cease to be in force and effect on ****\$. Unless a demand or claim under this Guarantee is made in writing before expiry of the Guarantee, the Bank shall be discharged from its liabilities hereunder.
- 9. The Bank undertakes not to revoke this Guarantee during its currency, except with the previous express consent of the Authority in writing and declares and warrants that it has the power to issue this Guarantee and the undersigned has full powers to do so on behalf of the Bank.
- 10. Any notice by way of request, demand or otherwise hereunder may be sent by post addressed to the Bank at its above referred branch, which shall be deemed to have been duly authorised to receive such notice and to effect payment thereof forthwith, and if sent by post it shall be deemed to have been given at the time when it ought to have been delivered in due course of post and in proving such notice, when given by post, it shall be sufficient to prove that the envelope containing the notice was posted and a certificate signed by an officer of the Authority that the envelope was so posted shall be conclusive.
- 11. This Guarantee shall come into force with immediate effect and shall remain in force and effect for up to the date specified in paragraph 8 above or until it is released earlier by the Authority pursuant to the provisions of the Agreement.
- 12. This guarantee shall also be operable at our Branch at New Delhi, from whom, confirmation regarding the issue of this guarantee or extension / renewal thereof shall be made available on demand. In the contingency of this guarantee being invoked and payment there under claimed, the said branch shall accept such invocation letter and make payment of amounts so demanded under the said invocation.
- 13. The guarantor/bank hereby confirms that it is on the SFMS (Structural Finance Messaging System) platform& shall invariably send an advice of this Bank Guarantee

to the designated bank of [MoRT&H/NHAI/NHIDCL/State PWD/BRO], details of which is as under:

Sr.No.	Particulars	Details
1.	NameofBeneficiary	MD-NHIDCL
2.	BeneficiaryBankAccountNo.	90621010002659
3.	BeneficiaryBankBranchNameand Address	CanaraBank(erstwhileSyndicate Bank), Transport Bhawan, 1stParliamentStreet,NewDelhi- 110001
4.	BeneficiaryBankBranchIFSC	CNRB0019062
5.	SwiftCode(ForForeignBidders)	SYNBINBB126

Signed and sealed this day of 20....... at

SIGNED, SEALED AND DELIVERED

For and on behalf of the Bank by:

(Signature)

(Name)

(Designation)

(Code Number)

(Address)

NOTES:

- 1. The bank guarantee should contain the name, designation and code number of the officer(s) signing the guarantee.
- 2. The address, telephone number and other details of the head office of the Bank as well as of issuing branch should be mentioned on the covering letter of issuing branch.

^{\$} Insert date being 2 (two) years from the date of issuance of this Guarantee (in accordance with Clause 7.2 of the Agreement).

Annex – II

(Schedule - G) (See Clause 19.2)

Form for Guarantee for Advance Payment

To National Highway & Highway Development Corporation Ltd. PTI Building, 3rd Floor, 4, Parliament Street, NewDelhi-110001

WHEREAS:

- [name and address of contractor] (hereinafter called the "Contractor") and [name and address of the authority] (hereinafter called the "Authority") have entered into an agreement (hereinafter called the "Agreement") for "Construction of Balance Work of the 4-laning of the Section from Jhanji to Demow of NH-37 (Old): Pkg-II: Road Works from Km 501+800 to Km 514+800 (13.000 Km), under SARDP- NE, under EPC Mode" subject to and in accordance with the provisions of the Agreement
- (B) In accordance with Clause 19.2 of the Agreement, the Authority shall make to the Contractor an interest bearing @Bank Rate + 3% advance payment (herein after called "Advance Payment") equal to 10% (ten per cent) of the Contract Price; and that the Advance Payment shall be made in two installments subject to the Contractor furnishing an irrevocable and unconditional guarantee by a scheduled bank for an amount equivalent to 110% (one hundred and ten percent) of such installment to remain effective till the complete and full repayment of the installment of the Advance Payment as security for compliance with its obligations in accordance with the Agreement. The amount of {first / second} installment of the Advance Payment is Rs. ----- cr. (Rupees ----- crore) and the amount of this Guarantee is Rs. ----- cr. (Rupees ----- crore) (the "Guarantee Amount")\$.
- - NOW, THEREFORE, the Bank hereby, unconditionally and irrevocably, guarantees and affirms as follows:
- 1. The Bank hereby unconditionally and irrevocably guarantees the due and faithful repayment on time of the aforesaid instalment of the Advance Payment under and in accordance with the Agreement, and agrees and undertakes to pay to the Authority,

upon its mere first written demand, and without any demur, reservation, recourse, contest or protest, and without any reference to the Contractor, such sum or sums up to an aggregate sum of the Guarantee Amount as the Authority shall claim, without the Authority being required to prove or to show grounds or reasons for its demand and / or for the sum specified therein.

- 2. A letter from the Authority, under the hand of an officer not below the rank of [General Manager in the National Highways Authority of India], that the Contractor has committed default in the due and faithful performance of all or any of its obligations for the repayment of the instalment of the Advance Payment under and in accordance with the Agreement shall be conclusive, final and binding on the Bank. The Bank further agrees that the Authority shall be the sole judge as to whether the Contractor is in default in due and faithful performance of its obligations during and under the Agreement and its decision that the Contractor is in default shall be final and binding on the Bank, notwithstanding any differences between the Authority and the Contractor, or any dispute between them pending before any court, tribunal, arbitrators or any other authority or body, or by the discharge of the Contractor for any reason whatsoever.
- 3. In order to give effect to this Guarantee, the Authority shall be entitled to act as if the Bank were the principal debtor and any change in the constitution of the Contractor and / or the Bank, whether by their absorption with any other body or corporation or otherwise, shall not in any way or manner affect the liability or obligation of the Bank under this Guarantee.
- 4. It shall not be necessary, and the Bank hereby waives any necessity, for the Authority to proceed against the Contractor before presenting to the Bank its demand under this Guarantee.
- 5. The Authority shall have the liberty, without affecting in any manner the liability of the Bank under this Guarantee, to vary at any time, the terms and conditions of the Advance Payment or to extend the time or period of its repayment or to postpone for any time, and from time to time, any of the rights and powers exercisable by the Authority against the Contractor, and either to enforce or forbear from enforcing any of the terms and conditions contained in the Agreement and / or the securities available to the Authority, and the Bank shall not be released from its liability and obligation under these presents by any exercise by the Authority of the liberty with

^{\$} The Guarantee Amount should be equivalent to 110% of the value of the applicable instalment.

reference to the matters aforesaid or by reason of time being given to the Contractor or any other forbearance, indulgence, act or omission on the part of the Authority or of any other matter or thing whatsoever which under any law relating to sureties and guarantors would but for this provision have the effect of releasing the Bank from its liability and obligation under this Guarantee and the Bank hereby waives all of its rights under any such law.

- 6. This Guarantee is in addition to and not in substitution of any other guarantee or security now or which may hereafter be held by the Authority in respect of or relating to the Advance Payment.
- 7. Notwithstanding anything contained hereinbefore, the liability of the Bank under this Guarantee is restricted to the Guarantee Amount and this Guarantee will remain in force for the period specified in paragraph 8 below and unless a demand or claim in writing is made by the Authority on the Bank under this Guarantee all rights of the Authority under this Guarantee shall be forfeited and the Bank shall be relieved from its liabilities hereunder.
- 8. The Guarantee shall cease to be in force and effect on ****.\$ Unless a demand or claim under this Guarantee is made in writing on or before the aforesaid date, the Bank shall be discharged from its liabilities hereunder.
- 9. The Bank undertakes not to revoke this Guarantee during its currency, except with the previous express consent of the Authority in writing and declares and warrants that it has the power to issue this Guarantee and the undersigned has full powers to do so on behalf of the Bank.
- 10. Any notice by way of request, demand or otherwise hereunder may be sent by post addressed to the Bank at its above referred branch, which shall be deemed to have been duly authorised to receive such notice and to effect payment thereof forthwith, and if sent by post it shall be deemed to have been given at the time when it ought to have been delivered in due course of post and in proving such notice, when given by post, it shall be sufficient to prove that the envelope containing the notice was posted and a certificate signed by an officer of the Authority that the envelope was so posted shall be conclusive.
- 11. This Guarantee shall come into force with immediate effect and shall remain in force and effect up to the date specified in paragraph 8 above or until it is released earlier by the Authority pursuant to the provisions of the Agreement.

- 12. This Guarantee shall come into force with immediate effect and shall remain in force and effect up to the date specified in paragraph 8 above or until it is released earlier by the Authority pursuant to the provisions of the Agreement.
- 13. Bank Guarantee has been sent to authority's bank through SFMS gateway as per the details below:-

Sr.No.	Particulars	Details
1.	NameofBeneficiary	RONHIDCLPROJECTS
2.	BeneficiaryBankAccountNo.	73653210000013
3.	BeneficiaryBankBranchIFSC	CNRB0019062
4.	BeneficiaryBankBranchName	CanaraBank,Dispur,Guwahati
5.	BeneficiaryBankBranchAddress	UpasanaComplex,Dr.R.P.Road, Ganeshguri,Dispur,Guwahati

Signed and sealed this day of, 20...... at

SIGNED, SEALED AND DELIVERED

For and on behalf of the Bank by:

(Signature)

(Name)

(Designation)

(Code Number)

(Address)

NOTES:

- 1. The bank guarantee should contain the name, designation and code number of the officer(s) signing the guarantee.
- 2. The address, telephone number and other details of the head office of the Bank as well as of issuing branch should be mentioned on the covering letter of issuing branch.
- 3. The bank shall be any bank listed in the list of nationalized / Govt banks only but not any scheduled commercial private banks.

^{\$} Insert a date being 90 (ninety) days after the end of one year from the date of payment of the Advance payment to the Contractor (in accordance with Clause 19.2 of the Agreement).

Schedule-H

(See Clause 19.3)

Contract Price Weightages

Schedule-H

(See Clause 19.3)

Contract Price Weightages

- 1.1 The Contract Price for this Agreement is Rs xxxxxxx
- 1.2 Proportions of the Contract Price for different stages of Construction of the Project Highway shall be as specified below:

Item	Weightage in Percentage to the Contract Price	Activity	Percentage Weightage in Payment Schedule	
		A.1) Widening and Strengthening of Existing Road to 2-Lan Shoulder including Rectification	e with Paved	
		(1) Earth Work up to Top of the Sub Grade	6.80%	
		(2) Sub base course (GSB,Shoulders)	2.19%	
		(3) Non-Bituminous Base Course (WMM)	1.62%	
		(4) Bituminous Base Course (DBM)	4.63%	
	including Rectification (1) Earth Work up to Top of the S	(5) Wearing Coat (BC)	2.67%	
Road Works		B.1 -Reconstruction/new 2 Lane realignment/ Bypass (Flexible Pavement) including Rectification		
Including		(1) Earth Work up to Top of the Sub Grade	14.53%	
Culverts, widening and	56.62%	(2) Sub base course (GSB,Shoulders)	21.98%	
repair of		(3) Non-Bituminous Base Course (WMM)	23.29%	
culverts		(4) Bituminous Base Course (DBM)	14.30%	
		(5) Wearing Coat (BC)	6.29%	
		C.1 Pending road Kerb construction	0.23%	
		D.1Widening and repair of culverts		
		Culverts (Length<6m)	0.75%	
		E.1Re-Construction and New culverts on existing road, real bypasses including Rectification	ignments,	
		Culverts (Length<6m)	0.72%	
Minor Bridges/Unde			nd <60m)	
rpass/Overpa ss (1) Minor Bridges		(1) Minor Bridges	As noted below	

1		A.2 - New Minor Bridges (Length>6m and <60m) including	Rectification
		1) Foundation + Sub structure	-
		2) Super-Structure	-
		3) Approaches	Covered in Road works
		4) Wearing Coat	As noted below
		B.2. New Underpasses/Overpasses including Rectification	•
		1) Foundation + Sub structure	-
		2) Super-Structure	-
		3) Wearing Coat& Road Markings	
		4) Approaches	As noted
		i) Casting of Panels	below
		ii) Erection of Panels	
		A.1 Widening and repairs of Major Bridges including Rec	ctification
		1) Foundation	-
		2) Sub-Structure	-
		3) Super Structure (including bearings)	-
		4) Wearing coat & Road Markings	As noted below
		5) Approaches	Covered in Road Works
Major Bridge		6) Miscellaneous Items like hand rails, crash barriers, expansion Joints etc.	-
(Length>60m		A.2 - New Major Bridges including Rectification	
) works and ROB/RUB/el		1) Foundation	-
evated	-	2) Sub-Structure	-
sections/flyov ers including		3) Super Structure (including bearings)	-
viaducts, if		3.1) Casting of Girder	-
any		3.2) Deck Slab	-
		4) Wearing coat & Road Markings	As noted below
		5) Approaches	Covered in Road Works
		5) Miscellaneous Items like hand rails, crash barriers, Expansion Joints etc.	-
		6) Wing walls /return walls	-
		7) Approaches (retaining walls, stone pitching and protection works)	-
		Other Works	
	as 13.19%	A)Toll Plaza	-
Other Works		B) Reconstruction/new Service Road (Flexible Pavement) including Rectification	
		(1) Earth Work up to Top of the Sub Grade	12.34%

	(2) Sub base course (GSB,Shoulders)		18.09%
(3) Non-Bituminous Base Course (WMM) (4) Bituminous Base Course (DBM) (5) Wearing Coat (BC)		(3) Non-Bituminous Base Course (WMM)	25.82%
		(4) Bituminous Base Course (DBM)	11.42%
		(5) Wearing Coat (BC)	7.45%
		C)Roads Side Drains (including Rectification)	24.88%
		1) Road Signs, Markings, K.M. Stones, Safety Devices, etc.	26.62%
		2) Project Facilities (Others)	
		a) Bus Bays	9.61%
		b) Truck lay-bayes	0.00%
		c) (Junctions)	12.01%
		3) Road Side& Median Plantation	5.55%
Misc. works	6.06%	4) Protection works other than approaches to the bridges, elevated sections/flyovers/grade separators and ROBs/RUBs.	1.85%
		5) Retaining wall	
		6) Toe wall with turfing	21.07%
		7) Wearing coat over bridge decks	4.81%
		8) Road safety management during construction	9.24%
		9) Others	9.24%
Slip road &	0.61%	Box culvert @ Km.513+675	30.86%
Box culverts		Slip Road for approach road (MJB)	69.14%
Reinforced		RCC Facia Elements Casting	30.00 %
Earth Wall Construction	22.33%	Erection of Panels i.e. Assembling, joining and anchoring the reinforcing elements, including earth-filling	50.00 %
		Friction Slab cum crash barrier over VUP Approaches	20.00%
Road		(1) Pedestrian Guard rail at Service road locations	30.41%
furniture	1.19%	(2) Highway Lighting	30.40%
		(3) Metal Beam Crash Barrier	39.19%

Note: * The above list is illustrative and may require modification as per the scope of the work.

- 1.3. Procedure of estimating the value of work done.
- 1.3.1 Road works including approaches to Minor Bridges, Major Bridges, Toll Plaza location and Structures.

Procedure for estimating the value of road work done shall be as follows:

Table 1.3.1

Stage of payment	% Weightage	Payment procedure	
A) Widening and Strengthening of Existing Road to 2-Lane with Paved Shoulder including Rectification			
(1) Earthwork up to top of the subgrade	6.80%	Unit of measurement is linear length.	
(2) Granular work (sub-base)	2.19%	Payment of each stage shall be made on	
3) Non-Bituminous Base Course (WMM)	1.62%	pro rata basis on completion of a stage in a length of not less than 0.5 (Point Five) Km in 2 lane.	
4) Bituminous Course (Dense Bituminous Macadam)	4.63%	Tive) Kill ili 2 lane.	
5) Wearing Course (Bituminous Concrete)	2.67%		
B.1 -Reconstruction/new 2 Lane realignment/ Bypass (Flexible Pavement) including Rectification			
(1) Earthwork up to top of the subgrade	14.53%	Unit of measurement is linear length.	
(2) Granular work (sub-base)	21.98%	Payment of each stage shall be made on pro rata basis on completion of a stage	
3) Non-Bituminous Base Course (WMM)	23.29%	in a length of not less than 0.5 (Poin Five) Km in 2 lane.	
4) Bituminous Course(Dense Bituminous Macadam)	14.30%	,	
5) Wearing Course (Bituminous Concrete)	6.29%		
C.1 Pending Road Kerb construction	0.23%	Unit of measurement is linear length. Payment of each stage shall be made on pro rata basis on completion of a stage in a length of not less than 0.500 (One) Km in one side.	
D.1Widening and repair of culverts			
Culverts (Length<6m)	0.75%	Cost of each culvert shall be determined on pro rata basis with respect to the total number of culverts. Payment shall be made on the completion of 1 (One) culvert for 2 lane carriageways. Further, 80% payment will be made for each culvert constructed in 4 lane	

		equivalent width without protection work. Further 20% will be released after completion of Protection work
E.1Re-Construction and New culverts on existing road, realignments, bypasses including Rectification		
Culverts (Length<6m)	0.72%	Cost of each culvert shall be determined on pro rata basis with respect to the total number of culverts. Payment shall be made on the completion of 1 (One) culvert for 2 lane carriageways. Further, 80% payment will be made for each culvert constructed in 2 lane equivalent width without protection work. Further 20% will be released after completion of Total Culvert & its Protection work
A.1 Widening and repairs of Minor Bridges (length >6m and <60m) including Rectification	-	-
A.2 - New Minor Bridges (Length>6m and <60m) including Rectification		
1) Foundation + Sub structure	-	-
2) Super-Structure	-	-
3) Approaches		Covered in Road Works
4) Wearing Coat	-	Cost of shall be determined on pro rata basis with respect to the total linear length as per the Scope. Payment shall be made on the completion of wearing coat over each Structure.
B.2. New Underpasses/Overpasses including Rectification		
1) Foundation + Sub structure	-	-
2) Super-Structure	-	-
3) Wearing Coat	-	Cost of shall be determined on pro rata basis with respect to the total linear length of the as per the Scope. Payment shall be made on the completion of wearing coat over each Structure.
4) Approaches		
a) RCC Facia Elements Casting	30.00 %	The unit of measurement is in sqm. Payment shall be made on a pro-rata basis on casting a minimum 750 sqm facia panel after getting satisfied with 7 days cube strength (Min 75% of the specified 28 days strength).

b) Erection of Panels i.e. Assembling, joining and anchoring the reinforcing elements, including earth-filling	50.00 %	The unit of Measurement is sqm. Payment shall be made on a pro rata basis upon completion of a stage that is not less than 750 sqm complete in all respects.
c) Friction Slab cum crash barrier over VUP Approaches	20.00%	The unit of measurement is linear length in meter. Payment shall be made on a pro-rata basis on completion of friction slab of not less than 250 m.

1.3.2 Major Bridge works and ROB/RUB

Procedure for estimating the value of Major Bridge works shall be as stated in table 1.3.2: Table 1.3.2

Stage of payment	% weightage	Payment Procedure
A-Widening and repairs of Major Bridges including Rectification Foundation: On completion of the Foundation work including Foundations for wing and return walls	-	
Sub-structure: On completion of abutments, piers up to the abutment/pier cap	-	
Super-structure: On completion of the super structure in all respects including hand rails/crash barriers, wing walls, return walls, guide bunds, if any, tests on completion etc., bridge complete in all respects and fir for use.	-	
4)Wearing coat	-	Cost of shall be determined on pro rata basis with respect to the total linear length of the as per the Scope. Payment shall be made on the completion of wearing coat over each Structure.
5) Road Markings		Covered in in Signages & Road Markings
5) Miscellaneous Items like hand rails, crash barriers, expansion joints etc.	-	
B- New Major Bridges including Rectification		
(1) Foundation: On completion of the foundation work including foundations for wing and return walls.	-	-
(2) Sub-structure: On completion of abutments, piers up to	-	

Stage of payment	% weightage	Payment Procedure
(3)Super-structure: On completion of the super structure in all respects including hand rails/crash barriers, wing walls, return walls, guide bunds, if any, tests on completion etc., complete in all respects and fit for use	-	
3.1) Casting of Girder	-	
3.2) Deck Slab	-	
4) Wearing coat		Cost of shall be determined on pro rata basis with respect to the total linear length of the as per the Scope. Payment shall be made on the completion of wearing coat over each Structure.
5) Road Markings		Covered in in Signages & Road Markings
6) Miscellaneous Items like hand rails, crash barriers, expansion joints etc.	-	
7) Wing walls /return walls	-	
8) Approaches (including retaining walls, stone pitching and protection works)	-	

1.3.3Other Engineering works

Procedure for estimating the value of other engineering works done shall be as stated in table 1.3.4.

Stage of payment	% weightage	Payment procedure
A) Toll plaza	-	-
B) Reconstruction/new Service Road (Flexible Pavement) including Rectification		
(1) Earth Work up to Top of the Sub Grade	12.34%	Unit of measurement is linear length in km. Cost per km shall be determined on pro rata basis with
(2) Sub base course (GSB,Shoulders)	18.09%	respect to the total length of the Service Roads. Payment shall be made completion of a stage in

(3) Non-Bituminous Base Course (WMM)	25.82%	length of not less than 0.5 Km (Point Five) in One Side.
(4) Bituminous Base Course (DBM)	11.42%	
(5) Wearing Coat (BC)	7.45%	
C)Roads Side Drains (including Rectification)	24.88%	The unit of measurement is linear length in Rm. Payment shall be made on a pro rata basis upon completion of a stage with a length of not less than 5% (Five percent) of the total scope on One Lane.
Miscellaneous work		
(i) Road signs, markings, km stones, safety devices.	26.62%	Unit of measurement is linear length in Rm. Payment shall be made on pro rata basis on completion of a stage in a length of not less than 5% (Five percent) of the total scope on One Lane.
(ii) Project Facilities	20.0270	of the total scope on one Lane.
a) Bus bays	9.61%	Payment shall be made on pro rata
b) Truck lay-bays	0.00%	basis for one unit completed facilities.
c) Junctions	12.01%	
(iii) Roadside & Median plantation		The unit of measurement is linear
	5.55%	length. Payment shall be made on
(iv) Repair & Protection works		a pro rata basis on completion of a stage with a length of not less than
other than bridge approaches		5% (ten per cent) of the total
	1.85%	length.
(v) Retaining wall		Unit of measurement is linear length. Payment shall be made on pro rata basis on completion of a
(vi) Toe wall with turfing	21.07%	stage in a length of not less than 5% (Five per cent) of the total length.
(vii) Wearing coat over		Unit of measurement is linear
Bridges/Under Passes	4.81%	length. Payment shall be made on pro rata basis on completion of each structure.
(viii) Road safety management	₸,01/0	Payment to be made monthly on
during construction	9.24%	pro rata basis based on Safety measures taken by the Contractor

		to the level of satisfaction of the Engineer
Others	9.24%	The unit of measurement is linear length. Payment shall be made on completion of a stage in a length of not less than 0.5 Km (Point Five).
Slip Road and Box culvert		
1. Box culvert @Km513+675	30.86%	Payment shall be made on completion of Culvert for 4 lane. Further 80% payment shall be made after completion without Protection works and 20% will be made after completion of Protection works.
2. Slip Road for MJB	69.14%	Payment shall be made on Pro rata basis on completion of each layer for each location
Road furniture		
(1) Pedestrian Guard rail at Service road location	30.41%	The unit of Measurement is linear length. Payment shall be made on
(2) Highway Lighting	30.40%	a pro rata basis upon completion of a stage representing at least 5%
(3) Metal Beam Crash Barrier	39.19%	of the specified scope.

Schedule - I

(See Clause 10.2 (iv))

Drawings

1. Drawings

In compliance of the obligations set forth in Clause 10.2 of this Agreement, the Contractor shall furnish to the Authority's Engineer, free of cost, all Drawings listed in Annex-I of this Schedule-I.

2. Additional Drawings

If the Authority's Engineer determines that for discharging its duties and functions under this Agreement, it requires any drawings other than those listed in Annex-I, it may by notice require the Contractor to prepare and furnish such drawings forthwith. Upon receiving a requisition to this effect, the Contractor shall promptly prepare and furnish such drawings to the Authority's Engineer, as if such drawings formed part of Annex-I of this Schedule-I.

Annex – I

(Schedule - I)

List of Drawings

- 1. A minimum list of the drawings of the various components/elements of the project highway and project facility required to be submitted by the Contractor is given below:
- (a) Drawing of horizontal alignment & vertical profile and detailed cross sections.
- (b) Drawings of cross drainage works i.e. Bridges/Culverts/Flyovers and Other Structures.
- (c) Drawings for River Training works.
- (d) Drawings of interchanges, major intersections and underpasses .
- (e) Drawing of control centre.
- (f) Drawings of road furniture items including traffic signage, marking, safety barriers, etc.
- (g) Drawings of traffic diversions plans and traffic control measures.
- (h) Drawings of road drainage measures.
- (i) Drawings of typical details slope protection measures.
- (j) Drawings of landscaping and horticulture.
- (k) Drawings of pedestrian crossing.
- (1) Drawings of street lighting.
- (m) Any other drawings as per instruction of Authority Engineer.
- (n) General Arrangement showing Base Camp and Administrative Block.

Schedule - J

(See Clause 10.3 (ii))

Project Completion Schedule

1. Project Completion Schedule – 12 months (360 Days) from appointed date.

During Construction period, the Contractor shall comply with the requirements set forth in this Schedule-J for each of the Project Milestones and the Scheduled Completion Date. Within 15 (fifteen) days of the date of each Project Milestone, the Contractor shall notify the Authority of such compliance along with necessary particulars thereof.

2. Project Milestone-I

- 2.1 Project Milestone-I shall occur on the date falling on the 90th day [25% of the Scheduled Construction Period] day from the Appointed Date (the "Project Milestone-I").
- 2.2 Prior to the occurrence of Project Milestone-I, the Contractor shall have commenced construction of the Project Highway and submitted to the Authority duly and validly prepared Stage Payment Statements for an amount not less than 10% (ten per cent) of the Contract Price.

3. Project Milestone-II

- 3.1 Project Milestone-II shall occur on the date falling on the 180th day [50% of the Scheduled Construction Period] day from the Appointed Date (the "Project Milestone-II").
- 3.2 Prior to the occurrence of Project Milestone-II, the Contractor shall have continued with construction of the Project Highway and submitted to the Authority duly and validly prepared Stage Payment Statements for an amount not less than 35% (thirty-five per cent) of the Contract Price and should have started construction of all bridges

4. Project Milestone-III

- 1.1. Project Milestone-III shall occur on the date falling on the 270th day [75% of the Scheduled Construction Period] day from the Appointed Date (the "Project Milestone-III").
- 1.2. Prior to the occurrence of Project Milestone-III, the Contractor shall have continued with construction of the Project Highway and submitted to the Authority

duly and validly prepared Stage Payment Statements for an amount not less than 70% (seventy per cent) of the Contract Price and should have started construction of all project facilities.

5. Scheduled Completion Date

- 5.1 The Scheduled Completion Date shall occur on the 360th day [Scheduled Construction Period] from the Appointed Date.
- 5.2 On or before the Scheduled Completion Date, the Contractor shall have completed construction in accordance with this Agreement.

6. Extension of time

Upon extension of any or all of the aforesaid Project Milestones or the Scheduled Completion Date, as the case may be, under and in accordance with the provisions of this Agreement, the Project Completion Schedule shall be deemed to have been amended accordingly.

SCHEDULE-K (SeeClause12.1(ii))

Tests on Completion

1 Schedule for Tests

- (i) The Contractor shall, no later than 30 (thirty) days prior to the likely completion of construction, notify the Authority's Engineer and the Authority of its intent to subject the Project Highway to Tests, and no later than 10(ten) days prior to the actual date of Tests, furnish to the Authority's Engineer and the Authority detailed inventory and particulars of all works and equipment forming part of Works.
- (ii) The Contractor shall notify the Authority's Engineer of its readiness to subject to the Project Highway to Tests at any time after 10 (ten) days from the date of such notice, and upon receipt of such notice, the Authority's Engineer shall, in consultation with the Contractor, determine the date and time for each Test and notify the same to the Authority who may designate its representative to witness the Tests. The Authority's Engineer shall thereupon conduct the Tests itself or cause any of the Tests to be conducted in accordance with Article 12 and this Schedule-K.

2 Tests

- 2.1 (Visual and physical test: The Authority's Engineer shall conduct a visual and physical check of construction to determine that all works and equipment forming part thereof conform to the provisions of this Agreement. The physical tests shall include [***].
- 2.2 Riding quality test: Riding quality of each lane of the carriageway shall be checked with the help of a Network Survey Vehicle (NSV) fitted with latest equipments and the maximum permissible roughness for purposes of this Test shall be [2,000 (two thousand)] mm for each kilometre.
- 2.3 Tests for bridges: All major and minor bridges shall be subjected to the rebound hammer and ultrasonic pulse velocity tests, to be conducted in accordance with the procedure described in Special Report No. 17: 1996 of the IRC Highway Research Board on Non-destructive Testing Techniques, at two spots in every span, to be

chosen at random by the Authority's Engineer. Bridges with a span of 15 (fifteen) metres or more shall also be subjected to load testing.

- Other tests: The Authority's Engineer may require the Contractor to carry out or cause to be carried additional tests, in accordance with Good Industry Practice, for determining the compliance of the Project Highway with Specifications and Standards, except tests as specified in clause 5, but shall include measuring the reflectivity of road markings and road signs; and measuring the illumination level (lux) of lighting using requisite testing equipment.
- 2.5 Environmental audit: The Authority's Engineer shall carry out a check to determine conformity of the Project Highway with the environmental requirements set forth in Applicable Laws and Applicable Permits.
- 2.6 Safety Audit: The Authority's Engineer shall carry out, or cause to be carried out, a safety audit to determine conformity of the Project Highway with the safety requirements and Good Industry Practice.

3 Agency for conducting Tests

All Tests set forth in this Schedule-K shall be conducted by the Authority's Engineer or such other agency or person as it may specify in consultation with the Authority.

4 Completion Certificate

Upon successful completion of Tests, the Authority's Engineer shall issue the Completion Certificate in accordance with the provisions of Article 12.

The Authority Engineer will carry out tests with following equipment at his own cost in the presence of contractor's representative.

S.No.	Keymetricso f Asset	Equipmenttobeused	Frequencyofconditionsurvey
1	Surface defectsof pavemen t	Network Survey Vehicle (NSV)	At least twice a year (As per survey months defined for the state basis rainy season)
2	Roughness of pavement	Network Survey Vehicle (NSV)	At least twice a year(As per survey months defined for the state basis rainy season)
3	Strengthof pavement	Falling Weight Deflectometer (FWD)	At least once a year
4	Bridges	Mobile Bridge Inspection Unit(MBU)	At least twice a year(As per survey months defined for the state basis Rainy season)

5	Roadsigns	Retro-reflectometer	At least twice a year(As per survey
			Months defined for the state basis
			rainy season)

The first testing with the help of NSV shall be conducted at the time of issue of Completion Certificate

Schedule - L

(See Clause 12.2)

Completion Certificate

1.	I,
2.	It is certified that, in terms of the aforesaid Agreement, all works forming part of Project Highway have been completed, and the Project Highway is hereby declared fir for entry into operation on this the day of 20
	SIGNED, SEALED AND DELIVERED
	For and on behalf of the Authority's Engineer by:
	(Signature)
	(Name)
	(Designation) (Address)

Schedule - M

(See Clauses 14.6, 15.2 and 19.7)

Payment Reduction for Non-Compliance

1. Payment reduction for non-compliance with the Maintenance Requirements

- (i) Monthly lump sum payments for maintenance shall be reduced in the case of noncompliance with the Maintenance Requirements set forth in Schedule-E.
- (ii) Any deduction made on account of non-compliance with the Maintenance Requirements shall not be paid even after compliance subsequently. The deductions shall continue to be made every month until compliance is done.
- (iii) The Authority's Engineer shall calculate the amount of payment reduction on the basis of weightage in percentage assigned to non-conforming items as given in Paragraph 2.

2. Percentage reductions in lump sum payments on monthly basis

(i) The following percentages shall govern the payment reduction:

Sl. No.	Item / Defect / Deficiency	Percentage
(a)	Carriageway / Pavement	
(i)	Potholes, cracks, other surface defects	15%
(ii)	Repairs of Edges, Rutting	5%
(b)	Road, Embankment, Cuttings, Shoulders	
(i)	Edge drop, inadequate cross fall, undulations, settlement, potholes, ponding, obstructions	10%
(ii)	Deficient slopes, rain cuts, disturbed pitching, vegetation growth, pruning of trees	5%
(c)	Bridges and Culverts	
(i)	Desilting, cleaning. vegetation growth, damaged pitching, flooring, parapets, wearing course, footpaths, any damage to foundations	20%
(ii)	Any Defects in superstructures, bearings and sub-structures	10%
(iii)	Painting, repairs / replacement kerbs, railings, parapets,	5%

Sl. No.	Item / Defect / Deficiency	Percentage
	guideposts / crash barriers	
(d)	Roadside Drains	
(i)	Cleaning and repair of drains	5%
(e)	Road Furniture	
(i)	Cleaning, painting, replacement of road signs, delineators, road markings, 200 m / km / 5th km stones	5%
(f)	Miscellaneous Items	
(i)	Removal of dead animals, broken down / accidented vehicles, fallen trees, road blockades or malfunctioning of mobile crane	10%
(ii)	Any other Defects in accordance with paragraph 1.	5%
(g)	Defects in Other Project Facilities	5%

2.1 The amount to be deducted from monthly lump-sum payment for non- compliance of particular item shall be calculated as under:

$$R = P/_{100} \times (M1 \text{ or } M2) \times L^{1}/_{L}$$

Where,

P= Percentage of particular item / Defect / deficiency for deduction

M1= Monthly lump-sum payment in accordance para 1.2 above of this Schedule

M2= Monthly lump-sum payment in accordance para 1.2 above of this Schedule

L1= Non-complying length

L = Total length of the road,

R= Reduction (the amount to be deducted for non-compliance for a particular item / Defect / deficiency

The total amount of reduction shall be arrived at by summation of reductions for such items / Defects / deficiency or non-compliance.

For any Defect in a part of one kilometre, the non-conforming length shall be taken as one kilometre.

Schedule - N

(See Clause 18.1 (i))

Selection of Authority's Engineer

1. Selection of Authority's Engineer

- 1.1 The provisions of the Model Request for Proposal for Selection of Technical Consultants, issued by the Ministry of Finance in May 2009, or any substitute thereof shall apply for selection of an experienced firm to discharge the functions and duties of an Authority's Engineer.
- 1.2 In the event of termination of the Technical Consultants appointed in accordance with the provisions of Paragraph 1.1, the Authority shall appoint another firm of Technical Consultants forthwith and may engage a government-owned entity in accordance with the provisions of Paragraph 3 of this Schedule-N.

2. Terms of Reference

2.1 The Terms of Reference for the Authority's Engineer (the "TOR") shall substantially conform with Annex 1 to this Schedule N.

3. Appointment of Government entity as Authority's Engineer

Notwithstanding anything to the contrary contained in this Schedule, the Authority may in its discretion appoint a government-owned entity as the Authority's Engineer; provided that such entity shall be a body corporate having as one of its primary functions the provision of consulting, advisory and supervisory services for engineering projects; provided further that a government-owned entity which is owned or controlled by the Authority shall not be eligible for appointment as Authority's Engineer.

Annex - I

(Schedule - N)

Terms of Reference for Authority's Engineer

1. Scope

- - # In case the bid of Authority's Engineer is invited simultaneously with the bid of EPC project, then the status of bidding of EPC project only to be indicated
- 1.2. The TOR shall apply to construction and maintenance of the Project Highway.

2. Definitions and interpretation

- 2.1 The words and expressions beginning with or in capital letters and not defined herein but defined in the Agreement shall have, unless repugnant to the context, the meaning respectively assigned to them in the Agreement.
- 2.2 References to Articles, Clauses and Schedules in this TOR shall, except where the context otherwise requires, be deemed to be references to the Articles, Clauses and Schedules of the Agreement, and references to Paragraphs shall be deemed to be references to Paragraphs of this TOR.
- 2.3 The rules of interpretation stated in Article 1 of the Agreement shall apply, mutatis mutandis, to this TOR.

3. General

- 3.1 The Authority's Engineer shall discharge its duties in a fair, impartial and efficient manner, consistent with the highest standards of professional integrity and Good Industry Practice.
- 3.2 The Authority's Engineer shall perform the duties and exercise the authority in accordance with the provisions of this Agreement, but subject to obtaining prior written approval of the Authority before determining:

- (a) any Time Extension;
- (b) any additional cost to be paid by the Authority to the Contractor;
- (c) the Termination Payment; or
- (d) issuance of Completion Certificate or
- (e) any other matter which is not specified in (a), (b), (c) or (d) above and which creates a financial liability on either Party.
- 3.3 The Authority's Engineer shall submit regular periodic reports, at least once every month, to the Authority in respect of its duties and functions under this Agreement. Such reports shall be submitted by the Authority's Engineer within 10 (ten) days of the beginning of every month.
- 3.4 The Authority's Engineer shall inform the Contractor of any delegation of its duties and responsibilities to its suitably qualified and experienced personnel; provided, however, that it shall not delegate the authority to refer any matter for the Authority's prior approval in accordance with the provisions of Clause 18.2.
- 3.5 The Authority's Engineer shall aid and advise the Authority on any proposal for Change of Scope under Article 13.
- 3.6 In the event of any disagreement between the Parties regarding the meaning, scope and nature of Good Industry Practice, as set forth in any provision of the Agreement, the Authority's Engineer shall specify such meaning, scope and nature by issuing a reasoned written statement relying on good industry practice and authentic literature.

4. Construction Period

4.1 During the Construction Period, the Authority's Engineer shall review and approve the Drawings furnished by the Contractor along with supporting data, including the geo-technical and hydrological investigations, characteristics of materials from borrow areas and quarry sites, topographical surveys, and the recommendations of the Safety Consultant in accordance with the provisions of Clause 10.1 (vi). The Authority's Engineer shall complete such review and approval and send its observations to the Authority and the Contractor within 15 (fifteen) days of receipt of such Drawings; provided, however that in case of a Major Bridge or Structure, the aforesaid period of 15 (fifteen) days may be extended upto 30 (thirty) days. In particular, such comments shall specify the conformity or otherwise of such Drawings with the Scope of the Project and Specifications and Standards.

- 4.2 The Authority's Engineer shall review and approve any revised Drawings sent to it by the Contractor and furnish its comments within 10 (ten) days of receiving such Drawings.
- 4.3 The Authority's Engineer shall review and approve the Quality Assurance Plan submitted by the Contractor and shall convey its comments to the Contractor within a period of 21 (twenty-one) days stating the modifications, if any, required thereto.
- 4.4 The Authority's Engineer shall complete the review and approve of the methodology proposed to be adopted by the Contractor for executing the Works and convey its comments to the Contractor within a period of 10 (ten) days from the date of receipt of the proposed methodology from the Contractor.
- 4.5 The Authority's Engineer shall grant written approval to the Contractor, where necessary, for interruption and diversion of the flow of traffic in the existing lane(s) of the Project Highway for purposes of maintenance during the Construction Period in accordance with the provisions of Clause 10.4.
- 4.6 The Authority's Engineer shall review the monthly progress report furnished by the Contractor and send its comments thereon to the Authority and the Contractor within 7 (seven) days of receipt of such report.
- 4.7 The Authority's Engineer shall inspect the Construction Works and the Project Highway and shall submit a monthly Inspection Report bringing out the results of inspections and the remedial action taken by the Contractor in respect of Defects or deficiencies. In particular, the Authority's Engineer shall include in its Inspection Report, the compliance of the recommendations made by the Safety Consultant.
- 4.8 The Authority's Engineer shall conduct the pre-construction review of manufacturer's test reports and standard samples of manufactured Materials, and such other Materials as the Authority's Engineer may require.
- 4.9 For determining that the Works conform to Specifications and Standards, the Authority's Engineer shall require the Contractor to carry out, or cause to be carried out, tests at such time and frequency and in such manner as specified in the Agreement and in accordance with Good Industry Practice for quality assurance. For purposes of this Paragraph 4 (ix), the tests specified in the IRC Special Publication-11 (Handbook of Quality Control for Construction of Roads and Runways) and the Specifications for Road and Bridge Works issued by MORTH (the "Quality Control Manuals") or any modification / substitution thereof shall be deemed to be tests conforming to Good Industry Practice for quality assurance.

- 4.10 The Authority's Engineer shall test check at least 50 (fifty) percent of the quantity or number of tests prescribed for each category or type of test for quality control by the Contractor.
- 4.11 The timing of tests referred to in Paragraph 4 (ix), and the criteria for acceptance / rejection of their results shall be determined by the Authority's Engineer in accordance with the Quality Control Manuals. The tests shall be undertaken on a random sample basis and shall be in addition to, and independent of, the tests that may be carried out by the Contractor for its own quality assurance in accordance with Good Industry Practice.
- 4.12 In the event that results of any tests conducted under Clause 11.10 establish any Defects or deficiencies in the Works, the Authority's Engineer shall require the Contractor to carry out remedial measures.
- 4.13 The Authority's Engineer may instruct the Contractor to execute any work which is urgently required for the safety of the Project Highway, whether because of an accident, unforeseeable event or otherwise; provided that in case of any work required on account of a Force Majeure Event, the provisions of Clause 21.6 shall apply.
- 4.14 In the event that the Contractor fails to achieve any of the Project Milestones, the Authority's Engineer shall undertake a review of the progress of construction and identify potential delays, if any. If the Authority's Engineer shall determine that completion of the Project Highway is not feasible within the time specified in the Agreement, it shall require the Contractor to indicate within 15 (fifteen) days the steps proposed to be taken to expedite progress, and the period within which the Project Completion Date shall be achieved. Upon receipt of a report from the Contractor, the Authority's Engineer shall review the same and send its comments to the Authority and the Contractor forthwith.
- 4.15 The Authority's Engineer shall obtain from the Contractor a copy of all the Contractor's quality control records and documents before the Completion Certificate is issued pursuant to Clause 12.2.
- 4.16 Authority's Engineer may recommend to the Authority suspension of the whole or part of the Works if the work threatens the safety of the Users and pedestrians. After the Contractor has carried out remedial measure, the Authority's Engineer shall inspect such remedial measures forthwith and make a report to the Authority recommending whether or not the suspension hereunder may be revoked.

- 4.17 In the event that the Contractor carries out any remedial measures to secure the safety of suspended works and Users, and requires the Authority's Engineer to inspect such works, the Authority's Engineer shall inspect the suspended works within 3 (three) days of receiving such notice, and make a report to the Authority forthwith, recommending whether or not such suspension may be revoked by the Authority.
- 4.18 The Authority's Engineer shall carry out, or cause to be carried out, all the Tests specified in Schedule-K and issue a Completion Certificate, as the case may be. For carrying out its functions under this Paragraph 4 (xviii) and all matters incidental thereto, the Authority's Engineer shall act under and in accordance with the provisions of Article 12 and Schedule-K.

5. Maintenance Period

- 5.1 The Authority's Engineer shall aid and advise the Contractor in the preparation of its monthly Maintenance Programme and for this purpose carry out a joint monthly inspection with the Contractor.
- 5.2 The Authority's Engineer shall undertake regular inspections, at least once every month, to evaluate compliance with the Maintenance Requirements and submit a Maintenance Inspection Report to the Authority and the Contractor.
- 5.3 The Authority's Engineer shall specify the tests, if any, that the Contractor shall carry out, or cause to be carried out, for the purpose of determining that the Project Highway is in conformity with the Maintenance Requirements. It shall monitor and review the results of such tests and the remedial measures, if any, taken by the Contractor in this behalf.
- 5.4 In respect of any defect or deficiency referred to in Paragraph 3 of Schedule- E, the Authority's Engineer shall, in conformity with Good Industry Practice, specify the permissible limit of deviation or deterioration with reference to the Specifications and Standards and shall also specify the time limit for repair or rectification of any deviation or deterioration beyond the permissible limit.
- 5.5 The Authority's Engineer shall examine the request of the Contractor for closure of any lane(s) of the Project Highway for undertaking maintenance / repair thereof, and shall grant permission with such modifications, as it may deem necessary, within 5 (five) days of receiving a request from the Contractor. Upon expiry of the permitted period of closure, the Authority's Engineer shall monitor the reopening of such lane(s), and in case of delay, determine the Damages payable by the Contractor to the Authority under Clause 14.5.

6. Determination of costs and time

- 6.1 The Authority's Engineer shall determine the costs, and / or their reasonableness, that are required to be determined by it under the Agreement.
- 6.2 The Authority's Engineer shall determine the period of Time Extension that is required to be determined by it under the Agreement.
- 6.3 The Authority's Engineer shall consult each Party in every case of determination in accordance with the provisions of Clause 18.5.

7. Payments

- 7.1 The Authority's Engineer shall withhold payments for the affected works for which the Contractor fails to revise and resubmit the Drawings to the Authority's Engineer in accordance with the provisions of Clause 10.2 (iv) (d).
- 7.2 Authority's Engineer shall -
- (a) within 10 (ten) days of receipt of the Stage Payment Statement from the Contractor pursuant to Clause 19.4, determine the amount due to the Contractor and recommend the release of 90 (ninety) percent of the amount so determined as part payment, pending issue of the Interim Payment Certificate; and
- (b) within 15 (fifteen) days of the receipt of the Stage Payment Statement referred to in Clause 19.4, deliver to the Authority and the Contractor an Interim Payment Certificate certifying the amount due and payable to the Contractor, after adjustments in accordance with the provisions of Clause 19.10.
- 7.3 The Authority's Engineer shall, within 15 (fifteen) days of receipt of the Monthly Maintenance Statement from the Contractor pursuant to Clause 19.6, verify the Contractor's monthly statement and certify the amount to be paid to the Contractor in accordance with the provisions of the Agreement.
- 7.4 The Authority's Engineer shall certify final payment within 30 (thirty) days of the receipt of the final payment statement of Maintenance in accordance with the provisions of Clause 19.16.

8. Other duties and functions

The Authority's Engineer shall perform all other duties and functions as specified in the Agreement.

9. Miscellaneous

- 9.1 A copy of all communications, comments, instructions, Drawings or Documents sent by the Authority's Engineer to the Contractor pursuant to this TOR, and a copy of all the test results with comments of the Authority's Engineer thereon, shall be furnished by the Authority's Engineer to the Authority forthwith.
- 9.2 The Authority's Engineer shall retain at least one copy each of all Drawings and Documents received by it, including 'as-built' Drawings, and keep them in its safe custody.
- 9.3 Within 90 (ninety) days of the Project Completion Date, the Authority's Engineer shall obtain a complete set of as-built Drawings, in 2 (two) hard copies and in micro film form or in such other medium as may be acceptable to the Authority, reflecting the Project Highway as actually designed, engineered and constructed, including an as-built survey illustrating the layout of the Project Highway and setback lines, if any, of the buildings and structures forming part of Project Facilities; and shall hand them over to the Authority against receipt thereof.
- 9.4 The Authority's Engineer, if called upon by the Authority or the Contractor or both, shall mediate and assist the Parties in arriving at an amicable settlement of any Dispute between the Parties.
- 9.5 The Authority's Engineer shall inform the Authority and the Contractor of any event of Contractor's Default within one week of its occurrence.

Schedule - O

(See Clauses 19.4 (i), 19.6 (i), and 19.8 (i))

Forms of Payment Statements

1. Stage Payment Statement for Works

The Stage Payment Statement for Works shall state:

- (a) the estimated amount for the Works executed in accordance with Clause 19.3(i) subsequent to the last claim;
- (b) amounts reflecting adjustments in price for the aforesaid claim;
- (c) the estimated amount of each Change of Scope Order executed subsequent to the last claim;
- (d) amounts reflecting adjustment in price, if any, for (c) above in accordance with the provisions of Clause 13.2 (iii) (a);
- (e) total of (a), (b), (c) and (d) above;
- (f) Deductions:
 - (i) Any amount to be deducted in accordance with the provisions of the Agreement except taxes;
 - (ii) Any amount towards deduction of taxes; and
 - (iii) Total of (i) and (ii) above.
- (g) Net claim: (e) (f) (iii);
- (h) The amounts received by the Contractor upto the last claim:
 - (i) For the Works executed (excluding Change of Scope orders);
 - (ii) For Change of Scope Orders, and
 - (iii) Taxes deducted

2. Monthly Maintenance Payment Statement

The monthly Statement for Maintenance Payment shall state:

- (a) the monthly payment admissible in accordance with the provisions of the Agreement;
- (b) the deductions for maintenance work not done;
- (c) net payment for maintenance due, (a) minus (b);
- (d) amounts reflecting adjustments in price under Clause 19.12; and
- (e) amount towards deduction of taxes

3. Contractor's claim for Damages

Note: The Contractor shall submit its claims in a form acceptable to the Authority.

Schedule - P

(See Clause 20.1)

Insurance

1. Insurance during Construction Period

- 1.1 The Contractor shall effect and maintain at its own cost, from the Appointed Date till the date of issue of the Completion Certificate, the following insurances for any loss or damage occurring on account of Non-Political Event of Force Majeure, malicious act, accidental damage, explosion, fire and terrorism:
 - (a) insurance of Works, Plant and Materials and an additional sum of [15 (fifteen)] per cent of such replacement cost to cover any additional costs of and incidental to the rectification of loss or damage including professional fees and the cost of demolishing and removing any part of the Works and of removing debris of whatsoever nature; and
 - (b) insurance for the Contractor's equipment and Documents brought onto the Site by the Contractor, for a sum sufficient to provide for their replacement at the Site.
 - 1.2 The insurance under sub para (a) and (b) of paragraph 1(i) above shall cover the Authority and the Contractor against all loss or damage from any cause arising under paragraph 1.1 other than risks which are not insurable at commercial terms.

2. Insurance for Contractor's Defects Liability

The Contractor shall effect and maintain insurance cover of not less than 15% of the Contract Price for the Works from the date of issue of the Completion Certificate until the end of the Defects Liability Period for any loss or damage for which the Contractor is liable and which arises from a cause occurring prior to the issue of the Completion Certificate. The Contractor shall also maintain other insurances for maximum sums as may be required under the Applicable Laws and in accordance with Good Industry Practice.

3. Insurance against injury to persons and damage to property

3.1 The Contractor shall insure against its liability for any loss, damage, death or bodily injury, or damage to any property (except things insured under Paragraphs 1 and 2 of this Schedule or to any person (except persons insured under Clause 20.9), which may arise out of the Contractor's performance of this Agreement. This

insurance shall be for a limit per occurrence of not less than the amount stated below with no limit on the number of occurrences.

The insurance cover shall be not less than: Rs. [*****]

- 3.2 The insurance shall be extended to cover liability for all loss and damage to the Authority's property arising out of the Contractor's performance of this Agreement excluding:
 - (a) the Authority's right to have the construction works executed on, over, under, in or through any land, and to occupy this land for the Works; and
 - (b) damage which is an unavoidable result of the Contractor's obligations to execute the Works.

4. Insurance to be in joint names

The insurance under paragraphs 1 to 3 above shall be in the joint names of the Contractor and the Authority.

Schedule - Q

(See Clause 14.10)

Tests on Completion of Maintenance Period

1. Riding Quality test:

Riding quality test: Riding quality of each lane of the carriageway shall be checked with the help of a calibrated bump integrator and the maximum permissible roughness for purposes of this Test shall be [2,200 (two thousand and two hundred only)] mm for each kilometre.

2. Visual and physical test:

The Authority's Engineer shall conduct a visual and physical check of construction to determine that all works and equipment forming part thereof conform to the provisions of this Agreement. The physical tests shall include measurement of cracking, rutting, stripping and potholes and shall be as per the requirement of maintenance mentioned in Schedule-E.