

RO/DDN/NH-134/STMC/S-B/24-25/ 6091

Dated: 24.02.2025

Corrigendum-I

To,

All Prospective Bidder's

Sub: Short term maintenance for one time Improvement of Road Quality Work from Km- 25.400 to 51.000(Near Silkyara Bend to Barkot Tunnel Portal) on NH-134 in the State of Uttarakhand (Part-02).

Tender I D- 2025_NHIDC_850078_1

Following is the revised provision in the tender documents:

S. No.	Reference of tender documents	Existing Provision as per RFP/NIT	Modified Provision
(i)	Section-2 Instructions to Bidder (ITB) F. Award of Contract Clause-32.5	The agreement will be executed within 10 days of receipt of Performance Security.	The agreement will be executed within 07 days of receipt of Performance Security.
(ii)	Section-5 General Conditions of Contract Clause-9.1	The Contractor shall employ the technical personnel named in the Contract Data or other technical persons approved by the Engineer. The Engineer will approve any proposed replacement of technical personnel only if the irrelevant qualifications and abilities are substantially equal to or better than those of the personnel stated in the Contract Data. If the personnel stated in the Contract Data are not deployed on site by the Contractor within 15 days of issue of notice to proceed with the work, a penalty of 5000/- per day per person shall be levied for next 30days, beyond which it shall be treated as a breach of Contract and action will be taken as per Clause51	The Contractor shall employ the technical personnel named in the Contract Data or other technical persons approved by the Engineer. The Engineer will approve any proposed replacement of technical personnel only if the irrelevant qualifications and abilities are substantially equal to or better than those of the personnel stated in the Contract Data. If the personnel stated in the Contract Data are not deployed on site by the Contractor within 07 days of issue of notice to proceed with the work, a penalty of 5000/- per day per person shall be levied for next 30days, beyond which it shall be treated as a breach of Contract and action will be taken as per Clause51

Y4
[Signature]

(iii)	Section-5 General Conditions of Contract Clause-24.1	The Engineer may instruct the Contractor to delay the start or progress of any activity within the Works. Delay/delays totaling more than 30 days will require prior written approval of the Employer.	The Engineer may instruct the Contractor to delay the start or progress of any activity within the Works. Delay/delays totaling more than 15 days will require prior written approval of the Employer.
(iv)	Section-5 General Conditions of Contract Clause-41 Advance Payment	<p>41.1 The Employer will make an interest bearing advance payment to the Contractor against provision by the Contractor of an Unconditional Bank Guarantee in a form and by a bank acceptable to the Employer in amounts equal to the advance payment up to 10% of Contract Price. The guarantee shall remain effective until the advance payment has been repaid, but the amount of the guarantee shall be progressively reduced by the amounts repaid by the Contractor. The Contractor shall take the above advance before 2nd running bill and if the contractor delays seeking the advance, the same is not payable.</p> <p>41.2 The Contractor is to use the advance payment only to pay for Equipment, plant and Mobilization expenses required specifically for execution of the Works. The Contractor shall demonstrate that the advance payment has been used in this way by supplying copies of invoices or other documents to the Engineer.</p> <p>41.3 The advance payment shall be repaid with interest @ SBI PLR applicable on the date of release of mobilisation advance, by deducting from payments otherwise due to the Contractor. The mobilisation advance will be recovered from third running bill upto 8th running bill in six equal</p>	Deleted



		installments and the interest will be recovered from 9th bill. In any case, the mobilisation advance with interest must be recovered within ten months from the date of agreement. No account shall be taken of the advance payment or its repayment in assessing valuations of work done, Variations, Compensation Events, or Liquidated Damages.	
(v)	Section-5 General Conditions of Contract Clause-48 Termination	(j) if the Contractor does not deploy any of the personnel stated in Contract Data within 45days of issue of notice to proceed;	if the Contractor does not deploy any of the personnel stated in Contract Data within 15 days of issue of notice to proceed;
(vi)	Contract Data Clause-05	The Start Date shall be within 15 days from the date of issue of the Notice to proceed with the work.	The Start Date shall be within 07 days from the date of issue of the Notice to proceed with the work. Trial run of HMP shall be ensured within this period, failing which damage as specified in clause 17 of the Contract Data will be applicable.
(vii)	Contract Data Clause-13	The period for submission of the programme for approval of Engineer shall be 30 days from the issue of Letter of Commencement.	The period for submission of the programme for approval of Engineer shall be 07days from the issue of Letter of Commencement.
(viii)	Contract Data Clause-15	The period for setting up a field laboratory with the prescribed equipment Relevant to items of work in BOQ is 30 days from the date of notice to start work.	The period for setting up a field laboratory with the prescribed equipment Relevant to items of work in BOQ is 15 days from the date of notice to start work.
(ix)	BOQ (item no.01)	Dense Graded Bituminous Macadam (Providing and laying dense bituminous macadam with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.0 to 4.5% by weight of total mix of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per	Dense Graded Bituminous Macadam (Providing and laying dense bituminous macadam with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.0 to 4.5% by weight of total mix of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRT&H specification clause No. 507 complete in all respects.) for GradingII(19 mm nominal size)



		MoRT&H specification clause No. 507 complete in all respects.) for Grading II (19 mm nominal size) Unit-Sqm	Unit-Cum
(x)	BOQ (item no.02)	Tack coat Providing and applying tack coat with with bitumen VG-10 grade pressure distributor Over dry and hungry bituminous surfaces @0.40 kg/sqm cleaned with mechanical broom. Unit-Cum	Tack coat Providing and applying tack coat with with bitumen VG-10 grade pressure distributor Over dry and hungry bituminous surfaces @0.40 kg/sqm cleaned with mechanical broom. Unit-Sqm
(xi)	Pre-Bid Meeting	24.02.2025@17:00Hrs	25.02.2025@17:00Hrs



(Raj Kishor Singh)
General Manager (P)
NHIDCL, RO-Dehradun, Uttarakhand