

# Corrigendum No.8

NHIDCL/ Civil work/Hayuliang-Hawai (0-17)/Ar.Pr./2016

Date: 13.10.2016

To,

All the prospective bidders

Subject: "T/o-Laning of Existing Khupa - Hayuliang - Hawai Road on EPC basis from design Km. 0.000 (Khupa) to Km. 17.000 [Existing Km 95.800 of (Khupa - Hayuliang Road) to Km 8.970 (Hayuliang - Hawai Road)] in the state of Arunachal Pradesh Under SARDP-NE, Project Highway-Corrigendum regarding Schedule A, Schedule B and Schedule F

Sir,

The following modifications have been made:

## As Existing

Annexure-II Schedule A	Sl. No	Design Chainage		Length	Width (m)	Date of Providing ROW
		From	To			
		(i) Full Right of way (full width)	0.00 15.000	15.000	18-24 (as shown in Schedule B, clause 2.4)	At Appointed date
	(ii) Balance Right of way (width)	15.000	17.000	2.000	18-24.0 (as shown in Schedule B, clause 2.4)	Within 90 days after the appointed Date

## As Modified

	Sl. No	Design Chainage		Length	Width (m)	Date of Providing ROW
		From	To			
		(i) Full Right of way (full width)	0.000 17.000	17.00	18-24 (as shown in Schedule B, clause 2.4)	90 % at appointed date
	(ii) Balance Right of way (width)	-	-	-	-	Within 90 days after the appointed Date as per clause 8.2 of DCA

Schedule B clause 11 i.e Hazardous locations	Sl No	Type of protection work	Minimum Length (m)	Height(range in M)	Remarks
	1	Parapet wall on valley side	7064		As per IRC SP:48- 1998
	2	W Beam Crash Barrier	4155		
	3.	Breast Wall	4239	2-6 m	
	4.	Retaining Wall	4946	2-4 m	
	5	Gabion wall	990	2-4m	
Annexure IV Schedule A	Environmental Clearances The project Highway does not required Environment Clearance as per MoEF corrigendum dated 22.08.2013				
Schedule F (New Clause to be added	<p>Environmental Clearances</p> <p>The project Highway does not required Environment Clearance as per MoEF corrigendum dated 22.08.2013.</p> <p>In addition, the ALP for the project has been received. The Final approval is yet to be received. Temporary working provision will be ensured before appointed date. All conditions imposed by MoEF while issuing the Approval in Principle(ALP) and final forest clearance(FC) to be adhered during construction stage and after construction stage are to be complied with.</p> <p>The muck dumping sites in forest area stand identified and freezed by Forest department to be abided by agency during dumping of muck as stated in Schedule 'F'</p> <p>2. The agency need to ensure compliance of ALP and FC stated in Schedule 'A' Annexure-IV. The necessary certifications need to be obtained from competent local forest department.</p> <p>3. Muck dumping locations in forest area to be freezed in consultation with the forest department, the necessary certifications from local competent forest department is to be submitted.</p>				

Sl No	Type of protection work	Minimum Length (m)	Height(range in M)	Remarks
1	Parapet wall on valley side	7064		
2	W Beam Crash Barrier	4155		
3.	Breast Wall	4239	2-6 m	
4.	Retaining Wall	4946	2-4 m	
5	Gabion wall	990	2-4m	As per manual and codes

  
 Y.C Srivastava  
 GM(T)