

## **Schedules**

**Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”**

---

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

---

---

## SCHEDULE - A

*(See Clauses 2.1 and 8.1)*

### SITE OF THE PROJECT

#### 1. The Site

- 1.1 Site of the Two-Laning of Existing Merangkong-Tamlu-Mon Road on EPC basis from Existing Km 73+640 to Km 98+065 (Design Km 63+800 to Km 86+835) in the state of Nagaland under SARDP-NE, Project Highway shall include the land, buildings, structures and road works as described in Annex-I of this Schedule-A.

The Project alignment is approachable for all locations for execution of works.

- 1.2 The dates of handing over the Right of Way to the Contractor are specified in Annex-II of this Schedule-A.

- 1.3 An inventory of the Site including the land, buildings, structures, road works, trees and any other immovable property on, or attached to, the Site shall be prepared jointly by the Authority's Representative and the Contractor, and such inventory shall form part of the memorandum referred to in Clause 8.2.1 of this Agreement.

- 1.4 The alignment plans of the Project Highway are specified in Annex-III. In the case of Sections where no modification in the existing alignment of the Project Highway is contemplated, the alignment plan has not been provided. Alignment plans have only been given for sections where the existing alignment is proposed to be upgraded. The proposed profile of the Project Highways shall be followed by the contractor with minimum FRL as indicated in the alignment plan. The Contractor, however, may improve/upgrade the road profile as indicated in Annexure-III based on site/design requirement.

- 1.5 The status of the environment clearances obtained or awaited is given in Annex-IV.
-

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

## ANNEXURE - I

### 1. The Site

The Existing Merangkong-Tamlu-Mon Road is 98.065 Km in length and after DPR Preparation the designated length is 86.835 Km. The complete road has been divided into four Packages for construction. The packages are as follows-

S.No.	Package Name	Existing Chainage(Km)		Design Chainage(Km)		Design Length (Km)
		From	To	From	To	
1	Package-4	73+640	98+065	63+800	86+835	23.035

The site for the instant work i.e.Design Km 63.800 to design Km 86.835 is either single lane or proposed for re-alignments. The Site of the [Single Lane / Two Lane] Project Highway comprises of Merangkong - Tamlu - Mon Road commencing from Existing Km 73.640 to Km 98.065 (Design Km 63+800 to Km 86+835) in the state of Nagaland. The road is of sub-standard single lane / Two Lane with poor / fair road surface, passing through mountainous/steep terrain, in general. The road is deficient in geometric features at almost all locations. The stretch lies within Mokochung, Longleng and Mon districts of Nagaland State.

The project corridor passes through Tanhai, Lengnyu and Mon Town.

There are certain stretches along Project Highway wherein construction activities partially (Earthwork in excavation, Earthwork in embankment, Subgrade, GSB, WMM, DBM, Box Culvert & Retaining Wall) have been commenced by agency under previously awarded terminated works.

The consolidated statement of Existing Chainage, Design Chainage, Improvement Proposal and Construction carried out fully or partially by Previous Contractor is as tabulated below-

Sl. No.	Existing Chainage		Length	Design Chainage		Length	Improvement Proposal	Details of Work done by Previous Contractor	Remarks
	From	To		From	To				
1	73+410	73+960	550	63+800	63+820	20.000	Widening & Strengthening	GSB	Profile corrective course, Camber correction, Desirable thickness & width of present layer shall be done by the
2				63+820	63+910	90.000	Widening & Strengthening	DBM	
3				63+910	63+950	40.000	Widening & Strengthening	DBM	
4				63+950	63+970	20.000	Widening & Strengthening	WMM	

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sl. No.	Existing Chainage		Length	Design Chainage		Length	Improvement Proposal	Details of Work done by Previous Contractor	Remarks
	From	To		From	To				
5				63+970	64+040	70.000	Widening & Strengthening	Subgrade	contractor to be appointed
6				64+040	64+060	20.000	Widening & Strengthening	Subgrade	
7				64+060	64+330	270.000	Widening & Strengthening	WMM	
8	73+960	73+995	35	64+330	64+340	10.000	Realignment	GSB	
9				64+340	64+360	20.000	Realignment	GSB	
10	73+995	74+090	95	64+360	64+450	90.000	Widening & Strengthening	WMM	
11	74+090	74+160	70	64+450	64+480	30.000	Realignment	WMM	
12				64+480	64+510	30.000	Realignment	WMM	
13				64+510	64+520	10.000	Widening & Strengthening	WMM	
14				64+520	64+550	30.000	Widening & Strengthening	WMM	
15	74+160	74+330	170	64+550	64+570	20.000	Widening & Strengthening	WMM	
16				64+570	64+630	60.000	Widening & Strengthening	WMM	
17				64+630	64+660	30.000	Widening & Strengthening	WMM	
18	74+330	74+430	100	64+660	64+670	10.000	Realignment	GSB	
19				64+670	64+750	80.000	Realignment	Subgrade	
20				64+750	64+790	40.000	Widening & Strengthening	GSB	
21	74+430	74+920	490	64+790	64+810	20.000	Widening & Strengthening	Subgrade	
22				64+810	64+818	8.000	Widening & Strengthening	GSB	
23				64+818	64+9	162.00	Widening &	WMM	

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sl. No.	Existing Chainage		Length	Design Chainage		Length	Improvement Proposal	Details of Work done by Previous Contractor	Remarks
	From	To		From	To				
				18	80	0	Strengthening		
24				64+980	65+100	120.000	Widening & Strengthening	DBM	
25				65+100	65+120	20.000	Widening & Strengthening	WMM	
26				65+120	65+130	10.000	Widening & Strengthening	GSB	
27				65+130	65+230	100.000	Widening & Strengthening	WMM	
28				65+230	65+245	15.000	Widening & Strengthening	WMM	
29	74+920	74+960	40	65+245	65+275	30.000	Realignment	WMM	
30				65+275	65+400	125.000	Widening & Strengthening	WMM	
31				65+400	65+440	40.000	Widening & Strengthening	WMM	
32	74+960	75+280	320	65+440	65+580	140.000	Widening & Strengthening	WMM	
33				65+580	65+600	20.000	Widening & Strengthening	DBM	
34				65+600	65+620	20.000	Realignment	DBM	
35				65+620	65+710	90.000	Realignment	DBM	
36				65+710	65+915	205.000	Widening & Strengthening	DBM	
37	75+280	75+410	130	65+915	66+170	255.000	Widening & Strengthening	DBM	
38				66+170	66+200	30.000	Widening & Strengthening	DBM	
39				66+200	66+300	100.000	Widening & Strengthening	DBM	
40				66+300	66+510	210.000	Widening & Strengthening	WMM	

Profile corrective course, Camber correction, Desirable thickness & width of present layer shall be done by the contractor to be appointed

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sl. No.	Existing Chainage		Length	Design Chainage		Length	Improvement Proposal	Details of Work done by Previous Contractor	Remarks
	From	To		From	To				
							g		
41				66+510	66+530	20.000	Widening & Strengthening	Subgrade	
42				66+530	66+700	170.000	Widening & Strengthening	GSB	
43	75+410	76+480	1070	66+700	66+720	20.000	Widening & Strengthening	GSB	
44				66+720	66+850	130.000	Realignment	GSB	
45	76+480	76+710	230	66+850	66+900	50.000	Realignment	WMM	
46				66+900	66+930	30.000	Realignment	WMM	
47				66+930	66+940	10.000	Widening & Strengthening	WMM	
48	76+710	76+830	120	66+940	67+040	100.000	Widening & Strengthening	WMM	
49				67+040	67+050	10.000	Widening & Strengthening	Subgrade	
50				67+050	67+160	110.000	Realignment	GSB	
51	76+830	77+000	170	67+160	67+190	30.000	Realignment	GSB	
52				67+190	67+200	10.000	Realignment	Subgrade	
53				67+200	67+300	100.000	Widening & Strengthening	GSB	
54	77+000	77+200	200	67+300	67+330	30.000	Widening & Strengthening	Subgrade	
55				67+330	67+390	60.000	Widening & Strengthening	WMM	
56	77+200	77+265	65	67+390	67+420	30.000	Realignment	Subgrade	
57				67+420	67+445	25.000	Realignment	GSB	
58	77+265	77+420	155	67+445	67+470	25.000	Widening & Strengthening	GSB	
59				67+470	67+605	135.000	Widening & Strengthening	WMM	Profile Corrective

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sl. No.	Existing Chainage		Length	Design Chainage		Length	Improvement Proposal	Details of Work done by Previous Contractor	Remarks
	From	To		From	To				
							g		course, Camber Correction, Desirable thickness & width of present layer shall be done by the contractor to be appointed
60	77+420	77+500	80	67+605	67+670	65.000	Realignment	Subgrade	
61	77+500	77+520	20	67+670	67+700	30.000	Realignment	WMM	
62	77+520	77+620	100	67+700	67+760	60.000	Widening & Strengthening	WMM	
63				67+760	67+810	50.000	Widening & Strengthening	WMM	
64	77+620	77+820	200	67+810	67+880	70.000	Realignment	WMM	
65				67+880	67+900	20.000	Widening & Strengthening	GSB	
66				67+900	67+920	20.000	Realignment	WMM	
67				67+920	67+960	40.000	Realignment	WMM	
68	77+820	77+890	70	67+960	67+980	20.000	Widening & Strengthening	WMM	
69				67+980	68+005	25.000	Widening & Strengthening	WMM	
70				68+005	68+010	5.000	Widening & Strengthening	WMM	
71				68+010	68+030	20.000	Widening & Strengthening	WMM	
72	77+890	77+920	30	68+030	68+060	30.000	Realignment	WMM	
73	77+920	78+000	80	68+060	68+120	60.000	Widening & Strengthening	WMM	
74				68+120	68+150	30.000	Widening & Strengthening	WMM	
75	78+000	78+270	270	68+150	68+215	65.000	Widening & Strengthening	WMM	
76				68+215	68+285	70.000	Widening & Strengthening	WMM	
77				68+285	68+405	120.000	Widening & Strengthening	DBM	



Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sl. No.	Existing Chainage		Length	Design Chainage		Length	Improvement Proposal	Details of Work done by Previous Contractor	Remarks
	From	To		From	To				
78	78+270	78+320	50	68+405	68+450	45.000	Realignment	WMM	
79	78+320	78+360	40	68+450	68+495	45.000	Widening & Strengthening	DBM	
80	78+360	78+470	110	68+495	68+500	5.000	Realignment	DBM	
81				68+500	68+550	50.000	Realignment	WMM	
82				68+550	68+595	45.000	Realignment	GSB	
83	78+470	79+000	530	68+595	68+630	35.000	Widening & Strengthening	GSB	
84				68+630	68+650	20.000	Widening & Strengthening	WMM	
85				68+650	68+720	70.000	Widening & Strengthening	DBM	
86				68+720	68+740	20.000	Widening & Strengthening	WMM	
87				68+740	68+750	10.000	Widening & Strengthening	Subgrade	
88				68+750	68+780	30.000	Widening & Strengthening	GSB	
89				68+780	68+800	20.000	Widening & Strengthening	WMM	
90				68+800	68+910	110.000	Widening & Strengthening	WMM	
91				68+910	68+930	20.000	Widening & Strengthening	Subgrade	
92				68+930	68+960	30.000	Widening & Strengthening	GSB	
93	79+000	79+060	60	68+960	69+000	40.000	Widening & Strengthening	DBM	
94				69+000	69+030	30.000	Widening & Strengthening	GSB	
95				69+030	69+040	10.000	Widening & Strengthening	Subgrade	

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sl. No.	Existing Chainage		Length	Design Chainage		Length	Improvement Proposal	Details of Work done by Previous Contractor	Remarks
	From	To		From	To				
							g		
96				69+040	69+060	20.000	Widening & Strengthening	GSB	
97				69+060	69+120	60.000	Widening & Strengthening	DBM	
98				69+120	69+130	10.000	Widening & Strengthening	Subgrade	
99				69+130	69+140	10.000	Realignment	Subgrade	Profile Corrective course, Camber Correction, Desirable thickness & width of present layer shall be done by the contractor to be appointed
100				69+140	69+180	40.000	Realignment	WMM	
101	79+000	79+130	130	69+180	69+210	30.000	Realignment	Subgrade	
102				69+210	69+220	10.000	Realignment	GSB	
103				69+220	69+245	25.000	Realignment	WMM	
104	79+130	79+220	90	69+245	69+320	75.000	Widening & Strengthening	DBM	
105				69+320	69+330	10.000	Widening & Strengthening	WMM	
106	79+220	79+270	50	69+330	69+375	45.000	Realignment	Subgrade	
107				69+375	69+400	25.000	Widening & Strengthening	Subgrade	
108	79+270	79+440	170	69+400	69+480	80.000	Widening & Strengthening	WMM	
109				69+480	69+550	70.000	Widening & Strengthening	DBM	
110	79+440	79+570	130	69+550	69+590	40.000	Realignment	WMM	
111				69+590	69+650	60.000	Realignment	Subgrade	
112				69+650	69+660	10.000	Widening & Strengthening	Subgrade	
113	79+570	79+670	100	69+660	69+680	20.000	Widening & Strengthening	WMM	
114				69+680	69+740	60.000	Widening & Strengthening	DBM	

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sl. No.	Existing Chainage		Length	Design Chainage		Length	Improvement Proposal	Details of Work done by Previous Contractor	Remarks
	From	To		From	To				
							g		
115	79+6 70	79+8 60	190	69+7 40	69+8 00	60.000	Realignment	WMM	Profile Corrective course, Camber Correction, Desirable thickness & width of present layer shall be done by
116				69+8 00	69+8 40	40.000	Realignment	Subgrade	
117				69+8 40	69+8 80	40.000	Realignment	WMM	
118				69+8 80	69+9 10	30.000	Realignment	WMM	
119	79+8 60	80+0 20	160	69+9 10	69+9 20	10.000	Widening & Strengthenin g	GSB	
120				69+9 20	69+9 40	20.000	Widening & Strengthenin g	Subgrade	
121				69+9 40	69+9 50	10.000	Widening & Strengthenin g	WMM	
122				69+9 50	70+0 50	100.00 0	Widening & Strengthenin g	DBM	
123	80+0 20	80+0 80	60	70+0 50	70+1 20	70.000	Widening & Strengthenin g	DBM	
124				70+1 20	70+1 35	15.000	Widening & Strengthenin g	WMM	
125	80+0 80	80+1 60	80	70+1 35	70+1 50	15.000	Realignment	WMM	
126				70+1 50	70+1 90	40.000	Realignment	WMM	
127	80+1 60	80+2 20	60	70+1 90	70+2 40	50.000	Widening & Strengthenin g	WMM	
128				70+2 40	70+2 50	10.000	Widening & Strengthenin g	WMM	
129	80+2 20	80+3 70	150	70+2 50	70+2 80	30.000	Realignment	WMM	
130				70+2 80	70+3 10	30.000	Realignment	WMM	
131	80+3 70	80+5 30	160	70+3 10	70+3 40	30.000	Widening & Strengthenin g	WMM	
132				70+3 40	70+3 50	10.000	Widening & Strengthenin g	Subgrade	
133				70+3 50	70+4 50	100.00 0	Widening & Strengthenin	WMM	

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sl. No.	Existing Chainage		Lengt h	Design Chainage		Lengt h	Improvemen t Proposal	Details of Work done by Previous Contractor	Remarks
	From	To		From	To				
							g		the contractor to be appointed
134				70+450	70+475	25.000	Widening & Strengthenin g	WMM	
135	80+530	80+590	60	70+475	70+515	40.000	Realignment	WMM	
136	80+590	80+860	270	70+515	70+540	25.000	Widening & Strengthenin g	WMM	
137				70+540	70+590	50.000	Widening & Strengthenin g	Subgrade	
138				70+590	70+670	80.000	Widening & Strengthenin g	WMM	
139				70+670	70+720	50.000	Widening & Strengthenin g	WMM	
140				70+720	70+750	30.000	Widening & Strengthenin g	GSB	
141				70+750	70+790	40.000	Widening & Strengthenin g	WMM	
142	80+860	81+220	360	70+790	70+800	10.000	Realignment	WMM	
143				70+800	70+840	40.000	Realignment	WMM	
144				70+840	71+020	180.000	Realignment	Subgrade	
145				71+020	71+060	40.000	Realignment	GSB	
146	81+220	81+470	250	71+060	71+080	20.000	Widening & Strengthenin g	GSB	
147				71+080	71+150	70.000	Widening & Strengthenin g	GSB	
148				71+150	71+300	150.000	Widening & Strengtheni ng	WMM	
149	81+470	81+585	115	71+300	71+360	60.000	Realignment	GSB	
150				71+360	71+390	30.000	Realignment	GSB	
151				71+390	71+400	10.000	Realignment	GSB	
152	81+585	81+620	35	71+400	71+440	40.000	Widening & Strengthenin	Subgrade	

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sl. No.	Existing Chainage		Length	Design Chainage		Length	Improvement Proposal	Details of Work done by Previous Contractor	Remarks
	From	To		From	To				
							g		
153	81+620	81+690	70	71+440	71+500	60.000	Realignment	WMM	
154				71+500	71+520	20.000	Widening & Strengthening	GSB	
155				71+520	71+640	120.000	Widening & Strengthening	GSB	
156	81+690	82+000	310	71+640	71+660	20.000	Widening & Strengthening	Subgrade	
157				71+660	71+700	40.000	Widening & Strengthening	GSB	
158				71+700	71+780	80.000	Widening & Strengthening	WMM	
159	82+000	82+125	125	71+780	71+830	50.000	Widening & Strengthening	GSB	
160				71+830	71+850	20.000	Widening & Strengthening	Subgrade	
161	82+125	82+320	195	71+850	71+980	130.000	Widening & Strengthening	GSB	
162				71+980	72+050	70.000	Realignment	Subgrade	
163				72+050	72+150	100.000	Realignment	WMM	
164				72+150	72+310	160.000	Widening & Strengthening	WMM	
165				72+310	72+450	140.000	Widening & Strengthening	WMM	
166	82+320	83+040	720	72+450	72+480	30.000	Widening & Strengthening	GSB	
167				72+480	72+500	20.000	Widening & Strengthening	Subgrade	
168				72+500	72+570	70.000	Widening & Strengthening	Subgrade	
169				72+570	72+590	20.000	Widening & Strengthening	Subgrade	

Profile Corrective course, Camber Correction, Desirable thickness & width of present layer shall be done by the contractor to be appointed

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sl. No.	Existing Chainage		Length	Design Chainage		Length	Improvement Proposal	Details of Work done by Previous Contractor	Remarks
	From	To		From	To				
170				72+590	72+640	50.000	Widening & Strengthening	Subgrade	
171				72+640	72+660	20.000	Widening & Strengthening	Subgrade	
172				72+660	72+760	100.000	Widening & Strengthening	Subgrade	
173				72+760	72+780	20.000	Widening & Strengthening	Subgrade	
174				72+780	72+800	20.000	Widening & Strengthening	WMM	
175	83+040	83+120	80	72+800	72+865	65.000	Realignment	WMM	Profile Corrective
176	83+120	83+220	100	72+865	72+930	65.000	Widening & Strengthening	WMM	
177				72+930	72+965	35.000	Widening & Strengthening	WMM	
178	83+220	83+270	50	72+965	73+005	40.000	Realignment	WMM	
179	83+270	83+520	250	73+005	73+050	45.000	Widening & Strengthening	WMM	
180				73+050	73+060	10.000	Widening & Strengthening	WMM	
181				73+060	73+150	90.000	Widening & Strengthening	WMM	
182				73+150	73+230	80.000	Widening & Strengthening	GSB	
183	83+520	83+540	20	73+230	73+255	25.000	Widening & Strengthening	GSB	
184	83+540	83+600	60	73+255	73+305	50.000	Realignment	WMM	
185	83+600	83+940	340	73+305	73+330	25.000	Widening & Strengthening	GSB	
186				73+330	73+390	60.000	Widening & Strengthening	GSB	
187				73+390	73+410	20.000	Widening & Strengthening	Subgrade	

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sl. No.	Existing Chainage		Length	Design Chainage		Length	Improvement Proposal	Details of Work done by Previous Contractor	Remarks
	From	To		From	To				
				90	10		Strengthening		course, Camber Correction, Desirable thickness & width of present layer shall be done by the contractor to be appointed
188				73+410	73+515	105.000	Widening & Strengthening	WMM	
189				73+515	73+650	135.000	Widening & Strengthening	No Work Done	
190	83+940	84+090	150	73+650	73+690	40.000	Realignment	No Work Done	
191				73+690	73+760	70.000	Realignment	No Work Done	
192	84+090	84+180	90	73+760	73+830	70.000	Widening & Strengthening	No Work Done	
193				73+830	73+850	20.000	Widening & Strengthening	Subgrade	
194	84+180	84+240	60	73+850	73+905	55.000	Realignment	No Work Done	
195				73+905	73+930	25.000	Widening & Strengthening	GSB	
196				73+930	73+960	30.000	Widening & Strengthening	GSB	
197				73+960	73+980	20.000	Widening & Strengthening	GSB	
198				73+980	74+000	20.000	Widening & Strengthening	GSB	
199	84+240	84+600	360	74+000	74+100	100.000	Widening & Strengthening	No Work Done	
200				74+100	74+160	60.000	Widening & Strengthening	No Work Done	
201				74+160	74+180	20.000	Widening & Strengthening	No Work Done	
202				74+180	74+230	50.000	Widening & Strengthening	No Work Done	
203				74+230	74+250	20.000	Widening & Strengthening	No Work Done	
204				74+250	74+255	5.000	Widening & Strengthening	No Work Done	

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sl. No.	Existing Chainage		Length	Design Chainage		Length	Improvement Proposal	Details of Work done by Previous Contractor	Remarks
	From	To		From	To				
							g		
205	84+600	84+660	60	74+255	74+295	40.000	Realignment	No Work Done	Profile Corrective course, Camber Correction, Desirable thickness & width of present layer shall be done by the contractor to be appointed
206	84+660	85+060	400	74+295	74+410	115.000	Widening & Strengthening	No Work Done	
207				74+410	74+430	20.000	Widening & Strengthening	No Work Done	
208				74+430	74+610	180.000	Widening & Strengthening	No Work Done	
209				74+610	74+640	30.000	Widening & Strengthening	No Work Done	
210				74+640	74+735	95.000	Widening & Strengthening	No Work Done	
211	85+060	85+310	250	74+735	74+920	185.000	Realignment	No Work Done	
212	85+310	85+360	50	74+920	74+970	50.000	Widening & Strengthening	No Work Done	
213	85+360	85+770	410	74+970	75+000	30.000	Realignment	WMM	
214				75+000	75+240	240.000	Widening & Strengthening	WMM	
215	85+770	85+900	130	75+240	75+320	80.000	Widening & Strengthening	No Work Done	
216				75+320	75+390	70.000	Widening & Strengthening	No Work Done	
217	85+900	86+160	260	75+390	75+400	10.000	Realignment	Subgrade	
218				75+400	75+530	130.000	Realignment	WMM	
219				75+530	75+555	25.000	Realignment	Subgrade	
220	86+160	86+200	40	75+555	75+560	5.000	Widening & Strengthening	Subgrade	
221				75+560	75+600	40.000	Widening & Strengthening	GSB	
222	86+200	86+360	160	75+600	75+640	40.000	Realignment	WMM	
223				75+640	75+660	50.000	Realignment	WMM	



Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sl. No.	Existing Chainage		Length	Design Chainage		Length	Improvement Proposal	Details of Work done by Previous Contractor	Remarks
	From	To		From	To				
				40	90				
224	86+360	86+475	115	75+690	75+800	110.000	Widening & Strengthening	GSB	
225	86+475	86+570	95	75+800	75+870	70.000	Realignment	WMM	
226				75+870	75+920	50.000	Widening & Strengthening	GSB	
227				75+920	75+950	30.000	Widening & Strengthening	GSB	
228	86+570	86+750	180	75+950	75+960	10.000	Widening & Strengthening	GSB	
229				75+960	76+040	80.000	Widening & Strengthening	GSB	
230				76+040	76+050	10.000	Widening & Strengthening	GSB	
231	86+750	86+820	70	76+050	76+110	60.000	Widening & Strengthening	Subgrade	
232				76+110	76+280	170.000	Widening & Strengthening	GSB	
233	86+820	87+130	310	76+280	76+300	20.000	Widening & Strengthening	GSB	
234				76+300	76+340	40.000	Widening & Strengthening	Subgrade	
235				76+340	76+400	60.000	Widening & Strengthening	WMM	
236	87+130	87+180	50	76+400	76+445	45.000	Realignment	WMM	
237				76+445	76+465	20.000	Widening & Strengthening	WMM	
238	87+180	87+330	150	76+465	76+540	75.000	Widening & Strengthening	WMM	
239				76+540	76+560	20.000	Widening & Strengthening	WMM	
240				76+560	76+600	40.000	Widening & Strengthening	WMM	

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sl. No.	Existing Chainage		Length	Design Chainage		Length	Improvement Proposal	Details of Work done by Previous Contractor	Remarks
	From	To		From	To				
							g		
241	87+330	87+400	70	76+600	76+620	20.000	Realignment	WMM	Profile Corrective course, Camber Correction, Desirable thickness & width of present layer shall be done by the contractor to be appointed
242				76+620	76+660	40.000	Realignment	WMM	
243	87+400	87+940	540	76+660	76+730	70.000	Widening & Strengthening	GSB	
244				76+730	76+750	20.000	Widening & Strengthening	Subgrade	
245				76+750	76+950	200.000	Widening & Strengthening	Subgrade	
246				76+950	77+050	100.000	Widening & Strengthening	GSB	
247				77+050	77+100	50.000	Widening & Strengthening	Subgrade	
248				77+100	77+190	90.000	Widening & Strengthening	WMM	
249	87+940	88+000	60	77+190	77+300	110.000	Realignment	WMM	
250	88+000	88+320	320	77+300	77+320	20.000	Realignment	Subgrade	
251				77+320	77+380	60.000	Realignment	WMM	
252				77+380	77+400	20.000	Realignment	WMM	
253				77+400	77+440	40.000	Realignment	WMM	
254				77+440	77+500	60.000	Realignment	Earthwork in Excavation	
255	88+320	88+380	60	77+500	77+510	10.000	Widening & Strengthening	GSB	
256				77+510	77+540	30.000	Widening & Strengthening	WMM	
257				77+540	77+560	20.000	Widening & Strengthening	WMM	
258	88+380	88+550	170	77+560	77+630	70.000	Realignment	WMM	
259				77+630	77+670	40.000	Realignment	Earthwork in	

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sl. No.	Existing Chainage		Length	Design Chainage		Length	Improvement Proposal	Details of Work done by Previous Contractor	Remarks
	From	To		From	To				
								Excavation	
260				77+670	77+700	30.000	Realignment	WMM	
261				77+700	77+720	20.000	Widening & Strengthening	WMM	
262				77+720	77+780	60.000	Widening & Strengthening	WMM	
263				77+780	77+810	30.000	Widening & Strengthening	GSB	
264				77+810	77+850	40.000	Widening & Strengthening	WMM	
265				77+850	77+940	90.000	Realignment	WMM	
266				77+940	78+000	60.000	Realignment	Subgrade	
267				78+000	78+080	80.000	Widening & Strengthening	GSB	
268				78+080	78+220	140.000	Widening & Strengthening	GSB	
269				78+220	78+240	20.000	Widening & Strengthening	Subgrade	
270				78+240	78+260	20.000	Widening & Strengthening	Subgrade	
271				78+260	78+350	90.000	Widening & Strengthening	Subgrade	
272				78+350	78+410	60.000	Widening & Strengthening	GSB	
273				78+410	78+500	90.000	Widening & Strengthening	GSB	
274	88+390	89+440	50	78+500	78+540	40.000	Realignment	WMM	Profile Corrective course, Camber Correction, Desirable thickness & width of present
275	89+440	89+470	30	78+540	78+550	10.000	Widening & Strengthening	GSB	
276	89+470	89+640	170	78+550	78+610	60.000	Realignment	WMM	
277				78+610	78+670	60.000	Realignment	WMM	

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sl. No.	Existing Chainage		Length	Design Chainage		Length	Improvement Proposal	Details of Work done by Previous Contractor	Remarks
	From	To		From	To				
278	89+640	89+690	50	78+670	78+710	40.000	Realignment	WMM	layer shall be done by the contractor to be appointed
279				78+710	78+735	25.000	Widening & Strengthening	GSB	
280	89+690	89+750	60	78+735	78+790	55.000	Realignment	GSB	
281	89+750	89+870	120	78+790	78+820	30.000	Widening & Strengthening	GSB	
282				78+820	78+830	10.000	Widening & Strengthening	Subgrade	
283				78+830	78+945	115.000	Widening & Strengthening	GSB	
284	89+870	89+990	120	78+945	79+025	80.000	Realignment	WMM	
285				79+025	79+110	85.000	Realignment	Earthwork in Excavation	
286	89+990	90+540	550	79+110	79+260	150.000	Widening & Strengthening	Subgrade	
287				79+260	79+280	20.000	Widening & Strengthening	Subgrade	
288				79+280	79+320	40.000	Widening & Strengthening	Subgrade	
289				79+320	79+500	180.000	Widening & Strengthening	Subgrade	
290				79+500	79+520	20.000	Widening & Strengthening	Subgrade	
291				79+520	79+650	130.000	Widening & Strengthening	Subgrade	
292	90+540	90+600	60	79+650	79+700	50.000	Realignment	Earthwork in Excavation	
293	90+600	90+650	50	79+700	79+750	50.000	Widening & Strengthening	Subgrade	
294	90+650	91+170	520	79+750	79+870	120.000	Realignment	GSB	
295				79+870	79+960	90.000	Widening & Strengthening	Subgrade	

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sl. No.	Existing Chainage		Length	Design Chainage		Length	Improvement Proposal	Details of Work done by Previous Contractor	Remarks
	From	To		From	To				
							g		
296				79+960	80+100	140.000	Widening & Strengthening	GSB	
297				80+100	80+160	60.000	Realignment	Earthwork in Excavation	
298				80+160	80+180	20.000	Widening & Strengthening	Subgrade	
299	91+170	91+330	160	80+180	80+300	120.000	Widening & Strengthening	GSB	
300				80+300	80+340	40.000	Widening & Strengthening	Subgrade	
301	91+330	91+420	90	80+340	80+420	80.000	Realignment	Subgrade	
302	91+420	91+600	180	80+420	80+600	180.000	Widening & Strengthening	Subgrade	
303	91+600	91+610	10	80+600	80+640	40.000	Realignment	Earthwork in Excavation	
304	91+610	91+660	50	80+640	80+730	90.000	Widening & Strengthening	Subgrade	
305	91+660	91+760	100	80+730	80+750	20.000	Widening & Strengthening	Subgrade	
306	91+760	91+820	60	80+750	80+800	50.000	Realignment	No Work Done	
307				80+800	80+810	10.000	Widening & Strengthening	No Work Done	
308				80+810	80+880	70.000	Widening & Strengthening	Subgrade	
309	91+820	92+105	285	80+880	80+955	75.000	Widening & Strengthening	Subgrade	
310				80+955	80+975	20.000	Widening & Strengthening	No Work Done	
311				80+975	81+095	120.000	Widening & Strengthening	Subgrade	
312	92+105	92+240	135	81+095	81+130	35.000	Realignment	No Work Done	

Profile Corrective course, Camber Correction, Desirable thickness & width of present layer shall be done by the contractor to be appointed

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sl. No.	Existing Chainage		Length	Design Chainage		Length	Improvement Proposal	Details of Work done by Previous Contractor	Remarks
	From	To		From	To				
313				81+130	81+200	70.000	Realignment	Subgrade	
314				81+200	81+210	10.000	Widening & Strengthening	No Work Done	
315	92+240	92+290	50	81+210	81+240	30.000	Widening & Strengthening	Subgrade	
316				81+240	81+250	10.000	Widening & Strengthening	No Work Done	
317	92+290	92+350	60	81+250	81+290	40.000	Realignment	GSB	
318				81+290	81+305	15.000	Realignment	No Work Done	
319				81+305	81+410	105.000	Widening & Strengthening	No Work Done	
320	92+350	92+580	230	81+410	81+430	20.000	Widening & Strengthening	No Work Done	
321				81+430	81+525	95.000	Widening & Strengthening	No Work Done	
322				81+525	81+540	15.000	Widening & Strengthening	No Work Done	
323	92+580	92+770	190	81+540	81+660	120.000	Widening & Strengthening	GSB	
324	92+770	92+880	110	81+660	81+900	240.000	Widening & Strengthening	GSB	Profile Corrective course, Camber Correction, Desirable thickness & width of present layer shall be done by the contractor to be appointed
325	92+880	93+005	125	81+900	82+160	260.000	Widening & Strengthening	Subgrade	
326	93+005	93+480	475	82+160	82+440	280.000	Widening & Strengthening	No Work Done	
327	93+480	93+520	40	82+440	82+465	25.000	Realignment	No Work Done	
328	93+520	97+890	4370	82+465	82+600	135.000	No Geometric Improvement	No Work Done	
329				82+600	83+300	700.000	Widening & Strengthening	Subgrade	
330				83+300	84+500	1250.000	No	No Work	

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sl. No.	Existing Chainage		Length	Design Chainage		Length	Improvement Proposal	Details of Work done by Previous Contractor	Remarks
	From	To		From	To				
				00	50	00	Geometric Improvement	Done	
331				84+550	84+800	250.000	No Geometric Improvement	DBM in MON Town	
332				84+800	84+850	50.000	No Geometric Improvement	No Work Done	
333				84+850	85+420	570.000	No Geometric Improvement	DBM in MON Town	
334				85+420	86+835	1415.000	No Geometric Improvement	No Work Done	

The Index Map is appended at the end of this Schedule-A

## 2. Chainage References (Existing Vs Design)

"ExistingChainage" means distance measured along existing roadway /vehicle pathway on the Project Highway. During topography survey, observations are made to these locations and after finalization of alignment by improving the existing geometry the chainage has been referred to "Design Chainage". The relationship between the "Existing Chainage" and the "Design Chainage" as per field surveys of the location for the "Project Highway" is given below:

Sl No.	Existing Chainage	Design Chainage	Remark
1.	63+800	Realignment	
2.	64+000	Realignment	
3.	65+000	Realignment	
4.	66+000	Realignment	
5.	67+000	Realignment	
6.	68+000	Realignment	
7.	69+000	Realignment	
8.	70+000	Realignment	
9.	71+000	Realignment	
10.	72+000	Realignment	
11.	73+995	64+360	

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

12.	74+430	64+750	
13.	75+410	65+710	
14.	76+480	66+750	
15.	77+820	67+960	
16.	77+890	68+030	
17.	78+470	68+595	
18.	79+000	69+130	
19.	79+130	69+245	
20.	79+570	69+650	
21.	80+530	70+475	
22.	81+690	71+500	
23.	82+320	72+100	
24.	83+600	73+305	
25.	84+660	74+295	
26.	85+060	74+735	
27.	86+200	75+600	
28.	87+180	76+445	
29.	88+550	77+700	
30.	89+640	78+705	
31.	90+600	79+700	
32.	91+420	80+420	
33.	92+240	81+200	
34.	93+520	82+465	

### 3. Land

The Site of the Project Highway comprises the land described below:

Sl No.	Existing Chainage		Design Chainage		Length In M (Design)	Existing/ Available Row (M)	Remark
	From	To	From	To			
1	73+640	98+065	63+800	86+835	23035		No RoW available in realignment stretches of total 10.370 km as given in para 2.1.3 of Annexure-1 Schedule-B

### 4. Carriageway

The present carriageway of the Project Highway is substandard single lane configuration. The type of the existing pavement is flexible.

Sl No.	Existing Chainage	Design Chainage	Length In M (Design)	Existing/ Lane Width	Remark
--------	-------------------	-----------------	----------------------	----------------------	--------



Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

	From	To	From	To			
1	73+640	98+065	63+800	86+835	23035	3 to 3.5/ 7.0	Land Width Other Then realignment

#### 5. Major Bridges

The site includes the following medium size Bridge.

Sl No.	Design Chainage	Type of Structures			No. of Span with span length	width(m)
		Foundation	Sub-Structure	Super Structure		
Nil						

#### 6. Railway over Bridges (ROB)

The site includes the following Railway over Bridges.

Sl No.	Design Chainage	Type Of Structures			No. of Span with span length	width(m)
		foundation	sub-structure	Super Structure		
Nil						

#### 7. Grade Separators

The site includes the following Grade Separators.

Sl No.	Design Chainage	Type Of Structures			No. of Span with span length	Width(m)
		Foundation	Sub-structure	Super Structure		
Nil						

#### 8. Minor bridges

The site includes the following medium size Bridge.

Sl No.	Road Segment	Design Chainage	Type Of Structures			No. of Span with span length	Width(m)
			foundation	sub-structure	Super Structure		
1	Merangkong-Tamlu-Mon	89900	not visible	stone masonry	Steel truss	1x15.25	4
2	Merangkong-Tamlu-Mon	98024	not visible	stone masonry	RccSlab	1x6	7.2

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

## 9. Railway level crossings/Railway track

The site includes the following railway crossings.

Sl No.	Road Segment	Existing Chainage (km)	Remarks
Nil			

## 10. Underpass (vehicular, Non-Vehicular)

The site includes the following Underpasses.

Sl No.	Road Segment	Existing Chainage (km)	Type of structure	no. of span with span length	width
Nil					

## 11. Culverts

11.1 The site includes 90 nos. of culverts at the following locations and types. (Culvert Detail before awarding previous contractor)

Sl No.	Existing Chainage (km)	Type of structure	Span/Dia (m)	Width of Structure	Remarks
1.	73+960	Slab	1X1.5	5.1	
2.	74+150	Slab	1X1.5	4.5	
3.	74+202	Slab	1X0.9	5.3	
4.	74+280	Slab	1X1.5	5.2	
5.	75+084	Slab	1X1.0	5.6	
6.	75+278	Slab	1X1.0	7.3	
7.	75+388	Slab	1X1.0	7	
8.	76+272	Slab	1X1.0	7.5	
9.	76+425	Slab	1X1.5	7.6	
10.	76+500	Slab	1X1.0	7.3	
11.	76+715	Slab	1X1.0	6.1	
12.	77+100	Slab	1X1.0	6.3	
13.	77+240	Slab	1X1.0	6.3	
14.	77+431	Slab	1X1.0	6.4	
15.	77+798	Slab	1X1.0	6.2	
16.	78+415	Pipe	1X1.2	13	
17.	78+593	Pipe	1X1.0	12.5	
18.	78+763	Slab	1X1.0	6.7	
19.	78+965	Slab	1X1.5	7.6	

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

20.	79+047	Slab	1X1.0	6.9	
21.	79+181	Slab	1X1.0	8.5	
22.	79+250	Slab	1X1.5	8.8	
23.	79+431	Slab	1X1.5	8.1	
24.	79+650	Slab	1X1.5	7	
25.	79+752	Slab	1X2.0	7.3	
26.	79+980	Slab	1X1.5	7	
27.	80+232	Slab	1X1.5	6.7	
28.	80+515	Slab	1X1.0	7	
29.	80+690	Slab	1X0.9	7	
30.	81+025	Slab	1X2.0	5.5	
31.	81+450	Slab	1X2.0	5.6	
32.	81+551	Slab	1X1.5	7.1	
33.	82+072	Slab	1X1.5	6.6	
34.	82+150	Slab	1X1.5	6.1	
35.	82+262	Slab	1X1.5	7	
36.	82+559	not visible	1X1.5	6.1	
37.	82+760	Slab	1X1.5	7.1	
38.	82+900	not visible	1X1.5	5.6	
39.	82+960	Slab	1X0.9	6.2	
40.	83+292	Slab	1X1.5	3.8	
41.	83+462	Slab	1X1.0	6.1	
42.	83+985	not visible	1X1.0	7.4	
43.	84+375	Slab	1X0.9	5.6	
44.	85+358	Slab	1X1.0	6	
45.	85+455	Pipe	1X0.9	9	
46.	86+072	Slab	1X1.5	8	
47.	86+430	Slab	1X0.9	7	
48.	86+580	Slab	1X1.5	7.3	
49.	86+650	Slab	1X1.0	7.1	
50.	86+960	Slab	1X1.0	6	
51.	87+268	Pipe	1X1.0	12.9	
52.	87+383	Pipe	1X1.0	10.3	
53.	87+733	Pipe	1X1.0	10.2	
54.	87+914	Pipe	1X1.0	10.3	
55.	88+018	Slab	1X1.5	6.3	
56.	88+121	Slab	1X2.0	7	
57.	88+182	Slab	1X1.5	5.5	
58.	88+535	Pipe	1X1.0	13.3	
59.	88+825	Pipe	1X1.0	12.7	

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

60.	89+100	Pipe	1X1.0	14.5	
61.	89+258	Slab	1X1.5	6.3	
62.	89+525	Slab	1X2.0	6.5	
63.	89+650	Pipe	1X1.0	14.7	
64.	90+116	Pipe	1X1.0	13	
65.	90+533	Pipe	1X1.0	9.5	
66.	90+785	Pipe	1X1.0	10.3	
67.	90+858	not visible	not visible	15	
68.	91+033	Slab	1X3.0	7.5	
69.	91+588	Slab	1X1.5	7.1	
70.	91+788	Slab	1X1.0	6.7	
71.	91+975	Slab	1X1.0	6.4	
72.	92+158	Slab	1X1.0	7.2	
73.	92+407	Slab	1X1.0	6.2	
74.	92+547	Slab	1X1.0	7.2	
75.	92+875	Slab	1X1.0	6.5	
76.	93+037	Slab	1X1.0	6.2	
77.	93+452	Slab	1X1.5	6.6	
78.	93+687	Slab	1X1.0	6.3	
79.	93+932	Slab	1X1.0	7.2	
80.	94+349	Slab	1X1.5	6.9	
81.	94+455	Slab	1X1.0	7.1	
82.	94+530	Slab	1X1.0	8	
83.	94+640	Pipe	1X0.9	10.8	
84.	94+978	Pipe	1X1.0	9.7	
85.	96+480	Pipe	1X0.5	8.6	
86.	96+910	Slab	1X1.0	7	
87.	97+087	Slab	1X1.5	6.9	
88.	97+515	Slab	1X1.5	7.1	
89.	97+600	Slab	1X1.0	6.2	
90.	97+725	Slab	1X1.0	7.2	

11.2 Previous Contractor has been completed Box Culvert 73Nos. at site. The following locations and types.

Sl No.	Existing Chainage (km)	Type of Structure	Span/Dia (m)	Width of Structure	Remarks
1.	64+005	Box	1.5x1.5	12	New Constructed
2.	64+350	Box	1.5x1.5	12	New Constructed
3.	64+560	Box	1.5x1.5	12	New Constructed
4.	64+770	Box	1.5x1.5	12	New Constructed

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

5.	64+900	Box	3x3	12	New Constructed
6.	65+130	Box	1.5x1.5	12	New Constructed
7.	65+590	Box	1.5x1.5	12	New Constructed
8.	65+690	Box	1.5x1.5	12	New Constructed
9.	66+527	Box	1.5x1.5	12	New Constructed
10.	66+660	Box	3x3	12	New Constructed
11.	66+947	Box	2x2	12	New Constructed
12.	67+130	Box	1.5x1.5	12	New Constructed
13.	67+320	Box	1.5x1.5	6	New Constructed
14.	67+645	Box	2x2	12	New Constructed
15.	67+900	Box	2x2	12	New Constructed
16.	67+950	Box	2x2	12	New Constructed
17.	67+990	Box	1.5x1.5	12	New Constructed
18.	68+650	Box	2x2	12	New Constructed
19.	68+720	Box	1.5x1.5	12	New Constructed
20.	68+929	Box	3x3	12	New Constructed
21.	69+020	Box	2x2	12	New Constructed
22.	69+135	Box	1.5x1.5	12	New Constructed
23.	69+201	Box	2x2	6	New Constructed
24.	69+400	Box	3x3	6	New Constructed
25.	69+575	Box	2x2	12	New Constructed
26.	69+700	Box	2x2	12	New Constructed
27.	69+915	Box	2x2	12	New Constructed
28.	69+965	Box	2x2	12	New Constructed
29.	70+166	Box	2x2	12	New Constructed
30.	70+326	Box	2x2	12	New Constructed
31.	70+537	Box	1.5x1.5	12	New Constructed
32.	70+665	Box	2x2	12	New Constructed
33.	70+800	Box	1.5x1.5	12	New Constructed
34.	70+942	Box	2x2	6	New Constructed
35.	71+018	Box	2x2	6	New Constructed
36.	71+330	Box	2x2	12	New Constructed
37.	71+575	Box	2x2	6	New Constructed
38.	71+965	Box	2x2	6	New Constructed
39.	72+037	Box	2x2	6	New Constructed
40.	72+125	Box	2x2	12	New Constructed
41.	72+380	Box	2x2	12	New Constructed
42.	72+984	Box	1.5x1.5	12	New Constructed
43.	73+250	Box	2x2	12	New Constructed
44.	73+840	Box	2x2	6	New Constructed
45.	75+404	Box	2x2	12	New Constructed
46.	75+542	Box	2x2	12	New Constructed
47.	75+652	Box	2x2	6	New Constructed
48.	75+838	Box	2x2	12	New Constructed
49.	75+970	Box	2x2	12	New Constructed

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

50.	76+240	Box	1.5x1.5	12	New Constructed
51.	76+402	Box	1.5x1.5	12	New Constructed
52.	76+545	Box	2x2	12	New Constructed
53.	76+846	Box	3x3	12	New Constructed
54.	76+900	Box	2x2	12	New Constructed
55.	77+040	Box	1.5x1.5	12	New Constructed
56.	77+274	Box	2x2	12	New Constructed
57.	77+449	Box	1.5x1.5	12	New Constructed
58.	77+640	Box	1.5x1.5	12	New Constructed
59.	77+740	Box	2x2	12	New Constructed
60.	77+920	Box	1.5x1.5	12	New Constructed
61.	78+104	Box	2x2	6	New Constructed
62.	78+450	Box	1.5x1.5	12	New Constructed
63.	78+740	Box	1.5x1.5	12	New Constructed
64.	78+900	Box	2x2	12	New Constructed
65.	79+231	Box	3x3	12	New Constructed
66.	79+520	Box	3x3	6	New Constructed
67.	79+700	Box	1.5x1.5	12	New Constructed
68.	79+820	Box	2x2	12	New Constructed
69.	79+900	Box	2x2	12	New Constructed
70.	80+015	Box	3x3	12	New Constructed
71.	80+086	Box	3x3	12	New Constructed
72.	80+994	Box	3x3	6	New Constructed
73.	82+486	Box	2X2	6	New Constructed

#### 12. Bus shelters

Sl No.	Road Segment	Existing Chainage (km)	length	left hand side	right hand side
Nil					

#### 13. Truck lay bye

Sl No.	Road Segment	Existing Chainage (km)	length	left hand side	right hand side
Nil					

#### 14. Road side drain

The details of the road side drains on the site are as follows.

Sl No.	Existing Chainage (km)		Side	Type		Remarks
	from	To		Masonry	Earthen(katcha)	
1.	90+500	91+100	left		Earthen(katcha)	
2.	94+500	94+700	left	Masonry		

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

3.	94+900	95+400	right	Masonry		
4.	95+700	95+800	right	Masonry		
5.	95+800	96+000	left	Masonry		
6.	96+100	96+500	left		Earthen(katcha)	

### 15. Major Junctions

The details of the major junctions are as follows.

SI No.	Location		At Grade	Separated	Type				Remarks
	Ex. Km	Design km			NH	SH	MDR	Other	
Nil									

### 16. Minor Junctions

The details of the minor junctions are as follows.

SI No.	Existing chainage (km)	Design Chainage	Type	
			T Junction	Cross road both sides
1.	84+450	74+150	T Junction	
2.	94+520	83+500	T Junction	
3.	94+670	83+650	T Junction	
4.	94+675	83+655	T Junction	
5.	95+125	84+110	T Junction	
6.	95+190	84+175	T Junction	
7.	95+192	84+177	T Junction	
8.	95+195	84+180	T Junction	
9.	95+245	84+240	T Junction	
10.	95+450	84+245	T Junction	
11.	95+595	84+600	T Junction	
12.	95+630	84+640	T Junction	
13.	95+965	84+970	T Junction	
14.	96+060	85+050	T Junction	
15.	96+340	85+350	T Junction	
16.	96+650	85+575	T Junction	
17.	97+075	85+855	T Junction	

### 17. Bypasses

The details of bypass are as follows.

S.no.	Name Of Proposed Bypass	Road Segment	Existing Chainage		length	Carriageway	
			from	to		width	type
NIL							

### 18. Other Structures/Details

The details of other structures are as follows.

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

---

S.no.	Type	Existing Chainage	length	width
NIL				

---



Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

---

**Annex - II**  
*(Schedule-A)*

**Dates for providing Right of Way**

The dates on which the Authority shall provide Right of Way to the Contractor on different stretches of the Site are stated below:

Sl. No	Design Chainage		Length (Km)	Proposed ROW Width (m)	Date of Providing proposed ROW
	From	To			
i) 90% of ROW (full width)	63+800	86+835	23.035	Varying ROW from minimum 24 m to maximum 45 m at different locations as per cross section in DPR	At Appointment Date
ii) Balance Right of way (width)	63+800	86+835	23.035	Varying ROW from minimum 24 m to maximum 45 m at different locations as per cross section in DPR	Within 150 days after the Appointed Date

Annex - III  
(Schedule-A)

**Alignment Plans**

The existing alignment of the Project Highway shall be modified in the following sections as per the alignment plan indicated below:

- i) The alignment of the Project Highway is enclosed in alignment plan. Finished road level indicated in the alignment plan shall be followed by the contractor as minimum FRL. In any case, the finished road level of the project highway shall not be less than those indicated in the alignment plan. The contractor shall, however, improve/upgrade the Road profile as indicated in Annex-III based on site/design requirement.
- ii) Traffic Signage plan of the Project Highway showing numbers & location of traffic signs is enclosed. The contractor shall, however, improve/upgrade upon the traffic signage plan as indicated in Annex-III based on site/design requirement as per IRC: SP: 99 & IRC: 67 and other IRC codes or manuals, if applicable

Project: Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

---

Annex - IV  
(Schedule-A)

**Environment Clearances**

As per notification of MOEF F.O. 2559(E) dated 22/08/2013, the project will not attract Environmental Clearance

---

**SCHEDULE - B**  
*(See Clause 2.1)*

**DEVELOPMENT OF THE PROJECT HIGHWAY**

**1. Development of the Project Highway**

Development of the Project Highway shall include design and construction of the Project Highway as described in this Schedule – B and in Schedule – C.

**2. Rehabilitation and Augmentation**

Rehabilitation and augmentation shall include [Two-Lane and strengthening] of the Project Highway as described in Annex-I of this Schedule-B and in Schedule-C.

**3. Specifications and Standards**

The Project Highway shall be designed and constructed in conformity with the Specification and Standards specified in Annex-I of Schedule-D.

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

## **Annex – I (Schedule – B)**

### **Description of Two Lanning**

The particulars specified in this Schedule-B are listed below as per the requirements of the Manual of Specifications and Standards for Two Laning of Highways (IRC SP:73-2015), referred to as the manual. If any standards, specifications or details are not given in the manual, the minimum design/construction requirements are specified in this Schedule or Schedule D.

Refer remarks column of table under Para 1.1 of Annex – I of Schedule A, construction carried out by previous contractor has been indicated. The contractor has to satisfy himself about the site conditions, quantity and quality of work done. He will be accordingly fully responsible for further requirement of design and construction of 2 lane with hard shoulders.

#### **1. Widening of The Existing Highway**

**1.1.** The Project Highway shall follow the existing alignment unless otherwise specified by the Authority and shown in the alignment plans specified in Annex-III of Schedule – A. Geometric deficiencies, if any, in the existing horizontal and vertical profiles shall be corrected as per the prescribed standards for [plain/rolling/hilly] terrain to the extend land available.

#### **1.2. Width of Carriageway**

**1.2.1.** Two Laning with hard shoulders shall be undertaken. The paved carriageway shall be 7 (Seven) m wide in accordance with the typical cross-sections drawings in the manual.

Provided that in the built-up areas [refer to paragraphs 2.1 (ii) of the manual and provide necessary details] the width of the carriageway shall be as specified in the following table:

Sr. No.	Built-up stretch (Township)	Location (Design Chainage)		Width (M)	Typical Cross Section
		From (Km)	To (Km)		
1	Tanhai	66+075	68+335	10	TCS IV & V
2	Lengnyu	78+210	78+410	10	
3	Mon	82+650	86+835	10	

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

**1.2.2.** Except as otherwise provided in this Agreement, the width of the paved carriageway and cross-sectional features shall conform to paragraph 1.2.1 above.

**1.2.3.** On horizontal curves with radius upto 300 m width of pavement and Roadway shall be increased as follows:-

Sr. No.	Radius of Curve (M)	Extra width of Carriageway (M)
1	21 to 40	1.5
2	41 to 60	1.2
3	61 to 100	0.9
4	101 to 300	0.6

**1.2.4** At hairpin bends the roadway width of 11.5 m should be surfaced as per section 13.4 of the Manual for minimum length of 50m.

## **1. Geometric Design and General Features**

### **2.1. General**

Geometric design and general features of the Project Highway shall be in accordance with section 2 of the manual.

### **2.2. Design Speed**

The design speed shall be as per IRC SPP 73: 2015 however in exceptional cases the minimum design speed can be 30 Km per hour for hilly and mountainous terrain and 20 Km per hour for hair pin bend locations.

### **2.3 Improvement of the Existing Road Geometrics**

In the following sections, where improvement of the existing road geometrics to the prescribed standards is not possible, the existing road geometrics shall be improved to the extent possible in accordance with section 13 of the Manual within the given right of way and proper road signs and safety measures shall be provided and in other sections it shall be designed in accordance with section 2 of the manual.

Sr. No.	Design Chainage (M)		Side	Type of Deficiency	Remarks
	From	To			

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sr. No.	Design Chainage (M)		Side	Type of Deficiency	Remarks
	From	To			
1.	64322.56	64381.89	Left	Radius<40	
2.	64381.89	64441.87	Right	Radius<40	
3.	64482.91	64518.23	Left	Radius<40	
4.	64616.96	64695.26	Left	Radius<40	
5.	66360.13	66435.07	Left	Radius<40	
6.	66435.07	66506.46	Right	Radius<40	
7.	66546.96	66577.84	Left	Radius<40	
8.	69940.31	70003.85	Left	Radius<40	
9.	70313.88	70379.81	Left	Radius<40	
10.	70893.14	70953.05	Right	Radius<40	
11.	71429.76	71474.51	Right	Radius<40	
12.	72066.87	72127.27	Right	Radius<40	
13.	72824.77	72886.36	Right	Radius<40	
14.	72960.88	73024.56	Left	Radius<40	
15.	73684.59	73739.82	Right	Radius<40	
16.	76258.75	76330.76	Right	Radius<40	
17.	76391.33	76453.13	Right	Radius<40	
18.	76611.30	76710.85	Left	Radius<40	
19.	77072.18	77137.61	Left	Radius<40	
20.	77557.61	77617.19	Left	Radius<40	

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sr. No.	Design Chainage (M)		Side	Type of Deficiency	Remarks
	From	To			
21.	78431.95	78509.08	Left	Radius<40	
22.	78614.42	78673.22	Right	Radius<40	
23.	78956.46	79113.28	Right	Radius<40	
24.	79113.28	79181.23	Left	Radius<40	
25.	80046.15	80105.41	Right	Radius<40	
26.	80288.09	80343.62	Left	Radius<40	
27.	80582.27	80642.63	Left	Radius<40	
28.	80642.63	80706.11	Right	Radius<40	
29.	81129.14	81197.08	Left	Radius<40	
30.	81251.19	81332.47	Right	Radius<40	
31.	81640.96	81684.00	Right	Radius<40	
32.	82419.46	82477.28	Right	Radius<40	
33.	82562.32	82609.26	Left	Radius<40	
34.	82798.79	82842.93	Left	Radius<40	
35.	82893.21	82913.01	Left	Radius<40	
36.	82913.01	82933.70	Right	Radius<40	
37.	83141.80	83155.95	Left	Radius<40	
38.	83175.25	83196.29	Left	Radius<40	
39.	83238.02	83251.59	Right	Radius<40	
40.	83292.06	83339.02	Right	Radius<40	

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”



Sr. No.	Design Chainage (M)		Side	Type of Deficiency	Remarks
	From	To			
41.	83355.01	83372.09	Left	Radius<40	
42.	83380.20	83392.52	Right	Radius<40	
43.	83411.39	83425.47	Left	Radius<40	
44.	83439.66	83463.38	Right	Radius<40	
45.	83490.14	83518.43	Left	Radius<40	
46.	83634.60	83687.90	Right	Radius<40	
47.	83733.72	83768.20	Left	Radius<40	
48.	84046.00	84078.96	Left	Radius<40	
49.	84373.77	84392.69	Left	Radius<40	
50.	84406.88	84431.19	Right	Radius<40	
51.	84517.84	84548.64	Right	Radius<40	
52.	84587.00	84613.77	Left	Radius<40	
53.	84634.89	84670.54	Right	Radius<40	
54.	85164.04	85191.81	Left	Radius<40	
55.	85216.43	85238.74	Right	Radius<40	
56.	85451.62	85471.19	Left	Radius<40	
57.	85518.42	85530.41	Left	Radius<40	
58.	85570.04	85604.21	Left	Radius<40	
59.	85633.64	85658.38	Right	Radius<40	
60.	85839.27	85860.74	Right	Radius<40	

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sr. No.	Design Chainage (M)		Side	Type of Deficiency	Remarks
	From	To			
61.	85904.02	85948.45	Right	Radius<40	
62.	86049.86	86067.20	Left	Radius<40	
63.	86259.75	86284.52	Left	Radius<40	
64.	86340.48	86382.37	Left	Radius<40	
65.	86398.19	86426.10	Right	Radius<40	
66.	86551.42	86573.10	Right	Radius<40	
67.	86662.29	86703.67	Right	Radius<40	
68.	86703.67	86769.81	Left	Radius<40	
69.	86769.81	86788.81	Left	Radius<40	

### 2.3.1 Improvement due to Realignments:

Sr. No.	Existing Chainage (Km)		Length (M)	Design Chainage (Km)		Length (M)
	From	To		From	To	
1.	65+145	73+400	8255	-	-	-
2.	73+960	73+995	35	64+330	64+360	30
3.	74+090	74+160	70	64+450	64+510	60
4.	74+330	74+430	100	64+660	64+750	90
5.	74+920	74+960	40	65+245	65+275	30
6.	75+280	75+410	130	65+600	65+710	110
7.	76+480	76+710	230	66+750	66+930	180
8.	76+830	77+000	170	67+050	67+200	150

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sr. No.	Existing Chainage (Km)		Length (M)	Design Chainage (Km)		Length (M)
	From	To		From	To	
9.	77+200	77+265	65	67+390	67+445	55
10.	77+420	77+520	100	67+605	67+700	95
11.	77+620	77+820	200	67+810	67+960	150
12.	77+890	77+920	30	68+030	68+060	30
13.	78+270	78+320	50	68+405	68+450	45
14.	78+360	78+470	110	68+495	68+595	100
15.	79+000	79+130	130	69+130	69+245	115
16.	79+220	79+270	50	69+330	69+375	45
17.	79+440	79+570	130	69+550	69+650	100
18.	79+670	79+860	190	69+740	69+910	170
19.	80+080	80+160	80	70+135	70+190	55
20.	80+220	80+370	150	70+250	70+310	60
21.	80+530	80+590	60	70+475	70+515	40
22.	80+860	81+220	360	70+790	71+060	270
23.	81+470	81+585	115	71+300	71+400	100
24.	81+620	81+690	70	71+440	71+500	60
25.	82+125	82+320	195	71+950	72+100	150
26.	83+040	83+120	80	72+800	72+865	65
27.	83+220	83+270	50	72+965	73+005	40
28.	83+540	83+600	60	73+255	73+305	50

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sr. No.	Existing Chainage (Km)		Length (M)	Design Chainage (Km)		Length (M)
	From	To		From	To	
29.	83+940	84+090	150	73+650	73+760	110
30.	84+180	84+240	60	73+850	73+905	55
31.	84+600	84+660	60	74+255	74+295	40
32.	85+060	85+310	250	74+735	74+920	185
33.	85+360	85+770	410	74+970	75+260	290
34.	85+900	86+160	260	75+390	75+555	165
35.	86+200	86+360	160	75+600	75+690	90
36.	86+475	86+570	95	75+800	75+870	70
37.	86+750	86+820	70	76+050	76+110	60
38.	87+130	87+180	50	76+400	76+445	45
39.	87+330	87+400	70	76+600	76+660	60
40.	87+940	88+320	380	77+190	77+500	310
41.	88+380	88+550	170	77+560	77+700	140
42.	88+700	88+890	190	77+850	78+000	150
43.	89+390	89+440	50	78+500	78+54	40
44.	89+470	89+640	170	78+565	78+705	140
45.	89+690	89+750	60	78+750	78+790	40
46.	89+870	89+990	120	78+945	79+110	165
47.	90+540	90+600	60	79+650	79+700	50
48.	90+650	91+170	520	79+750	80+160	410

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sr. No.	Existing Chainage (Km)		Length (M)	Design Chainage (Km)		Length (M)
	From	To		From	To	
49.	91+330	91+420	90	80+340	80+420	80
50.	91+600	91+660	60	80+600	80+640	40
51.	91+760	91+820	60	80+750	80+800	50
52.	92+105	92+240	135	81+095	81+200	105
53.	92+290	92+350	60	81+250	81+305	55
54.	92+580	92+770	190	81+540	81+760	220
55.	92+880	93+005	125	81+870	81+965	95
56.	93+480	93+520	40	82+440	82+465	25

## 2.4. Proposed Right of Way

**Details of the Right of way are given in Annex-II of Schedule A.**

Contractor has to design and construct the road, if required by provision of retaining walls and/or breast walls/slope stabilization/protection measures within the right of way given above and provision of the same shall not constitute a change of scope.

## 2.5 Type of Shoulders

- In built-up sections, footpaths/fully paved shoulders shall be provided in accordance with clause 1.2.1 above.
- In open country, Hard Shoulders with GSB having thickness of 200mm, total 3 m wide including both sides shall be provided and balance width shall be covered with 150 mm thick compacted layer of granular material.
- Design and specifications of paved shoulders and granular material shall conform to the requirements specified in paragraphs 5.10 and 5.11 of the Manual.

## 2.6 Lateral and vertical clearances at underpasses

**2.6.1** Lateral and Vertical clearances at underpasses and provision of guardrails/crash barriers shall be as per paragraph 2.10 of the manual.

**2.6.2 Lateral Clearance:** The width of the opening at the underpasses shall be as follow:

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sr. No.	Location (Chainage (Km))		Span/Opening (M)	Remarks
	From	To		
1.	Nil			

## 2.7. Lateral and Vertical Clearances at overpasses

2.7.1. Lateral and Vertical Clearances at overpasses shall be as per paragraph 2.11 of the Manual.

2.7.2 Lateral Clearance: The width of the opening at the overpasses shall be as follows;

Sr. No	Location [Chainage Km]		Span/Opening	Remark
	From	To		
1.	Nil			

## 2.8. Services Roads

Services roads shall be constructed at the locations and for the lengths indicated below: [Refer to paragraph 2.12 of the Manual and provide details]

Sr. No	Location of Service Road		Right Hand side(RHS)/Left Hand side(LHS)/Both Sides	Length (Km) of Services Road
	From	To		
Nil				

## 2.9. Grade Separated Structures

2.9.1 Grade separated structures shall be provided as per paragraph 2.13 of the Manual. The requisite particulars are given below:

Sr.No.	Location of Structure	Length (M)	Number and Length of Spans (M)	Approach Gradient	Remarks, if any
Nil					

2.9.2 In the case of grade separated structures, the type of structure and the level of the Project Highway and the cross roads shall be as follows: [Refer to paragraphs 2.13.1 of the Manual and specify the type of vehicular under pass/overpass structure and whether the cross road is to be carried at the existing level, raised or lowered].

Sr. No.	Location	Type of Structure/Length (M)	Cross Road at			Remarks, if any
			Existing Level	Raised Level	Lowered Level	

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

<b>Nil</b>
------------

**2.10 Cattle and pedestrian underpass / Overpass**

Cattle and pedestrian underpass/overpass shall be constructed as follows:

Sr. No.	Location	Type of Crossing
Nil		

**2.11 Typical cross-sections of the Project Highway**

The proposed cross sections for various situations are given in Fig.B-1 to B-6. These illustrate the cross sectional improvement proposals for the project highway. The Project Highway (length 23.035 km) shall be 2-lane carriageway with 3 m wide Hard shoulders facility including both sides.

Following typical cross sections shall be provided for the Project Highway However to be designed as per manual.

TCS I (a): Typical Cross Section for project road sections in Hill / Valley locations

TCS I (b): Typical Cross Section for Project Road Sections requiring Fill on Valley Side

TCS II: Typical Cross Section for project road section on ridge

TCS III: Typical Cross Section for Project Road Sections through Box Cut Locations

TCS IV: Typical Cross Section for Project Road Section through Town with Hill Valley Combination

TCS V: Typical Cross Section for Project Road Section through Town on Ridge

The cross section schedule shall be as follows:

Sr. No.	Chainage (Km)		Length(M)	Type	Remarks
	From	To			
1.	63+800	63+865	65	I	
2.	63+865	63+910	45	II	
3.	63+910	63+940	30	I	
4.	63+940	64+040	100	II	
5.	64+040	66+045	2005	I	
6.	66+045	66+120	75	II	


Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”



Sr. No.	Chainage (Km)		Length(M)	Type	Remarks
	From	To			
7.	66+120	66+380	260	I	
8.	66+380	66+400	20	II	
9.	66+400	68+200	1800	I	
10.	68+200	68+260	60	II	
11.	68+260	69+350	1090	I	
12.	69+350	69+370	20	III	
13.	69+370	70+030	660	I	
14.	70+030	74+200	4170	I	
15.	74+200	74+210	10	III	
16.	74+210	74+300	90	I	
17.	74+300	74+315	15	III	
18.	74+315	74+505	190	I	
19.	74+505	74+525	20	III	
20.	74+525	74+710	185	I	
21.	74+710	75+070	360	III	
22.	75+070	75+100	30	I	
23.	75+100	75+350	250	III	
24.	75+350	75+370	20	I	
25.	75+370	75+480	110	III	
26.	75+480	75+510	30	I	

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”





Sr. No.	Chainage (Km)		Length(M)	Type	Remarks
	From	To			
27.	75+510	75+520	10	II	
28.	75+520	78+650	3130	I	
29.	78+650	78+680	30	I	
30.	78+680	80+340	1660	I	
31.	80+340	81+665	1325	I	
32.	81+664	81+760	96	III	
33.	81+760	81+950	190	I	
34.	81+950	81+965	15	III	
35.	81+965	82+760	795	I	
36.	82+760	86+834	4074	V	





Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”



### 3.0 INTERSECTIONS AND GRADE SEPARATORS

All intersections shall be as per Section 3 of the Manual. Existing intersections which are deficient shall be improved to the prescribed standards.

Properly designed intersections shall be provided at the locations and of the types and features given in the tables below:

#### (a) At-grade Intersections

##### (i) Major Intersections

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sr. No.	Location of Intersection	Intersection Towards	Type of Intersection	Figure No.	Other Features
Nil					

Details of junction improvements shall be as per IRC SP: 73-2015.

**(ii) Minor Intersections**

Sr. No.	Location of Intersection (Design Chainage, Km)	Type of Intersection	Side
1.	74+150	T	Left
2.	83+500	T	Left
3.	83+650	T	Right
4.	83+655	T	Left
5.	84+110	T	Left
6.	84+175	T	Left
7.	84+177	T	Left
8.	84+180	T	Right
9.	84+240	T	Right
10.	84+245	T	Right
11.	84+600	T	Right
12.	84+640	T	Left
13.	84+970	T	Right
14.	85+050	T	Right
15.	85+350	T	Left
16.	85+575	T	Right
17.	85+855	T	Left / Left

Details of junction improvements shall be as per IRC SP: 73-2015.

**(b) Grade Separated Intersections with/without Ramps**

Sr. No.	Location (km)	Salient Features	Minimum Length of Viaduct to be Provided	Road to be carried Over/Under the
---------	---------------	------------------	--	-----------------------------------

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

			<b>(M)</b>	<b>Structure</b>
<b>Nil</b>				

#### 4.0 ROAD EMBANKMENT AND CUT SECTION

**4.1** Widening and improvement of the existing road embankment/cuttings and construction of new road embankment/ cuttings shall conform to the Specifications and Standards given in section 4 of the Manual and the specified cross sectional details. Deficiencies in the plan and profile of the existing road shall be corrected.

**4.2** Raising of the existing road [Refer to paragraph 4.2 of the Manual and specify sections to be raised]

The existing road shall be raised in the following sections:

Sr. No.	Section (Km)		Length (Km)	Extent of Raising [Top of finished road level]
	From	To		
Nil				

#### 5.0 PAVEMENT DESIGN

**5.1** Pavement design shall be carried out in accordance with section 5 of the Manual.

##### 5.2 Type of pavement

Flexible pavement shall be adopted for Project Highway. Notwithstanding anything contrary contained in this Agreement or the Manual, the pavement shall be designed as given below.

##### 5.3 Design Requirements

The granular layers (base and sub base) shall be designed for minimum 20 msa. The bituminous courses (Dense Bituminous Macadam and Bituminous Concrete) shall be designed for minimum 5 msa. Bituminous Concrete shall be minimum 40 mm thick.

Bituminous Grade VG 40 shall be used for BC.

##### 5.4 Reconstructions of stretches/ Realignment/ Bypass of sections

###### 5.4.1 Deleted

**5.4.2** The following stretches of the existing road shall be reconstructed. These shall be designed as new pavement.

Sr. No.	Existing Section (Km)	Remarks
---------	-----------------------	---------

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

	<b>From</b>	<b>To</b>	
<b>1.</b>	<b>73+640</b>	<b>98+065</b>	<b>Poor condition of existing pavement and or Realignment Section</b>

### 5.4. 3 Rigid Pavement

No rigid pavement has been considered for the Project Highway.

## 6.0 ROAD SIDE DRAINAGE

Drainage system including surface and subsurface drains for the Project Highway shall be provided as per section 6 of the Manual.

The improvements in the drainage and the slope erosion shall be made as per the following norms:

### 6.1 Drainage Measures

Following measures shall be adopted:

- i) Minimum length of Road Side Drains= 15516 m
- ii) Minimum length of lined covered RCC drain with Kerb Channel on Hill Side=8149 m

RCC Lined drains having rectangular shape have also been proposed in urban/semi urban/intersection stretches. The concrete drains shall be covered in reaches along commercial establishments and intersections. The drains outfall into the natural water courses i.e. either in culverts or bridges. Table below gives the location of lined drains.

These are guidelines for minimum provisions. However, contractor has to design as per requirement of road in accordance with manual.

#### Details of Drains

Sr. No.	Chainage (Km)		Length (M)	Remarks
	From	To		
1.	63.800	63.865	65	Trapezoidal-shaped PCC Drain on Hill Side
2.	63.865	63.910	45	Trapezoidal-shaped PCC Drain on Hill Side
3.	63.910	63.940	30	Trapezoidal-shaped PCC Drain on Hill Side
4.	63.940	64.040	100	Trapezoidal-shaped PCC Drain on Hill Side
5.	64.040	66.045	2005	Trapezoidal-shaped PCC Drain on Hill Side

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sr. No.	Chainage (Km)		Length (M)	Remarks
	From	To		
6.	66.045	66.120	75	Trapezoidal-shaped PCC Drain on Hill Side
7.	66.120	66.380	260	Trapezoidal-shaped PCC Drain on Hill Side
8.	66.380	66.400	20	Trapezoidal-shaped PCC Drain on Hill Side
9.	66.400	68.200	1800	Trapezoidal-shaped PCC Drain on Hill Side
10.	68.200	68.260	60	Trapezoidal-shaped PCC Drain on Hill Side
11.	68.260	69.350	1090	Trapezoidal-shaped PCC Drain on Hill Side
12.	69.350	69.370	20	Trapezoidal-shaped PCC Drain on Hill Side
13.	69.370	70.030	660	Trapezoidal-shaped PCC Drain on Hill Side
14.	70.030	74.200	4170	Trapezoidal-shaped PCC Drain on Hill Side
15.	74.200	74.210	10	Trapezoidal-shaped PCC Drain on Hill Side
16.	74.210	74.300	90	Trapezoidal-shaped PCC Drain on Hill Side
17.	74.300	74.315	15	Trapezoidal-shaped PCC Drain on Hill Side
18.	74.315	74.505	190	Trapezoidal-shaped PCC Drain on Hill Side
19.	74.505	74.525	20	Trapezoidal-shaped PCC Drain on Hill Side
20.	74.525	74.710	185	Trapezoidal-shaped PCC Drain on Hill Side
21.	74.710	75.070	360	Trapezoidal-shaped PCC Drain on Hill Side
22.	75.070	75.100	30	Trapezoidal-shaped PCC Drain on Hill Side
23.	75.100	75.350	250	Trapezoidal-shaped PCC Drain on Hill Side
24.	75.350	75.370	20	Trapezoidal-shaped PCC Drain on Hill Side
25.	75.370	75.480	110	Trapezoidal-shaped PCC Drain on Hill Side

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sr. No.	Chainage (Km)		Length (M)	Remarks
	From	To		
26.	75.480	75.510	30	Trapezoidal-shaped PCC Drain on Hill Side
27.	75.510	75.520	10	Trapezoidal-shaped PCC Drain on Hill Side
28.	75.520	78.650	3130	Trapezoidal-shaped PCC Drain on Hill Side
29.	78.650	78.680	30	Trapezoidal-shaped PCC Drain on Hill Side
30.	78.680	80.340	1660	Trapezoidal-shaped PCC Drain on Hill Side
31.	80.340	81.665	1325	Trapezoidal-shaped PCC Drain on Hill Side
32.	81.665	81.760	95	Trapezoidal-shaped PCC Drain on Hill Side
33.	81.760	81.950	190	Trapezoidal-shaped PCC Drain on Hill Side
34.	81.950	81.965	15	Trapezoidal-shaped PCC Drain on Hill Side
35.	81.965	82.760	795	Trapezoidal-shaped PCC Drain on Hill Side
36.	82.760	86.834	4074	Trapezoidal-shaped PCC Drain on Hill Side

**Note: (i) Road side drain shall have wetted area of 0.4 sqm**

**(ii)** The above locations shall be reviewed in consultation with the Authority Engineer at the time of construction as per the site condition.

## **7.0 DESIGN OF STRUCTURES**

### **7.1 General**

**7.1.1** Project road from Merangkong to Mon from Km. 63.800 to Km.86.835 (design chainages), includes provision of 2 minor bridges (span<60m), and 41 box culverts. All bridges, culverts and structures shall be designed and constructed in accordance with section 7 of the Manual and shall conform to the cross - sectional features and other details specified therein.

**7.1.2** Width of the carriageway of new bridges and Structures shall be as per Clause 7. 3 of the Manual.

**7.1.3 All bridges shall be high-level bridges.**

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”



**7.1.4** The following structures shall be designed to carry utility services specified in the table below:

Sr. No.	Bridge at Km	Utility Services to be Carried	Remarks
Nil			

**7.1.5** Cross-section of the new culverts and bridges at deck level for the Project Highway shall conform to the typical cross sections given in the section 7 of the Manual.

## 7.2 Culverts

**7.2.1** Overall width of all culverts shall be equal to the roadway width of the approaches. Catch water pit at every culvert location shall be provided as per IRC standard and Breast wall of varying height shall also be provided at the end of catch pit along hill side to protect against hill toe erosion. All box culverts (excluding the box culverts in cushion) shall be provided with approach slabs on both sides.

Minimum no. of box culverts with Span arrangement are given herein under:

Sr. No.	Span (M)	No. of Culverts (New / Reconstruction)	Culverts (Widening & Repairing)	Total
1.	1.5	11	01	12
2.	2.0	18	08	26
3.	3.0	12	03	15
4.	4.0	00	00	00
5.	5.0	01	00	01

## 7.2.2 Reconstruction of existing culverts

The existing culverts at the following locations shall be re-constructed as new culverts:

Sr. No.	Existing Chainage (Km)	Proposed Chainage (Km)	Proposed Span (M)	Remark
1.	75.084	65.425	2.00	
2.	76.272	66.560	3.00	

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sr. No.	Existing Chainage (Km)	Design Chainage (Km)	Proposed Span (M)	Remark
3.	76.715	66.945	3.00	
4.	78.415	68.560	1.50	
5.	79.047	69.190	2.00	
6.	79.431	69.565	3.00	
7.	79.752	69.850	3.00	
8.	82.150	72.000	3.00	
9.	82.262	72.095	3.00	
10.	83.292	73.050	2.00	
11.	83.985	73.720	5.00	
12.	85.358	74.840	3.00	
13.	85.455	75.075	1.50	
14.	86.072	75.520	3.00	
15.	87.268	76.560	1.50	
16.	90.116	79.270	1.50	
17.	91.975	80.965	2.00	
18.	92.158	81.160	2.00	
19.	92.547	81.560	3.00	
20.	92.875	81.905	2.00	
21.	93.037	82.045	2.00	
22.	93.452	82.455	3.00	
23.	93.687	82.680	3.00	

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sr. No.	Existing Chainage (Km)	Proposed Chainage (Km)	Proposed Span (M)	Remark
24.	93.932	82.930	2.00	
25.	94.349	83.340	2.00	
26.	94.455	83.450	2.00	
27.	94.530	83.515	2.00	
28.	94.640	83.635	1.50	
29.	94.978	83.990	1.50	
30.	96.480	85.480	1.50	
31.	96.910	85.830	2.00	
32.	97.087	86.007	2.00	
33.	97.515	86.435	2.00	
34.	97.600	86.520	2.00	
35.	97.725	86.645	2.00	

\* All box culverts (excluding the box culverts in cushion) shall be provided with approach slabs on both sides. Moreover upstream and downstream protection works, including connecting stream with the culvert, catch pits; baffle piers/blocks etc. shall be provided which must be ascertained as per the site conditions and details given in drawings of culvert.

**7.2.3** Additional new culverts shall be constructed as per particulars given in the table below:

Sr. No.	Existing Chainage (Km)	Proposed Chainage (Km)	Proposed Span (M)	Proposal	Remark
1.	-	63.830	2.00	RCC BOX	
2.	75.875	66.187	1.50	RCC BOX	
3.	84.525	74.170	1.50	RCC BOX	

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

4.	84.910	74.290	1.50	RCC BOX	
5.	85.885	75.420	2.00	RCC BOX	
6.	90.375	79.515	3.00	RCC BOX	
7.	91.890	80.870	1.50	RCC BOX	

**7.2.4** Widening/Repairs/replacements of railing/parapets, flooring and protection works of the existing culverts shall be undertaken as follows:

<b>Sr. No.</b>	<b>Design Chainage</b>	<b>Proposal</b>	<b>Proposed Span</b>
1.	67+320	Widening & Repairing	1.5x1.5
2.	69+201	Widening & Repairing	2.0x2.0
3.	70+942	Widening & Repairing	2.0x2.0
4.	71+018	Widening & Repairing	2.0x2.0
5.	72+037	Widening & Repairing	2.0x2.0
6.	73+840	Widening & Repairing	2.0x2.0
7.	75+652	Widening & Repairing	2.0x2.0
8.	78+104	Widening & Repairing	2.0x2.0
9.	79+520	Widening & Repairing	3.0x3.0
10.	80+620	Widening & Repairing	3.0x3.0
11.	80+994	Widening & Repairing	3.0 X3.0
12.	71+575	Widening & Repairing	2.0x2.0

**7.2.5** Floor protection works shall be as specified in the relevant IRC Codes and Specifications.

### **7. 3 Bridges**

**7.3.1** The existing bridges to be re-constructed/widened

(i) The existing bridges at the following locations shall be reconstructed as new structures:

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sr. No.	Bridge Location (Km)	Salient Details of Existing Bridges					Adequacy or Otherwise of the Existing Waterway, Vertical Clearance etc.	Remarks
		Span Arrangement (M)	Carriageway width (M)	Total width (M)	Type of Superstructure	Type of Foundation		
1.	89.900	1 x 15.25	3.5	4.0	Steel Truss	Not Visible	Inadequate	Reconstruction
2.	98.024	1 x 6.0	4.3	7.2	RCC Slab	Not Visible	Inadequate	Reconstruction

### 7.3.2 Additional New Bridges

#### (i) Minor Bridges

New minor bridges at the following locations on the project highways shall be constructed. GADs for the new minor bridges are attached in the drawings folder.

Sr. No.	Location Designed (Km)	Total Length (M)	Remarks
Nil			

#### (ii) Major bridges

New major bridges at the following locations on the project highways shall be constructed. GADs for the new major bridges are attached in the drawings folder.

Sr. No.	Location Designed (Km)	Total Length (M)	Remarks
Nil			

7.3.3 The railings of existing bridges shall be replaced by crash barriers at the following locations:

Sr. No.	Location (Km)	Remarks
Nil		

7.3.4 Repairs/replacements of railings/parapets of the existing bridges shall be undertaken as follows:

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sr. No.	Location (Km)	Remarks
Nil		

### 7.3.5 Drainage system for bridge decks

An effective drainage system for bridge decks shall be provided as specified in paragraph 7.20 of the Manual

### 7.3.6 Structures in marine environment

Nil

## 7.4 Rail-road Bridges

7.4.1 Design, construction and detailing of ROB/RUB shall be as specified in section 7 of the Manual.

### 7.4.2 Road over-bridges

Road over-bridges (road over rail) shall be provided at the following level crossings, as per GAD drawings attached:

Sr. No.	Location of Level Crossing (Km)	Length of Bridge (M)
Nil		

### 7.4.3 Road under-bridges

Road under-bridges (road under railway line) shall be provided at the following level crossings, as per GAD drawings attached:

Sr. No.	Location of Level Crossing (Km)	Number and Length of Span (M)
Nil		

## 7.5 Grade Separated Structures

The grade separated structures shall be provided at the locations and of the type and length specified in paragraphs 2.9 and 3 of this Annex-I.

### 7.5.1 Underpasses/Overpasses

There is no Underpass/Overpass proposed on the Project Highway.

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

## 7.6 Repairs and strengthening of bridges and structures

The existing bridges and structures to be repaired /strengthened, and the nature and extent of repairs/strengthening required are given below:

### A. Bridges

Sr. No.	Location of Bridge (Km)	Nature and Extent of Repairs/Strengthening to be carried out
Nil		

### B. ROB/RUB

Sr. No.	Location of ROB/RUB (Km)	Nature and Extent of Repairs/Strengthening to be carried out
Nil		

### C. Overpasses/Underpasses and Other Structures

Sr. No.	Location Structure (Km)	Nature and Extent of Repairs/Strengthening to be carried out
Nil		

## 7.7 List of Major Bridges and Structures

The following is the list of Major Bridges and Structures

Sr. No.	Location Design (Km)
Nil	

## 8.0 TRAFFIC CONTROL DEVICES AND ROAD SAFETY WORKS

8.1 Traffic control devices and road safety works shall be provided in accordance with Section 9 of the Manual.

8.2 Specifications of the reflective sheeting [Refer to paragraph 9.2 of the Manual and specify]

8.3 The minimum quantity of Traffic signages and pavement marking are tabulated here for Package

Traffic Signage's Road Marking and other appurtenances	Unit	Quantity
--	------	----------

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Road Marking on Centre line & Edge	Sqm	7191.1
Direction & Place Identification up to 0.9 sqm	Sqm	58
Direction & Place Identification more than 0.9 sqm	Sqm	Nil
60 cm Equilateral Triangle	Number	253
60 cm Circular	Number	40
60 cm High Octagon	Number	39
60 cm x 45 cm Rectangular	Number	49
60 cm x 50 cm Chevron Sign	Number	902
Hectometer Stone	Number	92
Km stone	Number	20
5 <sup>th</sup> Km stone	Number	4
Boundary Stone (as per clause 13 herein under)	Number	230
Road Delineators	Number	1492
Road Marker / Road Stud	Number	11520
Hazard Marker	Number	278
PCC kerbs (duly painted) in bus bays and islands	Rm	8149

## 9.0 ROAD SIDE FURNITURE

**9.1** Roadside furniture shall be provided in accordance with the provisions of Section 11 of the Manual IRC: SP: 73-2007 and corresponding updates as per IRC:SP 73 -2018

**9.2** Overhead traffic signs: location and size

The overhead signs shall be the reflectorized type with high intensity retro-reflective sheeting conforming to ASTM D 4956-01, type VIII and /or type IX of micro prismatic type. The retro reflected sheets of Engineering Grade and high intensity grade (ordinary) shall not be used. The height, lateral clearance, location the overhead signs shall be the reflectorized type with high intensity retro-reflective sheeting conforming to ASTM D 4956-01, type VIII and / or type IX of micro prismatic type. The retro reflected sheets of Engineering Grade and high intensity grade Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”



(ordinary) shall not be used. The height, lateral clearance, location and instillation shall be as per relevant clauses of MoRTH specifications. Overhead sign shall be installed ahead of major intersections and urban areas as per detailed design requirements. The minimum number of overhead signs shall be 02 (01 No. of gantry and 01 No. of Cantilever) as per this manual. Location shall be given by the AE.

## 10.0 COMPULSORY AFFORESTATION

Minimum 3000 nos. trees with deep and broad roots are required to be planted for soil conservation, in consultation with the Forest Department and AE for type and location.

## 11.0 HAZARDOUS LOCATIONS

Metal Beam crash barrier length of minimum 3170 (single runner, heavy duty and W-shape) or equivalent shall be provided at the locations of bridge approaches built up sections, high embankments (3.0m and more) and at sharp curves. Heavy duty metal beam crash barriers shall be provided on this project by the Construction Contractor at the locations finalized in consultation with NHIDCL.

Typical details of metal crash barrier are given in as per manual. Location of sharp curves are tabulated below.

Sr. No.	Design Chainage (M)		Side	Type of Deficiency	Remarks
	From	To			
1.	64322.56	64381.89	Left	Radius<40	
2.	64381.89	64441.87	Right	Radius<40	
3.	64482.91	64518.23	Left	Radius<40	
4.	64616.96	64695.26	Left	Radius<40	
5.	66360.13	66435.07	Left	Radius<40	
6.	66435.07	66506.46	Right	Radius<40	
7.	66546.96	66577.84	Left	Radius<40	
8.	69940.31	70003.85	Left	Radius<40	
9.	70313.88	70379.81	Left	Radius<40	

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sr. No.	Design Chainage (M)		Side	Type of Deficiency	Remarks
	From	To			
10.	70893.14	70953.05	Right	Radius<40	
11.	71429.76	71474.51	Right	Radius<40	
12.	72066.87	72127.27	Right	Radius<40	
13.	72824.77	72886.36	Right	Radius<40	
14.	72960.88	73024.56	Left	Radius<40	
15.	73684.59	73739.82	Right	Radius<40	
16.	76258.75	76330.76	Right	Radius<40	
17.	76391.33	76453.13	Right	Radius<40	
18.	76611.30	76710.85	Left	Radius<40	
19.	77072.18	77137.61	Left	Radius<40	
20.	77557.61	77617.19	Left	Radius<40	
21.	78431.95	78509.08	Left	Radius<40	
22.	78614.42	78673.22	Right	Radius<40	
23.	78956.46	79113.28	Right	Radius<40	
24.	79113.28	79181.23	Left	Radius<40	
25.	80046.15	80105.41	Right	Radius<40	
26.	80288.09	80343.62	Left	Radius<40	
27.	80582.27	80642.63	Left	Radius<40	
28.	80642.63	80706.11	Right	Radius<40	
29.	81129.14	81197.08	Left	Radius<40	

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sr. No.	Design Chainage (M)		Side	Type of Deficiency	Remarks
	From	To			
30.	81251.19	81332.47	Right	Radius<40	
31.	81640.96	81684.00	Right	Radius<40	
32.	82419.46	82477.28	Right	Radius<40	
33.	82562.32	82609.26	Left	Radius<40	
34.	82798.79	82842.93	Left	Radius<40	
35.	82893.21	82913.01	Left	Radius<40	
36.	82913.01	82933.70	Right	Radius<40	
37.	83141.80	83155.95	Left	Radius<40	
38.	83175.25	83196.29	Left	Radius<40	
39.	83238.02	83251.59	Right	Radius<40	
40.	83292.06	83339.02	Right	Radius<40	
41.	83355.01	83372.09	Left	Radius<40	
42.	83380.20	83392.52	Right	Radius<40	
43.	83411.39	83425.47	Left	Radius<40	
44.	83439.66	83463.38	Right	Radius<40	
45.	83490.14	83518.43	Left	Radius<40	
46.	83634.60	83687.90	Right	Radius<40	
47.	83733.72	83768.20	Left	Radius<40	
48.	84046.00	84078.96	Left	Radius<40	
49.	84373.77	84392.69	Left	Radius<40	

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Sr. No.	Design Chainage (M)		Side	Type of Deficiency	Remarks
	From	To			
50.	84406.88	84431.19	Right	Radius<40	
51.	84517.84	84548.64	Right	Radius<40	
52.	84587.00	84613.77	Left	Radius<40	
53.	84634.89	84670.54	Right	Radius<40	
54.	85164.04	85191.81	Left	Radius<40	
55.	85216.43	85238.74	Right	Radius<40	
56.	85451.62	85471.19	Left	Radius<40	
57.	85518.42	85530.41	Left	Radius<40	
58.	85570.04	85604.21	Left	Radius<40	
59.	85633.64	85658.38	Right	Radius<40	
60.	85839.27	85860.74	Right	Radius<40	
61.	85904.02	85948.45	Right	Radius<40	
62.	86049.86	86067.20	Left	Radius<40	
63.	86259.75	86284.52	Left	Radius<40	
64.	86340.48	86382.37	Left	Radius<40	
65.	86398.19	86426.10	Right	Radius<40	
66.	86551.42	86573.10	Right	Radius<40	
67.	86662.29	86703.67	Right	Radius<40	
68.	86703.67	86769.81	Left	Radius<40	
69.	86769.81	86788.81	Left	Radius<40	

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

## 12.0 SPECIAL REQUIREMENTS FOR HILL ROADS

In accordance with section 13 of the manual, IRC: SP: 48-1998 and Recommended practices for Treatment of Embankment and Roadside slopes for Erosion control (First Revision), IRC: 56-2011 and relevant IRC codes.

### 12. 1 Slope Protection

As the project involves cutting of existing hill slopes, it is imperative that slopes are stabilized for ensuring longevity of the slope and the road. Slope stability, erosion control and landslide correction shall be accomplished in accordance with IRC: SP: 48-1998. Reference may be drawn from IRC: 56- 2011.

The minimum quantity of protection work to be taken as below:

Type of Protection Work		
Protection Work	Unit	Minimum Quantity
Parapet Wall having size 0.45mx0.7m with 0.7 m spacing between two parapets	Rm	2,765
Breast wall of PCC/RCC/Gabion/Cement masonry having minimum height of 1.5 m	Rm	3,489
Retaining Structure on valley side of PCC/RCC/Gabion/Cement masonry of varying height between 1 to 6 meter depending upon the slope with parapet walls	Rm	5,605
RE wall in PCC	Rm	289
Subsurface drain with perforated pipe for collection of seepage water to avoid sinking of payment	Rm	1,098
Seeding and Mulching with Jute Net	Sqm	78,323
Hydro seeding	Sqm	16,195
Catch Water Drain (Unlined)	Rm	19,545

**Note-** The Contractor shall be responsible for accurate assessment of the actual requirement as per site situation Et prepare designs for slope protection & stabilization as per the specifications & standards stipulated in schedule 'D' and submit the same to the AE for review through the proof consultant and implement it accordingly thereafter.

Any increase in quantity (length, breadth and height) over and above the tentative quantity as mentioned in above table or change in specifications will not be considered as change of scope. Therefore contractor shall make thorough investigation at site and assess the requirement of slope protection and slide prone zone and other safety features at his own before submission of bid.

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

**12.1.1 Summary of Retaining Structure on valley side of varying height between 1 to 6metre depending upon the slope**

<b>Sr. No.</b>	<b>Height of Retaining Structure</b>	<b>Aggregate Length</b>
1	Upto 2 m	2149.6
2	2 m to 4 m	2691.4
3	4 m to 6 m	764

**12.1. 2 Tentative Locations and Length**

<b>Sr. No.</b>	<b>From Design Chainage (in M)</b>	<b>To Design Chainage (in M)</b>	<b>Length (M)</b>
1.	64+425	64+437	12
2.	64+563	64+568	5
3.	64+595	64+613	18
4.	64+755	64+765	10
5.	64+975	64+985	10
6.	65+285	65+375	90
7.	65+485	65+495	10
8.	65+532	65+545	13
9.	65+605	65+625	20
10.	65+695	65+707	12
11.	65+782	65+815	33
12.	65+916	65+965	49
13.	66+050	66+060	10
14.	66+096	66+115	19

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

<b>Sr. No.</b>	<b>From Design Chainage (in M)</b>	<b>To Design Chainage (in M)</b>	<b>Length (M)</b>
15.	67+045	67+055	10
16.	67+095	67+145	50
17.	67+252	67+335	83
18.	67+365	67+386	21
19.	67+455	67+475	20
20.	67+555	67+565	10
21.	68+876	68+883	7
22.	69+015	69+025	10
23.	69+865	69+876	11
24.	70+045	70+075	30
25.	70+285	70+325	40
26.	70+355	70+415	60
27.	70+615	70+625	10
28.	70+659	70+685	26
29.	70+745	70+807	62
30.	70+904	70+935	31
31.	71+000	71+165	165
32.	71+415	71+424	9
33.	71+575	71+605	30
34.	71+701	71+725	24
35.	71+755	71+763	8

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

<b>Sr. No.</b>	<b>From Design Chainage (in M)</b>	<b>To Design Chainage (in M)</b>	<b>Length (M)</b>
36.	71+768	71+795	27
37.	71+824	71+855	31
38.	71+884	71+925	41
39.	71+935	71+945	10
40.	71+985	71+995	10
41.	72+006	72+015	9
42.	72+065	72+165	100
43.	72+175	72+265	90
44.	72+315	72+365	50
45.	72+555	72+575	20
46.	72+616	72+644	28
47.	72+695	72+715	20
48.	73+015	73+075	60
49.	73+105	73+145	40
50.	73+275	73+315	40
51.	73+345	73+435	90
52.	73+455	73+565	110
53.	73+578	73+645	67
54.	73+775	73+855	80
55.	73+905	73+965	60
56.	73+994	74+035	41

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”



<b>Sr. No.</b>	<b>From Design Chainage (in M)</b>	<b>To Design Chainage (in M)</b>	<b>Length (M)</b>
57.	74+325	74+355	30
58.	74+415	74+445	30
59.	74+455	74+495	40
60.	75+515	75+525	10
61.	75+565	75+605	40
62.	75+645	75+685	40
63.	75+829	75+874	45
64.	75+943	76+025	82
65.	76+045	76+105	60
66.	76+147	76+225	78
67.	76+265	76+295	30
68.	76+335	76+345	10
69.	76+375	76+405	30
70.	76+535	76+575	40
71.	76+605	76+665	60
72.	76+725	76+735	10
73.	76+740	76+755	15
74.	76+813	76+905	92
75.	76+965	77+046	81
76.	77+083	77+115	32
77.	77+255	77+275	20

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

<b>Sr. No.</b>	<b>From Design Chainage (in M)</b>	<b>To Design Chainage (in M)</b>	<b>Length (M)</b>
78.	77+405	77+455	50
79.	77+525	77+538	13
80.	77+807	77+836	29
81.	77+855	77+863	8
82.	77+904	77+915	11
83.	77+955	77+995	40
84.	78+155	78+206	51
85.	78+245	78+255	10
86.	78+315	78+428	113
87.	78+485	78+513	28
88.	78+535	78+596	61
89.	78+698	78+808	110
90.	78+815	78+825	10
91.	78+855	78+865	10
92.	78+878	78+956	79
93.	78+956	78+958	2
94.	79+516	79+545	29
95.	79+575	79+605	30
96.	79+635	79+665	30
97.	79+684	79+705	21
98.	79+735	79+795	60

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

<b>Sr. No.</b>	<b>From Design Chainage (in M)</b>	<b>To Design Chainage (in M)</b>	<b>Length (M)</b>
99.	79+855	79+885	30
100.	79+955	80+015	60
101.	80+069	80+085	16
102.	80+105	80+175	70
103.	80+215	80+305	90
104.	80+465	80+578	113
105.	80+595	80+635	40
106.	80+667	80+745	78
107.	80+805	80+815	10
108.	80+865	81+015	150
109.	81+055	81+085	30
110.	81+125	81+130	5
111.	81+135	81+185	50
112.	81+195	81+254	59
113.	81+265	81+545	280
114.	81+565	81+585	20
115.	81+595	81+615	20
116.	81+625	81+635	10
117.	81+775	81+845	70
118.	81+855	81+915	60
119.	81+985	82+075	90

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

<b>Sr. No.</b>	<b>From Design Chainage (in M)</b>	<b>To Design Chainage (in M)</b>	<b>Length (M)</b>
120.	82+095	82+175	80
121.	82+205	82+325	120
122.	82+335	82+453	118
123.	82+475	82+485	10
124.	82+496	82+525	29
125.	82+545	82+566	21
126.	82+595	82+675	80
127.	82+685	82+695	10
128.	82+735	82+800	65
<b>Total</b>			<b>5605</b>

### 12.1.3 Reinforced Earth Wall

The locations for providing RE wall are listed in the table below.

Improvement Proposals: Reinforced Earth Wall Length

<b>Sr. No.</b>	<b>From Chainage (in M)</b>	<b>To Chainage (in M)</b>	<b>Length (M)</b>
1.	63+875	63+915	40
2.	73+565	73+573	8
3.	75+525	75+565	40
4.	75+605	75+645	40
5.	75+685	75+723	38
6.	75+735	75+795	60
7.	75+805	75+815	10

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

8.	78+513	78+535	23
9.	79+665	79+675	10
10.	82+525	82+545	20
<b>Total</b>			<b>289</b>

**12.1.4 Subsurface Drains:** Location of Subsurface drain with perforated pipe are provided at water seepage locations for collection of seepage water to avoid sinking of pavement

#### **Water Seepage Locations**

<b>Sr. No.</b>	<b>Existing Location From</b>	<b>New Design Chainage From</b>
1.	68+740	Realignment
2.	82+960	72+720
3.	85+580	75+200

## **12.2 ROAD LAND BOUNDARY (Clause 12.2 IRC SP: 73: 2015)**

Road land (ROW) boundary shall be demarcated by putting RCC boundary pillars of size 60cm x 15cm x 15 cm embedded in concrete (as per IRC:25) along the Project Highway at 50 m interval on both sides. All the components used in delineating road land boundary shall be aesthetically pleasing, sturdy and vandal proof. The road land boundary shall be demarcated in consultation with NHIDCL.

## **12.3 Disposal of Debris: - As per Manual**

## **13.0 CHANGE OF SCOPE**

The size of Structures, bridges, culverts and slope protection works whatsoever in terms of retaining wall, breast wall, gabion wall, RE wall, chute drain, catch pit, baffle piers/blocks etc. Under special requirement of hill slope specified hereinabove shall be treated as an approximate assessment. The actual lengths, heights and widths as required on the basis of detailed investigations shall be determined by the Contractor in accordance with the Specifications and Standards. Any variations in the lengths, heights and widths and specifications in this Schedule-B shall not constitute a Change of Scope, save and except any variations in the length, height and width arising out of a Change of Scope expressly undertaken in accordance with the provisions of Article 13.

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

SCHEDULE – C  
(See Clause 2.1)

**PROJECT FACILITIES**

**1 Project Facilities**

The Contractor shall construct the Project Facilities in accordance with the provisions of this Agreement. Such Project Facilities shall include:

- (a) Roadside furniture
- (b) Pedestrian facilities
- (c) Tree plantation
- (d) Bus shelters
- (e) Passing Places
- (f) Truck lay byes and
- (g) Others to be specified

**2 Description of Project Facilities**

**Toll Plaza**

NIL

**Bus Shelters**

To ensure orderly movement of the through traffic, bus shelters have been proposed outside the residential area, away from bridges, and high embankments and not too close to the road intersections. The bus stops have been proposed on one side of the road.

Bus shelters 6 Nos shall be provided on the Project Highway at 3 locations as mentioned herein under. Bus shelters shall be constructed as per Manual on both sides of the Project Highway. These bus shelters will also have passenger shelter.

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

**Details of Bus Shelters**

<b>SL. No.</b>	<b>Project Facility (in pair)</b>	<b>Design Chainage (km)</b>
<b>1</b>	<b>Bus Shelter</b>	<b>67+500</b>
<b>2</b>	<b>Bus Shelter</b>	<b>78+300</b>
<b>3</b>	<b>Bus Shelter</b>	<b>84+500</b>

**Pedestrian Facilities**

Pedestrian facilities shall be provided at the locations of urban sections in order to ensure safety of pedestrians while crossing in consultation with AE. This should include (a) minimum Zebra Crossing with flashing Beacon or (b) Zebra Crossing with separate pedestrian phase or (c) any other provision as approved by AE.

**Landscaping**

Landscape treatment of the Project Highway shall be undertaken through planting of trees and ground cover of appropriate varieties and landscaping on surplus land in the ROW. The Construction Contractor should plant at least 3000 nos. of trees of minimum 6 ft. height with tree guard made up of MS sections.

Plantation scheme shall be prepared in consultation with the Forest Department of the Government of Nagaland, and AE.

**Environment**

The Project Highway during design, construction and maintenance during implementation period shall conform to the environmental rules and regulations in force. The Construction Contractor shall be responsible for the same

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

## **SCHEDULE – D**

*(See Clause 2.1)*

### **SPECIFICATIONS AND STANDARDS**

#### **1. Construction**

The Contractor shall comply with the Specifications and Standards set forth in Annex – I of this Schedule – D for construction of the Project Highway.

#### **2. Design Standards**

The Project Highway including Project Facilities shall conform to design requirements set out in the following documents:

Manual of specification and standards for two laning of Highways with paved shoulder (Second revision) IRC:SP:73-2018, Hill road manual IRC:SP:48-1998 and Specification of roads and bridges work (fifth revision), MoRTH.



Annex – I  
(Schedule – D)

## Specifications and Standards for Construction

### 1 Specifications and Standards

All materials, works and construction operations shall confirm to the Manual of Specifications and Standards for Two Laning of Highways (IRC: SP: 73 – 2018), referred as the Manual, MORTH Specifications for Road and Bridge Works, and IRC: SP: 48-1998. Where the specification for a work is not given, Good Industry Practice shall be adopted to the satisfaction of the Authority’s Engineer.

### 2 Deviations from the Specifications and Standards

The terms ‘Concessionaire’, ‘Independent Engineer’ and ‘Concession Agreement’ used in the Manual (IRC: SP 73- 2018) shall be deemed to be substituted by the terms ‘**Contractor**’, ‘**Authority’s Engineer**’ and ‘**Agreement**’ respectively.

Notwithstanding anything to the contrary contained in Paragraph 1 above, the following Specifications and Standards shall apply to the Project Highway, and for purposes of this Agreement, aforesaid Specifications and Standards of following clauses shall be deemed to be amended to the extent set forth below:

S. No.	Clause	Provision as per Manual ( IRC:SP:73-2018)	Modified Provision
1	2.2	<b>Design Speed:</b> Ruling or minimum Design speed shall be followed	Design speed shall be as per IRC 73:2018 for project highway excepting hair pin bend locations wherein design speed shall be as per IRC 73:2018. The same is mentioned in the Plan&Profile drawings given in <b>Annexure-III</b> of <b>Schedule A</b> .
2	2.7.2	<b>Roadway Width:</b> On horizontal curves with radius up to 300 m width of pavement and roadway shall be increased as per Table 2.4	On horizontal Curves with radius up to 300 m width of pavement and roadway shall be increased as per Plan & Profile drawings given in Annexure – III of Schedule A
3	2.9.4	<b>Radius of Horizontal Curves:</b>	Radius of Horizontal curves shall be as per the alignment plan shown in Plan & Profile drawings given in <b>Annexure-III</b> of <b>Schedule A</b> .

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

## SCHEDULE - E

*(See Clauses 2.1 and 14.2)*

### **MAINTENANCE REQUIREMENTS**

#### **1. Maintenance Requirements**

The Contractor shall, at all times maintain the Project Highway in accordance with the provisions of this Agreement, Applicable Laws and Applicable Permits.

The Contractor shall repair or rectify any Defect or deficiency set forth in Paragraph 2 of this Schedule-E within the time limit specified therein and any failure in this behalf shall constitute non-fulfilment of the Maintenance obligations by the Contractor. Upon occurrence of any breach hereunder, the Authority shall be entitled to effect reduction in monthly lump sum payment as set forth in Clause 14.6 of this Agreement, without prejudice to the rights of the Authority under this Agreement, including Termination thereof.

All Materials, works and construction operations shall conform to the MORTH Specifications for Road and Bridge Works, and the relevant IRC publications. Where the specifications for a work are not given, Good Industry Practice shall be adopted.

#### **2.Repair/Rectification of Defects and Deficiencies**

The obligations of the Contractor in respect of Maintenance Requirements shall include repair and rectification of the Defects and deficiencies specified in Annex - I of this Schedule-E within the time limit set forth therein.

#### **3. Other Defects and Deficiencies**

In respect of any Defect or deficiency not specified in Annex - I of this Schedule-E, the Authority's Engineer may, in conformity with Good Industry Practice, specify the permissible limit of deviation or deterioration with reference to the Specifications and Standards, and any deviation or deterioration beyond the permissible limit shall be repaired or rectified by the Contractor within the time limit specified by the Authority's Engineer.

#### **4. Extension of Time Limit**

Notwithstanding anything to the contrary specified in this Schedule-E, if the nature and extent of any Defect or deficiency justifies more time for its repair or rectification than the time specified

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

herein, the Contractor shall be entitled to additional time in conformity with Good Industry Practice. Such additional time shall be determined by the Authority's Engineer and conveyed to the Contractor and the Authority with reasons thereof.

### **5. Emergency Repairs/Restoration**

Notwithstanding anything to the contrary contained in this Schedule-E, if any Defect, deficiency or deterioration in the Project Highway poses a hazard to safety or risk of damage to property, the Contractor shall promptly take all reasonable measures for eliminating or minimizing such danger.

### **6. Daily inspection by the Contractor**

The Contractor shall, through its engineer, undertake a daily visual inspection of the Project Highway and maintain a record thereof in a register to be kept in such form and manner as the Authority's Engineer may specify. Such record shall be kept in safe custody of the Contractor and shall be open to inspection by the Authority and the Authority's Engineer at any time during office hours.

### **7. Pre-monsoon Inspection / Post-monsoon Inspection**

The Contractor shall carry out a detailed pre-monsoon inspection of all bridges, culverts and drainage system before [1st June] every year in accordance with the guidelines contained in IRC: SP35. Report of this inspection together with details of proposed maintenance works as required on the basis of this inspection shall be sent to the Authority's Engineer before the [10th June] every year. The Contractor shall complete the required repairs before the onset of the monsoon and send to the Authority's Engineer a compliance report. Post monsoon inspection shall be done by the [30th September] and the inspection report together with details of any damages observed and proposed action to remedy the same shall be sent to the Authority's Engineer.

### **8. Repairs on account of natural calamities**

All damages occurring to the Project Highway on account of a Force Majeure Event or default or neglect of the Authority shall be undertaken by the Authority at its own cost. The Authority may instruct the Contractor to undertake the repairs at the rates agreed between the Parties.

## Annex - I

*(Schedule-E)***Repair/rectification of Defects and Deficiencies**

The Contractor shall repair and rectify the Defects and deficiencies specified in this Annex-I of Schedule-E within the time limit set forth in the table below.

Nature of Defect or deficiency		Time limit for repair/rectification
<b>ROADS</b>		
<b>(a)</b>	<b>Carriageway and paved shoulders</b>	
(i)	Breach or blockade	Temporary restoration of traffic within 24 hours; permanent restoration within 15 (fifteen) days
(ii)	Roughness value exceeding 2,200 mm in a stretch of 1 km (as measured by a calibrated bump integrator)	120 (one hundred and twenty) days
(iii)	Pot holes	24 hours
(iv)	Any cracks in road surface	15 (fifteen) days
(v)	Any depressions, rutting exceeding 10 mm in road surface	30 (thirty) days
(vi)	Bleeding/skidding	7 (seven) days
(vii)	Any other defect/distress on the road	15 (fifteen) days
(viii)	Damage to pavement edges	15 (fifteen) days
(ix)	Removal of debris, dead animals	6 hours
<b>(b)</b>	<b>Granular earth shoulders, side slopes, drains and culverts</b>	
(i)	Variation by more than 1 % in the prescribed slope of camber/cross fall (shall not be less than the camber on the main carriageway)	7 (seven) days
(ii)	Edge drop at shoulders exceeding 40 mm	7 (seven) days
(iii)	Variation by more than 15% in the prescribed side (embankment) slopes	30 (thirty) days
(iv)	Rain cuts/gullies in slope	7 (seven) days
(v)	Damage to or silting of culverts and side drains	7 (seven) days

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Nature of Defect or deficiency		Time limit for repair/rectification
(vi)	Desilting of drains in urban/semi-urban areas	24 hours
(vii)	Railing, parapets, crash barriers	7 (seven) days (Restore immediately if causing safety hazard)
<b>(c)</b>	<b>Road side furniture including road sign and pavement marking</b>	
(i)	Damage to shape or position, poor visibility or loss of retro-reflectivity	48 hours
(ii)	Painting of km stone, railing, parapets, crash barriers	As and when required/Once every year
(iii)	Damaged/missing road signs requiring replacement	7 (seven) days
(iv)	Damage to road mark ups	7 (seven) days
<b>(d)</b>	<b>Road Lighting</b>	
(i)	Any major failure of the system	24 hours
(ii)	Faults and minor failures	8 hours
<b>(e)</b>	<b>Trees and Plantation</b>	
(i)	Obstruction in a minimum head-room of 5 m above carriageway or obstruction in visibility of road signs	24 hours
(ii)	Removal of fallen trees from carriageway	4 hours
(iii)	Deterioration in health of trees and bushes	Timely watering and treatment
(iv)	Trees and bushes requiring replacement	30 (thirty) days
(v)	Removal of vegetation affecting sight line and road structures	15 (fifteen) days
<b>(f)</b>	<b>Rest Area</b>	
(i)	Cleaning of toilets	Every 4 hours
(ii)	Defects in electrical, water and sanitary installations	24 hours
<b>(g)</b>	<b>Toll Plazas</b>	
<b>(h)</b>	<b>Other Project Facilities and Approach Roads</b>	
(i)	Damage in approach roads, pedestrian facilities, truck lay-byes, bus-bays, bus-shelters, cattle crossings, [Traffic Aid Posts, Medical Aid Posts] and service roads	15 (fifteen) days

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Nature of Defect or deficiency		Time limit for repair/rectification
(ii)	Damaged vehicles or debris on the road	4 (four) hours
(iii)	Malfunctioning of the mobile crane	4 (four) hours
<b>Bridges</b>		
<b>(a)</b>	<b>Superstructure</b>	
(i)	Any damage, cracks, spalling/ scaling Temporary measures Permanent measures	within 48 hours within 15 (fifteen) days or as specified by the Authority's Engineer
<b>(b)</b>	<b>Foundations</b>	
(i)	Scouring and/or cavitation	15 (fifteen) days
<b>(c)</b>	<b>Piers, abutments, return walls and wing walls</b>	
(i)	Cracks and damages including settlement and tilting, spalling, scaling	30 (thirty) days
<b>(d)</b>	<b>Bearings (metallic) of bridges</b>	
(i)	Deformation, damages, tilting or shifting of bearings	15 (fifteen) days Greasing of metallic bearings once in a year
<b>(e)</b>	<b>Joints</b>	
(i)	Malfunctioning of joints	15 (fifteen) days
<b>(f)</b>	<b>Other items</b>	
(i)	Deforming of pads in elastomeric bearings	7 (seven) days
(ii)	Gathering of dirt in bearings and joints; or clogging of spouts, weep holes and vent-holes	3 (three) days
(iii)	Damage or deterioration in kerbs, parapets, handrails and crash barriers	3 (three) days (Immediately within 24 hours if posing danger to safety)
(iv)	Rain-cuts or erosion of banks of the side slopes of approaches	7 (seven) days
(v)	Damage to wearing coat	15 (fifteen) days
(vi)	Damage or deterioration in approach slabs, pitching, apron, toes, floor or guide bunds	30 (thirty) days
(vii)	Growth of vegetation affecting the structure or obstructing the waterway	15 (fifteen) days

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Nature of Defect or deficiency		Time limit for repair/rectification
<b>(g)</b>	<b>Hill Roads</b>	
(i)	Damage to retaining wall/breast wall	7 (seven) days
(ii)	Landslides requiring clearance	12 (twelve) hours
(iii)	Snow requiring clearance	24 (twenty-four) hours

[Note: Where necessary, the Authority may modify the time limit for repair/rectification, or add to the nature of Defect or deficiency before issuing the bidding document, with the approval of the competent authority.]

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

**SCHEDULE - F**  
(See Clause 3.1.7(a))

**APPLICABLE PERMITS**

**1 Applicable Permits**

The Contractor shall obtain, as required under the Applicable Laws, the following Applicable Permits:

- a) Permission of the State Government for extraction of boulders from quarry;
- b) Permission of Village Panchayats and Pollution Control Board for installation of crushers;
- c) License for use of explosives;
- d) Permission of the State Government for drawing water from river/reservoir;
- e) License from inspector of factories or other competent Authority for setting up batching plant;
- f) Clearance of Pollution Control Board for setting up batching plant;
- g) Clearance of Village Panchayats and Pollution Control Board for setting up asphalt plant;
- h) Permission of Village Panchayats and State Government for borrow earth; and
- i) Any other permits or clearances required under Applicable Laws.

Applicable Permits, as required, relating to environmental protection and conservation shall have been procured by the Authority in accordance with the provisions of this Agreement.

The agency need to ensure compliance of AIP and FC stated in schedules 'A', Annexure – IV. The necessary certifications need to be obtained from competent local forest department.

Muck dumping locations in forest area to be freezed in consultation with the forest department, the necessary certifications from local competent forest department is to be submitted.



SCHEDULE - G  
(See Clauses 7.1.1, 7.5.3 and 19.2)  
**FORM OF BANK GUARANTEE**  
Annex-I  
(See Clause 7.1.1)  
**Performance Security**

The Managing Director,  
National Highways & Infrastructural Development Corporation Ltd.  
PTI Building, 3<sup>rd</sup> Floor,  
4, Parliament Street  
New Delhi - 110001

WHEREAS:

\_\_\_\_\_ [name and address of contractor] (hereinafter called the “**Contractor**”) and Managing Director, NHIDCL, PTI Building, 3<sup>rd</sup> Floor, 4, Parliament Street, New Delhi-110001 (hereinafter called the “**Authority**”) have entered into an agreement (hereinafter called the “**Agreement**”) for the Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

, subject to and in accordance with the provisions of the Agreement

- A. The Agreement requires the Contractor to furnish a Performance Security for due and faithful performance of its obligations, under and in accordance with the Agreement, during the {Construction Period/ Defects Liability Period and Maintenance Period} (as defined in the Agreement) in a sum of Rs. .... cr. (Rupees ..... crore) (the “**Guarantee Amount**”).
- B. We, ..... through our branch at ..... (the “**Bank**”) have agreed to furnish this bank guarantee (hereinafter called the “**Guarantee**”) by way of Performance Security.

NOW, THEREFORE, the Bank hereby, unconditionally and irrevocably, guarantees and affirms as follows:

- 1. The Bank hereby unconditionally and irrevocably guarantees the due and faithful performance of the Contractor’s obligations during the {Construction Period/ Defects Liability Period and Maintenance Period} under and in accordance with the Agreement, and agrees and undertakes to pay to the Authority, upon its mere first written demand, and without any demur, reservation, recourse, contest or protest, and without any reference to the Contractor, such sum or sums up to an aggregate sum of the Guarantee Amount as the Authority shall claim, without the Authority being required to prove or to show grounds or reasons for its demand and/or for the sum specified therein.

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

2. A letter from the Authority, under the hand of an officer not below the rank of [General Manager in the National Highways & Infrastructural Development Corporation Ltd], that the Contractor has committed default in the due and faithful performance of all or any of its obligations under and in accordance with the Agreement shall be conclusive, final and binding on the Bank. The Bank further agrees that the Authority shall be the sole judge as to whether the Contractor is in default in due and faithful performance of its obligations during and under the Agreement and its decision that the Contractor is in default shall be final and binding on the Bank, notwithstanding any differences between the Authority and the Contractor, or any dispute between them pending before any court, tribunal, arbitrators or any other authority or body, or by the discharge of the Contractor for any reason whatsoever.
3. In order to give effect to this Guarantee, the Authority shall be entitled to act as if the Bank were the principal debtor and any change in the constitution of the Contractor and/or the Bank, whether by their absorption with any other body or corporation or otherwise, shall not in any way or manner affect the liability or obligation of the Bank under this Guarantee.
4. It shall not be necessary, and the Bank hereby waives any necessity, for the Authority to proceed against the Contractor before presenting to the Bank its demand under this Guarantee.
5. The Authority shall have the liberty, without affecting in any manner the liability of the Bank under this Guarantee, to vary at any time, the terms and conditions of the Agreement or to extend the time or period for the compliance with, fulfilment and/ or performance of all or any of the obligations of the Contractor contained in the Agreement or to postpone for any time, and from time to time, any of the rights and powers exercisable by the Authority against the Contractor, and either to enforce or forbear from enforcing any of the terms and conditions contained in the Agreement and/or the securities available to the Authority, and the Bank shall not be released from its liability and obligation under these presents by any exercise by the Authority of the liberty with reference to the matters aforesaid or by reason of time being given to the Contractor or any other forbearance, indulgence, act or omission on the part of the Authority or of any other matter or thing whatsoever which under any law relating to sureties and guarantors would but for this provision have the effect of releasing the Bank from its liability and obligation under this Guarantee and the Bank hereby waives all of its rights under any such law.
6. This Guarantee is in addition to and not in substitution of any other guarantee or security now or which may hereafter be held by the Authority in respect of or relating to the Agreement or for the fulfilment, compliance and/or performance of all or any of the obligations of the Contractor under the Agreement.
7. Notwithstanding anything contained hereinbefore, the liability of the Bank under this Guarantee is restricted to the Guarantee Amount and this Guarantee will

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

remain in force for the period specified in paragraph 8 below and unless a demand or claim in writing is made by the Authority on the Bank under this Guarantee all rights of the Authority under this Guarantee shall be forfeited and the Bank shall be relieved from its liabilities hereunder.

8. The Guarantee shall cease to be in force and effect on \*\*\*\*<sup>\$</sup>. Unless a demand or claim under this Guarantee is made in writing before expiry of the Guarantee, the Bank shall be discharged from its liabilities hereunder.
9. The Bank undertakes not to revoke this Guarantee during its currency, except with the previous express consent of the Authority in writing, and declares and warrants that it has the power to issue this Guarantee and the undersigned has full powers to do so on behalf of the Bank.
10. Any notice by way of request, demand or otherwise hereunder may be sent by post addressed to the Bank at its above referred branch, which shall be deemed to have been duly authorised to receive such notice and to effect payment thereof forthwith, and if sent by post it shall be deemed to have been given at the time when it ought to have been delivered in due course of post and in proving such notice, when given by post, it shall be sufficient to prove that the envelope containing the notice was posted and a certificate signed by an officer of the Authority that the envelope was so posted shall be conclusive.
11. This Guarantee shall come into force with immediate effect and shall remain in force and effect for up to the date specified in paragraph 8 above or until it is released earlier by the Authority pursuant to the provisions of the Agreement.
12. This guarantee shall also be operable at our..... Branch at New Delhi, from whom, confirmation regarding the issue of this guarantee or extension / renewal thereof shall be made available on demand. In the contingency of this guarantee being invoked and payment thereunder claimed, the said branch shall accept such invocation letter and make payment of amounts so demanded under the said invocation.
13. Bank Guarantee has been sent to authority's bank through SFMS gateway as per the details below: -

Sl. No	Particulars	Details
1	Name of the Beneficiary	National Highways and Infrastructure Development Corporation Limited

<sup>\$</sup>Insert date being 2 (two) years from the date of issuance of this Guarantee (in accordance with Clause 7.2 of the Agreement).

2	Beneficiary Bank Account No.	90621010002610
3	Beneficiary Bank Branch	IFSC CNRB0019062
4	Beneficiary Bank Branch Name	Transport Bhawan, New Delhi
5	Beneficiary Bank Address	Syndicate Bank, Transport Bhawan, 1st Parliament street, New Delhi-110001

Signed and sealed this ..... day of ....., 20..... at .....

SIGNED, SEALED AND DELIVERED

For and on behalf of the Bank by:

(Signature)

(Name)

(Designation)

(Code Number)

(Address)

NOTES:

(i) The bank guarantee should contain the name, designation and code number of the officer(s) signing the guarantee.

(ii) The address, telephone number and other details of the head office of the Bank as well as of issuing branch should be mentioned on the covering letter of issuing branch.

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

Annex – II  
(Schedule - G)  
(See Clause 7.5.3)

**Form for Guarantee for Withdrawal of Retention Money**

The Managing Director,  
National Highways & Infrastructural Development Corporation Ltd.  
PTI Building, 3<sup>rd</sup> Floor,  
4, Parliament Street  
New Delhi - 110001

WHEREAS:

(A) [name and address of contractor] (hereinafter called the “**Contractor**”) has executed an agreement (hereinafter called the “**Agreement**”) with the and The Managing Director , NHIDCL, PTI Building, New Delhi (hereinafter called the “**Authority**”) have entered into an agreement (hereinafter called the “**Agreement**”) for the Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

, subject to and in accordance with the provisions of the Agreement.

(B) In accordance with Clause 7.5.3 of the Agreement, the Contractor may withdraw the retention money (hereinafter called the “**Retention Money**”) after furnishing to the Authority a bank guarantee for an amount equal to the proposed withdrawal.

(C) We, ..... through our branch at ..... (the “**Bank**”) have agreed to furnish this bank guarantee (hereinafter called the “**Guarantee**”) for the amount of Rs. ----- cr. (Rs -----crore) (the “**Guarantee Amount**”).

NOW, THEREFORE, the Bank hereby unconditionally and irrevocably guarantees and affirms as follows:

1. The Bank hereby unconditionally and irrevocably undertakes to pay to the Authority, upon its mere first written demand, and without any demur, reservation, recourse, contest or protest, and without any reference to the Contractor, such sum or sums up to an aggregate sum of the Guarantee Amount as the Authority shall claim, without the Authority being required to prove or to show grounds or reasons for its demand and/or for the sum specified

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A”

therein.

2. A letter from the Authority, under the hand of an officer not below the rank of General Manager in the National Highways & Infrastructural Development Corporation Ltd, that the Contractor has committed default in the due and faithful performance of all or any of its obligations for under and in accordance with the Agreement shall be conclusive, final and binding on the Bank. The Bank further agrees that the Authority shall be the sole judge as to whether the Contractor is in default in due and faithful performance of its obligations during and under the Agreement and its decision that the Contractor is in default shall be final, and binding on the Bank, notwithstanding any differences between the Authority and the Contractor, or any dispute between them pending before any court, tribunal, arbitrators or any other authority or body, or by the discharge of the Contractor for any reason whatsoever.
3. In order to give effect to this Guarantee, the Authority shall be entitled to act as if the Bank were the principal debtor and any change in the constitution of the Contractor and/or the Bank, whether by their absorption with any other body or corporation or otherwise, shall not in any way or manner affect the liability or obligation of the Bank under this Guarantee.
4. It shall not be necessary, and the Bank hereby waives any necessity, for the Authority to proceed against the Contractor before presenting to the Bank its demand under this Guarantee.
5. The Authority shall have the liberty, without affecting in any manner the liability of the Bank under this Guarantee, to vary at any time, the terms and conditions of the Retention Money and any of the rights and powers exercisable by the Authority against the Contractor, and either to enforce or forbear from enforcing any of the terms and conditions contained in the Agreement and/or the securities available to the Authority, and the Bank shall not be released from its liability and obligation under these presents by any exercise by the Authority of the liberty with reference to the matters aforesaid or by reason of time being given to the Contractor or any other forbearance, indulgence, act or omission on the part of the Authority or of any other matter or thing whatsoever which under any law relating to sureties and guarantors would but for this provision have the effect of releasing the Bank from its liability and obligation under this Guarantee and the Bank hereby waives all of its rights under any such law.
6. This Guarantee is in addition to and not in substitution of any other guarantee or security now or which may hereafter be held by the Authority in respect of or relating to the Retention Money.
7. Notwithstanding anything contained hereinbefore, the liability of the Bank under this Guarantee is restricted to the Guarantee Amount and this Guarantee will remain in force for the period specified in paragraph 8 below and unless a demand or claim in writing is made by the Authority on the Bank under this Guarantee all rights of the Authority under this Guarantee shall be forfeited and the Bank shall be relieved from its liabilities hereunder.

8. The Guarantee shall cease to be in force and effect 90 (ninety) days after the date of the Completion Certificate specified in Clause 12.4 of the Agreement.
9. The Bank undertakes not to revoke this Guarantee during its currency, except with the previous express consent of the Authority in writing, and declares and warrants that it has the power to issue this Guarantee and the undersigned has full powers to do so on behalf of the Bank.
10. Any notice by way of request, demand or otherwise hereunder may be sent by post addressed to the Bank at its above referred branch, which shall be deemed to have been duly authorized to receive such notice and to effect payment thereof forthwith, and if sent by post it shall be deemed to have been given at the time when it ought to have been delivered in due course of post and in proving such notice, when given by post, it shall be sufficient to prove that the envelope containing the notice was posted and a certificate signed by an officer of the Authority that the envelope was so posted shall be conclusive.
11. This Guarantee shall come into force with immediate effect and shall remain in force and effect up to the date specified in paragraph 8 above or until it is released earlier by the Authority pursuant to the provisions of the Agreement.
12. This guarantee shall also be operable at our..... Branch at New Delhi, from whom, confirmation regarding the issue of this guarantee or extension / renewal thereof shall be made available on demand. In the contingency of this guarantee being invoked and payment thereunder claimed, the said branch shall accept such invocation letter and make payment of amounts so demanded under the said invocation.
13. Bank Guarantee has been sent to authority's bank through SFMS gateway as per the details below: -

Sl. No	Particulars	Details
1	Name of the Beneficiary	National Highways and Infrastructure Development Corporation Limited
2	Beneficiary Bank Account No.	90621010002610
3	Beneficiary Bank Branch	IFSC CNRB0019062
4	Beneficiary Bank Branch Name	Transport Bhawan, New Delhi
5	Beneficiary Bank Address	Syndicate Bank, Transport Bhawan, 1st Parliament street, New Delhi-110001

Signed and sealed this ..... day of ....., 20..... at .....

Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length- 23.035 km) in the state of Nagaland under SARDP-NE Phase A”

**SIGNED, SEALED AND DELIVERED**

For and on behalf of the Bank by:

(Signature)

(Name)

(Designation)

(Code Number)

(Address)

NOTES:

- (i) The bank guarantee should contain the name, designation and code number of the officer(s) signing the guarantee.
- (ii) The address, telephone number and other details of the head office of the Bank as well as of issuing branch should be mentioned on the covering letter of issuing branch.



Annex – III  
(Schedule - G)  
(See Clause 19.2)

**Form for Guarantee for Advance Payment**

The Managing Director,  
National Highways & Infrastructural Development Corporation Ltd.  
PTI Building, 3<sup>rd</sup> Floor,  
4, Parliament Street  
New Delhi - 110001

WHEREAS:

(A) [name and address of contractor] (hereinafter called the “Contractor”) has executed an agreement (hereinafter called the “Agreement”) with the Managing Director, Head Office New Delhi (hereinafter called the “Authority”) have entered into an agreement (hereinafter called the “Agreement”) for the Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A

, subject to and in accordance with the provisions of the Agreement.

(B) In accordance with Clause 19.2 of the Agreement, the Authority shall make to the Contractor an interest free advance payment (herein after called “**Advance Payment**”) equal to 10% (ten per cent) of the Contract Price; and that the Advance Payment shall be made in three installments subject to the Contractor furnishing an irrevocable and unconditional guarantee by a scheduled bank for an amount equivalent to 110% (one hundred and ten percent) of such installment to remain effective till the complete and full repayment of the installment of the Advance Payment as security for compliance with its obligations in accordance with the Agreement. The amount of {first/second/third} installment of the Advance Payment is Rs. --- --- cr. (Rupees ----- crore) and the amount of this Guarantee is Rs. ----- cr. (Rupees ----- crore)(the “**Guarantee Amount**”)<sup>§</sup>.

(C) We, ..... through our branch at..... (the “**Bank**”) have agreed to furnish this bank guarantee (hereinafter called the “**Guarantee**”) for the Guarantee Amount.

NOW, THEREFORE, the Bank hereby, unconditionally and irrevocably, guarantees and affirms as follows:

---

<sup>§</sup>The Guarantee Amount should be equivalent to 110% of the value of the applicable instalment.

1. The Bank hereby unconditionally and irrevocably guarantees the due and faithful repayment on time of the aforesaid instalment of the Advance Payment under and in accordance with the Agreement, and agrees and undertakes to pay to the Authority, upon its mere first written demand, and without any demur, reservation, recourse, contest or protest, and without any reference to the Contractor, such sum or sums up to an aggregate sum of the Guarantee Amount as the Authority shall claim, without the Authority being required to prove or to show grounds or reasons for its demand and/or for the sum specified therein.
2. A letter from the Authority, under the hand of an officer not below the rank of [General Manager in the National Highways & Infrastructural Development Corporation Ltd], that the Contractor has committed default in the due and faithful performance of all or any of its obligations for the repayment of the instalment of the Advance Payment under and in accordance with the Agreement shall be conclusive, final and binding on the Bank. The Bank further agrees that the Authority shall be the sole judge as to whether the Contractor is in default in due and faithful performance of its obligations during and under the Agreement and its decision that the Contractor is in default shall be final and binding on the Bank, notwithstanding any differences between the Authority and the Contractor, or any dispute between them pending before any court, tribunal, arbitrators or any other authority or body, or by the discharge of the Contractor for any reason whatsoever.
3. In order to give effect to this Guarantee, the Authority shall be entitled to act as if the Bank were the principal debtor and any change in the constitution of the Contractor and/or the Bank, whether by their absorption with any other body or corporation or otherwise, shall not in any way or manner affect the liability or obligation of the Bank under this Guarantee.
4. It shall not be necessary, and the Bank hereby waives any necessity, for the Authority to proceed against the Contractor before presenting to the Bank its demand under this Guarantee.
5. The Authority shall have the liberty, without affecting in any manner the liability of the Bank under this Guarantee, to vary at any time, the terms and

conditions of the Advance Payment or to extend the time or period of its repayment or to postpone for any time, and from time to time, any of the rights and powers exercisable by the Authority against the Contractor, and either to enforce or forbear from enforcing any of the terms and conditions contained in the Agreement and/or the securities available to the Authority, and the Bank shall not be released from its liability and obligation under these presents by any exercise by the Authority of the liberty with reference to the matters aforesaid or by reason of time being given to the Contractor or any other forbearance, indulgence, act or omission on the part of the Authority or of any other matter or thing whatsoever which under any law relating to sureties and guarantors would but for this provision have the effect of releasing the Bank from its liability and obligation under this Guarantee and the Bank hereby waives all of its rights under any such law.

6. This Guarantee is in addition to and not in substitution of any other guarantee or security now or which may hereafter be held by the Authority in respect of or relating to the Advance Payment.
7. Notwithstanding anything contained hereinbefore, the liability of the Bank under this Guarantee is restricted to the Guarantee Amount and this Guarantee will remain in force for the period specified in paragraph 8 below and unless a demand or claim in writing is made by the Authority on the Bank under this Guarantee all rights of the Authority under this Guarantee shall be forfeited and the Bank shall be relieved from its liabilities hereunder.
8. The Guarantee shall cease to be in force and effect on \*\*\*\*.<sup>s</sup> Unless a demand or claim under this Guarantee is made in writing on or before the aforesaid date, the Bank shall be discharged from its liabilities hereunder.
9. The Bank undertakes not to revoke this Guarantee during its currency, except with the previous express consent of the Authority in writing, and declares and warrants that it has the power to issue this Guarantee and the undersigned has

---

<sup>s</sup> Insert a date being 90 (ninety) days after the end of one year from the date of payment of the Advance payment to the Contractor (in accordance with Clause 19.2 of the Agreement).

full powers to do so on behalf of the Bank.

10. Any notice by way of request, demand or otherwise hereunder may be sent by post addressed to the Bank at its above referred branch, which shall be deemed to have been duly authorised to receive such notice and to effect payment thereof forthwith, and if sent by post it shall be deemed to have been given at the time when it ought to have been delivered in due course of post and in proving such notice, when given by post, it shall be sufficient to prove that the envelope containing the notice was posted and a certificate signed by an officer of the Authority that the envelope was so posted shall be conclusive.
11. This Guarantee shall come into force with immediate effect and shall remain in force and effect up to the date specified in paragraph 8 above or until it is released earlier by the Authority pursuant to the provisions of the Agreement.
12. This guarantee shall also be operatable at our.....Branch at New Delhi, from whom, confirmation regarding the issue of this guarantee or extension / renewal thereof shall be made available on demand. In the contingency of this guarantee being invoked and payment thereunder claimed, the said branch shall accept such invocation letter and make payment of amounts so demanded under the said invocation.
13. Bank Guarantee has been sent to authority's bank through SFMS gateway as per the details below: -

Sl. No	Particulars	Details
1	Name of the Beneficiary	National Highways and Infrastructure Development Corporation Limited
2	Beneficiary Bank Account No.	90621010002610
3	Beneficiary Bank Branch	IFSC CNRB0019062
4	Beneficiary Bank Branch Name	Transport Bhawan, New Delhi
5	Beneficiary Bank Address	Syndicate Bank, Transport Bhawan, 1st Parliament street, New Delhi-110001

Signed and sealed this ..... day of ....., 20..... at .....

SIGNED, SEALED AND DELIVERED

For and on behalf of the Bank by:

(Signature)

(Name)

(Designation)

(Code Number)

(Address)

NOTES:

- (i) The bank guarantee should contain the name, designation and code number of the officer(s) signing the guarantee.
- (ii) The address, telephone number and other details of the head office of the Bank as well as of issuing branch should be mentioned on the covering letter of issuing branch.

**SCHEDULE-H***(See Clauses 10.1.4 and 19.3)***CONTRACT PRICE WEIGHTAGE**

1.1 The Contract Price for this Agreement is .....

1.2 Proportions of the Contract Price for different stages of Construction of the Project

Highway shall be as specified below:

<b>Item</b>	<b>Weightage in percentage to the Contract Price</b>	<b>Stage for Payment</b>	<b>Percentage weightage to Particular item (col.2)</b>
<b>1</b>	<b>2</b>	<b>3</b>	<b>4</b>
<b>Road works including culverts widening and repair of culverts.</b>	<b>44.47%</b>	<b>A- Widening and strengthening of existing road</b>	
		(1) Earthwork up to top of the sub-grade including excavation in soil/soft rock/ hard rock and clearing & grubbing	1.21%
		(2) Sub Base Course.	2.78%
		(3) Non-Bituminous Base Course.	5.55%
		(4) Dense Graded Bituminous Macadam.	5.20%
		(5) Bituminous Concrete	3.88%
		(6) Widening, reconstruction and repair of culverts	0.00%
		(7) Hard Shoulder	1.36%
		<b>B.1 - Reconstruction/New 2 - lane realignment/ bypass - (Flexible pavement)</b>	
		(1) Earthwork up to top of the sub-grade including excavation in soil/soft rock/ hard rock and clearing & grubbing	3.33%
		(2) Sub Base Course	0.87%
		(3) Non-Bituminous Base Course	2.36%
		(4) Dense Graded Bituminous Macadam.	1.69%
		(5) Bituminous Concrete	0.83%
		(6) Hard Shoulder	1.38%
		<b>D- Reconstruction and New culverts on existing road, realignment, bypasses.</b>	
		(1) Culverts (length <6m)	14.02%
<b>Minor Bridge / Underpasses / Over pass</b>	<b>6.00%</b>	<b>A.1-Widening and repair of Minor Bridge (length &gt;6m &lt;60m)</b>	
		(1) Minor bridge	
		<b>A.2-New Minor Bridge (length &gt;6m &lt;60m)</b>	

		(1) <b>Foundation + substructure:</b> On completion of the foundation of the foundation work including foundation for wing and return walls, abutment, piers up to the abutment/pier cap	4.10%
		(2) <b>Super-structure :</b> On completion of the super structure in all respects including wearing coat, bearings, road signs & markings, tests in completion etc. complete in all respect.	1.18%
		(3) <b>Approaches :</b> On completion of approaches including Retaining walls/ Reinforced Earth walls, stone pitching, protection works complete in all respect and fit for use.	0.73%
<b>Other works</b>	<b>49.53%</b>		
		(i) Toll Plaza	0.00%
		(ii) Road side drains	12.38%
		(iii) Road signs, markings, km stones, boundary stones, safety devices etc.	
		a) Pavement Marking	1.59%
		b) Crash Barrier/ W-metal crash barrier	0.85%
		c) Road / Traffic sign	0.53%
		d) Road boundary stone, km stone, 5th km stone, Hecto meter stone, rumble strips, other items etc.	0.04%
		e) Traffic blinker, LED delineators, studs, reflective pavement markers, tree reflectors	1.92%
		f) Road furniture (over head sign board etc.)	0.03%
		<u>(iv) Project facilities</u>	
		a) Bus bye / Bus shelter	0.16%
		b) Junctions - (Major & Minor)	3.89%
		c) Others including cable duct & lighting on bridges, etc.	0.00%
		(v) Road side Plantation	0.02%
		(vi) Slope protection works as special requirement for hill road	
		(a) Hydro seeding	0.02%
		(b) Seeding and Mulching with jute net	2.11%
		(c) Catch water drain	0.11%
		(d) Retaining Structure on valley side of PCC/RCC/Gabion/Cement Masonry of Varying height	18.68%

		between 1 to 6 meter with parapet walls	
		(e) Reinforced earth wall	1.38%
		(f) Breast wall	5.40%
		(g) Sub surface drain with perforated pipe & Aggregate drain	0.03%
		(h) Parapet wall	0.38%

### 1.3 Procedure of estimating the value of work done.

#### 1.3.1 Road works

Procedure for estimating the value of road work done shall be as follows:

TABLE 1.3.1		
STAGE OF PAYMENT	PERCENTAGE WEIGHTAGE	PAYMENT PROCEDURE
<b>A-Widening and strengthening of existing road</b>		Unit of measurement is linear length. Payment of each stage shall be made on prorated basis on completion of a stage in a length of not less than 10% (ten percent) of the total length. Further, If existing road length (excluding bypasses, re-alignment, structure) is say 'L' Km and the unencumbered length along the existing road as handed over on the appointed date is 'L1' Km and the balance length i.e. 'L2' Km (L-L1) is to be handed over on a later date as per the memorandum signed under provision of clause 8.2.1 of the contract document, then the stage payment shall be worked out for the 'L1' Km length handed over on the appointed date. The stage payment for the remaining 'L2' Km shall be worked out on prorated basis from the date of handing over of such length.
(1) Earthwork up to top of the Sub-grade including excavation in soil, soft rock and hard rock including clearing & grubbing with required site clearance etc.	1.21%	
(2) Sub Base Course.	2.78%	
(3) Non-Bituminous Base Course.	5.55%	
(4) Dense Graded Bituminous Macadam.	5.20%	
(5) Bituminous Concrete.	3.88%	Cost of completed culverts shall be determined pro rata basis with respect to the total no. of culverts. The payment shall be made on the completion of at least five culverts.
(6) Widening, reconstruction and repair of culverts	0.00%	
(7) Hard Shoulder	1.36%	Unit of measurement is linear length. Payment of each stage shall be made on pro rata basis on completion of a stage in a length of not less than 10 (ten) percent of the total length. Further, If existing road length (excluding bypasses, re-alignment, structure) is say 'L' Km and the unencumbered length along the existing road as handed over on the appointed date is 'L1' Km and the balance length i.e. 'L2' Km (L-L1) is to be handed over on a later date as per the memorandum signed under provision of clause 8.2.1 of the contract



		document, then the stage date. The stage payment for the remaining 'L2' Km shall be worked out on pro rate basis from the date of handing over of such length.
<b>B.1 Reconstruction / New 2 lane realignment / bypass (Flexible pavement)</b>		Unit of measurement is linear length. Payment of each stage shall be made on pro rate basis on completion of a stage in full length or 5(five) Km. length, whichever is less.
(1) Earthwork up to top of the sub-grade including excavation in soil/soft rock/ hard rock and clearing & grubbing	3.33%	Further, Unit of Measurement is linear length of each Bypass /realignment (excluding structures) and payment of each stage shall be made on pro rate basis on completion of a stage in full length or 5 (Five) Km length of each bypass/realignment taken separately
(2) Sub Base Course	0.87%	
(3) Non-Bituminous Base Course	2.36%	
(4) Dense Graded Bituminous Macadam.	1.69%	
(5) Bituminous Concrete.	0.83%	
(6) Hard Shoulder	1.38%	
<b>C.1 Reconstruction /New Service road (Flexible Pavement)</b>		Unit of measurement is linear length. Payment of each stage shall be made on prorate basis on completion of a stage in full length or 5(five) km. length, whichever is less.
(1) Earthwork upto top of the Sub-grade including excavation in soil, soft rock and hard rock including Clearing & grubbing with required site clearance etc.	0.00%	
(2) Sub-Base Course.	0.00%	
(3) Non Bituminous Base Course.	0.00%	
(4) Bituminous Base Course	0.00%	
(5) Wearing Coat.	0.00%	
<b>C.2 Reconstruction / New Service road (Rigid Pavement)</b>		Unit of measurement is linear length. Payment of each stage shall be made on prorate basis on completion of a stage in full length or 5(five) km. length, whichever is less.
(1)Earthwork upto top of the Sub-grade including excavation in soil, soft rock and hard rock including clearing & grubbing with required site clearance etc.	0.00%	
(2) Sub-Base Course.	0.00%	
(3)Dry Lean Concrete(DLC)Course	0.00%	
(4)Pavement Quality Control(PQC) Course	0.00%	
<b>D-Re-construction and New culverts on existing road, realignment, bypass.</b>		Cost of each culvert shall be determined on prorate basis with respect to the total number of culverts. Payment shall be made on the completion of at least five culverts.
(1)Culverts(Length<6m)	14.02%	

@. For example , if the total length of bituminous work to be done is 100km ,the cost per km of bituminous work shall be determined as follows:

Cost per km = P x weightage for road work x weightage for bituminous work x

(1/L)Where P=Contract Price

L=Total length in km

Similarly, the rates per km for stages shall be worked out accordingly.

Note: The length affected due to law and order problems or litigation during execution due to which the contractor is unable to execute the work, may be deducted from the total project length for payment purposes. The total length calculated here is only for payment purposes and will not affect and referred in other clauses of the contract Agreement.

### 1.3.2 Minor Bridge and Underpasses/Overpasses

Procedure for estimating the value of Minor Bridge and Underpasses/Overpasses shall be as stated in table 1.3.2:

TABLE 1.3.2		
STAGE OF PAYMENT	PERCENTAGE WEIGHTAGE	PAYMENT PROCEDURE
<b>A.1 Widening and Repair of Minor Bridges (length &gt; 6m and &lt; 60m)</b>	0.00%	Cost of each minor bridge shall be determined on prorated basis with respect to the total linear length of the minor bridges. Payment shall be made on the completion of widening & repair works of a minor bridge.
<b>A.2-New Minor Bridges (length &gt; 6m and &lt; 60m)</b>		
(i) <b>Foundation + Sub Structure</b> : On completion of the foundation work including foundation for wing and return walls, abutments, piers upto the abutment/ pier cap	4.10%	(i) <b>Foundation + Sub Structure</b> : Cost of each minor bridge shall be determined on prorated basis with respect to the total linear length (m) of the minor bridges. Payment against foundation + substructure shall be made on pro rate basis on completion of a stage i.e not less than 25% of the scope of foundation + substructure of each bridge subject to completion of at least two foundations along with sub structure upto abutment / pier cap level of each bridge. In case where load testing is required for foundation, the trigger of first payment shall include load testing also where specified
(ii) <b>Super Structure</b> : On completion of the super structures in all respects including wearing coat, bearing, expansion joint, hand rail, crash barriers, road signs & markings, tests on completion etc. Complete in all respect.	1.18%	(ii) <b>Super Structure</b> : Payment shall be made on pro rate basis on completion of a stage i.e completion of super structure of at least one span in all respects as specified in the column of "Stage of Payment" in this sub clause.
(iii) <b>Approaches</b> : On completion of approaches including Retaining walls, stone pitching, protection works complete in all respect	0.73%	(iii) <b>Approaches</b> : Payment shall be made on pro rate basis on completion of a stage i.e completion of approaches in all respect as specified in the column of "Stage of Payment"

and fit for use.		in this sub clause.
<b>(iv)Guide Bunds and River Training Works:</b> On completion of Guide Bunds and river Training works complete in all respects.	0.00%	<b>(iv)Guide Bunds and River Training Works:</b> Payment shall be made on pro rate basis on completion of a stage i.e completion of Guide Bunds and River Training Works in all respects as specified
<b>B.1 Widening and Repair of underpasses / overpasses</b>	0.00%	Cost of each underpass /overpass shall be determined on pro rate basis with respect to the total linear length of the underpasses /overpasses. Payment shall be made on the completion of Widening & repair works of a underpass /overpass
<b>B.2-New Underpasses /Overpasses</b>		
<b>(i)Foundation + Sub Structure</b> :On completion of the foundation work including foundation for wing and return walls, abutments, piers up to the abutment/pier cap	0.00%	<b>(i)Foundation + Sub Structure</b> :Cost of each Underpass/Overpass shall be determined on pro rate basis with respect to the total linear length (m) of the Underpasses / Overpasses .Payment against foundation + sub structure shall be made on pro rate basis on completion of a stage i.e not less than 25% of the scope of foundation + sub structure of each underpasses / overpasses subject to completion of at least two foundation along with sub structure up to abutment /pier cap level each underpass/overpass. In case where load testing is required for foundation, the trigger of first payment shall include load testing also where specified.
<b>(ii)Super Structure</b> : On completion of the super structures in all respects including wearing coat, bearing, expansion joint, hand rail, crash barriers, road signs & marking, tests on completion etc. Complete in all respect. Wearing Coat (a) incase of overpass wearing coat including expansion joints complete in all respects as specified and(b) incase of underpass-rigid pavement including facility complete in all respects as specified as specified.	0.00%	<b>(ii) Super Structure:</b> Payment shall be made on pro rate basis on completion of a stage I,completion of super structure of at least onespan in all respects as specified in the columnof"StageofPayment" inthissub clause.
<b>(iii) Approaches:</b> On completion of approaches including Retaining walls /Reinforced Earth walls, stone pitching, protection works complete in all respect and fit for use.	0.00%	<b>(iii) Approaches:</b> Payment shall be made on pro rate basis on completion of stage i.e completion of approaches in all respect as specified.

## 1.3.3 Major Bridge works, ROB/RUB and Structures

Procedure for estimating the value of Major Bridge works, ROB/RUB and Structures shall be as stated in table 1.3.3

TABLE 1.3.3		
STAGE OF PAYMENT	PERCENTAGE WEIGHTAGE	PAYMENT PROCEDURE
<b>A.1- Widening and repairs of Major Bridges</b> (i) Foundation	0.00%	(i) <b>Foundation:</b> Cost of each Major Bridge shall be determined on pro rate basis with respect to the total linear length (m) of the Major Bridge. Payment against foundation shall be made on prorated basis on completion of a stage i.e not less than 25% of the scope of foundation of the major bridge subject to completion of at least two foundation of the Major Bridge. In case where load testing is required for foundation, the trigger of first payment shall include load testing also where specified.
(ii) <b>Sub Structure</b> :On completion of the foundation work including foundation for wing and return walls, abutments, piers up to the abutment/ pier cap	0.00%	(ii) <b>Sub Structure</b> : Payment against Sub Structure shall be made on pro rate basis on completion of a stage i.e not less than 25% of the scope of sub structure of the major bridge subject to completion of at least two substructure of abutment/piers up to abutment/pier cap level of the major bridge.
(iii) <b>Super Structure</b> : (including bearings)	0.00%	(iii) <b>Super Structure:</b> Payment shall be made pro rate basis on completion of a stage i.e completion of super structure including bearing of at least one span in all respect as specified.
(iv) Wearing Coat including expansion joints	0.00%	(iv) <b>Wearing Coat:</b> Payment shall be made on completion of wearing coat including expansion joint complete in all respects as specified.
(v) Miscellaneous items like hand rails, crash barriers, road markings etc	0.00%	(v) <b>Miscellaneous</b> :Payment shall be made on completion of miscellaneous work like hand rail, crash barriers, road marking etc. complete in all respect as specified.
(vi) wing walls / return walls	0.00%	(vi) <b>Wing walls/return walls:</b> Payments shall be made on completion of wing walls/return walls complete in all respects as specified.
(vii) Guide Bunds, River Training works etc	0.00%	(vii) <b>Guide Bunds, River Training works:</b> Payments shall be made on completion of all guide bunds/river training works etc. complete in all respects as specified..

(viii) Approaches (including Retaining walls, stone pitching and protection works)	0.00%	(viii) <b>Approaches:</b> Payments shall be made on completion of both approaches including stone pitching ,protection works, etc. complete in all respect as specified.
<b>A.2-NewMajorBridges</b>		
(i)Foundation	0.00%	(i) <b>Foundation:</b> Cost of each Major Bridge shall be determined on pro rate basis with respect to the total linear length (m) of the Major Bridge. Payment against foundation shall be made on prorated basis on completion of stage i.e not less than 25% of the scope of foundation of the major bridge subject to completion of at least two foundation of the major bridge.In case where load testing is required for foundation, thetrigger of first payment shall include load testing also wherespecified.
(ii)Sub-structure	0.00%	(ii) <b>Sub Structure:</b> Payment against Sub-structure shall be made on pro rate basis on completion of a stage i.e not less than 25% of scope of sub structure of the major bridge subject to completion of at least two sub structure of abutment/ piers upto abutment/pier cal level of the major bridge.
(iii)Super-structure (including bearings)	0.00%	(iii) <b>Super Structure :</b> Payment shall be made on prorated basis on completion of a stage i.e completion of super structure including bearing of at least one span in all respects as specified.
(iv)Wearing Coat including expansion joints	0.00%	(iv) <b>Wearing Coat:</b> Payment shall be made on completion of wearing coat including expansion joint complete in all respects as specified.
(v)Miscellaneous items like handrails, crash barriers, road markings etc	0.00%	(v) <b>Miscellaneous:</b> Payment shall be made on completion of all miscellaneous work like hand rail, crash barriers, road marking etc. Complete in all respects as specified.
(vi) wing walls/return walls	0.00%	(vi) <b>Wing walls / Return walls:</b> Payment shall be made on completion of all wing walls/return walls complete in all respects as specified.
(vii) Guide Bunds, River Training works etc	0.00%	(vii) <b>Guide Bunds, River Training works :</b> Payment shall be made on completion of all guide bunds /river training works etc. complete in all respects as specified.
(viii) Approaches (including	0.00%	(viii) <b>Approaches:</b> Payment shall be

Retaining walls, stone pitching and protection works)		made on completion of both approaches including stone pitching, protection works, etc complete in all respects as specified.
<b>B.1-Widening and Repair of</b> <b>(a) ROB</b> <b>(b) RUB</b>		
(i)Foundation	0.00%	(i) <b>Foundation:</b> Cost of each ROB/RUB shall be determined on pro rate basis with respect to the total liner length (m) of the ROB/RUBs. Payment foundation shall be made on pro rate basis on completion of a stage i.e not less than 25% of the scope of foundation of the ROB/RUB subject to completion of a stage i.e not less than 25% of the scope of foundation of the ROB/RUB subject to completion of at least two foundation of the ROB/RUB. In case where load testing is required for foundation, The trigger of first payment 0.00% shall include load testing also where specified.
(ii)Sub-structure	0.00%	(ii) <b>Sub Structure :</b> Payment against sub structure shall be made on pro rate basis on completion of a stage i.e not less than 25% of the scope of sub structure of the ROB/RUB subject to completion of at least two substructure of abutments/piers upto Abutment/pier cap level of the ROB/RUB.
(iii) Super-structure(including bearings)	0.00%	(iii) <b>Super Structure:</b> Payment shall be made on prorated basis on completion of a stage i.e completion of super structure including bearing of at least one span In all respects as specified.
(iv)Wearing Coat(a) in case of ROB-wearing coat including expansion joints complete in all respects as specified and (b) in case of RUB-rigid pavement under RUB including drainage facility complete in all respects as specified	0.00%	(iv) <b>Wearing Coat:</b> Payments shall be made on completion of (a) in case of ROB-wearing coat including expansion joints complete in all respects as specified and (b) in case of RUB-rigid pavement under including drainage facility complete in all respects as specified.
(v)Miscellaneous items like hand rails, crash barriers, road marking etc	0.00%	(v) <b>Miscellaneous:</b> Payment shall be made on completion of all miscellaneous work like hand rail, crash barriers, road marking etc. Complete in all respects as specified.
(vi)wing wall/return walls	0.00%	(vi) <b>Wing walls/return walls:</b> Payment shall be made on completion of all wing walls/return

		walls Complete in all respects as specified.
(vii)Approaches (including Retaining walls, stone pitching and Protection work	0.00%	(vii) <b>Approaches:</b> Payment shall be made on completion of both approaches including stone pitching, protection works, etc complete in all respect As specified.
<b>C.1-Widening and repairs of Elevated Section / Flyovers/Grade Separators</b>		
(i)Foundation	0.00%	(i) <b>Foundation:</b> Cost of each structure shall be determined on pro rate basis with respect to the total liner length(m)of the structure Payment against foundation shall be made on prorated basis on completion of a stage i.e not less than 25% of the scope of foundation of the structure subject to completion of at least two foundation of the structure. Incase where load testing is required for foundation ,the trigger of first payment shall include load testing also where specified.
(ii)Sub-structure	0.00%	(ii) <b>Sub Structure</b> : Payment against sub structure shall be made on pro rate basis on completion of a stage i.e not less than 25% of the scope of sub structure of the structure subject to completion of at least two substructure of abutments/piers upto abutment/pier cap level of the structure.
(iii)Super structure (including bearings)	0.00%	(iii) <b>Super Structure</b> : Payment shall be made on prorated basis on completion of a stage i.e completion of Super structure including bearing of at least one span in all respects as specified.
(iv)Wearing Coat including expansion joints	0.00%	(iv) <b>Wearing Coat:</b> Payment shall be made on completion of wearing coat including expansion joints complete in all respectsas specified
(v)Miscellaneous items like handrails ,crash barriers ,road marking etc	0.00%	(v) <b>Miscellaneous:</b> Payment shall be made on completion of all miscellaneous work like hand rail,crashbarriers,roadmarkingetc.Co mpleteinallrespectsasspecified.
(vi)wing wall/return walls	0.00%	(vi) <b>Wing walls/return walls:</b> Payment shall be made on completion of all wing walls/return walls complete in all respects as specified.
vii)Approaches (including Retaining walls/ Reinforced Earth wall, stone pitching and protection work)	0.00%	(vii) <b>Approaches:</b> Payment shall be made on completion of both approaches including stone pitching, protection works, etc complete in all respect As specified.

**Note:(1)In case of innovate Major Bridge projects like cable suspension /cable stayed /Extra Dozed and exceptionally long span bridges, the schedule may be modified as per site requirements before bidding with due approval of DG(RD) & SS, MoRT&H.**

**Note:(2)TheScheduleforexclusivetunnelprojectmaybepreparedas persiterequirementbefore bidding with dueapproval ofDG (RD)&SS, MoRT&H**

#### 1.3.4 Others works

Procedure for estimating the value of others works done shall be as stated in table**1.3.4**:

<b>TABLE 1.3.4</b>		
<b>STAGE OF PAYMENT</b>	<b>PERCENTAGE WEIGHTAGE</b>	<b>PAYMENT PROCEDURE</b>
(i) Toll Plaza	0.00%	Unit of measurement is each completed toll plaza. Payment of each toll plaza shall be made on pro Rate basis with respect to the total of all toll plazas.
(ii) Road sidedrain	12.38%	Unit of measurement is linear length in Km. Payments shall be made on prorated basis on completion of a stage in a length of not less than 10% (ten per cent) of the total length.
(iii) Road signs, marking, Km stones, Safety devices etc.	0.53%	
(a) Pavement Marking	1.59%	
(b) Crash Barrier/W metal crash Barrier	0.85%	
(c) Traffic Sign		
(d) Road Boundary stone, km Stone, 5th km Stone and hectometer stone	0.04%	
(e) Traffic blinker LED delineator, stud, reflective pavement marker, traffic reflector	1.92%	
(f) Traffic impact At Abutments And Pier traffic island		
(g) Road furniture (overhead sign board etc.)	0.03%	
h) Others including construction of median & median kerb with channel, paint, rumble strip, Roadside Plantation etc.		
(iv) Project facilities		Payments shall be made on prorated basis for completed facilities.
(a) Bus bays & Bus Shelter	0.16%	
(b) Truck lay-bys		
(c,) Rest areas		
(d) Others		



(e)Junctions(Major&Minor)	3.89%	
(v)RoadsidePlantation	0.02%	Unit of measurement is linear length. Payment shall be made on pro rate basis on completion of a stage in a length of not less than10%(ten percent) of the total length.
(vi) Repair of protection works other than approaches to the bridges elevated section /flyovers /grade separators and ROBS/RUBs		
(vii)Safety and traffic management during construction		Payment shall be made on pro rate basis every six month.
(viii)Slope Protection Works as special Requirement for hill road		Unit of measurement is linear length in Km. Payment shall be made on prorated basis on completion of a stage in a length of not less than 10% (ten per cent) of the total length.
(a)Hydro Seeding of Cut Slopes in Soil	0.02%	
(b)Seeding and Mulching with Jute net all a long the perpetual slide locations	2.11%	
(c)Catch water Drain	0.11%	
(d)Gabion Structure on hill side/valleys sideOf varying height between 1to6 meter depending upon the slope	18.68%	
(e)Reinforced earth wall	1.38%	
(e)Breast wall	5.40%	
(f)Sub Surface drain with perforated pipe For collection of seepage water to avoid sinking of pavement	0.03%	
(g)Parapet wall	0.38%	
(h)Toe wall		

## ***2. Procedure for payment for Maintenance***

### **2.1 The cost for maintenance shall be as stated inClause14.1.1**

Payment for Maintenance shall be made in quarterly installment in accordance with the provisions of Clause 19.7

SCHEDULE - I  
(See Clause 10.2.4)  
**DRAWINGS**

**1 Drawings**

In compliance of the obligations set forth in Clause 10.2 of this Agreement, the Contractor shall furnish to the Authority's Engineer, free of cost, all Drawings listed in Annex-I of this Schedule-I.

**2 Additional Drawings**

If the Authority's Engineer determines that for discharging its duties and functions under this Agreement, it requires any drawings other than those listed in Annex-I, it may by notice require the Contractor to prepare and furnish such drawings forthwith. Upon receiving a requisition to this effect, the Contractor shall promptly prepare and furnish such drawings to the Authority's Engineer, as if such drawings formed part of Annex-I of this Schedule-I.

Annex - I  
(Schedule - I)

**List of Drawings**

[Note: The Authority shall describe in this Annex-I, all the Drawings that the Contractor is required to furnish under Clause 10.2.]

1. A minimum list of the drawings of the various components/elements of the project highway and project facility required to be submitted by the Contractor is given below:
  - (a) Drawing of plan, profile and cross sections
  - (b) Drawings of cross drainage works
  - (c) Drawings of junctions
  - (d) Drawing of typical cross sections
  - (e) Drawings of bus-bay and bus shelters with furniture and drainage system
  - (f) Drawing of a truck parking lay bye with furniture and drainage system
  - (g) Drawings of road furniture items including traffic signage, marking, safety barriers, etc.
  - (h) Drawings of traffic diversions plans and traffic control measures
  - (i) Drawings of road drainage measures
  - (j) Drawings of typical details slope protection measures

## **Schedule - J**

*(See Clause 10.3 (ii))*

### **Project Completion Schedule**

#### **1. Project Completion Schedule**

During Construction period, the Contractor shall comply with the requirements set forth in this Schedule-J for each of the Project Milestones and the **Scheduled Completion Date**. Within 15 (fifteen) days of the date of each Project Milestone, the Contractor shall notify the Authority of such compliance along with necessary particulars thereof.

#### **2. Project Milestone-I**

- (i) Project Milestone-I shall occur on the date falling on the [192<sup>nd</sup>] day from the Appointed Date (the “**Project Milestone- I**”).
- (ii) Prior to the occurrence of Project Milestone-I, the Contractor shall have commenced construction of the Project Highway and submitted to the Authority duly and validly prepared Stage Payment Statements for an amount not less than 10% (ten per cent) of the Contract Price.

#### **3. Project Milestone-II**

- (i) Project Milestone-II shall occur on the date falling on the [329<sup>th</sup>] day from the Appointed Date (the “**Project Milestone- II**”).
- (ii) Prior to the occurrence of Project Milestone-II, the Contractor shall have continued with construction of the Project Highway and submitted to the Authority duly and validly prepared Stage Payment Statements for an amount not less than 35% (thirty five per cent) of the Contract Price and should have started construction of all bridges

#### **4. Project Milestone-III**

- (i) Project Milestone-III shall occur on the date falling on the [467<sup>th</sup>] day from the Appointed Date (the “**Project Milestone- III**”).

- (ii) Prior to the occurrence of Project Milestone-III, the Contractor shall have continued with construction of the Project Highway and submitted to the Authority duly and validly prepared Stage Payment Statements for an amount not less than 70% (seventy per cent) of the Contract Price and should have started construction of all project facilities.

**5. Scheduled Completion Date**

- (i) The Scheduled Completion Date shall occur on the [549<sup>th</sup>] day from the Appointed Date.
- (ii) On or before the Scheduled Completion Date, the Contractor shall have completed construction in accordance with this Agreement.

**6. Extension of time**

Upon extension of any or all of the aforesaid Project Milestones or the Scheduled Completion Date, as the case may be, under and in accordance with the provisions of this Agreement, the Project Completion Schedule shall be deemed to have been amended accordingly.

SCHEDULE - K  
(See Clause 12.1.2)

**TESTS ON COMPLETION**

**1 Schedule for Tests**

The Contractor shall, no later than 30 (thirty) days prior to the likely completion of construction, notify the Authority's Engineer and the Authority of its intent to subject the Project Highway to Tests, and no later than 10 (ten) days prior to the actual date of Tests, furnish to the Authority's Engineer and the Authority detailed inventory and particulars of all works and equipment forming part of Works.

The Contractor shall notify the Authority's Engineer of its readiness to subject the Project Highway to Tests at any time after 10 (ten) days from the date of such notice, and upon receipt of such notice, the Authority's Engineer shall, in consultation with the Contractor, determine the date and time for each Test and notify the same to the Authority who may designate its representative to witness the Tests. The Authority's Engineer shall thereupon conduct the Tests itself or cause any of the Tests to be conducted in accordance with Article 12 and this Schedule-K.

**2 Tests**

Visual and physical test: The Authority's Engineer shall conduct a visual and physical check of construction to determine that all works and equipment forming part thereof conform to the provisions of this Agreement. The physical tests shall include (to be decided in consultation with Authority's Engineer as per relevant IRC codes/manual).

Riding quality test: Riding quality of each lane of the carriageway shall be checked with the help of a calibrated bump integrator and the maximum permissible roughness for purposes of this Test shall be 2,000 (two thousand) mm for each kilometre.

Tests for bridges: All major and minor bridges shall be subjected to the rebound hammer and ultrasonic pulse velocity tests, to be conducted in accordance with the procedure described in Special Report No. 17: 1996 of the IRC Highway Research Board on Non-destructive Testing Techniques, at two spots in every span, to be chosen at random by the Authority's Engineer. Bridges with a span of 15 (fifteen) metres or more shall also be subjected to load testing.

Other tests: The Authority's Engineer may require the Contractor to carry out or cause to be carried additional tests, in accordance with Good Industry Practice, for determining the compliance of the Project Highway with Specifications and Standards.

Environmental audit: The Authority's Engineer shall carry out a check to determine conformity of the Project Highway with the environmental requirements set forth in Applicable Laws and Applicable Permits.

Safety Audit: The Authority's Engineer shall carry out, or cause to be carried out, a safety audit to determine conformity of the Project Highway with the safety requirements and Good Industry Practice.

**3 Agency for conducting Tests**

All Tests set forth in this Schedule-K shall be conducted by the Authority's Engineer or such other agency or person as it may specify in consultation with the Authority.

**4 Completion Certificate**

Upon successful completion of Tests, the Authority's Engineer shall issue the Completion Certificate in accordance with the provisions of Article 12.

SCHEDULE - L  
(See Clause 12.2 and 12.4)

**PROVISIONAL CERTIFICATE**

**1** I, ..... (Name of the Authority's Engineer), acting as the Authority's Engineer, under and in accordance with the Agreement dated ..... (the "Agreement"), for Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A (the "Project Highway") on Engineering, Procurement and Construction (EPC) basis through

..... (Name of Contractor), hereby certify that the Tests in accordance with Article 12 of the Agreement have been undertaken to determine compliance of the Project Highway with the provisions of the Agreement.

**2** Works that are incomplete on account of Time Extension have been specified in the Punch List appended hereto, and the Contractor has agreed and accepted that it shall complete all such works in the time and manner set forth in the Agreement. In addition, certain minor works are incomplete and these are not likely to cause material inconvenience to the Users of the Project Highway or affect their safety. The Contractor has agreed and accepted that as a condition of this Provisional Certificate, it shall complete such minor works within 30 (thirty) days hereof. These minor works have also been specified in the aforesaid Punch List.

**3** In view of the foregoing, I am satisfied that the Project Road *of* Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A can be safely and reliably placed in service of the Users thereof, and in terms of the Agreement, the Project Highway is hereby provisionally declared fit for entry into operation on this the ..... day of ..... 20.....

ACCEPTED, SIGNED, SEALED

AND DELIVERED

For and on behalf of

SIGNED, SEALED AND

DELIVERED

for and on behalf of



CONTRACTOR by: AUTHORITY's ENGINEER by:

(Signature)

(Signature)

### COMPLETION CERTIFICATE

1 I,..... (Name of the Authority's Engineer), acting as the Authority's Engineer, under and in accordance with the Agreement dated.....(the "Agreement"), for ***Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A***

(the "Project Highway") on Engineering, Procurement and Construction (EPC) basis through ..... (Name of Contractor), hereby certify that the Tests in accordance with Article 12 of the Agreement have been successfully undertaken to determine compliance of the Project Highway with the provisions of the Agreement, and I am satisfied that the Project Highway can be safely and reliably placed in service of the Users thereof.

2 It is certified that, in terms of the aforesaid Agreement, all works forming part of Project Highway have been completed, and the Project Highway is hereby declared fit for entry into operation on this the ..... day of ..... 20.....

SIGNED, SEALED AND DELIVERED

For and on behalf of

The Authority's Engineer by:

(Signature)

(Name)

(Designation)

(Address)

SCHEDULE - M  
*(See Clauses 14.6, 15.2 and 19.7)*

**PAYMENT REDUCTION FOR NON-COMPLIANCE**

**1. Payment reduction for non-compliance with the Maintenance Requirements**

Monthly lump sum payments for maintenance shall be reduced in the case of non-compliance with the Maintenance Requirements set forth in Schedule-E.

Any deduction made on account of non-compliance with the Maintenance Requirements shall not be paid even after compliance subsequently. The deductions shall continue to be made every month until compliance is done.

The Authority's Engineer shall calculate the amount of payment reduction on the basis of weightage in percentage assigned to non-conforming items as given in Paragraph 2.

**2. Percentage reductions in lump sum payments**

The following percentages shall govern the payment reduction:

<b>S. No.</b>	<b>Item/Defect/Deficiency</b>	<b>Percentage</b>
<b>(a)</b>	<b>Carriageway/Pavement</b>	
(i)	Potholes, cracks, other surface defects	15%
(ii)	Repairs of Edges, Rutting	5%
<b>(b)</b>	<b>Road, Embankment, Cuttings, Shoulders</b>	
(i)	Edge drop, inadequate crossfall, undulations, settlement, potholes, ponding, obstructions	10%
(ii)	Deficient slopes, raincuts, disturbed pitching, vegetation growth, pruning of trees	5%
<b>(c)</b>	<b>Bridges and Culverts</b>	
(i)	Desilting, cleaning, vegetation growth, damaged pitching, flooring, parapets, wearing course, footpaths, any damage to foundations	20%
<b>S. No.</b>	<b>Item/Defect/Deficiency</b>	<b>Percentage</b>
(ii)	Any Defects in superstructures, bearings and sub-structures	10%
(iii)	Painting, repairs/replacement kerbs, railings, parapets, guideposts/crash barriers	5%
<b>(d)</b>	<b>Roadside Drains</b>	
(i)	Cleaning and repair of drains	5%
<b>(e)</b>	<b>Road Furniture</b>	
(i)	Cleaning, painting, replacement of road signs, delineators, road markings, 200 m/km/5 <sup>th</sup> km stones	5%
<b>(f)</b>	<b>Miscellaneous Items</b>	
(i)	Removal of dead animals, broken down/accidental vehicles, fallen trees, road blockades or malfunctioning of mobile crane	10%
(ii)	Any other Defects in accordance with paragraph 1.	5%
<b>(g)</b>	<b>Defects in Other Project Facilities</b>	5%

The amount to be deducted from monthly lump-sum payment for non-compliance of particular item shall be calculated as under:

$$R = P / IOO \times M \times L1 / L$$

Where P = Percentage of particular item/Defect/deficiency for deduction

M = Monthly lump-sum payment in accordance with the Bid

L1 = Non-complying length

L = Total length of the road,

R = Reduction (the amount to be deducted for non-compliance for a particular item/Defect/deficiency

The total amount of reduction shall be arrived at by summation of reductions for such items/Defects/deficiency or non-compliance.

For any Defect in a part of one kilometer, the non-conforming length shall be taken as one kilometer.

SCHEDULE - N  
(See Clause 18.1.1)

**SELECTION OF AUTHORITY'S ENGINEER**

**1 Selection of Authority's Engineer**

The provisions of the Model Request for Proposal for Selection of Technical Consultants, issued by the Ministry of Finance in **May 2009**, or any substitute thereof shall apply for selection of an experienced firm to discharge the functions and duties of an Authority's Engineer.

In the event of termination of the Technical Consultants appointed in accordance with the provisions of Paragraph 1.1, the Authority shall appoint another firm of Technical Consultants forthwith and may engage a government-owned entity in accordance with the provisions of Paragraph 3 of this Schedule-N.

**2 Terms of Reference**

The Terms of Reference for the Authority's Engineer (the "**TOR**") shall substantially conform with Annex 1 to this Schedule N.

**3 Appointment of Government entity as Authority's Engineer**

Notwithstanding anything to the contrary contained in this Schedule, the Authority may in its discretion appoint a government-owned entity as the Authority's Engineer; provided that such entity shall be a body corporate having as one of its primary functions the provision of consulting, advisory and supervisory services for engineering projects; provided further that a government-owned entity which is owned or controlled by the Authority shall not be eligible for appointment as Authority's Engineer.

Annex – I

*(Schedule - N)*

**TERMS OF REFERENCE FOR AUTHORITY’S ENGINEER**

**1 Scope**

These Terms of Reference (the “**TOR**”) for the Authority’s Engineer are being specified pursuant to the EPC Agreement dated.....(the “**Agreement**”), which has been entered into between the National Highways and Infrastructure Development Corporation Ltd, 3rd Floor, PTI Building, 4, Parliament Street, New Delhi – 110001 the “**Authority**”) and ..... (the “**Contractor**”) Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A and a copy of which is annexed hereto and marked as Annex-A to form part of this TOR.

The TOR shall apply to construction and maintenance of the Project Highway.

**2 Definitions and interpretation**

The words and expressions beginning with or in capital letters and not defined herein but defined in the Agreement shall have, unless repugnant to the context, the meaning respectively assigned to them in the Agreement.

References to Articles, Clauses and Schedules in this TOR shall, except where the context otherwise requires, be deemed to be references to the Articles, Clauses and Schedules of the Agreement, and references to Paragraphs shall be deemed to be references to Paragraphs of this TOR.

The rules of interpretation stated in Clauses 1.2, 1.3 and 1.4 of the Agreement shall apply, mutatis mutandis, to this TOR.

**3. General**

The Authority’s Engineer shall discharge its duties in a fair, impartial and efficient manner, consistent with the highest standards of professional integrity and Good Industry Practice.

The Authority's Engineer shall perform the duties and exercise the authority in accordance with the provisions of this Agreement, but subject to obtaining prior written approval of the Authority before determining:

- (a) any Time Extension;
- (b) any additional cost to be paid by the Authority to the Contractor;
- (c) the Termination Payment; or
- (d) any other matter which is not specified in (a), (b) or (c) above and which creates an obligation or liability on either Party for a sum exceeding Rs. 5,000,000 (Rs. fifty lakh).

The Authority's Engineer shall submit regular periodic reports, at least once every month, to the Authority in respect of its duties and functions under this Agreement. Such reports shall be submitted by the Authority's Engineer within 10 (ten) days of the beginning of every month.

The Authority's Engineer shall inform the Contractor of any delegation of its duties and responsibilities to its suitably qualified and experienced personnel; provided, however, that it shall not delegate the authority to refer any matter for the Authority's prior approval in accordance with the provisions of Clause 18.2.

The Authority's Engineer shall aid and advise the Authority on any proposal for Change of Scope under Article 13.

In the event of any disagreement between the Parties regarding the meaning, scope and nature of Good Industry Practice, as set forth in any provision of the Agreement, the Authority's Engineer shall specify such meaning, scope and nature by issuing a reasoned written statement relying on good industry practice and authentic literature.

#### **4 Construction Period**

During the Construction Period, the Authority's Engineer shall review the Drawings furnished by the Contractor along with supporting data, including the geo-technical and hydrological investigations, characteristics of materials from borrow areas and quarry sites, topographical surveys, and the recommendations of the Safety Consultant in accordance with the provisions of Clause 10.1.6. The Authority's Engineer shall complete such review and send its observations to the Authority and the Contractor within 15 (fifteen) days of receipt of such Drawings; provided,

however that in case of a Major Bridge or Structure, the aforesaid period of 15 (fifteen) days may be extended up to 30 (thirty) days. In particular, such comments shall specify the conformity or otherwise of such Drawings with the Scope of the Project and Specifications and Standards.

The Authority's Engineer shall review any revised Drawings sent to it by the Contractor and furnish its comments within 10 (ten) days of receiving such Drawings.

The Authority's Engineer shall review the Quality Assurance Plan submitted by the Contractor and shall convey its comments to the Contractor within a period of 21 (twenty-one) days stating the modifications, if any, required thereto.

The Authority's Engineer shall complete the review of the methodology proposed to be adopted by the Contractor for executing the Works, and convey its comments to the Contractor within a period of 10 (ten) days from the date of receipt of the proposed methodology from the Contractor.

The Authority's Engineer shall grant written approval to the Contractor, where necessary, for interruption and diversion of the flow of traffic in the existing lane(s) of the Project Highway for purposes of maintenance during the Construction Period in accordance with the provisions of Clause 10.4.

The Authority's Engineer shall review the monthly progress report furnished by the Contractor and send its comments thereon to the Authority and the Contractor within 7 (seven) days of receipt of such report.

The Authority's Engineer shall inspect the Construction Works and the Project Highway and shall submit a monthly Inspection Report bringing out the results of inspections and the remedial action taken by the Contractor in respect of Defects or deficiencies. In particular, the Authority's Engineer shall include in its Inspection Report, the compliance of the recommendations made by the Safety Consultant.

The Authority's Engineer shall conduct the pre-construction review of manufacturer's test reports and standard samples of manufactured Materials, and such other Materials as the Authority's Engineer may require.

For determining that the Works conform to Specifications and Standards, the Authority's Engineer shall require the Contractor to carry out, or cause to be carried out, tests at such time and frequency and in such manner as specified in the Agreement and



in accordance with Good Industry Practice for quality assurance. For purposes of this Paragraph 4.9, the tests specified in the IRC Special Publication-11 (Handbook of Quality Control for Construction of Roads and Runways) and the Specifications for Road and Bridge Works issued by MORTH (the “Quality Control Manuals”) or any modification/substitution thereof shall be deemed to be tests conforming to Good Industry Practice for quality assurance.

The Authority’s Engineer shall test check at least 20 (twenty) percent of the quantity or number of tests prescribed for each category or type of test for quality control by the Contractor.

The timing of tests referred to in Paragraph 4.9, and the criteria for acceptance/ rejection of their results shall be determined by the Authority’s Engineer in accordance with the Quality Control Manuals. The tests shall be undertaken on a random sample basis and shall be in addition to, and independent of, the tests that may be carried out by the Contractor for its own quality assurance in accordance with Good Industry Practice.

In the event that results of any tests conducted under Clause 11.10 establish any Defects or deficiencies in the Works, the Authority’s Engineer shall require the Contractor to carry out remedial measures.

The Authority’s Engineer may instruct the Contractor to execute any work which is urgently required for the safety of the Project Highway, whether because of an accident, unforeseeable event or otherwise; provided that in case of any work required on account of a Force Majeure Event, the provisions of Clause 21.6 shall apply.

In the event that the Contractor fails to achieve any of the Project Milestones, the Authority’s Engineer shall undertake a review of the progress of construction and identify potential delays, if any. If the Authority’s Engineer shall determine that completion of the Project Highway is not feasible within the time specified in the Agreement, it shall require the Contractor to indicate within 15 (fifteen) days the steps proposed to be taken to expedite progress, and the period within which the Project Completion Date shall be achieved. Upon receipt of a report from the Contractor, the Authority’s Engineer shall review the same and send its comments to the Authority and the Contractor forthwith.

The Authority’s Engineer shall obtain from the Contractor a copy of all the Contractor’s quality control records and documents before the Completion Certificate is issued pursuant to Clause 12.4.

Authority’s Engineer may recommend to the Authority suspension of the whole or part of the Works if the work threatens the safety of the Users and pedestrians. After the

Contractor has carried out remedial measure, the Authority's Engineer shall inspect such remedial measures forthwith and make a report to the Authority recommending whether or not the suspension hereunder may be revoked.

In the event that the Contractor carries out any remedial measures to secure the safety of suspended works and Users, and requires the Authority's Engineer to inspect such works, the Authority's Engineer shall inspect the suspended works within 3 (three) days of receiving such notice, and make a report to the Authority forthwith, recommending whether or not such suspension may be revoked by the Authority.

The Authority's Engineer shall carry out, or cause to be carried out, all the Tests specified in Schedule-K and issue a Completion Certificate or Provisional Certificate, as the case may be. For carrying out its functions under this Paragraph 4.18 and all matters incidental thereto, the Authority's Engineer shall act under and in accordance with the provisions of Article 12 and Schedule-K.

## **5. Maintenance Period**

The Authority's Engineer shall aid and advise the Contractor in the preparation of its monthly Maintenance Programme and for this purpose carry out a joint monthly inspection with the Contractor.

The Authority's Engineer shall undertake regular inspections, at least once every month, to evaluate compliance with the Maintenance Requirements and submit a Maintenance Inspection Report to the Authority and the Contractor.

The Authority's Engineer shall specify the tests, if any, that the Contractor shall carry out, or cause to be carried out, for the purpose of determining that the Project Highway is in conformity with the Maintenance Requirements. It shall monitor and review the results of such tests and the remedial measures, if any, taken by the Contractor in this behalf.

In respect of any defect or deficiency referred to in Paragraph 3 of Schedule-E, the Authority's Engineer shall, in conformity with Good Industry Practice, specify the permissible limit of deviation or deterioration with reference to the Specifications and Standards and shall also specify the time limit for repair or rectification of any deviation or deterioration beyond the permissible limit.

The Authority's Engineer shall examine the request of the Contractor for closure of any lane(s) of the Project Highway for undertaking maintenance/repair thereof, and shall grant permission with such modifications, as it may deem necessary, within 5 (five) days of receiving a request from the Contractor. Upon expiry of the permitted period of

closure, the Authority's Engineer shall monitor the reopening of such lane(s), and in case of delay, determine the Damages payable by the Contractor to the Authority under Clause 14.5.

## **6 Determination of costs and time**

The Authority's Engineer shall determine the costs, and/or their reasonableness, that are required to be determined by it under the Agreement.

The Authority's Engineer shall determine the period of Time Extension that is required to be determined by it under the Agreement.

The Authority's Engineer shall consult each Party in every case of determination in accordance with the provisions of Clause 18.5.

## **7. Payments**

The Authority's Engineer shall withhold payments for the affected works for which the Contractor fails to revise and resubmit the Drawings to the Authority's Engineer in accordance with the provisions of Clause 10.2.4 (d).

Authority's Engineer shall -

- (a) within 10 (ten) days of receipt of the Stage Payment Statement from the Contractor pursuant to Clause 19.4, determine the amount due to the Contractor and recommend the release of 90 (ninety) percent of the amount so determined as part payment, pending issue of the Interim Payment Certificate; and
- (b) within 15 (fifteen) days of the receipt of the Stage Payment Statement referred to in Clause 19.4, deliver to the Authority and the Contractor an Interim Payment Certificate certifying the amount due and payable to the Contractor, after adjustments in accordance with the provisions of Clause 19.10.

The Authority's Engineer shall, within 15 (fifteen) days of receipt of the Monthly Maintenance Statement from the Contractor pursuant to Clause 19.6, verify the Contractor's monthly statement and certify the amount to be paid to the Contractor in accordance with the provisions of the Agreement.

The Authority's Engineer shall certify final payment within 30 (thirty) days of the receipt of the final payment statement of Maintenance in accordance with the provisions of Clause 19.16.

## **8. Other duties and functions**

The Authority's Engineer shall perform all other duties and functions as specified in the Agreement.

## **9 Miscellaneous**

A copy of all communications, comments, instructions, Drawings or Documents sent by the Authority's Engineer to the Contractor pursuant to this TOR, and a copy of all the test results with comments of the Authority's Engineer thereon, shall be furnished by the Authority's Engineer to the Authority forthwith.

The Authority's Engineer shall retain at least one copy each of all Drawings and Documents received by it, including 'as-built' Drawings, and keep them in its safe custody.

Within 90 (ninety) days of the Project Completion Date, the Authority's Engineer shall obtain a complete set of as-built Drawings, in 2 (two) hard copies and in micro film form or in such other medium as may be acceptable to the Authority, reflecting the Project Highway as actually designed, engineered and constructed, including an as-built survey illustrating the layout of the Project Highway and setback lines, if any, of the buildings and structures forming part of Project Facilities; and shall hand them over to the Authority against receipt thereof.

The Authority's Engineer, if called upon by the Authority or the Contractor or both, shall mediate and assist the Parties in arriving at an amicable settlement of any Dispute between the Parties.

The Authority's Engineer shall inform the Authority and the Contractor of any event of Contractor's Default within one week of its occurrence.

SCHEDULE - O  
*(See Clauses 19.4.1, 19.6.1, and 19.8.1)*

**Forms of Payment Statements**

**1. Stage Payment Statement for Works**

The Stage Payment Statement for Works shall state:

- a. the estimated amount for the Works executed in accordance with Clause 19.3.1 subsequent to the last claim;
- b. amounts reflecting adjustments in price for the aforesaid claim;
- c. the estimated amount of each Change of Scope Order executed subsequent to the last claim;
- d. amounts reflecting adjustment in price, if any, for (c) above in accordance with the provisions of Clause 13.2.3 (a);
- e. total of (a), (b), (c) and (d) above;
- f. Deductions:
  - i. Any amount to be deducted in accordance with the provisions of the Agreement except taxes;
  - ii. Any amount towards deduction of taxes; and
  - iii. Total of (i) and (ii) above.
- g. Net claim: (e) – (f) (iii);
- h. The amounts received by the Contractor upto the last claim:
  - i. For the Works executed (excluding Change of Scope orders);
  - ii. For Change of Scope Orders, and
  - iii. Taxes deducted

**2. Monthly Maintenance Payment Statement**

The monthly Statement for Maintenance Payment shall state:

- (a) the monthly payment admissible in accordance with the provisions of the Agreement;
- (b) the deductions for maintenance work not done;
- (c) net payment for maintenance due, (a) minus (b);
- (d) amounts reflecting adjustments in price under Clause 19.12; and

(e) amount towards deduction of taxes

### **3. Contractor's claim for Damages**

**Note:** The Contractor shall submit its claims in a form acceptable to the Authority.

## **SCHEDULE - P**

*(See Clause 20.1)*

### **INSURANCE**

#### **1. Insurance during Construction Period**

The Contractor shall effect and maintain at its own cost, from the Appointed Date till the date of issue of the Completion Certificate, the following insurances for any loss or damage occurring on account of Non Political Event of Force Majeure, malicious act, accidental damage, explosion, fire and terrorism:

- a) insurance of Works, Plant and Materials and an additional sum of [15 (fifteen)] per cent of such replacement cost to cover any additional costs of and incidental to the rectification of loss or damage including professional fees and the cost of demolishing and removing any part of the Works and of removing debris of whatsoever nature; and
- b) insurance for the Contractor's equipment and Documents brought onto the Site by the Contractor, for a sum sufficient to provide for their replacement at the Site.

The insurance under paragraph 1.1 (a) and (b) above shall cover the Authority and the Contractor against all loss or damage from any cause arising under paragraph 1.1 other than risks which are not insurable at commercial terms.

#### **2. Insurance for Contractor's Defects Liability**

The Contractor shall effect and maintain insurance cover for the Works from the date of issue of the Completion Certificate until the end of the Defects Liability Period for any loss or damage for which the Contractor is liable and which arises from a cause occurring prior to the issue of the Completion Certificate. The Contractor shall also maintain other insurances for maximum sums as may be required under the Applicable Laws and in accordance with Good Industry Practice.

#### **3. Insurance against injury to persons and damage to property**

The Contractor shall insure against its liability for any loss, damage, death or bodily injury, or damage to any property (except things insured under Paragraphs 1 and 2 of this Schedule or to

any person (except persons insured under Clause 20.9), which may arise out of the Contractor's performance of this Agreement. This insurance shall be for a limit per occurrence of not less than the amount stated below with no limit on the number of occurrences.

The insurance cover shall be not less than value of the contract price.

The insurance shall be extended to cover liability for all loss and damage to the Authority's property arising out of the Contractor's performance of this Agreement excluding:

- a) the Authority's right to have the construction works executed on, over, under, in or through any land, and to occupy this land for the Works; and
- b) damage which is an unavoidable result of the Contractor's obligations to execute the Works.

**4. Insurance to be in joint names**

The insurance under paragraphs 1 to 3 above shall be in the joint names of the Contractor and the Authority.



## **Schedule-Q**

*(See Clause 14.10)*

### **Tests on Completion of Maintenance Period**

**1. Riding Quality test:**

Riding quality test: Riding quality of each lane of the carriageway shall be checked with the help of a calibrated bump integrator and the maximum permissible roughness for purposes of this Test shall be [2,200 (two thousand and two hundred only)] mm for each kilometre.

**2. Visual and physical test:**

*The Authority's Engineer shall conduct a visual and physical check of construction to determine that all works and equipment forming part thereof conform to the provisions of this Agreement. The physical tests shall include measurement of cracking, rutting, stripping and potholes and shall be as per the requirement of maintenance mentioned in Schedule-E.*

**Schedule-R**

*(See Clause 14.10)*

**Taking Over Certificate**

I,..... (Name and designation of the Authority's Representative) under and in accordance with the Agreement dated ..... (the "**Agreement**"), for "Balance work of Construction of Two-lane with hard shoulders of Merangkong-Tamlu-Mon Road on EPC basis from existing Km 76.640 to Km 98.065 [Design Km. 63.800 to Km. 86.835] (Design length-23.035 km) in the state of Nagaland under SARDP-NE Phase A"(the "**Project Highway**") on Engineering, Procurement and Construction (EPC) basis through (Name of Contractor), hereby certify that the Tests on completion of Maintenance Period in accordance with Article 14 of the Agreement have been successfully undertaken to determine compliance of the Project Highway with the provisions of the Agreement and I hereby certify that the Authority has taken over the Project highway from the Contractor on this day.....

SIGNED, SEALED AND  
DELIVERED

(Signature)

(Name and designation of Authority's

Representative)

(Address)