


MAJOR BRIDGE AT CHAINAGE 572+427

DRAWING INDEX


MAJOR BRIDGE AT DESIGN CH.- 572+427

SR. No.	DRAWING TITLE	DRAWING NUMBER
1	GENERAL ARRANGEMENT DRAWING	NHIDCL/MB/JOR-DIB/ST/MJB/572+427/101 (3 SHEETS)
2	KEY PLAN	NHIDCL/MB/JOR-DIB/ST/MJB/572+427/102 (SHEET 1 OF 1)
3	DETAILS OF TEST PILE	NHIDCL/MB/JOR-DIB/ST/MJB/572+427/103 (SHEET 1 OF 1)
4	DIMENSION DETAILS OF ABUTMENT & FOUNDATION FOR A1 & A2	NHIDCL/MB/JOR-DIB/ST/MJB/572+427/201 (SHEET 1 OF 1)
5	REINFORCEMENT DETAILS OF ABUTMENT & FOUNDATION FOR A1 & A2	NHIDCL/MB/JOR-DIB/ST/MJB/572+427/202 (3 SHEETS)
6	DIMENSION DETAILS OF PIER & FOUNDATION FOR P1-P5	NHIDCL/MB/JOR-DIB/ST/MJB/572+427/203 (SHEET 1 OF 1)
7	REINFORCEMENT DETAILS OF PIER & FOUNDATION FOR P1-P5	NHIDCL/MB/JOR-DIB/ST/MJB/572+427/204 (3 SHEETS)
8	DIMENSION AND REINFORCEMENT DETAILS OF STOPPER AND PEDESTAL OF ABUTMENT	NHIDCL/MB/JOR-DIB/ST/MJB/572+427/205 (SHEET 1 OF 1)
9	DIMENSION AND REINFORCEMENT DETAILS OF STOPPER AND PEDESTAL OF PIER	NHIDCL/MB/JOR-DIB/ST/MJB/572+427/206 (SHEET 1 OF 1)
10	DIMENSION DETAILS OF SUPER STRUCTURE	NHIDCL/MB/JOR-DIB/ST/MJB/572+427/301 (2 SHEETS)
11	CABLE & PRESTRESSING DETAILS	NHIDCL/MB/JOR-DIB/ST/MJB/572+427/302 (SHEET 1 OF 1)
12	REINFORCEMENT DETAILS OF LONGITUDINAL GIRDER	NHIDCL/MB/JOR-DIB/ST/MJB/572+427/303 (SHEET 1 OF 1)
13	DETAILS OF END BLOCK AND ANCHORAGES	NHIDCL/MB/JOR-DIB/ST/MJB/572+427/304 (SHEET 1 OF 1)
14	GENERAL NOTES FOR PRESTRESSING GIRDER	NHIDCL/MB/JOR-DIB/ST/MJB/572+427/305 (SHEET 1 OF 1)
15	REINFORCEMENT DETAILS OF END CROSS GIRDER	NHIDCL/MB/JOR-DIB/ST/MJB/572+427/306 (SHEET 1 OF 1)
16	REINFORCEMENT DETAILS OF INTERMEDIATE CROSS GIRDER	NHIDCL/MB/JOR-DIB/ST/MJB/572+427/307 (SHEET 1 OF 1)
17	REINFORCEMENT DETAILS OF RCC DECK SLAB	NHIDCL/MB/JOR-DIB/ST/MJB/572+427/308 (SHEET 1 OF 1)
18	DETAILS OF LOADS FOR POT CUM PTFE BEARING	NHIDCL/MB/JOR-DIB/ST/MJB/572+427/309 (SHEET 1 OF 1)



PROPOSED FRL (IN m)	91.250	91.250	91.250	91.250
GROUND LEVEL (IN m)	86.656	82.392	84.786	79.779
CHAINAGE (IN Km)	572+308.630	572+347.740	572+387.390	572+427

SECTION AT A-A
(SCALE-1:300)



ANUPAM TAMULI
Project Manager
M/S Manuranjan Brahma
Moran Bypass to Bogibee Junction
(NHIDCL, 4-Lane Project)

LEGEND:-

FRL	FINISHED ROAD LEVEL	U/S	UP STREAM
HFL	HIGHEST FLOOD LEVEL	D/S	DOWN STREAM
GL	GROUND LEVEL	FX	FIXED END
LBL	LOWEST BED LEVEL	FR	FREE END
FDN. LVL.	FOUNDING LEVEL		

LEVELS:-

A1 AND A2	PILE CAP TOP LEVEL	FOUNDING LEVEL
A1 AND A2	84.600m	57.600m
P1-P5	82.847m	45.847m

HYDROLOGICAL DATA

HFL	85.980 m
DISCHARGE	3702.660 cumec
VELOCITY	2.000 m/s

NOTES:

- ALL DIMENSIONS ARE IN MILLIMETRES OTHERWISE SPECIFIED.
- DIMENSIONS NOT TO SCALED. ONLY WRITTEN DIMENSIONS TO BE FOLLOWED.

REFERENCE DRAWING:-

- GENERAL ARRANGEMENT DRAWING
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/101 (SH. 2 OF 3)
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/101 (SH. 3 OF 3)

HALF TOP PLAN HALF BOTTOM PLAN
PLAN
(SCALE-1:300)




Bridge Engineer
VSPL, Sivasagar


REV. NO	DATE	DESCRIPTION	CLIENT:	AUTHORITY ENGINEER :	EPC CONTRACTOR:	SAFETY CONSULTANT:	PROOF CONSULTANT:	PROJECT:	DRAWN	S.S.	TITLE:	DESIGN DIRECTOR:		
R0	NOV. 2019	INITIAL SUBMISSION FOR REVIEW	 NHIDCL BUILDING INFRASTRUCTURE - BUILDING THE NATION	 VOYANTS SOLUTIONS PVT. LTD.	 M/S MANARANJAN BRAHMA WARD NO.-4, DEPOT ROAD, KOKRAJHAR, DIST: KOKRAJHAR, PIN : 783370, ASSAM	 SUVADRA CONSULTANTS H Q-PP-97 TANKAPANI ROAD, BHUBANESWAR-751018, ODISHA (INDIA)	 INDIAN INSTITUTE OF TECHNOLOGY GUWAHATI NEAR DOUL GOBINDA ROAD, AMBICACIN, NORTH GUWAHATI, GUWAHATI, ASSAM, PIN : 781029	MORAN BYPASS ROAD (NH-37) FOUR LANE OF NH-37 FROM END OF MORAN BYPASS (KM 562.525) TO BOGIBEE JUNCTION NEAR LAPETKETA (KM 581.700) IN THE STATE OF ASSAM UNDER SARDP-NE, PHASE 'A' ON EPC MODE- BALANCE WORK.	DRAWN	S.S.	GENERAL ARRANGEMENT DRAWING FOR MAJOR BRIDGE AT DESIGN CH. 572+427			
									DESIGNED	A.M.	SCALE:	AS SHOWN	REVISION:	Sheet:
									CHECKED	B.O.	DRG. NO:	NHIDCL/MB/JOR-DIB/ST/MJB/572+427/101	R0	1 OF 3
									DATE: NOV. 2019					

TO JHORHAT

TO DIBRUGARH



SECTION AT A-A
(SCALE-1:300)




SECTION AT SUPPORT




SECTION AT MID
DETAILED FOR PRECAST
PSC GIRDER
(SCALE-1:40)

HALF TOP PLAN HALF BOTTOM PLAN
PLAN
(SCALE-1:300)

- NOTES:**
- ALL DIMENSIONS ARE IN MILLIMETRES OTHERWISE SPECIFIED.
 - DIMENSIONS NOT TO SCALED. ONLY WRITTEN DIMENSIONS TO BE FOLLOWED.
- REFERENCE DRAWING:-**
- GENERAL ARRANGEMENT DRAWING
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/101 (SH. 1 OF 3)
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/101 (SH. 3 OF 3)



REINF. DETAILS OF TEST PILE
(SCALE 1:25)



BAR SHAPE SCHEDULE

BAR MKD.	DESCRIPTION	BAR SHAPE
01	16#-24 Nos.	
02	12#150c/c	

DIAMETER OF TEST PILE = 1200MM
INITIAL LOAD TEST

S. No.	TEST DIRECTION	DESIGN LOAD (T)	TEST LOAD (T)
1	VERTICAL	280.0	700.0.0 (=2.5x280.0)
	HORIZONTAL	23.0	15.0 (=2.5x23.0/4) (FOR FREE HEAD TEST PILE)

LEVELS

S. No.	LOCATION	GROUND LVL (m)	BOTTOM LVL/TEST LVL (m)	SCOUR LVL (m)	FOUNDING LVL (m)
1	REFER NOTE NO. 10	AS PER TEST PILE LOCATION	80.847	67.500	45.847

NOTES:

- ALL DIMENSIONS ARE IN MM, AND LEVELS IN METERS UNLESS OTHERWISE MENTIONED.
- NO DIMENSION SHALL BE MEASURED FROM THE DRAWINGS. ONLY WRITTEN DIMENSIONS ARE TO BE FOLLOWED.
- GRADE OF CONCRETE FOR TEST PILE SHALL BE M35.
- GRADE OF STEEL FOR TEST PILE SHALL BE Fe-500D CONFORMING TO IS:1786.
- MINIMUM LAP LENGTH SHALL BE 51d WHERE 'd' IS THE DIA OF THE BAR TO BE LAPPED.
- MINIMUM CLEAR COVER TO ANY REINFORCEMENT INCLUDING STIRRUPS SHALL BE 75MM.
- PILES SHALL BE BORED CAST-IN-SITU OF 1200MM DIA. PLACED VERTICALLY.
- LOAD TEST ON PILE SHALL BE CARRIED OUT NOT EARLIER THAN 28 DAYS FROM THE TIME OF CASTING OF PILE.
- THE INITIAL LOAD TEST ON PILE SHALL BE CONDUCTED AS PER IRC:78-2014, IS-2911 (PART-IV) AND TECHNICAL SPECIFICATION (CLAUSE 1100) OF MORTH SPECIFICATIONS FOR 2.5 TIMES THE DESIGN LOAD.
- THE INITIAL LOAD TEST SHALL BE CONDUCTED NEAR TO ABUTMENT A1 OR A2 ON EITHER AS PER INSTRUCTIONS OF AUTHORITY ENGINEER.
- THE SCHEME FOR LOAD TESTING SHALL BE SUBMITTED BY THE LOAD TESTING AGENCY AND GOT APPROVED BEFORE COMMENCEMENT OF TESTING.
- THE PILE CAP SHALL NOT BE CAST BEFORE TESTING OF INITIAL PILE.


REFERENCE DRAWING:-





- GENERAL ARRANGEMENT DRAWING
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/101 (3 SHEETS)



Amulya
ANUPAM TAMULI
Project Manager
M/S Manuranjan Brahma
Moran Bypass to Bogibeel Junction
(NHIDCL, 4-Lane Project)

Adnan
Bridge Engineer
VSPL, Sivasagar

REV. NO		DATE	DESCRIPTION	CLIENT:  NHIDCL BUILDING INFRASTRUCTURE - BUILDING THE NATION	AUTHORITY ENGINEER :  VOYANTS SOLUTIONS PVT. LTD. <i>Team Leader</i>		EPC CONTRACTOR:  M/S MANARANJAN BRAHMA WARD NO.-4, DEPOT ROAD, KOKRAJHAR, DIST: KOKRAJHAR, PIN : 783370, ASSAM		SAFETY CONSULTANT:  SUVADRA CONSULTANTS H.Q.-PP-97 TANKAPANI ROAD, BHUBANESWAR-751018, ODISHA (INDIA)		PROOF CONSULTANT:  INDIAN INSTITUTE OF TECHNOLOGY GUWAHATI NEAR DOUL GOBINDA ROAD, AMBIGAR, NORTH GUWAHATI, GUWAHATI, ASSAM, PIN : 781029		PROJECT: MORAN BYPASS ROAD (NH-37) FOUR LANEING OF NH-37 FROM END OF MORAN BYPASS (KM 562.525) TO BOGIBEEL JUNCTION NEAR LAPETKETA (KM 561.700) IN THE STATE OF ASSAM UNDER SARDP-NE, PHASE 'A' ON EPC MODE- BALANCE WORK.		DRAWN	S.S.	TITLE: DETAILS OF TEST PILE FOR MAJOR BRIDGE AT CH. 572+427		DESIGN DIRECTOR: 		
R0		NOV. 2019	INITIAL SUBMISSION FOR REVIEW												DESIGNED	A.M.	SCALE: AS SHOWN		REVISION:		Sheet
															CHECKED	B.O.	DRG.No: NHIDCL/MB/JOR-DIB/ST/MJB/TP/572+427/103		R0		1 OF 1
															DATE: NOV. 2019						



LEGEND:-

●	BEARING IN PLAN
○	POT-CUM-PTE BEARING IN ELEVATION
○	JACK LOCATION IN PLAN
○	JACK LOCATION IN ELEVATION
○	BRG - BEARING
○	EJ - EXPANSION JOINT
○	LVL - LEVEL
○	FRL - FINISHED ROAD LEVEL
○	FDN - FOUNDATION
○	LVL - LEVEL
○	FR - FREE

NOTES:-

- ALL DIMENSIONS ARE IN MILLIMETERS, LEVELS ARE IN METERS UNLESS OTHERWISE MENTIONED.
- NO DIMENSION SHALL BE MEASURED FROM THE DRAWINGS. ONLY WRITTEN DIMENSIONS SHALL BE FOLLOWED.
- THE REINFORCEMENT SHALL BE HYSD BARS OF GRADE DESIGNATION Fe 500D CONFORMING TO IS 1786-2008.
- CONCRETE SHALL BE DESIGN MIX WITH A MINIMUM 28 DAYS CHARACTERISTIC CUBE STRENGTH FOR DIFFERENT ELEMENTS AS FOLLOWS:

a. RCC ABUT. & ABUT. CAP	M35
b. RCC PILE & PILE CAP	M35
c. RCC CRASH BARRIER	M40
d. PCC LEVELLING COURSE	M15
e. RCC PEDESTALS	M40
f. RCC RESTRAINERS	M35
- CLEAR COVER TO OUTER STEEL SHALL BE AS FOLLOWS:-



a. RCC ABUT. STEM EARTH SIDE	75MM
b. RCC ABUT. OUTER SIDE	40MM
c. RCC ABUT. CAP	40MM
d. RCC RESTRAINERS	40MM
e. RCC PILE & PILE CAP	75MM
f. RCC CRASH BARRIER	40MM
g. RCC PEDESTAL	40MM
- 600MM THICK FILTER MEDIA SHALL BE PROVIDED BEHIND SOLID ABUTMENT WALL & RETURN WALLS.
- BACK FILLING BEHIND WALLS/ABUTMENT SHALL CONSISTS OF SELECTED EARTH CONFORMING TO APPENDIX 6 OF IRC:78-2014 HAVING PROPERTIES $C=0$, $\phi=30^\circ$, $\gamma=2.0t/cu.m.$
- ALL SOLID WALLS RETAINING THE EARTH SHALL BE PROVIDED WITH WEED HOLES (100MM DIA AND SLOPE 1V:20H) STARTING 150MM ABOVE THE GROUND LEVEL AND SPACED 1000MM C/C BOTH HORIZONTALLY AND VERTICALLY IN STAGGERED MANNER.
- PERMANENT STEEL LINER 6MM THK. SHALL BE PROVIDED UPTO MAX. SCOUR LEVEL.
- LAPPING OF REINFORCEMENT SHALL BE AVOIDED AS FAR AS POSSIBLE. IN CASE LAPPING OF BARS BECOME UNAVOIDABLE, LAP LENGTH SHALL BE PROVIDED AS PER CLAUSE 15.2.5 IRC:112-2020:

* $\phi \times 36\phi$	(GRADE M35) FAVOURABLE CONDITION
* $\phi \times 1.43 \times 36\phi$	(GRADE M35) UNFAVOURABLE CONDITION

PERCENTAGE OF LAPPED BARS RELATIVE TO TOTAL CROSS-SECTIONAL AREA	<25%	33%	50%	>50%
?	1	1.15	1.4	1.5

- ANCHORAGE LENGTH SHALL BE AS PER CLAUSE 15.2.3 & 15.2.4, IRC:112-2020:

* 36ϕ	(GRADE M35) FAVORABLE CONDITION
* $1.43 \times 36\phi$	(GRADE M35) UNFAVOURABLE CONDITION



REFERENCE DRAWING:-

- GENERAL ARRANGEMENT DRAWING
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/101 (3 SHEETS)
- REINFORCEMENT DETAILS OF ABUTMENT & FOUNDATION FOR A1 & A2
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/202 (3 SHEETS)


ANUPAM TAMULI
Project Manager
M/S Manuranjan Brahma
Moran Bypass to Bogibee Junction
(NHIDCL, 4-Lane Project)

Bridge Engineer
VSPL, Sivasagar




DR

REV. NO	DATE	DESCRIPTION	CLIENT:	AUTHORITY ENGINEER:	EPC CONTRACTOR:	SAFETY CONSULTANT:	PROOF CONSULTANT:	PROJECT:	DRAWN	S.S.	TITLE:	DESIGN DIRECTOR:
R0	NOV. 2019	INITIAL SUBMISSION FOR REVIEW	NHIDCL	VOYANTS SOLUTIONS PVT. LTD.	M/S MANURANJAN BRAHMA WARD NO. 4, DEPOT ROAD, KOKRAJHAR, DIST: KOKRAJHAR, PIN: 783370, ASSAM	SUVADRA CONSULTANTS H.Q. PP-97 TANKAPANI ROAD, BHUBANESWAR-751018, ODISHA (INDIA)	INDIAN INSTITUTE OF TECHNOLOGY GUWAHATI NEAR DOLA GORHIDA ROAD, ARUNACHAL NORTH GUWAHATI, GUWAHATI, ASSAM, PIN: 781039	MORAN BYPASS ROAD (NH-37) FOUR LANE OF NH-37 FROM END OF MORAN BYPASS (KM 562.525) TO BOGIBEE JUNCTION NEAR LAPETKETA (KM 581.700) IN THE STATE OF ASSAM UNDER SAROP-NE, PHASE 'A' ON EPC MODE- BALANCE WORK.	DRAWN	S.S.	DIMENSION DETAILS OF ABUTMENT & FOUNDATION FOR A1 & A2 FOR MAJOR BRIDGE AT CH. 572+427	DESIGN DIRECTOR:
									DESIGNED	A.M.	SCALE: AS SHOWN	REVISION:
									CHECKED	B.O.		Sheet:
									DATE: NOV. 2019		DRG. NO: NHIDCL/MB/JOR-DIB/ST/MJB/572+427/201	1 OF 1



REINFORCEMENT DETAILS OF ABUTMENT
(SCALE 1:50)




SECTION A-A
(CORBEL R/F OF ABUTMENT CAP NOT SHOWN FOR CLARITY)
(SCALE 1:50)


ANUPAM TAMULI
Project Manager
M/S Manuranjan Brahma
Moran Bypass to Bogibee Junction
(NHIDCL, 4-Lane Project)

LEGEND:-


--- EARTH SIDE
--- OTHER SIDE




SECTION B-B
(SCALE 1:30)



SECTION C-C
(SCALE 1:30)




SECTION D-D
(SCALE 1:30)



DETAIL - 'A'
(SCALE 1:30)

Bridge Engineer
VSPL, Sivasagar

REV. NO	DATE	DESCRIPTION	CLIENT:	AUTHORITY ENGINEER :	EPC CONTRACTOR:	SAFETY CONSULTANT:	PROOF CONSULTANT:	PROJECT:	DRAWN	S.S.	TITLE:	DESIGN DIRECTOR:
R0	NOV. 2019	INITIAL SUBMISSION FOR REVIEW	NHIDCL	VOYANTS SOLUTIONS PVT. LTD.	M/S MANURANJAN BRAHMA WARD NO. 4, DEPOT ROAD, KOKRAJHAR, DIST. KOKRAJHAR, PIN: 783370, ASSAM	SUVADRA CONSULTANTS H.Q. PP-97 TANKAPANI ROAD, BHUBANESWAR-751018, ODISHA (INDIA)	INDIAN INSTITUTE OF TECHNOLOGY GUWAHATI NEAR DOA, GOBINDA ROAD, AMRIGADON, NORTH GUWAHATI, GUWAHATI, ASSAM, PIN: 781039	MORAN BYPASS ROAD (NH-37) FOUR LANE OF NH-37 FROM END OF MORAN BYPASS (KM 562.525) TO BOGIBEE JUNCTION NEAR LAPETKETA (KM 561.700) IN THE STATE OF ASSAM UNDER SARDP-NE, PHASE 'A' ON EPC MODE- BALANCE WORK.	DESIGNED	A.M.	REINFORCEMENT DETAILS OF ABUTMENT & FOUNDATION FOR A1 & A2 FOR MAJOR BRIDGE AT CH. 572+427	DESIGN DIRECTOR:
									CHECKED	B.O.	SCALE: AS SHOWN	REVISION:
									DATE: NOV. 2019		DRG. NO: NHIDCL/MB/JOR-DIB/ST/MJB/572+427/202	Sheet: 1 OF 3



IMPORTANT NOTE:

1. REINFORCEMENT DETAILS TO BE REFERRED ONLY FROM TABLE.
2. BARS SHALL BE PROVIDED IN BUNDLES WHEREVER REQUIRED TO ENSURE PROPER COMPACTION OF CONCRETE.
3. IN CASE OF BUNDLED BARS SHALL BE REPLACED WITH ϕ_n FOR LAP LENGTH & ANCHORAGE LENGTH. ($\phi_n = \phi \sqrt{n}$; WHERE ϕ = DIA. OF BAR BEING BUNDLED & n =NO. OF BARS IN BUNDLE)

REFERENCE DRAWING:-

1. GENERAL ARRANGEMENT DRAWING
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/101 (3 SHEETS)
2. DIMENSION DETAILS OF ABUTMENT & FOUNDATION FOR A1 & A2
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/201 (SHEET 1 OF 1)
3. REINFORCEMENT DETAILS OF ABUTMENT & FOUNDATION FOR A1 & A2
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/202 (SHEET 1 OF 3)
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/202 (SHEET 3 OF 3)




Anupam
ANUPAM TAMULI
Project Manager
M/S Manuranjan Brahma
Moran Bypass to Bogibeel Junction
(NHIDCL, 4-Lane Project)




[Signature]
Bridge Engineer
SPL, Sivasagar


REV. NO	DATE	DESCRIPTION	CLIENT:	AUTHORITY ENGINEER :	EPC CONTRACTOR:	SAFETY CONSULTANT:	PROOF CONSULTANT:	PROJECT:	DRAWN	S.S.	TITLE: REINFORCEMENT DETAILS OF ABUTMENT & FOUNDATION FOR A1 & A2 FOR MAJOR BRIDGE AT CH. 572+427	DESIGN DIRECTOR:	
R0	NOV. 2019	INITIAL SUBMISSION FOR REVIEW		 VOYANTS SOLUTIONS PVT. LTD. <i>Team Leader</i>	 M/S MANARANJAN BRAHMA WARD NO.-4, DEPOT ROAD, KOKRAJAHAR, DIST. KOKRAJAHAR, PIN - 783730, ASSAM	 SUVADRA CONSULTANTS H.Q.-PP-97 TANKAPANI ROAD, BHUBANESWAR-751018, ODISHA (INDIA)	 INDIAN INSTITUTE OF TECHNOLOGY GUWAHATI NEHRU DRG. GORHEN ROAD, AMRIGAON, NORTH GUWAHATI, GUWAHATI, ASSAM, PIN - 781039	MORAN BYPASS ROAD (NH-37) FOUR LANING OF NH-37 FROM END OF MORAN BYPASS (KM 562.525) TO BOGIBHEEL JUNCTION NEAR LAPEKETETA (KM 581.700) IN THE STATE OF ASSAM UNDER SARDP-NE, PHASE 'A' ON EPC MODE- BALANCE WORK.	CHECKED	B.O.	SCALE: AS SHOWN		
									DATE: NOV. 2019		ORG. NO: NHIDCL/MB/JOR-DIB/ST/MJB/572+427/202	REVISION: R0	Sheet: 2 OF 3




SECTION A-A
(SCALE 1:75)




SECTION B-B
(SCALE 1:75)




TOP PLAN OF PILE CAP
(SCALE 1:75)



REINF. DETAILS OF PILE SHAFT
(SCALE 1:50)



SECTION C-C
(SCALE 1:20)



SECTION D-D
(SCALE 1:20)

BAR SHAPE SCHEDULE


BAR MRKD.	DESCRIPTION	BAR SHAPE
01	25# 13Nos.	
1a	25# 13Nos.	
02	12# + 12# (BUNDLED) 120c/c	
2a	12# 120c/c	
03	NOT IN USE	
04	32# 90c/c	
05	16# 110c/c	
06	25# 180c/c ALTERNATELY WITH 6a	
6a	20# 180c/c ALTERNATELY WITH 6	
07	16# 110c/c	
08	12# 200c/c	
8a	12# 200c/c	
09	1L-10# 180 IN TRANSV. DIRECTION 220c/c IN LONG. DIRECTION	

IMPORTANT NOTE:


1. REINFORCEMENT DETAILS TO BE REFERRED ONLY FROM TABLE.
2. BARS SHALL BE PROVIDED IN BUNDLES WHEREVER REQUIRED TO ENSURE PROPER COMPACTION OF CONCRETE.
3. IN CASE OF BUNDLED BARS ϕ SHALL BE REPLACED WITH ϕn FOR LAP LENGTH & ANCHORAGE LENGTH CALCULATION.
($\phi n = \phi \times n$; WHERE ϕ = DIA. OF BAR BEING BUNDLED & n = NO. OF BARS IN BUNDLE)

LEGEND:-

- BAR ON TOP FACE
- BAR ON BOTTOM FACE



TYPICAL DETAIL INDICATING
ANCHORAGE OF LINK
(SCALE 1:2)



TYPICAL DETAIL INDICATING
ANCHORAGE OF STIRRUP
(SCALE 1:2)

LAP DETAILS OF SPIRAL
(SCALE 1:15)





ANUPAM TAMULI
Project Manager
M/S Manuranjan Brahma
Moran Bypass to Bogibee Junction
(NHIDCL, 4-Lane Project)

Bridge Engineer
VSPL, Sivasagar

LOCATION	LENGTH OF PILE (m)	DESIGN MAX. VERTICAL LOAD (t)		VERTICAL LOAD CARRYING CAPACITY (t) (AS PER GEOTECH REPORT)		LATERAL DEFLECTION OF PILE AT SCOUR LEVEL (PILE CAP BTM. LVL.) (mm)	PERMISSIBLE LATERAL DEFLECTION OF PILE AT SCOUR LEVEL (PILE CAP BTM. LVL.) (mm)
		NORMAL	SEISMIC	NORMAL	SEISMIC		
A1 & A2	25.000	201.00	180.00	220.00	275.00	5.0	12.0

REFERENCE DRAWING:-

1. REINFORCEMENT DETAILS OF ABUTMENT & FOUNDATION FOR A1 & A2
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/202 (SHEET 1 OF 3)
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/202 (SHEET 2 OF 3)



NOTES:-

- ALL DIMENSIONS ARE IN MILLIMETERS, LEVELS ARE IN METERS UNLESS OTHERWISE MENTIONED.
- NO DIMENSION SHALL BE MEASURED FROM THE DRAWINGS. ONLY WRITTEN DIMENSIONS SHALL BE FOLLOWED.
- THE REINFORCEMENT SHALL BE HYSD BARS OF GRADE DESIGNATION Fe 500D CONFORMING TO IS 1786-2008.
- CONCRETE SHALL BE DESIGN MIX WITH A MINIMUM 28 DAYS CHARACTERISTIC CUBE STRENGTH FOR DIFFERENT ELEMENTS AS FOLLOWS:

Element	Grade
a. RCC ABUT. & ABUT. CAP	M35
b. RCC PILE & PILE CAP	M35
c. RCC CRASH BARRIER	M40
d. RCC LEVELING COURSE	M15
e. RCC PEDESTALS	M40
- CLEAR COVER TO OUTER STEEL SHALL BE AS FOLLOWS:-

Element	Cover (mm)
a. RCC PIER STEM	40MM
b. RCC PIER CAP	40MM
c. RCC PILE & PILE CAP	75MM
d. RCC CRASH BARRIER	40MM
e. RCC PEDESTALS	40MM
- PERMANENT STEEL LINER 6MM THK. SHALL BE PROVIDED UPTO MAX. SCOUR LEVEL.
- LAPPING OF REINFORCEMENT SHALL BE AVOIDED AS FAR AS POSSIBLE. IN CASE LAPPING OF BARS BECOME UNAVOIDABLE, LAP LENGTH SHALL BE PROVIDED AS PER CLAUSE 15.2.5 IRC:112-2020:

Bar Size	Grade	Favourable Condition (%)	Unfavourable Condition (%)
36	M35	25	33
43	M35	1.15	1.4

- ANCHORAGE LENGTH SHALL BE AS PER CLAUSE 15.2.3 & 15.2.4, IRC:112-2020:

Bar Size	Grade	Favourable Condition (%)	Unfavourable Condition (%)
36	M35	25	33
43	M35	1.15	1.4

REFERENCE DRAWINGS

- GENERAL ARRANGEMENT DRAWING: 11530/E/DD/MJB/GAD-001

LEGEND:-

- BEARING IN PLAN
- POT-CUM-PTFE BEARING IN ELEVATION
- JACK LOCATION IN PLAN
- JACK LOCATION IN ELEVATION
- BEARING
- EXPANSION JOINT
- LEVEL
- FINISHED ROAD LEVEL
- FOUNDATION
- LEVEL
- FREE




ANUPAM TAMULI
Project Manager
M/S Manuram Brahma
Moran Bypass to Bogibee Junction
(NHIDCL, 4-Lane Project)

REFERENCE DRAWING:-


- GENERAL ARRANGEMENT DRAWING
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/101 (3 SHEETS)
- REINFORCEMENT DETAILS OF PIER & FOUNDATION FOR P1-P5
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/204 (3 SHEETS)




REV. NO.	DATE	DESCRIPTION	CLIENT:	AUTHORITY ENGINEER:	EPD CONTRACTOR:	SAFETY CONSULTANT:	PROOF CONSULTANT:	PROJECT:	DRAWN:	S.S.	TITLE:	DESIGN DIRECTOR:
R0	NOV. 2019	INITIAL SUBMISSION FOR REVIEW	NHIDCL	VOYANTS SOLUTIONS PVT. LTD.	M/S MANURAM BRAHMA WARD NO. 4, DEPOT ROAD, KOKRAJHAR, DIST: KOKRAJHAR, PIN: 783370, ASSAM	SUVADRA CONSULTANTS H.Q.-PP-97 TANKAPANI ROAD, BHUBANESWAR-751018, ODISHA (INDIA)	INDIAN INSTITUTE OF TECHNOLOGY GUWAHATI NEAR DOUL GORINDA ROAD, KAMRUP NORTH GUWAHATI, GUWAHATI, ASSAM, PIN: 781029	MORAN BYPASS ROAD (NH-37) FOUR LANE OF NH-37 FROM END OF MORAN BYPASS (KM 562.525) TO BOGIBEE JUNCTION NEAR LAPETKETA (KM 581.700) IN THE STATE OF ASSAM UNDER SAROP-NE, PHASE 'A' ON EPC MODE- BALANCE WORK.	DATE: NOV. 2019	DESIGNED: A.M. CHECKED: B.O.	TITLE: DIMENSION DETAILS OF PIER & FOUNDATION FOR P1-P5 FOR MAJOR BRIDGE AT CH. 572+427 SCALE: AS SHOWN	DESIGN DIRECTOR: [Signature]
											REVISION: R0	Sheet: 1 OF 1



REINFORCEMENT DETAILS OF PIER
(SCALE 1:50)



SECTION A-A
(SCALE 1:50)



SECTION D-D
(SCALE 1:50)

BAR SHAPE SCHEDULE

BAR MRKD.	DESCRIPTION	BAR SHAPE	REMARKS
01	32#-46Nos.		IN EACH COLUMN
1a	32#-46Nos.		IN EACH COLUMN
02	20#-90 c/c		
03	16#-100 c/c		
04	16#-26Nos.		
05	32#-26Nos.		
5a	32#-26Nos.		
06	NOT IN USE		
07	12#-8 Nos.	AS SHOWN	
08	2L-16#-100c/c		STIRRUPS
5a	2L-16#-100c/c		STIRRUPS
09	6NOS.-2L-16#-100c/c		STIRRUPS

REFERENCE DRAWING:-

- GENERAL ARRANGEMENT DRAWING
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/101 (3 SHEETS)
- DIMENSION DETAILS OF PIER & FOUNDATION FOR P1-P5
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/203 (SHEET 1 OF 1)
- REINFORCEMENT DETAILS OF PIER & FOUNDATION FOR P1-P5
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/204 (SHEET 2 OF 3)
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/204 (SHEET 3 OF 3)


ANUPAM TAMULI
Project Manager
M/S Manuranjan Brahma
Moran Bypass to Bogibee Junction
(NHIDCL, 4-Lane Project)




Bridge Engineer
VSPL, Sivasagar




REV. NO	DATE	DESCRIPTION	CLIENT:	AUTHORITY ENGINEER :	EPC CONTRACTOR:	SAFETY CONSULTANT:	PROOF CONSULTANT:	PROJECT:	DRAWN	S.S.	TITLE:	DESIGN DIRECTOR:
R0	NOV. 2019	INITIAL SUBMISSION FOR REVIEW	NHIDCL	VOYANTS SOLUTIONS PVT. LTD.	M/S MANURANJAN BRAHMA WARD NO. 4, DEPOT ROAD, KOKRAJHAR, DIST: KOKRAJHAR, PIN : 783370, ASSAM	SUVADRA CONSULTANTS H.Q.-PP-97 TANKAPANI ROAD, BHUBANESWAR-751018, ODISHA (INDIA)	INDIAN INSTITUTE OF TECHNOLOGY GUWAHATI NEAR DOLA GOSHIA ROAD, AMRIGAOI, NORTH GUWAHATI, GUWAHATI, ASSAM PIN - 781039	MORAN BYPASS ROAD (NH-37) FOUR LANE OF NH-37 FROM END OF MORAN BYPASS (KM 562.525) TO BOGIBEE JUNCTION NEAR LAPETKETA (KM 581.700) IN THE STATE OF ASSAM UNDER SARDIP-NE, PHASE 'A' ON EPC MODE- BALANCE WORK.	DRAWN	S.S.	REINFORCEMENT DETAILS OF PIER & FOUNDATION FOR P1-P5 FOR MAJOR BRIDGE AT CH. 572+427	DESIGN DIRECTOR:
									CHECKED	B.O.	SCALE: AS SHOWN	REVISION:
									DATE: NOV. 2019		DRG.No: NHIDCL/MB/JOR-DIB/ST/MJB/572+427/204	Sheet: 1 OF 3




SECTION B-B
(SCALE 1:20)




SECTION C-C
(SCALE 1:20)



LAP DETAILS OF SPIRAL
(SCALE 1:15)




8 Φ MESH (m1) FOR PEDESTAL
(UNDER BEARING LOCATION TWO LAYERS
ONE AT 20MM & ANOTHER AT 100MM
FROM TOP)
(SCALE: 1:20)




8 Φ MESH (m2)
(UNDER JACK LOCATION TWO LAYERS
ONE AT 20MM & ANOTHER AT 100MM
FROM TOP)
(SCALE 1:20)

REFERENCE DRAWING:-

1. REINFORCEMENT DETAILS OF PIER & FOUNDATION FOR P1-P5
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/204 (SHEET 1 OF 3)
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/204 (SHEET 3 OF 3)



SECTION E-E
(SCALE 1:25)



SECTION F-F
(SCALE 1:25)




Anupam Tamuli
ANUPAM TAMULI
Project Manager
M/S Manuranjan Brahma
Moran Bypass to Bogibeel Junction
(NHIDCL, 4-Lane Project)


VSPL
Bridge Engineer
VSPL, Sivasagar



REV. NO	DATE	DESCRIPTION	CLIENT:	AUTHORITY ENGINEER :	EPC CONTRACTOR:	SAFETY CONSULTANT:	PROJECT CONSULTANT:	PROJECT:	DRAWN	S.S.	TITLE:	DESIGN DIRECTOR:
R0	NOV. 2019	INITIAL SUBMISSION FOR REVIEW	NHIDCL	VOYANTS SOLUTIONS PVT. LTD.	M/S MANURANJAN BRAHMA WARD NO. 4, DEPOT ROAD, KOKRAJHAR, DIST: KOKRAJHAR, PIN : 783370, ASSAM	SUVADRA CONSULTANTS H.O. PP-97 TANKAPANI ROAD, BHUBANESWAR-751018, ODISHA (INDIA)	INDIAN INSTITUTE OF TECHNOLOGY GUWAHATI NEAR DOUL GOBANDA ROAD, AMBIGAOH NORTH GUWAHATI, GUWAHATI, ASSAM. PIN : 781029	MORAN BYPASS ROAD (NH-37) FOUR LANE OF NH-37 FROM END OF MORAN BYPASS (KM 562.525) TO BOGIBEEL JUNCTION NEAR LAPETKETA (KM 581.700) IN THE STATE OF ASSAM UNDER SAROP-NE, PHASE 'A' ON EPC MODE- BALANCE WORK.	DRAWN	S.S.	REINFORCEMENT DETAILS OF PIER & FOUNDATION FOR P1-P5 FOR MAJOR BRIDGE AT CH. 572+427	DESIGN DIRECTOR:
									DESIGNED	A.M.	SCALE: AS SHOWN	REVISION:
									CHECKED	B.O.	DATE: NOV. 2019	Sheet: 2 OF 3




SECTION A-A
(SCALE 1:75)




SECTION B-B
(SCALE 1:75)

LAP DETAILS OF SPIRAL
(SCALE 1:15)


LAP LENGTH =
ONE AND HALF TURN




PLAN OF PILE CAP
(SCALE 1:75)



REINF. DETAILS OF PILE SHAFT
(SCALE 1:50)



SECTION C-C
(SCALE 1:20)




SECTION D-D
(SCALE 1:20)

LEGEND:-


--- BAR ON TOP FACE
--- BAR ON BOTTOM FACE

BAR SHAPE SCHEDULE

BAR MRKD.	DESCRIPTION	BAR SHAPE
01	32#-13 Nos.	
1a	32#-13 Nos.	
02	12#+12# (BUNDLED) @ 120c/c	
2a	12# @ 150c/c	
03	NOT IN USE	
04	32# @ 160c/c	
05	32# @ 160c/c	
06	10# @ 80c/c	
07	10# @ 80c/c	
08	12# @ 200c/c	
8a	12# @ 200c/c	
09	1L-12# @ 320c/c IN TRANSV. DIR. @ 160c/c IN TRAFFIC DIR.	



TYPICAL DETAIL INDICATING
ANCHORAGE OF LINK
(SCALE 1:2)



TYPICAL DETAIL INDICATING
ANCHORAGE OF STIRRUP
(SCALE 1:2)

IMPORTANT NOTE:

1. REINFORCEMENT DETAILS TO BE REFERRED ONLY FROM TABLE.
2. BARS SHALL BE PROVIDED IN BUNDLES WHEREVER REQUIRED TO ENSURE PROPER COMPACTION OF CONCRETE.
3. IN CASE OF BUNDLED BARS ϕ SHALL BE REPLACED WITH ϕ_n FOR LAP LENGTH & ANCHORAGE LENGTH CALCULATION.
($\phi_n = \phi \sqrt{n}$; WHERE ϕ = DIA. OF BAR BEING BUNDLED & n =NO. OF BARS IN BUNDLE)

REFERENCE DRAWING:-

1. REINFORCEMENT DETAILS OF PIER & FOUNDATION FOR P1-P5 NHIDCL/MB/JOR-DIB/ST/MJB/572+427/204 (SHEET 1 OF 3)
- NHIDCL/MB/JOR-DIB/ST/MJB/572+427/204 (SHEET 2 OF 3)




LOCATION	LENGTH OF PILE (m)	DESIGN VERTICAL LOAD (t)		VERTICAL LOAD CARRYING CAPACITY (t) (AS PER GEOTECH REPORT)	
		NORMAL	SEISMIC	NORMAL	SEISMIC
P1 TO P5	35.0	276	256	280	350

ANUPAM TAMULI
Project Manager
M/S Manuranjan Brahma
Moran Bypass to Bogibee Junction
(NHIDCL, 4-Lane Project)



Bridge Engineer
VSPL, Sivasagar

REV. NO	DATE	DESCRIPTION	CLIENT:	AUTHORITY ENGINEER :	EPC CONTRACTOR:	SAFETY CONSULTANT:	PROOF CONSULTANT:	PROJECT:	DRAWN	S.S.	TITLE:	DESIGN DIRECTOR:
R0	NOV. 2019	INITIAL SUBMISSION FOR REVIEW	NHIDCL	VOYANTS SOLUTIONS PVT. LTD.	M/S MANURANJAN BRAHMA WARD NO. 4, DEPOT ROAD, KOKRAJHAR, DIST: KOKRAJHAR, PIN : 783370, ASSAM	SIVADRA CONSULTANTS H.Q.-PP-97 TANKAPANI ROAD, BHUBANESWAR-751018, ODISHA (INDIA)	INDIAN INSTITUTE OF TECHNOLOGY GUWAHATI NEAR DOL GORHENA ROAD, AMINGGAH NORTH GUWAHATI, GUWAHATI, ASSAM, PIN : 781039	MORAN BYPASS ROAD (NH-37) FOUR LANE OF NH-37 FROM END OF MORAN BYPASS (KM 562.525) TO BOGIBEE JUNCTION NEAR LAPETKETA (KM 581.700) IN THE STATE OF ASSAM UNDER SARDP-NE, PHASE 'A' ON EPC MODE-BALANCE WORK.	DRAWN	S.S.	REINFORCEMENT DETAILS OF PIER & FOUNDATION FOR P1-P5 FOR MAJOR BRIDGE AT CH. 572+427	DESIGN DIRECTOR:
									DESIGNED	A.M.	SCALE: AS SHOWN	
									CHECKED	B.O.	DATE: NOV. 2019	REVISION: R0
											DRG.No: NHIDCL/MB/JOR-DIB/ST/MJB/572+427/204	Sheet: 3 OF 3



REFERENCE DRAWING:-

1. GENERAL ARRANGEMENT DRAWING
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/101 (3 SHEETS)
2. DIMENSION DETAILS OF SUPER STRUCTURE
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/301 (SH. 2 OF 2)
3. GENERAL NOTES FOR PRESTRESSING GIRDER
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/305 (SH. 1 OF 1)





Anupam
ANUPAM TAMULI
Project Manager
M/S Manuranjan Brahma
Moran Bypass to Bogibee Junction
(NHIDCL, 4-Lane Project)



Bridge Engineer
VSPL, Sivasagar




REV. NO	DATE	DESCRIPTION	CLIENT:	AUTHORITY ENGINEER :	EPC CONTRACTOR:	SAFETY CONSULTANT:	PROOF CONSULTANT:	PROJECT:	DRAWN	S.S.	TITLE:	DESIGN DIRECTOR:
R0	NOV. 2019	INITIAL SUBMISSION FOR REVIEW	NHIDCL	VOYANTS SOLUTIONS PVT. LTD.	M/S MANARANJAN BRAHMA WARD NO-4, DEPOT ROAD, KOKRAJHAR, DIST: KOKRAJHAR, PIN: 783370, ASSAM	SUVADRA CONSULTANTS H.Q.-PP-97 TANKAPANI ROAD, BHUBANESWAR-751018, ODISHA (INDIA)	INDIAN INSTITUTE OF TECHNOLOGY GUWAHATI NEAR DOUL GORHOLA ROAD, GUWAHATI, NORTH GUWAHATI, PIN: 781035	MORAN BYPASS ROAD (NH-37) FOUR LANE OF NH-37 FROM END OF MORAN BYPASS (KM 562.525) TO BOGIBEE JUNCTION NEAR LAPETKETA (KM 581.700) IN THE STATE OF ASSAM UNDER SARDP-NE, PHASE 'A' ON EPC MODE- BALANCE WORK.	DRAWN	S.S.	DIMENSION DETAILS OF SUPER STRUCTURE FOR MAJOR BRIDGE AT DESIGN CH. 572+427	DESIGN DIRECTOR:
									DESIGNED	A.M.	SCALE: AS SHOWN	REVISION:
									CHECKED	B.O.	DRG. NO: NHIDCL/MB/JOR-DIB/ST/MJB/572+427/301	Sheet: 1 OF 2
									DATE: NOV. 2019			



ABUT/PIER	SPAN (M)	L1 (MM)
A1-P1	39.11	810
P1-P2	39.65	1080
P2-P3	39.61	1060
P3-P4	39.46	985
P4-P5	39.69	1100
P5-A2	38.86	685



ANUPAM TAMULI
Project Manager
M/S Manuranjan Brahma
Moran Bypass to Bogibee Junction
(NHIDCL, 4-Lane Project)



REFERENCE DRAWING:-

1. DIMENSION DETAILS OF SUPER STRUCTURE
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/301 (SH. 1 OF 2)

Bridge Engineer
SPL, Sivasagar





REV. NO	DATE	DESCRIPTION	CLIENT:	AUTHORITY ENGINEER :	EPC CONTRACTOR:	SAFETY CONSULTANT:	PROJECT CONSULTANT:	PROJECT:	DRAWN	S.S.	TITLE:	DESIGN DIRECTOR:
R0	NOV. 2019	INITIAL SUBMISSION FOR REVIEW	NHIDCL	VOYANTS SOLUTIONS PVT. LTD.	M/S MANURANJAN BRAHMA WARD NO. 4, DEPOT ROAD, KOKRAJHAR, DIST. KOKRAJHAR, PIN : 783370, ASSAM	SUVADRA CONSULTANTS H.Q. PP-97 TANKAPANI ROAD, BHUBANESWAR-751018, ODISHA (INDIA)	INDIAN INSTITUTE OF TECHNOLOGY GUWAHATI NEAR DOAL GORINDA ROAD, AMINGAON NORTH GUWAHATI, GUWAHATI, ASSAM, PIN : 781039	MORAN BYPASS ROAD (NH-37) FOUR LANE OF NH-37 FROM END OF MORAN BYPASS (KM 562.525) TO BOGIBEE JUNCTION NEAR LAPETKETA (KM 561.700) IN THE STATE OF ASSAM UNDER SARDP-NE, PHASE 'A' ON EPC MODE- BALANCE WORK.	DRAWN DESIGNED CHECKED DATE: NOV. 2019	S.S. A.M. B.O.	TITLE: SCALE: DRG. NO: NHIDCL/MB/JOR-DIB/ST/MJB/572+427/301	DESIGN DIRECTOR: REVISION: R0 Sheet: 2 OF 2



- ANCHORAGE RECESSES SHALL BE SEALED WITH PREPACKAGED NON-SHRINK MORTAR. END FACES OF GIRDERS TO BE COATED WITH TWO COATES OF EPOXY.
- THE ANCHORAGE DETAILS SHALL BE CONFIRMED WITH PRESTRESSING AGENCY.

BAR MKD.	BAR DIA.	NO./SPACING	SHAPE
01	20	13 NOS.	
02	16	2x2 NOS.	
03	20	10 NOS.	

OD - OUTER DIAMETER



1. GENERAL ARRANGEMENT DRAWING
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/101 (3 SHEETS)
2. DIMENSION DETAILS OF SUPER STRUCTURE
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/301 (2 SHEETS)

Anupam
ANUPAM TAMULI
Project Manager
M/S Manuranjan Brahma
Moran Bypass to Bogibeel Junction
(NHIDCL, 4-Lane Project)


Bridge Engineer
VSPL, Sivasagar

REV. NO	DATE	DESCRIPTION	CLIENT:	AUTHORITY ENGINEER :	EPC CONTRACTOR:	SAFETY CONSULTANT:	PROOF CONSULTANT:	PROJECT:	DRAWN	S.S.	TITLE:	DESIGN DIRECTOR:	
NO	NOV. 2019	INITIAL SUBMISSION FOR REVIEW		 VOYANTS SOLUTIONS PVT. LTD.	 M/S MANARANJAN BRAHMA WARD NO.-4, DEPOT ROAD, KOKRAJHAR, DIST: KOKRAJHAR, PIN - 783370, ASSAM	 SUVADRA CONSULTANTS H.Q.-PP-97 TANKAPANI ROAD, BHUBANESWAR-751018, ODISHA (INDIA)	 INDIAN INSTITUTE OF TECHNOLOGY GUWAHATI NEAR DOUL, GOBINDA ROAD, AHMAGACH, NORTH GUWAHATI, GUWAHATI, ASSAM, PIN - 781039	<u>MORAN BYPASS ROAD (NH-37)</u> FOUR LANING OF NH-37 FROM END OF MORAN BYPASS (KM 562.525) TO BOGIBHEL JUNCTION NEAR LAPEKETETA (KM 561.700) IN THE STATE OF ASSAM UNDER SARDP-NE. PHASE 'A' ON EPC MODE- BALANCE WORK.	DRAWN	S.S.	DETAILS OF END BLOCK AND ANCHORAGES FOR MAJOR BRIDGE AT DESIGN CH. 572+427		
									DESIGNED	A.M.	SCALE:	REVISION:	Sheet:
									CHECKED	B.O.	AS SHOWN	R0	1 OF 1
									DATE: NOV. 2019		DRG. NO: NHIDCL/MB/JOR-DIB-ST/MBJ/572+427/304		

NOTES

- ALL DIMENSIONS ARE IN MILLIMETERS, LEVELS ARE IN METERS UNLESS OTHERWISE MENTIONED.
- NO DIMENSIONS SHALL BE MEASURED FROM THE DRAWINGS. ONLY WRITTEN DIMENSIONS SHALL BE FOLLOWED.
- CONCRETE SHALL BE DESIGN MIX WITH A MINIMUM 28 DAYS CHARACTERISTIC CUBE STRENGTH FOR DIFFERENT ELEMENTS AS FOLLOWS:
 - PSC CAST-IN-SITU GIRDER - M45
 - RCC CAST-IN-SITU DECK SLAB - M35
 - RCC CAST-IN-SITU END CROSS GIRDER - M35
- SUITABLE HOLES SHALL BE LEFT IN PRECAST GIRDER FOR SUPPORTING THE DECK SLAB SHUTTERING.
- THE REINFORCEMENT OF CRASH BARRIER SHALL BE PROPERLY ANCHORED IN THE DECK SLAB BEFORE CASTING THE DECK SLAB.
- BEAMS SHALL BE KEPT UPRIGHT AT ALL TIMES AND TO BE CLEARLY MARKED INDICATING SPAN LOCATION & RESPECTIVE ENDS BEFORE REMOVAL FROM CASTING BED.
- TOP SURFACE OF PRECAST BEAM & VERTICAL EDGES OF END TO BE LEFT ROUGHENED FOR EFFECTIVE BONDING.
- THE REINFORCING STEEL SHALL BE HYSD BARS (GRADE DESIGNATION Fe-500D) CONFORMING TO IS:1786-2008.
- 6MM THK. WEARING COAT (50MM BITUMINOUS CONCRETE + 25MM ASPHALTIC ASPHALT) SHALL BE PROVIDED ABOVE THE DECK SLAB.
- LAPPING OF REINFORCEMENT SHALL BE AVOIDED AS FAR AS POSSIBLE. IN CASE LAPPING OF BARS BECOME UNAVOIDABLE, LAP LENGTH SHALL BE PROVIDED AS PER CLAUSE 15.2.5 IRC:112-2011:

PERCENTAGE OF LAPPED BARS RELATIVE TO TOTAL CROSS-SECTIONAL AREA	<25%	33%	50%	>50%
or	1	1.15	1.4	1.5

PERCENTAGE OF LAPPED BARS RELATIVE TO TOTAL CROSS-SECTIONAL AREA	<25%	33%	50%	>50%
or	1	1.15	1.4	1.5

- ANCHORAGE LENGTH SHALL BE AS PER CLAUSE 15.2.3 & 15.2.4, IRC:112-2011:

32#	(GRADE M45)	FAVORABLE CONDITION
1.43x32#	(GRADE M45)	UNFAVORABLE CONDITION
36#	(GRADE M35)	FAVORABLE CONDITION
1.43x36#	(GRADE M35)	UNFAVORABLE CONDITION
- PRESTRESSING SYSTEM
 - ALL PRESTRESSING STRANDS SHALL HAVE 7 PLY UNCOATED STRESS RELIEVED LOW RELAXATION HIGH TENSILE STRANDS OF 12.7MM DIA. CONFORMING TO CLASS 2 OF IS 14268-1995.
 - THE PARAMETERS ADOPTED FOR DESIGN ARE AS FOLLOWS:-

ANCHORAGE TYPE	19-T-13
SLIP AT EACH END (ASSUMED)	6MM
CO-EFFICIENT OF FRICTION (μ)	0.17/RADIAN
WOBBLE CO-EFFICIENT (K)	0.0020/M
NOMINAL AREA OF EACH STRAND	98.8 sq.MM
NOMINAL ULT. BREAKING LOAD OF EACH STRAND	183.7KN
MODULUS OF ELASTICITY OF HIGH TENSILE STEEL	1.95x10 ⁵ MPa
SHEATHING THICKNESS	2.5 MM
 - CORRUGATED HDPE SHEATHING DUCT OF 85MM DIA (INTERNAL) SHALL BE USED FOR ALL CABLES CONFORMING TO CODAL STANDARDS.
 - ALL THE DESIGN PARAMETERS ADOPTED SHALL BE VERIFIED AT SITE.
- PRESTRESSING OPERATIONS
 - ALL CABLES SHALL BE LAID IN SMOOTH PROFILE PASSING THROUGH THE GIVEN ORDINATES. FIRM SUPPORT SHALL BE INSTALLED AT EVERY METRE AS SHOWN.
 - CABLE LENGTHS MENTIONED IN THE DRAWING ARE INCLUSIVE OF 1000 MILLIMETRE EXTRA AT EACH END. THE TOTAL LENGTH OF CABLE SHALL BE VERIFIED AT SITE.
 - ABSCISSA (DISTANCE "X") OF CABLE GIVEN IN THE DRAWING ARE EVALUATED WITH REFERENCE TO END OF GIRDER. ORDINATES DISTANCE "Y" ARE WITH REFERENCE TO SOFFIT OF THE GIRDER.
 - EXTRA LENGTH OF STRAND PROJECTING BEYOND END BLOCK SHALL NOT BE CUT JUST AFTER THE STRESSING. THESE SHALL BE CUT ONLY AFTER INSTRUCTIONS OF GROUTING ARE ISSUED BY THE ENGINEER.
 - GROUTING OF CABLES SHALL BE DONE IN SAME SEQUENCE AS STRESSING AND SHALL CONFIRM TO TECHNICAL SPECIFICATIONS. ANCHORAGE POCKET SHALL BE FILLED WITH EPOXY MORTAR AFTER STRESSING & GROUTING.
 - TIME LAG BETWEEN STRESSING OF EACH CABLE SHALL BE AVOIDED.
 - EXTENSIONS SHALL BE RECHECKED AT 24 HOURS AFTER ANCHORING TO OBSERVE SLOW SLIPPAGE. IN CASE OF EXCESSIVE SLIPPAGE THE MATTER SHALL BE REPORTED TO THE ENGINEER-IN-CHARGE.
 - EXTENSIONS ARE GIVEN FOR HALF CABLE LENGTHS INCLUSIVE OF 600 MILLIMETER GRIP LENGTH AT EACH END. LOSS UPTO 6mm DUE TO SLIP OF ANCHORAGES ARE NOT TO BE COMPENSATED DURING SITE OPERATIONS. JACK PRESSURE AND EXTENSIONS OF CABLES AT EACH END GIVEN IN THE DRAWING SHALL BE VERIFIED AT SITE.
 - INITIAL SLACKNESS IN CABLES SHALL BE REMOVED BY APPLYING SMALL TENSION. THE INITIAL TENSION REQUIRED TO REMOVE SLACKNESS SHALL BE TAKEN AS THE STARTING POINT FOR MEASURING ELONGATION AND CORRECTION SHALL BE APPLIED AS PER CL. 12.2.1.3 OF IS:1343-1980.
 - IN CASE THE CALCULATED ELONGATION AND THE JACK PRESSURE ARE NOT ACHIEVED SIMULTANEOUSLY DURING PRESTRESSING OPERATION STRESSING SHALL BE CONTINUED / DISCONTINUED AS PER NOTE NO. 17 GIVEN BELOW.
 - EXCESS/DUMMY STRANDS AS SHOWN IN TABLE-2 SHALL BE STRESSED IF ANY SHORTFALL IN PRESTRESSING.
- THE EXTENSIONS GIVEN IN TABLE SHALL BE MODIFIED AT SITE IN CASE ACTUAL VALUE OF AREA OF STRANDS 'A' AND MODULUS OF ELASTICITY 'E' VARIES FROM THOSE ASSUMED IN DESIGN, (AS MENTIONED IN NOTE NO. 12 ABOVE) REVISED EXTENSION SHALL BE CALCULATED AS UNDER:
 REVISED EXTENSION = $(98.8 \times 195 \times 10^{-5}) / (\text{NEW AREA} \times \text{NEW MODULUS}) \times \text{ORIGINAL EXTENSION}$

- EXTENSION OF CABLE SHALL BE VERIFIED FOR A FEW CABLES AT SITE. IN CASE OF VALUE OF A AND K ARE FOUND TO BE DIFFERENT THAN THOSE CONSIDERED FOR DESIGN, EXTENSION SHALL BE SUITABLY MODIFIED AFTER APPROVAL OF DESIGN OFFICE.
- THE GRIP LENGTH FROM ANCHORAGE FACE UPTO GRIPPING POINT IN JACK ASSUMED IN EXTENSION CALCULATIONS IS 600MM AND THE ADDITIONAL LENGTH TAKEN FOR CUTTING IS 400MM. IN CASE GRIP LENGTH VARIES THAN THOSE CONSIDERED, THE EXTENSIONS SHALL BE MODIFIED AS UNDER:

$$Ex(\text{NEW}) = Ex(\text{OLD}) + \text{JACK FORCE} \times (\text{GRIP LENGTH} - 600) / (\text{AREA} \times Es)$$
- SPECIAL NOTE FOR PRESTRESSING
 IF THE CALCULATED ELONGATION IS REACHED BEFORE THE CALCULATED GAUGE PRESSURE IS OBTAINED, CONTINUE TENSIONING TILL ATTAINING THE CALCULATED GAUGE PRESSURE PROVIDED THE ELONGATION DOES NOT EXCEED 1.05 TIMES THE CALCULATED ELONGATION. IF THE CALCULATED ELONGATION HAS NOT BEEN REACHED CONTINUE TENSIONING IN INTERVALS OF 5 kg/sqcm UNTIL THE CALCULATED ELONGATION IS REACHED PROVIDED THE GAUGE PRESSURE DOES NOT EXCEED 1.05 TIMES THE CALCULATED GAUGE PRESSURE. IF THE ELONGATION AT 1.05 TIMES THE CALCULATED GAUGE PRESSURE IS LESS THAN 0.95 TIMES THE CALCULATED ELONGATION THE FOLLOWING MEASURES MUST BE TAKEN :
 - RECALIBRATE THE PRESSURE GAUGE
 - CHECK THE CORRECT FUNCTIONING OF THE JACK PUMP AND LEADS
 - DE-TENSION THE CABLE SLIDE IT IN ITS DUCT TO CHECK THAT IT IS NOT BLOCKED BY MORTAR WHICH HAS ENTERED THROUGH THE SHEATHING. RE-TENSION THE CABLE IF FREE. IF THE REQUIRED ELONGATION IS NOT OBTAINED FURTHER FINISHING OPERATION SUCH AS CUTTING OR SEALING SHOULD NOT BE UNDERTAKEN WITHOUT THE APPROVAL OF THE ENGINEER-IN-CHARGE.
- THE GAUGE PRESSURE FOR PRESTRESSING SHALL BE WORKED OUT PRIOR TO ANY STRESSING OPERATION DULY TAKING IN TO ACCOUNT THE RAM AREA OF THE JACK AND THE JACK EFFICIENCY. THE STRESSING EQUIPMENTS SHALL BE WELL MAINTAINED AND THE CALIBRATION CHARTS SHALL BE AVAILABLE AT SITE.
- THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT DRAWINGS.

CONSTRUCTION SEQUENCE OF GIRDERS

- AT 0TH DAY, GIRDER SHALL BE CASTED ON CASTING BED.
- STRESSING SHALL BE CARRIED OUT IN TWO STAGES. BOTH THE STAGES SHALL BE ON GROUND (BEFORE PLACING ON ABUTMENT/PIER CAP).
- FIRST STAGE PRE-STRESSING:
 - CABLE NO. 3, 4 & 5 SHALL BE STRESSED AT 7TH DAY OR WHEN CONCRETE CUBE STRENGTH IS 35MPa WHICHEVER IS LATER.
 - ALL STRANDS OF CABLES SHALL BE STRESSED FROM BOTH ENDS SIMULTANEOUSLY. THE RATE OF INCREASE OF STRESS IN THE TENDON AT BOTH ENDS SHALL BE EQUAL. ONLY MULTIPLE JACKS SHALL BE USED FOR STRESSING.
- SECOND STAGE PRE-STRESSING:
 - CABLE NO. 1 & 2 SHALL BE STRESSED AT 28TH DAY OR WHEN CONCRETE CUBE STRENGTH IS 45 MPa, WHICHEVER IS LATER.
 - STRANDS OF CABLE NO. 1 & 2 SHALL BE STRESSED FROM ONE END ONLY. HOWEVER, BOTH CABLES SHALL BE STRESSED FROM OPPOSITE ENDS SIMULTANEOUSLY TO AVOID BENDING OF GIRDER IN PLAN.
- GIRDERS SHALL THEN BE PLACED ON TEMPORARY SUPPORT ON PIER CAP.
- PERMANENT BEARING SHALL BE INSTALLED ON PEDESTALS.
- STEEL WEDGE SHALL BE FIXED UNDER GIRDER AT BEARING LOCATION AS PER RELEVANT WEDGE DETAILS.
- TEMPORARY SUPPORTS SHALL BE REMOVED SO THAT GIRDER CAN BE PLACED OVER PERMANENT BEARINGS.
- DECK SLAB SHALL THEN BE CAST AFTER 28 DAYS OF CASTING OF GIRDER.
- CRASH BARRIER/RAILING SHALL BE ERECTED/CAST 3 DAYS AFTER CASTING THE DECK SLAB. THE DECK CANTILEVER SHUTTERING MAY BE OPENED AFTER THE DECK SLAB ATTAINS A STRENGTH OF 25MPa.
- WEARING COAT MAY BE LAID AFTER REMOVAL OF SHUTTERING OF DECK 14 DAYS AFTER CASTING DECK SLAB OR WHEN DECK ATTAINS CONCRETE CUBE STRENGTH OF 35MPa.

LEGENDS

FRL	- FINISHED ROAD LEVEL
GL	- GROUND LEVEL
LVL	- LEVEL
IL	- INVERT LEVEL
EJ	- EXPANSION JOINT
BRG.	- BEARING

 CAST-IN-SITU PORTION

 PRECAST PORTION

REFERENCE DRAWING:-

- GENERAL ARRANGEMENT DRAWING
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/101 (3 SHEETS)
- DIMENSION DETAILS OF SUPER STRUCTURE
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/301 (2 SHEETS)





ANUPAM TAMULI
Project Manager
M/S Manuranjan Brahma
Moran Bypass to Bogibee Junction
(NHIDCL, 4-Lane Project)


Handwritten signature



Handwritten signature
Bridge Engineer
VSP, Sivasaagar

REV. NO	DATE	DESCRIPTION	CLIENT:	THORITY ENGINEER :	EPC CONTRACTOR:	SAFETY CONSULTANT:	PROOF CONSULTANT:	PROJECT:	DRAWN	S.S.	TITLE:	DESIGN DIRECTOR:
R0	NOV. 2019	INITIAL SUBMISSION FOR REVIEW		 VOYANTS SOLUTIONS PVT. LTD.	 M/S MANURANJAN BRAHMA WARD NO. 4, DEPOT ROAD, KOKRAJHAR, DIST: KOKRAJHAR, PIN: 783370, ASSAM	 H.Q.-PP-97 TANKAPANI ROAD, BHUBANESWAR-751018, ODISHA (INDIA)	 INDIAN INSTITUTE OF TECHNOLOGY GUWAHATI NEAR DOUL GOBINDA ROAD, AMRIGADH, NORTH GUWAHATI, GUWAHATI, ASSAM, PIN: 781039	MORAN BYPASS ROAD (NH-37) FOUR LANE OF NH-37 FROM END OF MORAN BYPASS (KM 562.525) TO BOGIBEE JUNCTION NEAR LAPETKETA (KM 581.700) IN THE STATE OF ASSAM UNDER SAROP-NE, PHASE 'A' ON EPC MODE-BALANCE WORK.	DESIGNED	A.M.	GENERAL NOTES FOR PRESTRESSING GIRDER FOR MAJOR BRIDGE AT DESIGN CH. 572+427	
									CHECKED	B.O.	SCALE: AS SHOWN	REVISION:
									DATE: NOV. 2019		DRG. NO: NHIDCL/MB/JOR-DIB/ST/MJB/572+427/305	Sheet: 1 OF 1

Voyants Solutions Pvt. Ltd.



REINFORCEMENT DETAIL OF END CROSS GIRDER
(SCALE 1:30)

IMPORTANT NOTES:


- SUITABLE DOWEL BARS SHALL BE PLACED IN LONGITUDINAL GIRDER (WHILE CASTING IN YARD) FOR CAST-IN-SITU CROSS GIRDER.

REFERENCE DRAWING:-


- GENERAL ARRANGEMENT DRAWING NHIDCL/MB/JOR-DIB/ST/MJB/572+427/101 (3 SHEETS)
- DIMENSION DETAILS OF SUPER STRUCTURE NHIDCL/MB/JOR-DIB/ST/MJB/572+427/301 (2 SHEETS)

SCHEDULE OF REINFORCEMENT


BAR MARK	SHAPE	BAR DIA & SPACING/Nos.
d1		25 ϕ -3 Nos.
d2		25 ϕ -3 Nos.
d2a		25 ϕ -3 Nos.
d2b		25 ϕ -3 Nos.
d3		12 ϕ -8 Nos. (EACH FACE)
d4		12 ϕ -8 Nos. (EACH FACE)
d5		2L-12 ϕ 120c/c
d5a		2L-12 ϕ 120c/c
d5b		2L-16 ϕ 100c/c
d6		25 ϕ -4 Nos.
d7		25 ϕ -3 Nos.
d8		25 ϕ -4 Nos.
d9		25 ϕ -3 Nos.
d10		10 ϕ -8 Nos. (VERTICALLY)
d10a		10 ϕ -8 Nos. (VERTICALLY)
d11		12 ϕ -4 Nos.
d12		12 ϕ -4 Nos.
d13		12 ϕ -8 Nos. (EACH FACE)
d14		12 ϕ -4 Nos.
d15		12 ϕ -4 Nos.
d16		12 ϕ -4 Nos.




SECTION C-C
(SCALE 1:15)




8 ϕ MESH TYPE-M2
(SCALE 1:10)




8 ϕ MESH TYPE-A
(AT BEARING LOCATION TWO LAYERS
ONE AT 20MM & ANOTHER AT
100MM FROM BOTTOM)
(SCALE 1:10)



8 ϕ MESH TYPE-M1
(AT JACK LOCATION TWO LAYERS
ONE AT 20MM & ANOTHER AT
100MM FROM BOTTOM)
(SCALE 1:10)





SECTION A-A
(SCALE 1:20)



SECTION B-B
(SCALE 1:20)

Bridge Engineer
VSPL, Sivasagar


REV. NO	DATE	DESCRIPTION
R0	NOV. 2019	INITIAL SUBMISSION FOR REVIEW



DRAWN	S.S.
DESIGNED	A.M.
CHECKED	B.O.
DATE	NOV. 2019




TITLE	REINFORCEMENT DETAILS OF END CROSS GIRDER FOR MAJOR BRIDGE AT DESIGN CH. 572+427
SCALE	AS SHOWN
DRG. NO.	NHIDCL/MB/JOR-DIB/ST/MJB/572+427/306

DESIGN DIRECTOR	
REVISION	R0
Sheet	1 OF 1



SCHEDULE OF REINFORCEMENT

BAR MARK	SHAPE	BAR DIA & SPACING/Nos.
d1		20 ϕ -2 Nos.
d2		20 ϕ -2 Nos.
d2a		20 ϕ -2 Nos.
d2b		20 ϕ -2 Nos.
d3		12 ϕ -8 Nos. (EACH FACE)
d4		12 ϕ -8 Nos. (EACH FACE)
d5		2L-12 ϕ @150 C/C
d6		25 ϕ -4 Nos.
d7		25 ϕ -2 Nos.
d8		25 ϕ -4 Nos.
d9		25 ϕ -2 Nos.
d10		10 ϕ -8 Nos. (VERTICALLY)



IMPORTANT NOTES:

- SUITABLE DOWEL BARS SHALL BE PLACED IN LONGITUDINAL GIRDER (WHILE CASTING IN YARD) FOR CAST-IN-SITU CROSS GIRDER.

ANUPAM TAMULI
Project Manager
M/S Manuranjan Brahma
Moran Bypass to Bogibeel Junction
(NHIDCL, 4-Lane Project)





REFERENCE DRAWING:-

- GENERAL ARRANGEMENT DRAWING
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/101 (3 SHEETS)
- DIMENSION DETAILS OF SUPER STRUCTURE
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/301 (2 SHEETS)

Bridge Engineer
VSPL, Sivasagar



REV. NO	DATE	DESCRIPTION	CLIENT:	AUTHORITY ENGINEER :	EPC CONTRACTOR:	SAFETY CONSULTANT:	PROJECT CONSULTANT:	PROJECT:	DRAWN	S.S.	TITLE:	DESIGN DIRECTOR:
R0	NOV. 2019	INITIAL SUBMISSION FOR REVIEW	NHIDCL	VOYANTS SOLUTIONS PVT. LTD.	M/S MANURANJAN BRAHMA WARD NO. 4, DEPOT ROAD, KOKRAJHAR, DIST: KOKRAJHAR, PIN : 783370, ASSAM	SUVADRA CONSULTANTS H.O.-PP-97 TANKAPANI ROAD, BHUBANESWAR-751018, ODISHA (INDIA)	INDIAN INSTITUTE OF TECHNOLOGY GUWAHATI NEAR DOUL GOBINDA ROAD, AMBIGACHAL NORTH GUWAHATI, GUWAHATI, ASSAM, PIN : 781029	MORAN BYPASS ROAD (NH-37) FOUR LANE OF NH-37 FROM END OF MORAN BYPASS (KM 562.525) TO BOGIBEEL JUNCTION NEAR LAPETKETA (KM 581.700) IN THE STATE OF ASSAM UNDER SARDP-NE, PHASE 'A' ON EPC MODE- BALANCE WORK.	DESIGNED A.M.	AS SHOWN	REINFORCEMENT DETAILS OF INTERMEDIATE CROSS GIRDER FOR MAJOR BRIDGE AT DESIGN CH. 572+427	
									CHECKED B.O.		SCALE:	REVISION:
									DATE: NOV. 2019		DRG. NO: NHIDCL/MB/JOR-DIB/ST/MJB/572+427/307	Sheet: 1 OF 1




LEGEND:-
 ——— ON BOTTOM FACE
 - - - - - ON TOP FACE

BAR MARK	SHAPE	BAR DIA & SPACING/Nos.
01	100 100	12 # 200c/c
02	100 100	12 # 200c/c
03	100 100	2x(16#-4NOS.)
04	100 100	2L-10#200c/c
05	100 100	12 # 200c/c
5a	100 100	16 # 200c/c
06	100 100	12 # 200c/c
07	100 100	12 # 200c/c
08	100 100	12#-2x6 NOS.
09	100 100	12 # 200c/c
10	100 100	10 # 200c/c
11	500 500	12 # 200c/c

REFERENCE DRAWING:-
 1. GENERAL ARRANGEMENT DRAWING
 NHIDCL/MB/JOR-DIB/ST/MJB/572+427/101 (3 SHEETS)
 2. DIMENSION DETAILS OF SUPER STRUCTURE
 NHIDCL/MB/JOR-DIB/ST/MJB/572+427/301 (2 SHEETS)

Anupam
ANUPAM TAMULI
 Project Manager
 M/S Manuranjan Brahma
 Moran Bypass to Bogibeel Junction
 (NHIDCL, 4-Lane Project)




Bridge Engineer
VSPL, Sivasagar

REV. NO	DATE	DESCRIPTION	CLIENT:	AUTHORITY ENGINEER :	EPC CONTRACTOR:	SAFETY CONSULTANT:	PROOF CONSULTANT:	PROJECT:	DRAWN	S.S.	TITLE:	DESIGN DIRECTOR:
R0	NOV. 2019	INITIAL SUBMISSION FOR REVIEW	NHIDCL	VOYANTS SOLUTIONS PVT. LTD.	M/S MANURANJAN BRAHMA WARD NO.-4, DEPOT ROAD, KOKRAJHAR, DIST: KOKRAJHAR, PIN : 783370, ASSAM	SUVADRA CONSULTANTS H.Q-PP-97 TANKAPANI ROAD, BHUBANESWAR-751018, ODISHA (INDIA)	INDIAN INSTITUTE OF TECHNOLOGY GUWAHATI NEAR DOUL GOBINDA ROAD, AMRIGAOH, NORTH GUWAHATI, GUWAHATI, ASSAM, PIN : 781039	MORAN BYPASS ROAD (NH-37) FOUR LANE OF NH-37 FROM END OF MORAN BYPASS (KM 562.525) TO BOGIBEEL JUNCTION NEAR LAPETKETA (KM 581.700) IN THE STATE OF ASSAM UNDER SARDP.NE. PHASE 'A' ON EPC MODE- BALANCE WORK.	DRAWN	S.S.	REINFORCEMENT DETAILS OF RCC DECK SLAB FOR MAJOR BRIDGE AT DESIGN CH. 572+427	DESIGN DIRECTOR:
									DESIGNED	A.M.	SCALE: AS SHOWN	REVISION:
									CHECKED	B.O.	DRG.NO: NHIDCL/MB/JOR-DIB/ST/MJB/572+427/308	Sheet: 1 OF 1
									DATE: NOV. 2019			

← JORHAT

DIBRUGARH →



TYPE OF BEARING		NORMAL CASE			SEISMIC LONG. CASE			SEISMIC TRANS. CASE			*LONG. MOVEMENT (mm)	DESIGN ROTATION (RADIAN)	TOTAL NO. OF BEARINGS PER SPAN
		VERTICAL LOAD (t)	LONG. FORCE (t)	TRANS. FORCE (t)	VERTICAL LOAD (t)	LONG. FORCE (t)	TRANS. FORCE (t)	VERTICAL LOAD (t)	LONG. FORCE (t)	TRANS. FORCE (t)			
PIN	PIN	0	25	0	0	306	37	0	107	124	0	0.01	1
TRANS. GUIDED	TGB	0	25	0	0	306	0	0	107	0	0	0.01	1
LONG. GUIDED	LGB	0	0	0	0	0	37	0	0	124	-55/+24	0.01	1
FREE	FR	265	27	0	265	27	0	265	27	0	-55/+24	0.01	8

*SIGN "-" INDICATES CONTRACTION, SIGN "+" INDICATES EXPANSION


LEGENDS:



PIN
RESISTS NO VERTICAL LOAD, RESTRAINED IN BOTH DIRECTION & ROTATION PERMITTED.



FR
RESISTS VERTICAL LOAD; FREE IN BOTH DIRECTION AND ROTATION PERMITTED.



LGB
LONGITUDINAL GUIDED BEARING; RESISTS NO VERTICAL LOAD FREE IN LONGITUDINAL DIRECTION, RESTRAINED IN TRANSVERSE DIRECTION AND ROTATION PERMITTED.

NOTES:-

- ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE SPECIFIED.
- THIS DWG. SHOWS THE DESIGN LOADS AND PARAMETERS OF POT/POT CUM PTFE BEARING, THE WORKING DRAWING SHALL BE SUPPLIED BY THE MANUFACTURER.
- THE BEARING SHALL BE POT/POT CUM PTFE ONLY AND MANUFACTURED, TESTED AND INSTALLED AS PER IRC:83 (PART III)/MOST SPECIFICATION.
- MATERIALS SHALL CONFORM TO CLAUSE 925 OF IRC : 83 (PART III) - 2002.
- WELDING :- WELDING SHALL CONFORM TO IS:9595 USING ELECTRODES OF SUITABLE GRADE AS PER IS:814 PRE HEATING AND POST WELD STRESS RELIEVING TO BE DONE AS PER IS:9595.
- NON WORKING SURFACES OF STEEL ELEMENTS SHALL BE GIVEN TWO COATS OF EPOXY PRIMER, AND ONE OR MORE COAT EACH OF EPOXY INTERMEDIATE AND FINISH PAINT WITH TOTAL DRY FILM THICKNESS NOT LESS THAN 150 MICRONS AFTER SUITABLE SURFACE PREPARATION MATING SURFACES OF PISTON AND CYLINDER SHALL BE HARDENED BY METALLURGICAL PROCESSING.
- SILICON GREASE SHALL BE APPLIED AT THE PTFE STAINLESS STEEL INTERFACE IN THE FACTORY AFTER TESTING.
- TOLERANCES :- FOR ALL PARTS SHALL BE AS PER CLAUSE No.927.1 & 930 OF IRC : 83 (PART III)-2002. PLAN DIMENSIONS 0 TO +5mm. OVERALL HEIGHT 0 TO +3mm HEIGHT OF ANY STEEL COMPONENT
 - MACHINED 0 TO +1mm.
 - UNMACHINED CLASS 2 OF IS-4897
- THE STAINLESS STEEL PLATES SHALL BE WELDED ON THE BACKING PLATES.
- ALL BEARINGS SHALL BE LOAD TESTED IN THE FACTORY TO 1.1 TIMES THE DESIGN LOAD INCLUDING SEISMIC FORCE. TWO BEARINGS SELECTED AT RANDOM WILL BE TESTED FOR PERMISSIBLE ROTATION. PAIR OF BEARINGS SELECTED AT RANDOM SHALL BE TESTED FOR CO-EFFICIENT OF FRICTION. CO-EFFICIENT OF FRICTION SHALL BE 0.05 AT THE DESIGN LOAD.
- CERTIFICATE FOR ACCEPTANCE TEST ON BEARINGS SHALL BE FURNISHED.
- SUITABLE ERECTION CLAMPS FOR SAFE TRANSPORTATION AND HANDLING ALONG WITH TEMPLATE FOR ALIGNMENT SHALL BE PROVIDED BY THE MANUFACTURER. THESE SHALL BE REMOVED AFTER INSTALLATION AT AN APPROPRIATE TIME.
- THE BEARING CYLINDER BASE PLATE SHALL BE OF CAST STEEL OF GRADE 280-520 W OF IS:1030-1989 AND THE MATERIAL AND FINISHED PRODUCT SHALL SATISFY ALL THE RELEVANT "IS" TEST & "IS" SPECIFICATIONS SUCH AS:-
 - THE SURFACE HARDNESS SHALL BE TO BRINELL HARDNESS NUMBER MINIMUM 350 BHN AS PER MOST SPECIFICATION (4th REVISION 2001). TOP PLATE AND PISTON WILL BE AS PER IS: 2062 GRADE B - 1992.
 - CASTING TAPER FILLETS ROUNDING OFF OF EDGES TO MATCHING ALLOWANCE TO BE AS PER STANDARD PRACTICE.
 - TESTING SPECIFIED IN IS:1030 i.e. TENSILE TEST IMPACT TEST AND BOND TEST SHALL BE CONDUCTED.
 - CASTING SHALL BE ULTRASONICALLY TESTED AND CERTIFICATES SHALL BE SUBMITTED.
 - QUALITY LEVEL OF CASTING AS PER IS:9565 SHALL BE LEVEL 3.
 - RECERTIFICATION OF CASTING BY WELDING SHALL BE DONE AS PER IS:1030 AND IS:5530.
- THE GROUT/BEDDING MORTAR SHALL BE A HIGH STRENGTH FREE FLOWING NON SHRINK GROUT.
- THE PTFE MAY BE PROVIDED AS SINGLE DIMPLED SHEET OR WITH SMALLER MODULES IN INDIVIDUAL POCKETS WITH 10mm GAP BETWEEN MODULES FILLED WITH SILICON GREASE. THE PTFE SHALL BE OF UNFILLED PURE VIRGIN QUALITY (MOST SPECIFICATION 2001)
- SUITABLE TAPER FOR THE PRESS FIT GUIDE KEY AS REQUIRED MAY BE PROVIDED BY THE MANUFACTURER.
- BEARING SHOULD BE PROCURED FROM THE MANUFACTURER AND APPROVED BY ENGINEER.
- THE DESIGN LATERAL LOAD:-
 - SHALL NOT BE LESS THAN 10% OF DESIGN VERTICAL LOAD AS PER CLAUSE 926.1.4 OF IRC 83 PART-III 2002.
 - SHALL NOT BE MORE THAN 25% OF DESIGN VERTICAL LOAD AS PER CLAUSE 926.1.4 OF IRC 83 PART-III 2002.
- PROCEDURE FOR BEARING INSTALLATION SHALL BE FURNISHED BY BEARING MANUFACTURER.
- GRADE OF CONCRETE ARE AS FOLLOW:-

PSC I-GIRDER	M45
RCC PEDESTAL	M40
- SIZE OF PEDESTAL ARE AS FOLLOW:-

FREE BEARINGS	800x800
PIN/GUIDED BEARING	1000x1000

REFERENCE DRAWING:-

- GENERAL ARRANGEMENT DRAWING
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/101 (3 SHEETS)
- DIMENSION DETAILS OF SUPER STRUCTURE
NHIDCL/MB/JOR-DIB/ST/MJB/572+427/301 (2 SHEETS)

ANUPAM TAMULI
Project Manager
M/S Manuranjan Brahma
Moran Bypass to Bogibeel Junction
(NHIDCL, 4-Lane Project)



Bridge Engineer
VSPL, Sivasagar

EV. NO	DATE	DESCRIPTION	CLIENT:	AUTHORITY ENGINEER :	EPC CONTRACTOR:	SAFETY CONSULTANT:	PROOF CONSULTANT:	PROJECT:	DRAWN	S.S.	TITLE:	DESIGN DIRECTOR:
R0	NOV. 2019	INITIAL SUBMISSION FOR REVIEW	NHIDCL	VOYANTS SOLUTIONS PVT. LTD.	M/S MANURANJAN BRAHMA WARD NO-4, DEPOT ROAD, KOKRAJHAR, DIST: KOKRAJHAR, PIN : 783370, ASSAM	SUVADRA CONSULTANTS H.Q.-PP-97 TANKAPANI ROAD, BHUBANESWAR-751018, ODISHA (INDIA)	INDIAN INSTITUTE OF TECHNOLOGY GUWAHATI NEAR DOUL GOBINDA ROAD, AMGAON, NORTH GUWAHATI, GUWAHATI, ASSAM. PIN : 781025	MORAN BYPASS ROAD (NH-37) FOUR LANE OF NH-37 FROM END OF MORAN BYPASS (KM 562.525) TO BOGIBEEL JUNCTION NEAR LAPETKETA (KM 581.700) IN THE STATE OF ASSAM UNDER SAROP-NE, PHASE 'A' ON EPC MODE- BALANCE WORK.	DRAWN	S.S.	DETAILS OF LOADS FOR POT CUM PTFE BEARING MAJOR BRIDGE AT DESIGN CH. 572+414	DESIGN DIRECTOR:
									DESIGNED	A.M.		
									CHECKED	B.O.	SCALE: AS SHOWN	REVISION:
									DATE: NOV. 2019		DRG. NO: NHIDCL/MB/JOR-DIB/ST/MJB/572+414/309	Sheet: 1 OF 1