

## **SCHEDULES**


## For

"Upgradation & Improvement of Tamenglong- Mahur Road (NH-137) to two lane with paved shoulders in the state of Assam on Engineering, Procurement & Construction (EPC) mode - Package-7 starting near Jiri River(Assam/Manipur Border) at km 96.870 and ending near Hangrum at km 116.550 (Length-19.68km)"

March, 2023

National Highways & Infrastructure Development Corporation Ltd 3rd floor, PTI Building, 4-Parliament Street,

New Delhi - 110001







**Technical Schedule** 

#### Schedule- A

(See Clauses 2.1 and 8.1)

#### Site of the Project

#### 1. TheSite

- (i) Site of the Two-Lane (proposed 4-lane divided carriageway)Project Highway shall include the land, buildings, structures and road works as described in Annex-I of this **Schedule-A**
- (ii) The dates of handing over the Right of Way to the Contractor are specified in Annex-II of this Schedule-A.
- (iii) An inventory of the Site including the land, buildings, structures, road works, trees and any other immovable property on, or attached to, the Site shall be prepared jointly by the Authority Representative and the Contractor, and such inventory shall form part of the memorandum referred to In Clause 8.2.1 of this Agreement.
- (iv) The alignment plans of the Project Highway are specified in Annex-III. In the case of sections where no modification in the existing alignment of the Project Highway is contemplated, the alignment plan has not been provided. Alignment plans have only been given for sections where the existing alignment is proposed to be upgraded. The proposed profile of the Project Highways shall be followed by the contractor with minimum FRL as indicated in the alignment plan. The Contractor, however, improve/upgrade the Road Profile as indicated in Annex-III based on site/design requirement.
- (v) The status of the environment clearances obtained or awaited is given in Annex IV.





**Technical Schedule** 

## **KEY PLAN**







**Technical Schedule** 

## Annex-I (Schedule-A)

Site

#### 1. Site

The Site of the two-lane (proposed 2-lanewith paved shoulder carriageway) Project Highway starts near Jiri River (Assam/ Manipur Border) ends near Hangrum (Package-7) from Existing Chainage km 99+287 of NH-137 to km 117+920 of NH 137 (Design Chainage km 96+870 to km 116+550) on Tamenglong - Mahur road in the state of Assam. The land, carriageway and structures comprising the Site are described below.

#### 2. Land

The Site of the Project Highway comprises the land described below:

| C No  | Existing Chainage (km) |         | Length | Dight of Way (m) | Domonules     |  |
|-------|------------------------|---------|--------|------------------|---------------|--|
| S No. | From                   | То      | (m)    | Right of Way (m) | Remarks       |  |
| 1     | 99+287                 | 109+240 | 9953   | 0                | Green Field   |  |
| 2     | 109+240                | 117+920 | 8680   | 7                | Existing Road |  |

## 3. Carriageway

The present carriageway of the Project Highway is 3.75m wide& some green field Stretch. The type of the existing pavement is flexible. The detail is given below.

| S No.  | Existing Chainage (km) |         | Length<br>(m) | Carriageway Width (m)   | Remarks     |  |
|--------|------------------------|---------|---------------|-------------------------|-------------|--|
| 3 140. | From                   | То      | (111)         | Carriageway Width (III) | Kelilai Ks  |  |
| 1      | 99+287                 | 109+240 | 9953          | -                       | Green Field |  |
| 2      | 109+240                | 117+920 | 8680          | 3.75                    | -           |  |
| Total  |                        |         | 18633         |                         |             |  |

#### 4. Major Bridges

The Site includes the following Major Bridges:

| S.<br>No. | Chainage(km) | Type of super structures |                   |                | No. of Spans            | Width |  |
|-----------|--------------|--------------------------|-------------------|----------------|-------------------------|-------|--|
|           |              | Foundation               | Sub-<br>structure | Superstructure | with span<br>length (m) | (m)   |  |
| NIL       |              |                          |                   |                |                         |       |  |

#### 5. Road over-bridges (ROB)/ Road under-bridges (RUB)

The Site includes the following ROB (road over railway line)/RUB (road under railway line):

| S.<br>No. | Chainage (km) | Type of Structure |                | No. of Spans with span length (m) | Width (m) | ROB/RUB |  |
|-----------|---------------|-------------------|----------------|-----------------------------------|-----------|---------|--|
|           |               | Foundation        | Superstructure | span tengui (iii)                 |           |         |  |
| NIL       |               |                   |                |                                   |           |         |  |





**Technical Schedule** 

#### 6. Grade separators

The Site includes the following grade separators:

| S.No. | Chainage | Type of Structure |                | No. of Spans with | Width (m)   |
|-------|----------|-------------------|----------------|-------------------|-------------|
| 3.NO. | (km)     | Foundation        | Superstructure | span length (m)   | Width (III) |
|       |          |                   |                |                   |             |

# 7. Minor bridges

The Site includes the following minor bridges:

| S.  | Chainage<br>(km) | Type of super structures |                   |                | No. of Spans            | Width |
|-----|------------------|--------------------------|-------------------|----------------|-------------------------|-------|
| No. |                  | Foundation               | Sub-<br>structure | Superstructure | with span<br>length (m) | (m)   |
| 1   | 114+525          | _                        | _                 | Bailey Bridge  | 1x19.8                  | 4.1   |

## 8. Railway level crossings

The Site includes the following railway level crossings:

| S. No. | Location (km) | Remarks |  |
|--------|---------------|---------|--|
|        | NIL           |         |  |

## 9. Underpasses (vehicular, non-vehicular)

The Site includes the following underpasses:

| S.No. | Chainage(km) | Type of Structure | No. of Spans with span length(m) | Width(m) |  |  |  |
|-------|--------------|-------------------|----------------------------------|----------|--|--|--|
|       | NIL          |                   |                                  |          |  |  |  |

#### 10. Culverts

The Site has the following culverts:

| S. No. | Chainage(km) | Type of Culvert | Span /Opening with span length (m) | Remarks |
|--------|--------------|-----------------|------------------------------------|---------|
| 1      | 109570       | Slab            | 1X2                                |         |
| 2      | 109695       | Slab            | 1X2                                |         |
| 3      | 109740       | Slab            | 1X1                                |         |
| 4      | 110020       | Slab            | 1X1                                |         |
| 5      | 110155       | Slab            | 1X1                                |         |
| 6      | 110490       | Slab            | 1X1                                |         |
| 7      | 110885       | SLAB            | 1X3                                |         |
| 8      | 110985       | Slab            | 1X1                                |         |
| 9      | 111085       | Slab            | 1X1                                |         |
| 10     | 111410       | HPC             | 1ROW900                            |         |
| 11     | 111955       | Slab            | 1X2                                |         |
| 12     | 112245       | Slab            | 1X1                                |         |





Technical Schedule

|        | Technical Schedule |                 |                                    |         |  |
|--------|--------------------|-----------------|------------------------------------|---------|--|
| S. No. | Chainage(km)       | Type of Culvert | Span /Opening with span length (m) | Remarks |  |
| 13     | 112100             | Slab            | 1X1                                |         |  |
| 14     | 112545             | Slab            | 1X1                                |         |  |
| 15     | 113015             | SLAB            | 1X3                                |         |  |
| 16     | 113210             | SLAB            | 1X3                                |         |  |
| 17     | 113300             | SLAB            | 1X3                                |         |  |
| 18     | 113565             | Slab            | 1X2                                |         |  |
| 19     | 113835             | Slab            | 1X2                                |         |  |
| 20     | 113990             | Slab            | 1X2                                |         |  |
| 21     | 114100             | Slab            | 1X1                                |         |  |
| 22     | 114610             | Slab            | 1X1                                |         |  |
| 23     | 114840             | SLAB 1X3        |                                    |         |  |
| 24     | 115050             | Slab            | 1X1                                |         |  |
| 25     | 115175             | SLAB            | 1X3                                |         |  |
| 26     | 115250             | Slab            | 1X1                                |         |  |
| 27     | 115420             | Slab            | 1X1                                |         |  |
| 28     | 115510             | Slab            | 1X1                                |         |  |
| 29     | 115775             | Slab            | 1X1                                |         |  |
| 30     | 115860             | Slab            | 1X1                                |         |  |
| 31     | 115975             | Slab            | 1X1                                |         |  |
| 32     | 116270             | SLAB            | 1X3                                |         |  |
| 33     | 116500             | HPC             | 1ROW900                            |         |  |
| 34     | 116680             | Slab            | 1X1                                |         |  |
| 35     | 116840             | SLAB            | 1X3                                |         |  |
| 36     | 117460             | Slab            | 1X2                                |         |  |
| 37     | 117550             | HPC             | 1ROW900                            |         |  |
| 38     | 117805             | SLAB            | 1X3                                |         |  |

## 11. Bus bays

The details of bus bays on the Site are as follows:

| S. No. | Chainage(km) | Length (m) | Left Hand Side | Right Hand side |  |  |
|--------|--------------|------------|----------------|-----------------|--|--|
| NIL    |              |            |                |                 |  |  |

## 12. Truck Lay byes

The details of truck lay byes are as follows:

| S. No. | Chainage(km) | Length (m) | Left Hand Side | Right Hand side |  |  |
|--------|--------------|------------|----------------|-----------------|--|--|
| NIL    |              |            |                |                 |  |  |

#### 13. Roadside drains

The details of the roadside drains are as follows:

| S. No. | Location | Туре |
|--------|----------|------|
|--------|----------|------|





**Technical Schedule** 

| From km to km |   | Masonry/cc (Pucca) | Earthen (Kutcha) |  |
|---------------|---|--------------------|------------------|--|
|               | ١ | IIL                |                  |  |

## 14. Major Junctions

The details of major junctions are as follow.

| S.  | Locat   | ion   | At          | Company   |    | Categor | y of Cross | Road   |
|-----|---------|-------|-------------|-----------|----|---------|------------|--------|
| No. | From km | To km | At<br>grade | Separated | NH | SH      | MDR        | Others |
|     | NIL     |       |             |           |    |         |            |        |

(NH: National Highway, SH: State Highway, MDR: Major District Road)

#### 15. Minor Junctions

The details of the minor junctions are as follows:

| S. No. | Existing Chainage | Chainage Design<br>Chainage |    | Type of<br>Junctions<br>(T,Y,+) | Side | Type of Road (SH/<br>MDR/ PMGSY/ VR) |
|--------|-------------------|-----------------------------|----|---------------------------------|------|--------------------------------------|
| 1      | 109+240           | -                           | ВТ | Y                               | LHS  | To N. Sonkhai<br>Village             |

## 16. Bypasses

The details of the bypasses are as follows:

| S.No. | Name of bypass (town) | Chainage (km) From km to km | Length |
|-------|-----------------------|-----------------------------|--------|
|       |                       | NIL                         |        |

## 17. Details of Existing Utilities Schedule

The existing utilities schedules as below,

#### 17.1 Electrical Utilities

The Site includes the following Electrical Utilities: -

## (a) Extra High-Tension Lines (EHT Lines)

|        |          |    | Lengt               | h of line(km) | No                  |       |         |
|--------|----------|----|---------------------|---------------|---------------------|-------|---------|
| S. No  | Chainage |    | Maintained by PGCIL |               | Maintained by PGCIL |       | Remarks |
| 3. 140 |          |    | De                  | partment      | Department          |       |         |
|        | From     | То | 400KV               | 132KV         | 400KV               | 132KV |         |
| NIL    |          |    |                     |               |                     |       |         |





b) High Tension/Low Tension Lines (HT/LT Lines)

| c  | S.No Chainage |       |        |         | Length of Line(in km) |         |         | Nos. of Crossings |         |         |         | Transformer |          |
|----|---------------|-------|--------|---------|-----------------------|---------|---------|-------------------|---------|---------|---------|-------------|----------|
| ٥. | NO [          | From  | То     | HT 33KV | HT 11KV               | LT 230V | LT 440V | HT 33KV           | HT 11KV | LT 230V | LT 440V | No          | Capacity |
|    | 1             | 99287 | 117920 | -       | 8670                  |         | -       |                   | 1       | -       |         | -           | -        |

0 nos. of Distribution Transformer

- c) Public Health Utilities (Water/Sewage Pipelines)
  - (a) The Site includes the following Public Health Utilities: -

|      | Chainage |        | Length (in m)     |                         |                 | Crossings (in m)        |                   |                         |                 | Remarks                 |   |
|------|----------|--------|-------------------|-------------------------|-----------------|-------------------------|-------------------|-------------------------|-----------------|-------------------------|---|
|      |          |        | Water Supply Line |                         | Sewage Line     |                         | Water Supply Line |                         | Sewage Line     |                         |   |
| S.No | From     | То     | With<br>Pumping   | With<br>Gravity<br>Flow | With<br>Pumping | With<br>Gravity<br>Flow | With<br>Pumping   | With<br>Gravity<br>Flow | With<br>Pumping | With<br>Gravity<br>Flow |   |
| 1    | 99287    | 117920 | -                 | 160                     | -               |                         | -                 | •                       | -               |                         | - |





**Technical Schedule** 

## (b) Bore well/Hand Pump within RoW

| SI. No. | Bore V   | Vell** | Hand Pump |     |  |
|---------|----------|--------|-----------|-----|--|
| 31. NO. | Chainage | Nos    | Chainage  | Nos |  |
|         |          |        |           |     |  |

## (c) Water Tank within RoW

| SI. No. |          | Water Tank |          |  |  |  |
|---------|----------|------------|----------|--|--|--|
|         | Chainage | Nos        | Capacity |  |  |  |
| NIL     |          |            |          |  |  |  |

## d) Any Other Items: 2no.

| CL N-   | Other Items  |     |
|---------|--|-----|
| Sl. No. | Items  | Nos |
| 1       | TP of RSF 2.00m <sup>2</sup> with internal connection, Back wash with Solar Panels | 1   |
| 2       | CWR 15KL Cap. With Chemical dosing pump  | 1   |

# 18. Other Structures: NIL





**Technical Schedule** 

# Annex-II (As per Clause 8.3 (i))

(Schedule-A)

## Dates for providing Right of Way of Construction Zone

The dates on which the Authority shall provide Right of Way of Construction Zone to the Contractor on different stretches of the Site are stated below:

## (i) Full Right of Way (full width)

| Description             | Design C |         | Length<br>(km) | Width  | Date of Providing ROW |
|-------------------------|----------|---------|----------------|--------|-----------------------|
|                         | From     | То      | (KIII)         | (m)    |                       |
|                         | 96.870   | 97.100  | 0.230          | 80.000 |                       |
|                         | 97.100   | 98.100  | 1.000          | 50.000 |                       |
|                         | 98.100   | 98.400  | 0.300          | 95.000 |                       |
|                         | 98.400   | 99.500  | 1.100          | 75.000 |                       |
|                         | 99.500   | 100.200 | 0.700          | 50.000 |                       |
|                         | 100.200  | 105.100 | 4.900          | 55.000 |                       |
|                         | 105.100  | 106.500 | 1.400          | 45.000 |                       |
|                         | 106.500  | 106.700 | 0.200          | 50.000 |                       |
|                         | 106.700  | 107.100 | 0.400          | 65.000 |                       |
|                         | 107.100  | 107.500 | 0.400          | 45.000 |                       |
|                         | 107.500  | 108.000 | 0.500          | 45.000 |                       |
|                         | 108.000  | 108.370 | 0.370          | 60.000 | Within180 days after  |
| Full Right of Way (full | 108.370  | 109.000 | 0.630          | 45.000 | Appointed Date        |
| width)                  | 109.000  | 109.240 | 0.240          | 60.000 |                       |
|                         | 109.240  | 109.280 | 0.040          | 45.000 |                       |
|                         | 109.280  | 109.500 | 0.220          | 65.000 |                       |
|                         | 109.500  | 109.900 | 0.400          | 50.000 |                       |
|                         | 109.900  | 111.100 | 1.200          | 45.000 |                       |
|                         | 111.100  | 111.320 | 0.220          | 75.000 |                       |
|                         | 111.320  | 114.200 | 2.880          | 45.000 |                       |
|                         | 114.200  | 116.200 | 2.000          | 35.000 |                       |
|                         | 116.200  | 116.550 | 0.350          | 45.000 |                       |





**Technical Schedule** 

#### Annex - III

#### (Schedule-A)

#### **Alignment Plans**

The alignment plan of the Project Highway is available on E - Tendering portal of NHIDCL

The existing alignment of the Project Highway shall be modified in the following sections as per the alignment plan indicated below:

- i. The alignment of the Project Highway is enclosed in alignment plan. Finished road level indicated in the alignment plan shall be followed by the contractor as minimum FRL. In any case, the finished road level of the project highway shall not be less than those indicated in the alignment plan. The contractor shall, however, improve/upgrade the Road profile as indicated in Annex-III based on site/design requirement.
- ii. Traffic Sign ages of the Project Highway showing numbers & location of traffic signs is enclosed. The contractor shall, however, improve/upgrade upon the traffic signage plan as indicated in Annex-III based on site/design requirement as per the relevant specifications/IRC Codes/Manual.





**Technical Schedule** 

#### Annex - IV

## (Schedule-A)

## **Environment Clearances**

As per MOEF notification F. No. 21-270/2008-1A.III (dated 22 August 2013), Environmental Clearance is not required for Assam state.





## Annexure -V

# (Schedule -A)

## Centre Line Coordinates of the Project Road

| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 1    | 96+870   | 532318.742 | 2774964.558 |
| 2    | 96+880   | 532308.799 | 2774965.445 |
| 3    | 96+890   | 532298.877 | 2774964.339 |
| 4    | 96+900   | 532289.372 | 2774961.283 |
| 5    | 96+910   | 532280.665 | 2774956.4   |
| 6    | 96+920   | 532273.097 | 2774949.888 |
| 7    | 96+930   | 532266.104 | 2774942.739 |
| 8    | 96+940   | 532259.112 | 2774935.591 |
| 9    | 96+950   | 532252.119 | 2774928.442 |
| 10   | 96+960   | 532245.127 | 2774921.293 |
| 11   | 96+970   | 532238.134 | 2774914.144 |
| 12   | 96+980   | 532231.142 | 2774906.996 |
| 13   | 96+990   | 532224.149 | 2774899.847 |
| 14   | 97+000   | 532217.157 | 2774892.698 |
| 15   | 97+010   | 532210.164 | 2774885.549 |
| 16   | 97+020   | 532203.172 | 2774878.401 |
| 17   | 97+030   | 532196.179 | 2774871.252 |
| 18   | 97+040   | 532189.186 | 2774864.103 |
| 19   | 97+050   | 532182.194 | 2774856.955 |
| 20   | 97+060   | 532175.201 | 2774849.806 |
| 21   | 97+070   | 532168.208 | 2774842.658 |
| 22   | 97+080   | 532161.127 | 2774835.597 |
| 23   | 97+090   | 532153.764 | 2774828.832 |
| 24   | 97+100   | 532146.073 | 2774822.442 |
| 25   | 97+110   | 532138.072 | 2774816.445 |
| 26   | 97+120   | 532129.782 | 2774810.855 |
| 27   | 97+130   | 532121.222 | 2774805.687 |
| 28   | 97+140   | 532112.415 | 2774800.953 |
| 29   | 97+150   | 532103.382 | 2774796.665 |
| 30   | 97+160   | 532094.146 | 2774792.834 |
| 31   | 97+170   | 532084.73  | 2774789.469 |
| 32   | 97+180   | 532075.159 | 2774786.578 |
| 33   | 97+190   | 532065.482 | 2774784.055 |
| 34   | 97+200   | 532055.781 | 2774781.628 |
| 35   | 97+210   | 532046.08  | 2774779.201 |
| 36   | 97+220   | 532036.379 | 2774776.773 |
| 37   | 97+230   | 532026.678 | 2774774.346 |
| 38   | 97+240   | 532016.977 | 2774771.919 |

| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 39   | 97+250   | 532007.276 | 2774769.492 |
| 40   | 97+260   | 531997.575 | 2774767.065 |
| 41   | 97+270   | 531987.874 | 2774764.637 |
| 42   | 97+280   | 531978.174 | 2774762.21  |
| 43   | 97+290   | 531968.473 | 2774759.783 |
| 44   | 97+300   | 531958.772 | 2774757.356 |
| 45   | 97+310   | 531949.071 | 2774754.929 |
| 46   | 97+320   | 531939.37  | 2774752.501 |
| 47   | 97+330   | 531929.669 | 2774750.074 |
| 48   | 97+340   | 531919.968 | 2774747.647 |
| 49   | 97+350   | 531910.267 | 2774745.22  |
| 50   | 97+360   | 531900.566 | 2774742.793 |
| 51   | 97+370   | 531890.865 | 2774740.366 |
| 52   | 97+380   | 531881.164 | 2774737.938 |
| 53   | 97+390   | 531871.48  | 2774735.444 |
| 54   | 97+400   | 531861.913 | 2774732.539 |
| 55   | 97+410   | 531852.557 | 2774729.014 |
| 56   | 97+420   | 531843.457 | 2774724.873 |
| 57   | 97+430   | 531834.653 | 2774720.134 |
| 58   | 97+440   | 531826.184 | 2774714.82  |
| 59   | 97+450   | 531818.088 | 2774708.954 |
| 60   | 97+460   | 531810.4   | 2774702.561 |
| 61   | 97+470   | 531803.152 | 2774695.675 |
| 62   | 97+480   | 531796.227 | 2774688.461 |
| 63   | 97+490   | 531789.367 | 2774681.185 |
| 64   | 97+500   | 531782.507 | 2774673.909 |
| 65   | 97+510   | 531775.647 | 2774666.633 |
| 66   | 97+520   | 531768.787 | 2774659.357 |
| 67   | 97+530   | 531761.927 | 2774652.081 |
| 68   | 97+540   | 531755.067 | 2774644.805 |
| 69   | 97+550   | 531748.207 | 2774637.529 |
| 70   | 97+560   | 531741.347 | 2774630.252 |
| 71   | 97+570   | 531734.575 | 2774622.895 |
| 72   | 97+580   | 531728.197 | 2774615.196 |
| 73   | 97+590   | 531722.593 | 2774606.921 |
| 74   | 97+600   | 531718.103 | 2774597.994 |
| 75   | 97+610   | 531714.786 | 2774588.566 |
| 76   | 97+620   | 531712.359 | 2774578.867 |





| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 77   | 97+630   | 531710.406 | 2774569.06  |
| 78   | 97+640   | 531708.548 | 2774559.234 |
| 79   | 97+650   | 531706.689 | 2774549.408 |
| 80   | 97+660   | 531704.831 | 2774539.582 |
| 81   | 97+670   | 531702.973 | 2774529.757 |
| 82   | 97+680   | 531701.115 | 2774519.931 |
| 83   | 97+690   | 531699.257 | 2774510.105 |
| 84   | 97+700   | 531697.399 | 2774500.279 |
| 85   | 97+710   | 531695.541 | 2774490.453 |
| 86   | 97+720   | 531693.682 | 2774480.627 |
| 87   | 97+730   | 531691.824 | 2774470.802 |
| 88   | 97+740   | 531689.855 | 2774460.998 |
| 89   | 97+750   | 531687.387 | 2774451.309 |
| 90   | 97+760   | 531684.006 | 2774441.904 |
| 91   | 97+770   | 531679.446 | 2774433.013 |
| 92   | 97+780   | 531673.773 | 2774424.785 |
| 93   | 97+790   | 531667.321 | 2774417.148 |
| 94   | 97+800   | 531660.466 | 2774409.868 |
| 95   | 97+810   | 531653.518 | 2774402.675 |
| 96   | 97+820   | 531646.57  | 2774395.484 |
| 97   | 97+830   | 531639.622 | 2774388.292 |
| 98   | 97+840   | 531632.673 | 2774381.101 |
| 99   | 97+850   | 531625.796 | 2774373.841 |
| 100  | 97+860   | 531619.27  | 2774366.267 |
| 101  | 97+870   | 531613.259 | 2774358.277 |
| 102  | 97+880   | 531607.794 | 2774349.905 |
| 103  | 97+890   | 531602.821 | 2774341.23  |
| 104  | 97+900   | 531598.03  | 2774332.452 |
| 105  | 97+910   | 531593.243 | 2774323.672 |
| 106  | 97+920   | 531588.457 | 2774314.892 |
| 107  | 97+930   | 531583.671 | 2774306.112 |
| 108  | 97+940   | 531578.884 | 2774297.332 |
| 109  | 97+950   | 531574.098 | 2774288.552 |
| 110  | 97+960   | 531569.311 | 2774279.772 |
| 111  | 97+970   | 531564.525 | 2774270.991 |
| 112  | 97+980   | 531559.739 | 2774262.211 |
| 113  | 97+990   | 531554.952 | 2774253.431 |
| 114  | 98+000   | 531550.166 | 2774244.651 |
| 115  | 98+010   | 531545.38  | 2774235.871 |
| 116  | 98+020   | 531540.578 | 2774227.099 |
| 117  | 98+030   | 531535.576 | 2774218.441 |
| 118  | 98+040   | 531530.173 | 2774210.027 |
| 119  | 98+050   | 531524.357 | 2774201.894 |
| 120  | 98+060   | 531518.141 | 2774194.062 |

| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 121  | 98+070   | 531511.543 | 2774186.549 |
| 122  | 98+080   | 531504.669 | 2774179.286 |
| 123  | 98+090   | 531497.731 | 2774172.084 |
| 124  | 98+100   | 531490.793 | 2774164.882 |
| 125  | 98+110   | 531483.855 | 2774157.681 |
| 126  | 98+120   | 531476.931 | 2774150.466 |
| 127  | 98+130   | 531470.213 | 2774143.06  |
| 128  | 98+140   | 531464.049 | 2774135.19  |
| 129  | 98+150   | 531458.831 | 2774126.668 |
| 130  | 98+160   | 531454.788 | 2774117.53  |
| 131  | 98+170   | 531451.995 | 2774107.936 |
| 132  | 98+180   | 531450.503 | 2774098.055 |
| 133  | 98+190   | 531450.335 | 2774088.064 |
| 134  | 98+200   | 531451.326 | 2774078.117 |
| 135  | 98+210   | 531453.048 | 2774068.268 |
| 136  | 98+220   | 531455.062 | 2774058.473 |
| 137  | 98+230   | 531457.097 | 2774048.682 |
| 138  | 98+240   | 531459.132 | 2774038.891 |
| 139  | 98+250   | 531461.167 | 2774029.1   |
| 140  | 98+260   | 531463.202 | 2774019.309 |
| 141  | 98+270   | 531465.237 | 2774009.519 |
| 142  | 98+280   | 531467.272 | 2773999.728 |
| 143  | 98+290   | 531469.272 | 2773989.93  |
| 144  | 98+300   | 531470.901 | 2773980.065 |
| 145  | 98+310   | 531471.696 | 2773970.101 |
| 146  | 98+320   | 531471.493 | 2773960.107 |
| 147  | 98+330   | 531470.294 | 2773950.184 |
| 148  | 98+340   | 531468.11  | 2773940.429 |
| 149  | 98+350   | 531464.968 | 2773930.94  |
| 150  | 98+360   | 531461.091 | 2773921.723 |
| 151  | 98+370   | 531456.934 | 2773912.628 |
| 152  | 98+380   | 531452.76  | 2773903.541 |
| 153  | 98+390   | 531448.585 | 2773894.454 |
| 154  | 98+400   | 531444.411 | 2773885.367 |
| 155  | 98+410   | 531440.191 | 2773876.301 |
| 156  | 98+420   | 531435.619 | 2773867.409 |
| 157  | 98+430   | 531430.322 | 2773858.933 |
| 158  | 98+440   | 531424.027 | 2773851.172 |
| 159  | 98+450   | 531416.757 | 2773844.318 |
| 160  | 98+460   | 531408.639 | 2773838.49  |
| 161  | 98+470   | 531399.819 | 2773833.794 |
| 162  | 98+480   | 531390.492 | 2773830.199 |
| 163  | 98+490   | 531380.902 | 2773827.372 |
| 164  | 98+500   | 531371.212 | 2773824.9   |





| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 165  | 98+510   | 531361.512 | 2773822.469 |
| 166  | 98+520   | 531351.812 | 2773820.038 |
| 167  | 98+530   | 531342.112 | 2773817.607 |
| 168  | 98+540   | 531332.412 | 2773815.175 |
| 169  | 98+550   | 531322.712 | 2773812.744 |
| 170  | 98+560   | 531313.03  | 2773810.244 |
| 171  | 98+570   | 531303.469 | 2773807.321 |
| 172  | 98+580   | 531294.206 | 2773803.566 |
| 173  | 98+590   | 531285.488 | 2773798.682 |
| 174  | 98+600   | 531277.498 | 2773792.682 |
| 175  | 98+610   | 531270.376 | 2773785.673 |
| 176  | 98+620   | 531264.163 | 2773777.842 |
| 177  | 98+630   | 531258.622 | 2773769.52  |
| 178  | 98+640   | 531253.407 | 2773760.988 |
| 179  | 98+650   | 531248.233 | 2773752.43  |
| 180  | 98+660   | 531243.06  | 2773743.872 |
| 181  | 98+670   | 531237.887 | 2773735.314 |
| 182  | 98+680   | 531232.713 | 2773726.756 |
| 183  | 98+690   | 531227.516 | 2773718.213 |
| 184  | 98+700   | 531222.022 | 2773709.86  |
| 185  | 98+710   | 531215.863 | 2773701.986 |
| 186  | 98+720   | 531208.95  | 2773694.766 |
| 187  | 98+730   | 531201.351 | 2773688.272 |
| 188  | 98+740   | 531193.142 | 2773682.569 |
| 189  | 98+750   | 531184.456 | 2773677.618 |
| 190  | 98+760   | 531175.553 | 2773673.065 |
| 191  | 98+770   | 531166.621 | 2773668.567 |
| 192  | 98+780   | 531157.69  | 2773664.07  |
| 193  | 98+790   | 531148.797 | 2773659.497 |
| 194  | 98+800   | 531140.147 | 2773654.484 |
| 195  | 98+810   | 531131.994 | 2773648.701 |
| 196  | 98+820   | 531124.46  | 2773642.132 |
| 197  | 98+830   | 531117.619 | 2773634.844 |
| 198  | 98+840   | 531111.539 | 2773626.909 |
| 199  | 98+850   | 531106.282 | 2773618.407 |
| 200  | 98+860   | 531101.9   | 2773609.423 |
| 201  | 98+870   | 531098.313 | 2773600.091 |
| 202  | 98+880   | 531095.117 | 2773590.615 |
| 203  | 98+890   | 531091.967 | 2773581.125 |
| 204  | 98+900   | 531088.816 | 2773571.634 |
| 205  | 98+910   | 531085.666 | 2773562.143 |
| 206  | 98+920   | 531082.515 | 2773552.652 |
| 207  | 98+930   | 531079.365 | 2773543.161 |
| 208  | 98+940   | 531076.203 | 2773533.675 |

| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 209  | 98+950   | 531072.805 | 2773524.271 |
| 210  | 98+960   | 531068.769 | 2773515.125 |
| 211  | 98+970   | 531063.738 | 2773506.491 |
| 212  | 98+980   | 531057.61  | 2773498.598 |
| 213  | 98+990   | 531050.486 | 2773491.59  |
| 214  | 99+000   | 531042.506 | 2773485.574 |
| 215  | 99+010   | 531033.943 | 2773480.415 |
| 216  | 99+020   | 531025.086 | 2773475.775 |
| 217  | 99+030   | 531016.149 | 2773471.288 |
| 218  | 99+040   | 531007.211 | 2773466.803 |
| 219  | 99+050   | 530998.273 | 2773462.319 |
| 220  | 99+060   | 530989.335 | 2773457.834 |
| 221  | 99+070   | 530980.397 | 2773453.35  |
| 222  | 99+080   | 530971.458 | 2773448.866 |
| 223  | 99+090   | 530962.52  | 2773444.381 |
| 224  | 99+100   | 530953.582 | 2773439.897 |
| 225  | 99+110   | 530944.644 | 2773435.412 |
| 226  | 99+120   | 530935.706 | 2773430.928 |
| 227  | 99+130   | 530926.796 | 2773426.388 |
| 228  | 99+140   | 530918.045 | 2773421.551 |
| 229  | 99+150   | 530909.543 | 2773416.288 |
| 230  | 99+160   | 530901.315 | 2773410.606 |
| 231  | 99+170   | 530893.382 | 2773404.52  |
| 232  | 99+180   | 530885.762 | 2773398.045 |
| 233  | 99+190   | 530878.476 | 2773391.198 |
| 234  | 99+200   | 530871.502 | 2773384.032 |
| 235  | 99+210   | 530864.655 | 2773376.744 |
| 236  | 99+220   | 530857.813 | 2773369.45  |
| 237  | 99+230   | 530850.972 | 2773362.157 |
| 238  | 99+240   | 530844.13  | 2773354.864 |
| 239  | 99+250   | 530837.288 | 2773347.57  |
| 240  | 99+260   | 530830.447 | 2773340.277 |
| 241  | 99+270   | 530823.605 | 2773332.984 |
| 242  | 99+280   | 530816.696 | 2773325.755 |
| 243  | 99+290   | 530809.423 | 2773318.895 |
| 244  | 99+300   | 530801.548 | 2773312.739 |
| 245  | 99+310   | 530793.116 | 2773307.369 |
| 246  | 99+320   | 530784.363 | 2773302.535 |
| 247  | 99+330   | 530775.532 | 2773297.843 |
| 248  | 99+340   | 530766.701 | 2773293.151 |
| 249  | 99+350   | 530757.869 | 2773288.46  |
| 250  | 99+360   | 530749.073 | 2773283.706 |
| 251  | 99+370   | 530741.075 | 2773277.731 |
| 252  | 99+380   | 530734.424 | 2773270.285 |





| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 253  | 99+390   | 530729.194 | 2773261.77  |
| 254  | 99+400   | 530724.205 | 2773253.103 |
| 255  | 99+410   | 530719.216 | 2773244.436 |
| 256  | 99+420   | 530714.228 | 2773235.769 |
| 257  | 99+430   | 530709.089 | 2773227.194 |
| 258  | 99+440   | 530702.611 | 2773219.599 |
| 259  | 99+450   | 530694.752 | 2773213.441 |
| 260  | 99+460   | 530685.827 | 2773208.968 |
| 261  | 99+470   | 530676.225 | 2773206.205 |
| 262  | 99+480   | 530666.52  | 2773203.793 |
| 263  | 99+490   | 530656.815 | 2773201.382 |
| 264  | 99+500   | 530647.11  | 2773198.97  |
| 265  | 99+510   | 530637.405 | 2773196.558 |
| 266  | 99+520   | 530627.701 | 2773194.147 |
| 267  | 99+530   | 530617.996 | 2773191.735 |
| 268  | 99+540   | 530608.291 | 2773189.323 |
| 269  | 99+550   | 530598.586 | 2773186.912 |
| 270  | 99+560   | 530588.881 | 2773184.5   |
| 271  | 99+570   | 530579.186 | 2773182.051 |
| 272  | 99+580   | 530569.585 | 2773179.258 |
| 273  | 99+590   | 530560.184 | 2773175.855 |
| 274  | 99+600   | 530551.03  | 2773171.834 |
| 275  | 99+610   | 530542.165 | 2773167.211 |
| 276  | 99+620   | 530533.609 | 2773162.037 |
| 277  | 99+630   | 530525.224 | 2773156.588 |
| 278  | 99+640   | 530516.855 | 2773151.115 |
| 279  | 99+650   | 530508.486 | 2773145.641 |
| 280  | 99+660   | 530500.117 | 2773140.168 |
| 281  | 99+670   | 530491.748 | 2773134.695 |
| 282  | 99+680   | 530483.378 | 2773129.221 |
| 283  | 99+690   | 530475.009 | 2773123.748 |
| 284  | 99+700   | 530466.64  | 2773118.275 |
| 285  | 99+710   | 530458.271 | 2773112.801 |
| 286  | 99+720   | 530449.902 | 2773107.328 |
| 287  | 99+730   | 530441.533 | 2773101.855 |
| 288  | 99+740   | 530433.164 | 2773096.381 |
| 289  | 99+750   | 530424.794 | 2773090.908 |
| 290  | 99+760   | 530416.425 | 2773085.435 |
| 291  | 99+770   | 530408.056 | 2773079.961 |
| 292  | 99+780   | 530399.724 | 2773074.432 |
| 293  | 99+790   | 530391.66  | 2773068.522 |
| 294  | 99+800   | 530384.159 | 2773061.915 |
| 295  | 99+810   | 530377.356 | 2773054.592 |
| 296  | 99+820   | 530371.318 | 2773046.626 |

| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 297  | 99+830   | 530366.105 | 2773038.097 |
| 298  | 99+840   | 530361.769 | 2773029.09  |
| 299  | 99+850   | 530358.355 | 2773019.695 |
| 300  | 99+860   | 530355.895 | 2773010.007 |
| 301  | 99+870   | 530354.415 | 2773000.121 |
| 302  | 99+880   | 530353.93  | 2772990.137 |
| 303  | 99+890   | 530354.443 | 2772980.155 |
| 304  | 99+900   | 530355.951 | 2772970.273 |
| 305  | 99+910   | 530358.437 | 2772960.591 |
| 306  | 99+920   | 530361.878 | 2772951.206 |
| 307  | 99+930   | 530366.238 | 2772942.212 |
| 308  | 99+940   | 530371.374 | 2772933.633 |
| 309  | 99+950   | 530376.879 | 2772925.285 |
| 310  | 99+960   | 530382.43  | 2772916.968 |
| 311  | 99+970   | 530387.982 | 2772908.65  |
| 312  | 99+980   | 530393.533 | 2772900.333 |
| 313  | 99+990   | 530399.084 | 2772892.015 |
| 314  | 100+000  | 530404.636 | 2772883.697 |
| 315  | 100+010  | 530410.187 | 2772875.38  |
| 316  | 100+020  | 530415.739 | 2772867.062 |
| 317  | 100+030  | 530421.29  | 2772858.745 |
| 318  | 100+040  | 530426.841 | 2772850.427 |
| 319  | 100+050  | 530432.364 | 2772842.091 |
| 320  | 100+060  | 530437.597 | 2772833.571 |
| 321  | 100+070  | 530442.142 | 2772824.668 |
| 322  | 100+080  | 530445.59  | 2772815.289 |
| 323  | 100+090  | 530447.761 | 2772805.535 |
| 324  | 100+100  | 530448.616 | 2772795.579 |
| 325  | 100+110  | 530448.14  | 2772785.598 |
| 326  | 100+120  | 530446.342 | 2772775.768 |
| 327  | 100+130  | 530443.252 | 2772766.265 |
| 328  | 100+140  | 530438.927 | 2772757.257 |
| 329  | 100+150  | 530433.443 | 2772748.904 |
| 330  | 100+160  | 530426.956 | 2772741.3   |
| 331  | 100+170  | 530419.826 | 2772734.291 |
| 332  | 100+180  | 530412.399 | 2772727.596 |
| 333  | 100+190  | 530404.926 | 2772720.951 |
| 334  | 100+200  | 530397.453 | 2772714.306 |
| 335  | 100+210  | 530389.98  | 2772707.661 |
| 336  | 100+220  | 530382.507 | 2772701.016 |
| 337  | 100+230  | 530375.02  | 2772694.387 |
| 338  | 100+240  | 530367.339 | 2772687.985 |
| 339  | 100+250  | 530359.275 | 2772682.074 |
| 340  | 100+260  | 530350.835 | 2772676.714 |





|      | <del> </del> |            |             |
|------|--------------|------------|-------------|
| S.N. | Chainage     | Northing   | Easting     |
| 341  | 100+270      | 530342.057 | 2772671.928 |
| 342  | 100+280      | 530332.98  | 2772667.738 |
| 343  | 100+290      | 530323.643 | 2772664.161 |
| 344  | 100+300      | 530314.089 | 2772661.214 |
| 345  | 100+310      | 530304.36  | 2772658.911 |
| 346  | 100+320      | 530294.499 | 2772657.26  |
| 347  | 100+330      | 530284.55  | 2772656.27  |
| 348  | 100+340      | 530274.557 | 2772655.946 |
| 349  | 100+350      | 530264.565 | 2772656.287 |
| 350  | 100+360      | 530254.617 | 2772657.294 |
| 351  | 100+370      | 530244.759 | 2772658.961 |
| 352  | 100+380      | 530235.034 | 2772661.281 |
| 353  | 100+390      | 530225.485 | 2772664.243 |
| 354  | 100+400      | 530216.152 | 2772667.831 |
| 355  | 100+410      | 530206.999 | 2772671.858 |
| 356  | 100+420      | 530197.887 | 2772675.977 |
| 357  | 100+430      | 530188.774 | 2772680.095 |
| 358  | 100+440      | 530179.662 | 2772684.214 |
| 359  | 100+450      | 530170.549 | 2772688.332 |
| 360  | 100+460      | 530161.437 | 2772692.45  |
| 361  | 100+470      | 530152.324 | 2772696.569 |
| 362  | 100+480      | 530143.212 | 2772700.687 |
| 363  | 100+490      | 530134.099 | 2772704.806 |
| 364  | 100+500      | 530124.986 | 2772708.924 |
| 365  | 100+510      | 530115.832 | 2772712.947 |
| 366  | 100+520      | 530106.475 | 2772716.469 |
| 367  | 100+530      | 530096.808 | 2772718.999 |
| 368  | 100+540      | 530086.873 | 2772720.017 |
| 369  | 100+550      | 530076.932 | 2772719.105 |
| 370  | 100+560      | 530067.369 | 2772716.237 |
| 371  | 100+570      | 530058.567 | 2772711.526 |
| 372  | 100+580      | 530050.877 | 2772705.16  |
| 373  | 100+590      | 530044.525 | 2772697.452 |
| 374  | 100+600      | 530039.366 | 2772688.893 |
| 375  | 100+610      | 530035.058 | 2772679.871 |
| 376  | 100+620      | 530031.177 | 2772670.655 |
| 377  | 100+630      | 530027.36  | 2772661.412 |
| 378  | 100+640      | 530023.523 | 2772652.177 |
| 379  | 100+650      | 530019.463 | 2772643.039 |
| 380  | 100+660      | 530014.975 | 2772634.105 |
| 381  | 100+670      | 530010.045 | 2772625.405 |
| 382  | 100+680      | 530004.687 | 2772616.963 |
| 383  | 100+690      | 529998.913 | 2772608.799 |
| 384  | 100+700      | 529992.739 | 2772600.934 |

| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 385  | 100+710  | 529986.18  | 2772593.388 |
| 386  | 100+720  | 529979.309 | 2772586.123 |
| 387  | 100+730  | 529972.338 | 2772578.952 |
| 388  | 100+740  | 529965.366 | 2772571.784 |
| 389  | 100+750  | 529958.393 | 2772564.616 |
| 390  | 100+760  | 529951.421 | 2772557.447 |
| 391  | 100+770  | 529944.464 | 2772550.264 |
| 392  | 100+780  | 529937.742 | 2772542.862 |
| 393  | 100+790  | 529931.65  | 2772534.938 |
| 394  | 100+800  | 529926.654 | 2772526.287 |
| 395  | 100+810  | 529923.286 | 2772516.889 |
| 396  | 100+820  | 529921.845 | 2772507.01  |
| 397  | 100+830  | 529922.195 | 2772497.026 |
| 398  | 100+840  | 529923.857 | 2772487.17  |
| 399  | 100+850  | 529926.323 | 2772477.48  |
| 400  | 100+860  | 529929.102 | 2772467.874 |
| 401  | 100+870  | 529931.903 | 2772458.275 |
| 402  | 100+880  | 529934.704 | 2772448.675 |
| 403  | 100+890  | 529937.504 | 2772439.075 |
| 404  | 100+900  | 529940.301 | 2772429.474 |
| 405  | 100+910  | 529942.906 | 2772419.82  |
| 406  | 100+920  | 529944.855 | 2772410.015 |
| 407  | 100+930  | 529945.837 | 2772400.068 |
| 408  | 100+940  | 529945.822 | 2772390.072 |
| 409  | 100+950  | 529944.808 | 2772380.128 |
| 410  | 100+960  | 529942.807 | 2772370.334 |
| 411  | 100+970  | 529939.839 | 2772360.789 |
| 412  | 100+980  | 529935.932 | 2772351.589 |
| 413  | 100+990  | 529931.126 | 2772342.824 |
| 414  | 101+000  | 529925.469 | 2772334.583 |
| 415  | 101+010  | 529919.018 | 2772326.948 |
| 416  | 101+020  | 529911.895 | 2772319.931 |
| 417  | 101+030  | 529904.435 | 2772313.273 |
| 418  | 101+040  | 529896.921 | 2772306.675 |
| 419  | 101+050  | 529889.406 | 2772300.076 |
| 420  | 101+060  | 529881.892 | 2772293.478 |
| 421  | 101+070  | 529874.378 | 2772286.88  |
| 422  | 101+080  | 529866.864 | 2772280.281 |
| 423  | 101+090  | 529859.35  | 2772273.683 |
| 424  | 101+100  | 529851.836 | 2772267.085 |
| 425  | 101+110  | 529844.322 | 2772260.486 |
| 426  | 101+120  | 529836.808 | 2772253.888 |
| 427  | 101+130  | 529829.294 | 2772247.29  |
| 428  | 101+140  | 529821.78  | 2772240.691 |





| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 429  | 101+150  | 529814.258 | 2772234.101 |
| 430  | 101+160  | 529806.578 | 2772227.699 |
| 431  | 101+170  | 529798.528 | 2772221.769 |
| 432  | 101+180  | 529790.101 | 2772216.389 |
| 433  | 101+190  | 529781.334 | 2772211.582 |
| 434  | 101+200  | 529772.266 | 2772207.369 |
| 435  | 101+210  | 529762.938 | 2772203.771 |
| 436  | 101+220  | 529753.391 | 2772200.801 |
| 437  | 101+230  | 529743.668 | 2772198.474 |
| 438  | 101+240  | 529733.811 | 2772196.8   |
| 439  | 101+250  | 529723.864 | 2772195.787 |
| 440  | 101+260  | 529713.872 | 2772195.438 |
| 441  | 101+270  | 529703.879 | 2772195.756 |
| 442  | 101+280  | 529693.929 | 2772196.738 |
| 443  | 101+290  | 529684.067 | 2772198.382 |
| 444  | 101+300  | 529674.336 | 2772200.679 |
| 445  | 101+310  | 529664.78  | 2772203.618 |
| 446  | 101+320  | 529655.441 | 2772207.188 |
| 447  | 101+330  | 529646.36  | 2772211.372 |
| 448  | 101+340  | 529637.579 | 2772216.152 |
| 449  | 101+350  | 529629.135 | 2772221.506 |
| 450  | 101+360  | 529621.067 | 2772227.411 |
| 451  | 101+370  | 529613.392 | 2772233.82  |
| 452  | 101+380  | 529605.943 | 2772240.491 |
| 453  | 101+390  | 529598.517 | 2772247.189 |
| 454  | 101+400  | 529591.092 | 2772253.887 |
| 455  | 101+410  | 529583.667 | 2772260.585 |
| 456  | 101+420  | 529576.241 | 2772267.283 |
| 457  | 101+430  | 529568.816 | 2772273.981 |
| 458  | 101+440  | 529561.39  | 2772280.679 |
| 459  | 101+450  | 529553.965 | 2772287.377 |
| 460  | 101+460  | 529546.539 | 2772294.075 |
| 461  | 101+470  | 529539.114 | 2772300.773 |
| 462  | 101+480  | 529531.688 | 2772307.471 |
| 463  | 101+490  | 529524.263 | 2772314.169 |
| 464  | 101+500  | 529516.881 | 2772320.915 |
| 465  | 101+510  | 529509.759 | 2772327.932 |
| 466  | 101+520  | 529503.182 | 2772335.46  |
| 467  | 101+530  | 529497.433 | 2772343.636 |
| 468  | 101+540  | 529492.625 | 2772352.399 |
| 469  | 101+550  | 529488.82  | 2772361.641 |
| 470  | 101+560  | 529486.062 | 2772371.248 |
| 471  | 101+570  | 529484.386 | 2772381.101 |
| 472  | 101+580  | 529483.814 | 2772391.079 |

| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 473  | 101+590  | 529484.351 | 2772401.06  |
| 474  | 101+600  | 529485.992 | 2772410.919 |
| 475  | 101+610  | 529488.716 | 2772420.536 |
| 476  | 101+620  | 529492.489 | 2772429.791 |
| 477  | 101+630  | 529497.265 | 2772438.571 |
| 478  | 101+640  | 529502.986 | 2772446.767 |
| 479  | 101+650  | 529509.58  | 2772454.278 |
| 480  | 101+660  | 529516.966 | 2772461.011 |
| 481  | 101+670  | 529525.053 | 2772466.885 |
| 482  | 101+680  | 529533.701 | 2772471.899 |
| 483  | 101+690  | 529542.681 | 2772476.296 |
| 484  | 101+700  | 529551.803 | 2772480.395 |
| 485  | 101+710  | 529560.942 | 2772484.453 |
| 486  | 101+720  | 529570.081 | 2772488.512 |
| 487  | 101+730  | 529579.221 | 2772492.571 |
| 488  | 101+740  | 529588.36  | 2772496.63  |
| 489  | 101+750  | 529597.499 | 2772500.688 |
| 490  | 101+760  | 529606.638 | 2772504.747 |
| 491  | 101+770  | 529615.778 | 2772508.806 |
| 492  | 101+780  | 529624.917 | 2772512.865 |
| 493  | 101+790  | 529634.045 | 2772516.948 |
| 494  | 101+800  | 529643.025 | 2772521.345 |
| 495  | 101+810  | 529651.614 | 2772526.459 |
| 496  | 101+820  | 529659.651 | 2772532.402 |
| 497  | 101+830  | 529667.054 | 2772539.118 |
| 498  | 101+840  | 529673.75  | 2772546.54  |
| 499  | 101+850  | 529679.672 | 2772554.593 |
| 500  | 101+860  | 529684.76  | 2772563.197 |
| 501  | 101+870  | 529688.964 | 2772572.266 |
| 502  | 101+880  | 529692.241 | 2772581.709 |
| 503  | 101+890  | 529694.559 | 2772591.432 |
| 504  | 101+900  | 529695.937 | 2772601.334 |
| 505  | 101+910  | 529696.718 | 2772611.303 |
| 506  | 101+920  | 529697.356 | 2772621.282 |
| 507  | 101+930  | 529697.993 | 2772631.262 |
| 508  | 101+940  | 529698.631 | 2772641.242 |
| 509  | 101+950  | 529699.268 | 2772651.221 |
| 510  | 101+960  | 529699.905 | 2772661.201 |
| 511  | 101+970  | 529700.542 | 2772671.181 |
| 512  | 101+980  | 529701.179 | 2772681.16  |
| 513  | 101+990  | 529701.817 | 2772691.14  |
| 514  | 102+000  | 529702.454 | 2772701.12  |
| 515  | 102+010  | 529703.091 | 2772711.1   |
| 516  | 102+020  | 529703.728 | 2772721.079 |





| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 517  | 102+030  | 529704.365 | 2772731.059 |
| 518  | 102+040  | 529705.003 | 2772741.039 |
| 519  | 102+050  | 529705.64  | 2772751.018 |
| 520  | 102+060  | 529706.277 | 2772760.998 |
| 521  | 102+070  | 529706.914 | 2772770.978 |
| 522  | 102+080  | 529707.551 | 2772780.957 |
| 523  | 102+090  | 529708.189 | 2772790.937 |
| 524  | 102+100  | 529708.826 | 2772800.917 |
| 525  | 102+110  | 529709.463 | 2772810.896 |
| 526  | 102+120  | 529710.1   | 2772820.876 |
| 527  | 102+130  | 529710.737 | 2772830.856 |
| 528  | 102+140  | 529711.375 | 2772840.835 |
| 529  | 102+150  | 529712.012 | 2772850.815 |
| 530  | 102+160  | 529712.649 | 2772860.795 |
| 531  | 102+170  | 529713.286 | 2772870.774 |
| 532  | 102+180  | 529713.923 | 2772880.754 |
| 533  | 102+190  | 529714.561 | 2772890.734 |
| 534  | 102+200  | 529715.198 | 2772900.713 |
| 535  | 102+210  | 529715.835 | 2772910.693 |
| 536  | 102+220  | 529716.503 | 2772920.671 |
| 537  | 102+230  | 529717.528 | 2772930.616 |
| 538  | 102+240  | 529719.371 | 2772940.441 |
| 539  | 102+250  | 529722.184 | 2772950.033 |
| 540  | 102+260  | 529725.941 | 2772959.296 |
| 541  | 102+270  | 529730.603 | 2772968.138 |
| 542  | 102+280  | 529736.125 | 2772976.47  |
| 543  | 102+290  | 529742.451 | 2772984.209 |
| 544  | 102+300  | 529749.518 | 2772991.278 |
| 545  | 102+310  | 529757.256 | 2772997.607 |
| 546  | 102+320  | 529765.587 | 2773003.131 |
| 547  | 102+330  | 529774.418 | 2773007.814 |
| 548  | 102+340  | 529783.551 | 2773011.886 |
| 549  | 102+350  | 529792.766 | 2773015.768 |
| 550  | 102+360  | 529801.984 | 2773019.646 |
| 551  | 102+370  | 529811.201 | 2773023.524 |
| 552  | 102+380  | 529820.418 | 2773027.403 |
| 553  | 102+390  | 529829.636 | 2773031.281 |
| 554  | 102+400  | 529838.853 | 2773035.159 |
| 555  | 102+410  | 529848.07  | 2773039.037 |
| 556  | 102+420  | 529857.288 | 2773042.916 |
| 557  | 102+430  | 529866.505 | 2773046.794 |
| 558  | 102+440  | 529875.722 | 2773050.672 |
| 559  | 102+450  | 529884.94  | 2773054.55  |
| 560  | 102+460  | 529894.157 | 2773058.429 |

| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 561  | 102+470  | 529903.373 | 2773062.31  |
| 562  | 102+480  | 529912.532 | 2773066.324 |
| 563  | 102+490  | 529921.511 | 2773070.723 |
| 564  | 102+500  | 529930.259 | 2773075.565 |
| 565  | 102+510  | 529938.754 | 2773080.839 |
| 566  | 102+520  | 529946.975 | 2773086.531 |
| 567  | 102+530  | 529954.902 | 2773092.626 |
| 568  | 102+540  | 529962.513 | 2773099.11  |
| 569  | 102+550  | 529969.791 | 2773105.966 |
| 570  | 102+560  | 529976.718 | 2773113.178 |
| 571  | 102+570  | 529983.275 | 2773120.726 |
| 572  | 102+580  | 529989.447 | 2773128.593 |
| 573  | 102+590  | 529995.267 | 2773136.724 |
| 574  | 102+600  | 530000.953 | 2773144.951 |
| 575  | 102+610  | 530006.634 | 2773153.18  |
| 576  | 102+620  | 530012.314 | 2773161.41  |
| 577  | 102+630  | 530017.995 | 2773169.64  |
| 578  | 102+640  | 530023.676 | 2773177.87  |
| 579  | 102+650  | 530029.357 | 2773186.1   |
| 580  | 102+660  | 530035.037 | 2773194.329 |
| 581  | 102+670  | 530040.718 | 2773202.559 |
| 582  | 102+680  | 530046.399 | 2773210.789 |
| 583  | 102+690  | 530052.079 | 2773219.019 |
| 584  | 102+700  | 530057.76  | 2773227.248 |
| 585  | 102+710  | 530063.441 | 2773235.478 |
| 586  | 102+720  | 530069.127 | 2773243.705 |
| 587  | 102+730  | 530074.948 | 2773251.835 |
| 588  | 102+740  | 530081.121 | 2773259.701 |
| 589  | 102+750  | 530087.68  | 2773267.248 |
| 590  | 102+760  | 530094.607 | 2773274.458 |
| 591  | 102+770  | 530101.887 | 2773281.313 |
| 592  | 102+780  | 530109.5   | 2773287.796 |
| 593  | 102+790  | 530117.427 | 2773293.89  |
| 594  | 102+800  | 530125.649 | 2773299.58  |
| 595  | 102+810  | 530134.145 | 2773304.852 |
| 596  | 102+820  | 530142.893 | 2773309.696 |
| 597  | 102+830  | 530151.813 | 2773314.215 |
| 598  | 102+840  | 530160.77  | 2773318.661 |
| 599  | 102+850  | 530169.727 | 2773323.107 |
| 600  | 102+860  | 530178.685 | 2773327.553 |
| 601  | 102+870  | 530187.642 | 2773331.999 |
| 602  | 102+880  | 530196.6   | 2773336.445 |
| 603  | 102+890  | 530205.557 | 2773340.89  |
| 604  | 102+900  | 530214.514 | 2773345.336 |





| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 605  | 102+910  | 530223.472 | 2773349.782 |
| 606  | 102+920  | 530232.429 | 2773354.228 |
| 607  | 102+930  | 530241.386 | 2773358.674 |
| 608  | 102+940  | 530250.344 | 2773363.119 |
| 609  | 102+950  | 530259.301 | 2773367.565 |
| 610  | 102+960  | 530268.259 | 2773372.011 |
| 611  | 102+970  | 530277.216 | 2773376.457 |
| 612  | 102+980  | 530286.173 | 2773380.903 |
| 613  | 102+990  | 530295.131 | 2773385.349 |
| 614  | 103+000  | 530304.088 | 2773389.794 |
| 615  | 103+010  | 530313.046 | 2773394.24  |
| 616  | 103+020  | 530322.003 | 2773398.686 |
| 617  | 103+030  | 530330.96  | 2773403.132 |
| 618  | 103+040  | 530339.918 | 2773407.578 |
| 619  | 103+050  | 530348.875 | 2773412.023 |
| 620  | 103+060  | 530357.832 | 2773416.469 |
| 621  | 103+070  | 530366.79  | 2773420.915 |
| 622  | 103+080  | 530375.747 | 2773425.361 |
| 623  | 103+090  | 530384.705 | 2773429.807 |
| 624  | 103+100  | 530393.662 | 2773434.253 |
| 625  | 103+110  | 530402.619 | 2773438.698 |
| 626  | 103+120  | 530411.577 | 2773443.144 |
| 627  | 103+130  | 530420.534 | 2773447.59  |
| 628  | 103+140  | 530429.492 | 2773452.036 |
| 629  | 103+150  | 530438.449 | 2773456.482 |
| 630  | 103+160  | 530447.406 | 2773460.927 |
| 631  | 103+170  | 530456.364 | 2773465.373 |
| 632  | 103+180  | 530465.274 | 2773469.912 |
| 633  | 103+190  | 530473.926 | 2773474.922 |
| 634  | 103+200  | 530482.071 | 2773480.716 |
| 635  | 103+210  | 530489.596 | 2773487.295 |
| 636  | 103+220  | 530496.428 | 2773494.592 |
| 637  | 103+230  | 530502.497 | 2773502.534 |
| 638  | 103+240  | 530507.743 | 2773511.043 |
| 639  | 103+250  | 530512.113 | 2773520.033 |
| 640  | 103+260  | 530515.563 | 2773529.415 |
| 641  | 103+270  | 530518.06  | 2773539.093 |
| 642  | 103+280  | 530519.578 | 2773548.973 |
| 643  | 103+290  | 530520.102 | 2773558.955 |
| 644  | 103+300  | 530519.627 | 2773568.94  |
| 645  | 103+310  | 530518.19  | 2773578.833 |
| 646  | 103+320  | 530516.132 | 2773588.618 |
| 647  | 103+330  | 530513.911 | 2773598.369 |
| 648  | 103+340  | 530511.689 | 2773608.119 |

| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 649  | 103+350  | 530509.467 | 2773617.869 |
| 650  | 103+360  | 530509.407 | 2773627.618 |
| 651  | 103+300  | 530507.243 | 2773637.368 |
| 652  |          |            | 2773647.118 |
|      | 103+380  | 530502.801 |             |
| 653  | 103+390  | 530500.579 | 2773656.868 |
| 654  | 103+400  | 530498.357 | 2773666.618 |
| 655  | 103+410  | 530496.135 | 2773676.368 |
| 656  | 103+420  | 530493.913 | 2773686.118 |
| 657  | 103+430  | 530491.69  | 2773695.868 |
| 658  | 103+440  | 530489.468 | 2773705.618 |
| 659  | 103+450  | 530487.246 | 2773715.368 |
| 660  | 103+460  | 530485.024 | 2773725.118 |
| 661  | 103+470  | 530482.802 | 2773734.868 |
| 662  | 103+480  | 530480.58  | 2773744.618 |
| 663  | 103+490  | 530478.358 | 2773754.368 |
| 664  | 103+500  | 530476.136 | 2773764.118 |
| 665  | 103+510  | 530473.914 | 2773773.868 |
| 666  | 103+520  | 530471.692 | 2773783.618 |
| 667  | 103+530  | 530469.47  | 2773793.368 |
| 668  | 103+540  | 530467.248 | 2773803.118 |
| 669  | 103+550  | 530465.046 | 2773812.873 |
| 670  | 103+560  | 530463.159 | 2773822.692 |
| 671  | 103+570  | 530462.058 | 2773832.627 |
| 672  | 103+580  | 530461.95  | 2773842.622 |
| 673  | 103+590  | 530462.84  | 2773852.578 |
| 674  | 103+600  | 530464.72  | 2773862.396 |
| 675  | 103+610  | 530467.571 | 2773871.977 |
| 676  | 103+620  | 530471.364 | 2773881.225 |
| 677  | 103+630  | 530476.061 | 2773890.048 |
| 678  | 103+640  | 530481.616 | 2773898.359 |
| 679  | 103+650  | 530487.972 | 2773906.073 |
| 680  | 103+660  | 530495.067 | 2773913.114 |
| 681  | 103+670  | 530502.829 | 2773919.412 |
| 682  | 103+680  | 530511.182 | 2773924.903 |
| 683  | 103+690  | 530520.021 | 2773929.573 |
| 684  | 103+700  | 530529.124 | 2773933.711 |
| 685  | 103+710  | 530538.285 | 2773937.722 |
| 686  | 103+720  | 530547.445 | 2773941.732 |
| 687  | 103+730  | 530556.606 | 2773945.743 |
| 688  | 103+740  | 530565.767 | 2773949.753 |
| 689  | 103+750  | 530574.927 | 2773953.763 |
| 690  | 103+760  | 530584.088 | 2773957.774 |
| 691  | 103+770  | 530593.248 | 2773961.784 |
| 692  | 103+780  | 530602.409 | 2773965.795 |
|      |          | 1          | 1 322323    |





| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 693  | 103+790  | 530611.569 | 2773969.805 |
| 694  | 103+800  | 530620.73  | 2773973.816 |
| 695  | 103+810  | 530629.891 | 2773977.826 |
| 696  | 103+820  | 530639.051 | 2773981.836 |
| 697  | 103+830  | 530648.212 | 2773985.847 |
| 698  | 103+840  | 530657.372 | 2773989.857 |
| 699  | 103+850  | 530666.533 | 2773993.868 |
| 700  | 103+860  | 530675.681 | 2773997.906 |
| 701  | 103+870  | 530684.717 | 2774002.189 |
| 702  | 103+880  | 530693.535 | 2774006.903 |
| 703  | 103+890  | 530702.106 | 2774012.052 |
| 704  | 103+900  | 530710.41  | 2774017.622 |
| 705  | 103+910  | 530718.424 | 2774023.601 |
| 706  | 103+920  | 530726.13  | 2774029.973 |
| 707  | 103+930  | 530733.508 | 2774036.722 |
| 708  | 103+940  | 530740.539 | 2774043.831 |
| 709  | 103+950  | 530747.206 | 2774051.283 |
| 710  | 103+960  | 530753.493 | 2774059.058 |
| 711  | 103+970  | 530759.383 | 2774067.139 |
| 712  | 103+980  | 530764.865 | 2774075.5   |
| 713  | 103+990  | 530770.059 | 2774084.045 |
| 714  | 104+000  | 530775.198 | 2774092.624 |
| 715  | 104+010  | 530780.336 | 2774101.203 |
| 716  | 104+020  | 530785.474 | 2774109.782 |
| 717  | 104+030  | 530790.612 | 2774118.361 |
| 718  | 104+040  | 530795.751 | 2774126.94  |
| 719  | 104+050  | 530800.889 | 2774135.519 |
| 720  | 104+060  | 530806.027 | 2774144.098 |
| 721  | 104+070  | 530811.165 | 2774152.677 |
| 722  | 104+080  | 530816.304 | 2774161.256 |
| 723  | 104+090  | 530821.442 | 2774169.835 |
| 724  | 104+100  | 530826.58  | 2774178.414 |
| 725  | 104+110  | 530831.718 | 2774186.993 |
| 726  | 104+120  | 530836.857 | 2774195.572 |
| 727  | 104+130  | 530841.995 | 2774204.151 |
| 728  | 104+140  | 530847.133 | 2774212.73  |
| 729  | 104+150  | 530852.232 | 2774221.332 |
| 730  | 104+160  | 530857.001 | 2774230.12  |
| 731  | 104+170  | 530861.193 | 2774239.197 |
| 732  | 104+180  | 530864.77  | 2774248.533 |
| 733  | 104+190  | 530867.718 | 2774258.087 |
| 734  | 104+200  | 530870.022 | 2774267.816 |
| 735  | 104+210  | 530871.673 | 2774277.677 |
| 736  | 104+220  | 530872.664 | 2774287.626 |

| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 737  | 104+230  | 530872.99  | 2774297.619 |
| 738  | 104+240  | 530872.649 | 2774307.611 |
| 739  | 104+250  | 530871.644 | 2774317.558 |
| 740  | 104+260  | 530869.978 | 2774327.417 |
| 741  | 104+270  | 530867.661 | 2774337.143 |
| 742  | 104+280  | 530864.861 | 2774346.742 |
| 743  | 104+290  | 530861.947 | 2774356.308 |
| 744  | 104+300  | 530859.032 | 2774365.874 |
| 745  | 104+310  | 530856.117 | 2774375.44  |
| 746  | 104+320  | 530853.202 | 2774385.005 |
| 747  | 104+330  | 530850.287 | 2774394.571 |
| 748  | 104+340  | 530847.372 | 2774404.137 |
| 749  | 104+350  | 530844.457 | 2774413.703 |
| 750  | 104+360  | 530841.542 | 2774423.268 |
| 751  | 104+370  | 530838.627 | 2774432.834 |
| 752  | 104+380  | 530835.712 | 2774442.4   |
| 753  | 104+390  | 530832.797 | 2774451.966 |
| 754  | 104+400  | 530829.882 | 2774461.531 |
| 755  | 104+410  | 530826.967 | 2774471.097 |
| 756  | 104+420  | 530824.052 | 2774480.663 |
| 757  | 104+430  | 530821.088 | 2774490.213 |
| 758  | 104+440  | 530817.785 | 2774499.651 |
| 759  | 104+450  | 530813.944 | 2774508.882 |
| 760  | 104+460  | 530809.568 | 2774517.872 |
| 761  | 104+470  | 530804.67  | 2774526.589 |
| 762  | 104+480  | 530799.268 | 2774535.003 |
| 763  | 104+490  | 530793.382 | 2774543.084 |
| 764  | 104+500  | 530787.03  | 2774550.806 |
| 765  | 104+510  | 530780.235 | 2774558.141 |
| 766  | 104+520  | 530773.021 | 2774565.064 |
| 767  | 104+530  | 530765.412 | 2774571.551 |
| 768  | 104+540  | 530757.435 | 2774577.579 |
| 769  | 104+550  | 530749.117 | 2774583.128 |
| 770  | 104+560  | 530740.488 | 2774588.178 |
| 771  | 104+570  | 530731.576 | 2774592.712 |
| 772  | 104+580  | 530722.414 | 2774596.714 |
| 773  | 104+590  | 530713.032 | 2774600.171 |
| 774  | 104+600  | 530703.463 | 2774603.07  |
| 775  | 104+610  | 530693.74  | 2774605.402 |
| 776  | 104+620  | 530683.897 | 2774607.158 |
| 777  | 104+630  | 530673.968 | 2774608.332 |
| 778  | 104+640  | 530663.986 | 2774608.921 |
| 779  | 104+650  | 530653.988 | 2774608.922 |
| 780  | 104+660  | 530644.006 | 2774608.336 |





| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 781  | 104+670  | 530634.06  | 2774607.3   |
| 782  | 104+680  | 530624.127 | 2774606.148 |
| 783  | 104+690  | 530614.194 | 2774604.996 |
| 784  | 104+700  | 530604.251 | 2774603.94  |
| 785  | 104+710  | 530594.279 | 2774604.406 |
| 786  | 104+720  | 530584.597 | 2774606.843 |
| 787  | 104+730  | 530575.593 | 2774611.155 |
| 788  | 104+740  | 530567.626 | 2774617.171 |
| 789  | 104+750  | 530561.012 | 2774624.649 |
| 790  | 104+760  | 530555.832 | 2774633.195 |
| 791  | 104+770  | 530550.906 | 2774641.898 |
| 792  | 104+780  | 530545.979 | 2774650.6   |
| 793  | 104+790  | 530541.052 | 2774659.302 |
| 794  | 104+800  | 530535.936 | 2774667.888 |
| 795  | 104+810  | 530529.432 | 2774675.463 |
| 796  | 104+820  | 530521.553 | 2774681.594 |
| 797  | 104+830  | 530512.613 | 2774686.038 |
| 798  | 104+840  | 530502.969 | 2774688.617 |
| 799  | 104+850  | 530493.004 | 2774689.228 |
| 800  | 104+860  | 530483.098 | 2774687.94  |
| 801  | 104+870  | 530473.255 | 2774686.174 |
| 802  | 104+880  | 530463.412 | 2774684.409 |
| 803  | 104+890  | 530453.569 | 2774682.644 |
| 804  | 104+900  | 530443.726 | 2774680.879 |
| 805  | 104+910  | 530433.883 | 2774679.113 |
| 806  | 104+920  | 530424.04  | 2774677.348 |
| 807  | 104+930  | 530414.198 | 2774675.583 |
| 808  | 104+940  | 530404.355 | 2774673.817 |
| 809  | 104+950  | 530394.511 | 2774672.053 |
| 810  | 104+960  | 530384.644 | 2774670.434 |
| 811  | 104+970  | 530374.699 | 2774669.418 |
| 812  | 104+980  | 530364.707 | 2774669.508 |
| 813  | 104+990  | 530354.865 | 2774671.194 |
| 814  | 105+000  | 530345.541 | 2774674.763 |
| 815  | 105+010  | 530337.064 | 2774680.044 |
| 816  | 105+020  | 530329.465 | 2774686.534 |
| 817  | 105+030  | 530322.546 | 2774693.751 |
| 818  | 105+040  | 530315.993 | 2774701.304 |
| 819  | 105+050  | 530309.502 | 2774708.911 |
| 820  | 105+060  | 530303.01  | 2774716.518 |
| 821  | 105+070  | 530296.519 | 2774724.124 |
| 822  | 105+080  | 530290.028 | 2774731.731 |
| 823  | 105+090  | 530283.536 | 2774739.338 |
| 824  | 105+100  | 530277.045 | 2774746.945 |

| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 825  | 105+110  | 530270.554 | 2774754.551 |
| 826  | 105+120  | 530264.062 | 2774762.158 |
| 827  | 105+130  | 530257.571 | 2774769.765 |
| 828  | 105+140  | 530251.08  | 2774777.372 |
| 829  | 105+150  | 530244.588 | 2774784.978 |
| 830  | 105+160  | 530238.097 | 2774792.585 |
| 831  | 105+170  | 530231.628 | 2774800.211 |
| 832  | 105+180  | 530225.373 | 2774808.012 |
| 833  | 105+190  | 530219.381 | 2774816.018 |
| 834  | 105+200  | 530213.66  | 2774824.219 |
| 835  | 105+210  | 530208.215 | 2774832.606 |
| 836  | 105+220  | 530203.053 | 2774841.17  |
| 837  | 105+230  | 530198.179 | 2774849.901 |
| 838  | 105+240  | 530193.598 | 2774858.79  |
| 839  | 105+250  | 530189.317 | 2774867.827 |
| 840  | 105+260  | 530185.246 | 2774876.961 |
| 841  | 105+270  | 530180.91  | 2774885.97  |
| 842  | 105+280  | 530175.885 | 2774894.611 |
| 843  | 105+290  | 530170.026 | 2774902.71  |
| 844  | 105+300  | 530163.388 | 2774910.184 |
| 845  | 105+310  | 530156.037 | 2774916.957 |
| 846  | 105+320  | 530148.046 | 2774922.963 |
| 847  | 105+330  | 530139.496 | 2774928.141 |
| 848  | 105+340  | 530130.472 | 2774932.439 |
| 849  | 105+350  | 530121.063 | 2774935.815 |
| 850  | 105+360  | 530111.365 | 2774938.235 |
| 851  | 105+370  | 530101.473 | 2774939.675 |
| 852  | 105+380  | 530091.487 | 2774940.12  |
| 853  | 105+390  | 530081.507 | 2774939.566 |
| 854  | 105+400  | 530071.632 | 2774938.018 |
| 855  | 105+410  | 530061.952 | 2774935.521 |
| 856  | 105+420  | 530052.449 | 2774932.408 |
| 857  | 105+430  | 530043.002 | 2774929.131 |
| 858  | 105+440  | 530033.555 | 2774925.851 |
| 859  | 105+450  | 530024.108 | 2774922.572 |
| 860  | 105+460  | 530014.661 | 2774919.293 |
| 861  | 105+470  | 530005.21  | 2774916.022 |
| 862  | 105+480  | 529995.687 | 2774912.976 |
| 863  | 105+490  | 529985.982 | 2774910.576 |
| 864  | 105+500  | 529976.076 | 2774909.261 |
| 865  | 105+510  | 529966.084 | 2774909.267 |
| 866  | 105+520  | 529956.18  | 2774910.601 |
| 867  | 105+530  | 529946.542 | 2774913.24  |
| 868  | 105+540  | 529937.341 | 2774917.136 |





| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 869  | 105+550  | 529928.739 | 2774922.221 |
| 870  | 105+560  | 529920.889 | 2774928.405 |
| 871  | 105+570  | 529913.932 | 2774935.577 |
| 872  | 105+580  | 529907.989 | 2774943.611 |
| 873  | 105+590  | 529903.167 | 2774952.363 |
| 874  | 105+600  | 529899.551 | 2774961.678 |
| 875  | 105+610  | 529897.205 | 2774971.392 |
| 876  | 105+620  | 529896.035 | 2774981.319 |
| 877  | 105+630  | 529895.647 | 2774991.31  |
| 878  | 105+640  | 529895.602 | 2775001.31  |
| 879  | 105+650  | 529895.589 | 2775011.31  |
| 880  | 105+660  | 529895.577 | 2775021.31  |
| 881  | 105+670  | 529895.565 | 2775031.31  |
| 882  | 105+680  | 529895.552 | 2775031.31  |
| 883  | 105+690  | 529895.54  | 2775051.31  |
| 884  | 105+700  | 529895.528 | 2775051.31  |
|      |          |            |             |
| 885  | 105+710  | 529895.515 | 2775071.31  |
| 886  | 105+720  | 529895.481 | 2775081.31  |
| 887  | 105+730  | 529895.122 | 2775091.302 |
| 888  | 105+740  | 529893.967 | 2775101.231 |
| 889  | 105+750  | 529891.83  | 2775110.996 |
| 890  | 105+760  | 529888.729 | 2775120.498 |
| 891  | 105+770  | 529884.695 | 2775129.644 |
| 892  | 105+780  | 529879.84  | 2775138.383 |
| 893  | 105+790  | 529874.552 | 2775146.871 |
| 894  | 105+800  | 529869.194 | 2775155.314 |
| 895  | 105+810  | 529863.836 | 2775163.758 |
| 896  | 105+820  | 529858.478 | 2775172.201 |
| 897  | 105+830  | 529853.12  | 2775180.644 |
| 898  | 105+840  | 529847.761 | 2775189.088 |
| 899  | 105+850  | 529842.403 | 2775197.531 |
| 900  | 105+860  | 529837.045 | 2775205.974 |
| 901  | 105+870  | 529831.687 | 2775214.418 |
| 902  | 105+880  | 529826.329 | 2775222.861 |
| 903  | 105+890  | 529820.971 | 2775231.305 |
| 904  | 105+900  | 529815.613 | 2775239.748 |
| 905  | 105+910  | 529810.255 | 2775248.191 |
| 906  | 105+920  | 529804.896 | 2775256.635 |
| 907  | 105+930  | 529799.538 | 2775265.078 |
| 908  | 105+940  | 529794.18  | 2775273.521 |
| 909  | 105+950  | 529788.822 | 2775281.965 |
| 910  | 105+960  | 529783.464 | 2775290.408 |
| 911  | 105+970  | 529778.605 | 2775299.134 |
| 912  | 105+980  | 529775.521 | 2775308.629 |

| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 913  | 105+990  | 529774.386 | 2775318.548 |
| 914  | 106+000  | 529775.244 | 2775328.494 |
| 915  | 106+010  | 529778.06  | 2775338.072 |
| 916  | 106+020  | 529782.724 | 2775346.899 |
| 917  | 106+030  | 529789.048 | 2775354.624 |
| 918  | 106+040  | 529796.658 | 2775361.101 |
| 919  | 106+050  | 529804.465 | 2775367.351 |
| 920  | 106+060  | 529812.23  | 2775373.65  |
| 921  | 106+070  | 529818.997 | 2775380.99  |
| 922  | 106+080  | 529824.171 | 2775389.528 |
| 923  | 106+090  | 529827.546 | 2775398.923 |
| 924  | 106+100  | 529828.987 | 2775408.802 |
| 925  | 106+110  | 529828.437 | 2775418.77  |
| 926  | 106+120  | 529825.918 | 2775428.43  |
| 927  | 106+130  | 529821.529 | 2775437.397 |
| 928  | 106+140  | 529815.446 | 2775445.314 |
| 929  | 106+150  | 529808.114 | 2775452.108 |
| 930  | 106+160  | 529800.65  | 2775458.763 |
| 931  | 106+170  | 529793.186 | 2775465.418 |
| 932  | 106+180  | 529785.722 | 2775472.073 |
| 933  | 106+190  | 529778.258 | 2775478.728 |
| 934  | 106+200  | 529770.794 | 2775485.383 |
| 935  | 106+210  | 529763.33  | 2775492.038 |
| 936  | 106+220  | 529755.866 | 2775498.693 |
| 937  | 106+230  | 529748.402 | 2775505.348 |
| 938  | 106+240  | 529740.938 | 2775512.003 |
| 939  | 106+250  | 529733.474 | 2775518.658 |
| 940  | 106+260  | 529726.01  | 2775525.313 |
| 941  | 106+270  | 529718.546 | 2775531.968 |
| 942  | 106+280  | 529711.082 | 2775538.623 |
| 943  | 106+290  | 529703.62  | 2775545.28  |
| 944  | 106+300  | 529696.242 | 2775552.03  |
| 945  | 106+310  | 529689.149 | 2775559.078 |
| 946  | 106+320  | 529682.417 | 2775566.471 |
| 947  | 106+330  | 529676.063 | 2775574.191 |
| 948  | 106+340  | 529670.103 | 2775582.22  |
| 949  | 106+350  | 529664.552 | 2775590.536 |
| 950  | 106+360  | 529659.423 | 2775599.119 |
| 951  | 106+370  | 529654.729 | 2775607.948 |
| 952  | 106+380  | 529650.475 | 2775616.997 |
| 953  | 106+390  | 529646.507 | 2775626.176 |
| 954  | 106+400  | 529642.583 | 2775635.374 |
| 955  | 106+410  | 529638.66  | 2775644.573 |
| 956  | 106+420  | 529634.715 | 2775653.762 |





| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 957  | 106+430  | 529630.49  | 2775662.824 |
| 958  | 106+440  | 529625.599 | 2775671.542 |
| 959  | 106+450  | 529619.726 | 2775679.626 |
| 960  | 106+460  | 529612.832 | 2775686.86  |
| 961  | 106+470  | 529605.038 | 2775693.113 |
| 962  | 106+480  | 529596.482 | 2775698.274 |
| 963  | 106+490  | 529587.347 | 2775702.332 |
| 964  | 106+500  | 529577.892 | 2775705.584 |
| 965  | 106+510  | 529568.307 | 2775708.434 |
| 966  | 106+520  | 529558.704 | 2775711.223 |
| 967  | 106+530  | 529549.101 | 2775714.012 |
| 968  | 106+540  | 529539.498 | 2775716.801 |
| 969  | 106+550  | 529529.894 | 2775719.588 |
| 970  | 106+560  | 529520.242 | 2775722.202 |
| 971  | 106+570  | 529510.444 | 2775724.181 |
| 972  | 106+580  | 529500.487 | 2775725.022 |
| 973  | 106+590  | 529490.535 | 2775724.217 |
| 974  | 106+600  | 529480.934 | 2775721.479 |
| 975  | 106+610  | 529472.058 | 2775716.906 |
| 976  | 106+620  | 529464.066 | 2775710.91  |
| 977  | 106+630  | 529456.833 | 2775704.009 |
| 978  | 106+640  | 529450.087 | 2775696.629 |
| 979  | 106+650  | 529443.493 | 2775689.111 |
| 980  | 106+660  | 529436.901 | 2775681.591 |
| 981  | 106+670  | 529430.31  | 2775674.071 |
| 982  | 106+680  | 529423.718 | 2775666.551 |
| 983  | 106+690  | 529417.127 | 2775659.031 |
| 984  | 106+700  | 529410.535 | 2775651.511 |
| 985  | 106+710  | 529403.925 | 2775644.008 |
| 986  | 106+720  | 529396.884 | 2775636.914 |
| 987  | 106+730  | 529388.766 | 2775631.111 |
| 988  | 106+740  | 529379.392 | 2775627.756 |
| 989  | 106+750  | 529369.439 | 2775627.633 |
| 990  | 106+760  | 529359.993 | 2775630.773 |
| 991  | 106+770  | 529352.095 | 2775636.831 |
| 992  | 106+780  | 529346.613 | 2775645.139 |
| 993  | 106+790  | 529344.152 | 2775654.784 |
| 994  | 106+800  | 529344.981 | 2775664.703 |
| 995  | 106+810  | 529348.726 | 2775673.946 |
| 996  | 106+820  | 529354.241 | 2775682.277 |
| 997  | 106+830  | 529360.481 | 2775690.091 |
| 998  | 106+840  | 529366.794 | 2775697.846 |
| 999  | 106+850  | 529373.108 | 2775705.601 |
| 1000 | 106+860  | 529379.421 | 2775713.356 |

| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 1001 | 106+870  | 529385.735 | 2775721.111 |
| 1002 | 106+880  | 529392.048 | 2775728.866 |
| 1003 | 106+890  | 529398.361 | 2775736.621 |
| 1004 | 106+900  | 529404.675 | 2775744.376 |
| 1005 | 106+910  | 529410.988 | 2775752.131 |
| 1006 | 106+920  | 529417.306 | 2775759.883 |
| 1007 | 106+930  | 529423.796 | 2775767.489 |
| 1008 | 106+940  | 529430.806 | 2775774.616 |
| 1009 | 106+950  | 529438.619 | 2775780.843 |
| 1010 | 106+960  | 529447.369 | 2775785.653 |
| 1011 | 106+970  | 529456.893 | 2775788.646 |
| 1012 | 106+980  | 529466.809 | 2775789.852 |
| 1013 | 106+990  | 529476.803 | 2775789.694 |
| 1014 | 107+000  | 529486.749 | 2775788.671 |
| 1015 | 107+010  | 529496.651 | 2775787.281 |
| 1016 | 107+020  | 529506.55  | 2775785.858 |
| 1017 | 107+030  | 529516.448 | 2775784.435 |
| 1018 | 107+040  | 529526.346 | 2775783.013 |
| 1019 | 107+050  | 529536.245 | 2775781.59  |
| 1020 | 107+060  | 529546.143 | 2775780.167 |
| 1021 | 107+070  | 529556.041 | 2775778.744 |
| 1022 | 107+080  | 529565.939 | 2775777.322 |
| 1023 | 107+090  | 529575.838 | 2775775.899 |
| 1024 | 107+100  | 529585.736 | 2775774.476 |
| 1025 | 107+110  | 529595.634 | 2775773.053 |
| 1026 | 107+120  | 529605.523 | 2775771.566 |
| 1027 | 107+130  | 529615.354 | 2775769.742 |
| 1028 | 107+140  | 529625.083 | 2775767.434 |
| 1029 | 107+150  | 529634.684 | 2775764.642 |
| 1030 | 107+160  | 529644.134 | 2775761.374 |
| 1031 | 107+170  | 529653.409 | 2775757.638 |
| 1032 | 107+180  | 529662.485 | 2775753.443 |
| 1033 | 107+190  | 529671.341 | 2775748.8   |
| 1034 | 107+200  | 529679.953 | 2775743.719 |
| 1035 | 107+210  | 529688.3   | 2775738.215 |
| 1036 | 107+220  | 529696.365 | 2775732.303 |
| 1037 | 107+230  | 529704.216 | 2775726.11  |
| 1038 | 107+240  | 529712.023 | 2775719.861 |
| 1039 | 107+250  | 529719.829 | 2775713.611 |
| 1040 | 107+260  | 529727.636 | 2775707.361 |
| 1041 | 107+270  | 529735.442 | 2775701.112 |
| 1042 | 107+280  | 529743.249 | 2775694.862 |
| 1043 | 107+290  | 529751.052 | 2775688.609 |
| 1044 | 107+300  | 529757.555 | 2775681.073 |





| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 1045 | 107+310  | 529761.235 | 2775671.825 |
| 1046 | 107+320  | 529761.709 | 2775661.879 |
| 1047 | 107+330  | 529760.893 | 2775651.912 |
| 1048 | 107+340  | 529760.078 | 2775641.945 |
| 1049 | 107+350  | 529760.469 | 2775631.994 |
| 1050 | 107+360  | 529764.06  | 2775622.711 |
| 1051 | 107+370  | 529770.49  | 2775615.113 |
| 1052 | 107+380  | 529779.053 | 2775610.037 |
| 1053 | 107+390  | 529788.774 | 2775607.791 |
| 1054 | 107+400  | 529798.638 | 2775606.146 |
| 1055 | 107+410  | 529808.501 | 2775604.502 |
| 1056 | 107+420  | 529818.365 | 2775602.857 |
| 1057 | 107+430  | 529828.229 | 2775601.213 |
| 1058 | 107+440  | 529838.093 | 2775599.568 |
| 1059 | 107+450  | 529847.957 | 2775597.924 |
| 1060 | 107+460  | 529857.821 | 2775596.279 |
| 1061 | 107+470  | 529867.687 | 2775594.647 |
| 1062 | 107+480  | 529877.643 | 2775593.923 |
| 1063 | 107+490  | 529887.241 | 2775596.415 |
| 1064 | 107+500  | 529894.547 | 2775603.091 |
| 1065 | 107+510  | 529897.757 | 2775612.452 |
| 1066 | 107+520  | 529896.086 | 2775622.206 |
| 1067 | 107+530  | 529889.946 | 2775629.968 |
| 1068 | 107+540  | 529881.087 | 2775634.512 |
| 1069 | 107+550  | 529871.467 | 2775637.23  |
| 1070 | 107+560  | 529861.789 | 2775639.748 |
| 1071 | 107+570  | 529852.111 | 2775642.265 |
| 1072 | 107+580  | 529842.433 | 2775644.783 |
| 1073 | 107+590  | 529832.879 | 2775647.706 |
| 1074 | 107+600  | 529824.046 | 2775652.358 |
| 1075 | 107+610  | 529816.313 | 2775658.672 |
| 1076 | 107+620  | 529809.989 | 2775666.397 |
| 1077 | 107+630  | 529805.326 | 2775675.224 |
| 1078 | 107+640  | 529802.509 | 2775684.802 |
| 1079 | 107+650  | 529801.651 | 2775694.748 |
| 1080 | 107+660  | 529802.343 | 2775704.722 |
| 1081 | 107+670  | 529802.934 | 2775714.701 |
| 1082 | 107+680  | 529801.822 | 2775724.622 |
| 1083 | 107+690  | 529798.761 | 2775734.124 |
| 1084 | 107+700  | 529793.873 | 2775742.829 |
| 1085 | 107+710  | 529787.359 | 2775750.395 |
| 1086 | 107+720  | 529780.233 | 2775757.411 |
| 1087 | 107+730  | 529773.107 | 2775764.426 |
| 1088 | 107+740  | 529765.98  | 2775771.442 |

| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 1089 | 107+750  | 529758.854 | 2775778.457 |
| 1090 | 107+760  | 529751.728 | 2775785.473 |
| 1091 | 107+770  | 529744.602 | 2775792.488 |
| 1092 | 107+780  | 529737.476 | 2775799.504 |
| 1093 | 107+790  | 529730.349 | 2775806.519 |
| 1094 | 107+800  | 529723.223 | 2775813.535 |
| 1095 | 107+810  | 529716.097 | 2775820.55  |
| 1096 | 107+820  | 529708.971 | 2775827.566 |
| 1097 | 107+830  | 529701.844 | 2775834.581 |
| 1098 | 107+840  | 529694.718 | 2775841.597 |
| 1099 | 107+850  | 529687.628 | 2775848.648 |
| 1100 | 107+860  | 529680.844 | 2775855.993 |
| 1101 | 107+870  | 529674.728 | 2775863.899 |
| 1102 | 107+880  | 529669.431 | 2775872.376 |
| 1103 | 107+890  | 529665.007 | 2775881.339 |
| 1104 | 107+900  | 529661.5   | 2775890.7   |
| 1105 | 107+910  | 529658.849 | 2775900.34  |
| 1106 | 107+920  | 529656.652 | 2775910.095 |
| 1107 | 107+930  | 529654.522 | 2775919.866 |
| 1108 | 107+940  | 529652.393 | 2775929.637 |
| 1109 | 107+950  | 529650.264 | 2775939.407 |
| 1110 | 107+960  | 529648.134 | 2775949.178 |
| 1111 | 107+970  | 529646.005 | 2775958.949 |
| 1112 | 107+980  | 529643.876 | 2775968.719 |
| 1113 | 107+990  | 529641.746 | 2775978.49  |
| 1114 | 108+000  | 529639.617 | 2775988.261 |
| 1115 | 108+010  | 529637.487 | 2775998.031 |
| 1116 | 108+020  | 529635.697 | 2776007.864 |
| 1117 | 108+030  | 529636.24  | 2776017.795 |
| 1118 | 108+040  | 529641.027 | 2776026.456 |
| 1119 | 108+050  | 529649.381 | 2776031.762 |
| 1120 | 108+060  | 529659.256 | 2776032.414 |
| 1121 | 108+070  | 529668.234 | 2776028.251 |
| 1122 | 108+080  | 529674.273 | 2776020.379 |
| 1123 | 108+090  | 529677.633 | 2776010.977 |
| 1124 | 108+100  | 529680.238 | 2776001.322 |
| 1125 | 108+110  | 529682.838 | 2775991.666 |
| 1126 | 108+120  | 529685.438 | 2775982.01  |
| 1127 | 108+130  | 529688.037 | 2775972.354 |
| 1128 | 108+140  | 529690.637 | 2775962.697 |
| 1129 | 108+150  | 529693.27  | 2775953.05  |
| 1130 | 108+160  | 529696.175 | 2775943.482 |
| 1131 | 108+170  | 529699.539 | 2775934.066 |
| 1132 | 108+180  | 529703.371 | 2775924.831 |





| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 1133 | 108+190  | 529707.659 | 2775915.798 |
| 1134 | 108+200  | 529712.393 | 2775906.991 |
| 1135 | 108+210  | 529717.562 | 2775898.431 |
| 1136 | 108+220  | 529723.151 | 2775890.141 |
| 1137 | 108+230  | 529729.149 | 2775882.14  |
| 1138 | 108+240  | 529735.538 | 2775874.449 |
| 1139 | 108+250  | 529742.304 | 2775867.087 |
| 1140 | 108+260  | 529749.429 | 2775860.072 |
| 1141 | 108+270  | 529756.897 | 2775853.422 |
| 1142 | 108+280  | 529764.639 | 2775847.094 |
| 1143 | 108+290  | 529772.472 | 2775840.877 |
| 1144 | 108+300  | 529780.306 | 2775834.662 |
| 1145 | 108+310  | 529788.141 | 2775828.448 |
| 1146 | 108+320  | 529795.975 | 2775822.233 |
| 1147 | 108+330  | 529803.81  | 2775816.018 |
| 1148 | 108+340  | 529811.644 | 2775809.804 |
| 1149 | 108+350  | 529819.478 | 2775803.589 |
| 1150 | 108+360  | 529827.313 | 2775797.375 |
| 1151 | 108+370  | 529835.147 | 2775791.16  |
| 1152 | 108+380  | 529842.982 | 2775784.945 |
| 1153 | 108+390  | 529850.816 | 2775778.731 |
| 1154 | 108+400  | 529858.651 | 2775772.516 |
| 1155 | 108+410  | 529866.485 | 2775766.301 |
| 1156 | 108+420  | 529874.32  | 2775760.087 |
| 1157 | 108+430  | 529882.154 | 2775753.872 |
| 1158 | 108+440  | 529889.989 | 2775747.658 |
| 1159 | 108+450  | 529897.823 | 2775741.443 |
| 1160 | 108+460  | 529905.657 | 2775735.228 |
| 1161 | 108+470  | 529913.492 | 2775729.014 |
| 1162 | 108+480  | 529921.293 | 2775722.758 |
| 1163 | 108+490  | 529928.889 | 2775716.255 |
| 1164 | 108+500  | 529936.155 | 2775709.386 |
| 1165 | 108+510  | 529943.069 | 2775702.162 |
| 1166 | 108+520  | 529949.613 | 2775694.602 |
| 1167 | 108+530  | 529955.771 | 2775686.724 |
| 1168 | 108+540  | 529961.527 | 2775678.549 |
| 1169 | 108+550  | 529966.913 | 2775670.124 |
| 1170 | 108+560  | 529972.148 | 2775661.603 |
| 1171 | 108+570  | 529977.41  | 2775653.1   |
| 1172 | 108+580  | 529982.922 | 2775644.757 |
| 1173 | 108+590  | 529988.835 | 2775636.694 |
| 1174 | 108+600  | 529995.143 | 2775628.935 |
| 1175 | 108+610  | 530001.83  | 2775621.502 |
| 1176 | 108+620  | 530008.879 | 2775614.411 |

| 1177         108+630         530016.184         2775607.582           1178         108+640         530023.545         2775600.813           1179         108+650         530030.906         2775594.044           1180         108+660         530038.268         2775587.276           1181         108+670         530045.629         2775580.507           1182         108+680         530052.99         2775560.202           1183         108+690         530060.351         2775560.202           1184         108+700         530067.712         2775560.202           1185         108+710         530075.187         2775548.447           1187         108+730         530093.559         2775547.259           1188         108+740         530102.753         277550.92           1189         108+750         530109.066         277558.541           1190         108+760         530110.953         277558.541           1191         108+770         530108.044         277557.732           1192         108+780         530102.098         277558.541           1193         108+790         530095.345         277560.258           1194         108+800         530088.577  | S.N. | Chainage | Northing   | Easting     |
|--|------|----------|------------|-------------|
| 1178         108+640         530023.545         2775600.813           1179         108+650         530030.906         2775594.044           1180         108+660         530038.268         2775587.276           1181         108+670         530045.629         2775580.507           1182         108+680         530052.99         2775573.739           1183         108+690         530060.351         2775560.202           1184         108+700         530067.712         2775560.202           1185         108+710         530083.733         2775553.562           1186         108+720         530083.733         2775554.447           1187         108+730         530093.559         2775547.259           1188         108+740         530102.753         2775550.92           1189         108+750         530109.066         2775558.541           1190         108+760         530110.953         2775568.255           1191         108+770         530108.044         277557.732           1192         108+780         530102.098         2775585.747           1193         108+780         530083.837         2775602.58           1194         108+800         530083.587 </th <th></th> <th></th> <th></th> <th></th> |      |          |            |             |
| 1179         108+650         530030.906         2775594.044           1180         108+660         530038.268         2775587.276           1181         108+670         530045.629         2775580.507           1182         108+680         530052.99         2775573.739           1183         108+690         530060.351         2775566.97           1184         108+700         530067.712         2775560.202           1185         108+710         530075.187         277553.562           1186         108+720         530083.733         2775548.447           1187         108+730         530093.559         2775547.259           1188         108+740         530102.753         2775550.92           1189         108+750         530109.066         277558.541           1190         108+760         530110.953         2775568.255           1191         108+770         530108.044         2775577.732           1192         108+780         530012.098         2775585.747           1193         108+790         530095.345         2775507.484           1195         108+810         530081.809         2775607.845           1194         108+820         530075.04 <td></td> <td></td> <td></td> <td></td>        |      |          |            |             |
| 1180         108+660         530038.268         2775587.276           1181         108+670         530045.629         2775580.507           1182         108+680         530052.99         2775573.739           1183         108+690         530060.351         2775560.202           1184         108+700         530067.712         2775560.202           1185         108+710         530075.187         2775553.562           1186         108+720         530083.733         2775548.447           1187         108+730         530093.559         2775547.259           1188         108+740         530102.753         2775550.92           1189         108+750         530109.066         277558.541           1190         108+760         530110.953         2775568.255           1191         108+770         530108.044         2775577.732           1192         108+780         530095.345         2775593.122           1194         108+800         530088.577         2775600.484           1195         108+810         530081.809         2775607.845           1196         108+820         530075.04         2775622.568           1198         108+840         530068.272 </td <td></td> <td></td> <td></td> <td></td> |      |          |            |             |
| 1181         108+670         530045.629         2775580.507           1182         108+680         530052.99         2775573.739           1183         108+690         530060.351         2775560.202           1184         108+700         530067.712         2775560.202           1185         108+710         530075.187         2775553.562           1186         108+720         530083.733         2775548.447           1187         108+730         530093.559         2775547.259           1188         108+740         530102.753         2775550.92           1189         108+750         530109.066         277558.541           1190         108+760         530110.953         2775568.255           1191         108+770         530108.044         2775577.732           1192         108+780         530102.098         2775585.747           1193         108+790         530095.345         2775593.122           1194         108+800         530088.577         2775600.484           1195         108+810         530075.04         2775622.568           1198         108+840         530061.504         2775622.568           1198         108+840         530054.739 </td <td></td> <td></td> <td></td> <td></td> |      |          |            |             |
| 1182         108+680         530052.99         2775573.739           1183         108+690         530060.351         2775560.202           1184         108+700         530067.712         2775560.202           1185         108+710         530075.187         2775553.62           1186         108+720         530083.733         2775548.447           1187         108+730         530093.559         2775547.259           1188         108+740         530102.753         2775550.92           1189         108+750         530109.066         277558.541           1190         108+760         530110.953         2775568.255           1191         108+770         530108.044         2775577.732           1192         108+780         530102.098         2775585.747           1193         108+790         530095.345         2775593.122           1194         108+800         530088.577         2775600.484           1195         108+810         530075.04         2775615.207           1197         108+830         530054.739         2775637.294           1200         108+840         530041.76         2775652.503           1201         108+850         530041.76   |      |          |            |             |
| 1183         108+690         530060.351         2775566.97           1184         108+700         530067.712         2775560.202           1185         108+710         530075.187         2775553.562           1186         108+720         530083.733         2775548.447           1187         108+730         530093.559         2775547.259           1188         108+740         530102.753         2775550.92           1189         108+750         530109.066         2775558.541           1190         108+760         530110.953         2775568.255           1191         108+770         530108.044         2775577.732           1192         108+780         530102.098         2775585.747           1193         108+790         530095.345         2775593.122           1194         108+800         530088.577         2775600.484           1195         108+810         530081.809         2775607.845           1196         108+820         530075.04         2775622.568           1198         108+840         530068.272         2775622.568           1198         108+850         530048.086         2775644.759           1201         108+860         530048.086<  |      |          |            |             |
| 1184         108+700         530067.712         2775560.202           1185         108+710         530075.187         2775553.562           1186         108+720         530083.733         2775548.447           1187         108+730         530093.559         2775547.259           1188         108+740         530102.753         2775550.92           1189         108+750         530109.066         277558.541           1190         108+760         530110.953         2775568.255           1191         108+770         530108.044         2775577.732           1192         108+780         530102.098         2775585.747           1193         108+790         530095.345         2775593.122           1194         108+800         530081.809         2775607.845           1195         108+810         530081.809         2775607.845           1196         108+820         530075.04         2775615.207           1197         108+830         530068.272         2775622.568           1198         108+840         530045.739         2775622.568           1199         108+850         530041.76         2775652.503           1201         108+860         530041.76 <td></td> <td></td> <td></td> <td></td>       |      |          |            |             |
| 1185         108+710         530075.187         2775553.562           1186         108+720         530083.733         2775548.447           1187         108+730         530093.559         2775547.259           1188         108+740         530102.753         2775550.92           1189         108+750         530109.066         277558.541           1190         108+760         530110.953         2775568.255           1191         108+770         530108.044         2775577.732           1192         108+780         530102.098         2775585.747           1193         108+790         530095.345         2775500.484           1195         108+810         530081.809         2775607.845           1196         108+820         530075.04         2775615.207           1197         108+830         530068.272         2775622.568           1198         108+840         530061.504         2775622.568           1199         108+850         530048.086         2775644.759           1201         108+870         530041.76         2775652.503           1202         108+880         530035.83         2775660.553           1203         108+990         530025.212 <td></td> <td></td> <td></td> <td></td>       |      |          |            |             |
| 1186         108+720         530083.733         2775548.447           1187         108+730         530093.559         2775547.259           1188         108+740         530102.753         2775550.92           1189         108+750         530109.066         2775558.541           1190         108+760         530110.953         2775568.255           1191         108+770         530108.044         2775577.732           1192         108+780         530102.098         2775585.747           1193         108+790         530095.345         2775500.484           1195         108+810         530081.809         2775607.845           1196         108+820         530075.04         2775615.207           1197         108+830         530068.272         2775622.568           1198         108+840         530061.504         2775622.568           1199         108+850         530048.086         2775644.759           1201         108+870         530041.76         2775652.503           1202         108+880         530035.83         2775665.53           1203         108+990         530025.81         2775666.553           1204         108+990         530025.212 <td></td> <td></td> <td></td> <td></td>        |      |          |            |             |
| 1187         108+730         530093.559         2775547.259           1188         108+740         530102.753         2775550.92           1189         108+750         530109.066         2775558.541           1190         108+760         530110.953         2775568.255           1191         108+770         530108.044         2775577.732           1192         108+780         530102.098         2775585.747           1193         108+790         530095.345         2775600.484           1195         108+810         530081.809         2775607.845           1196         108+820         530075.04         2775622.568           1197         108+830         530068.272         2775622.568           1198         108+840         530061.504         2775622.568           1199         108+850         530054.739         2775637.294           1200         108+860         530048.086         2775644.759           1201         108+870         530041.76         2775652.503           1202         108+880         530035.83         2775668.89           1204         108+900         530025.212         2775677.492           1205         108+910         530025.51 <td></td> <td></td> <td></td> <td></td>        |      |          |            |             |
| 1188         108+740         530102.753         2775550.92           1189         108+750         530109.066         2775558.541           1190         108+760         530110.953         2775568.255           1191         108+770         530108.044         2775577.732           1192         108+780         530102.098         2775585.747           1193         108+790         530095.345         2775600.484           1195         108+810         530081.809         2775607.845           1196         108+820         530075.04         2775615.207           1197         108+830         530068.272         2775622.568           1198         108+840         530068.272         2775622.568           1199         108+850         530048.086         2775644.759           1200         108+860         530048.086         2775644.759           1201         108+870         530041.76         2775652.503           1202         108+880         530035.83         2775660.553           1203         108+890         530030.309         2775668.89           1204         108+900         530025.212         2775677.492           1205         108+910         530025.212 <td></td> <td></td> <td></td> <td></td>       |      |          |            |             |
| 1189         108+750         530109.066         2775558.541           1190         108+760         530110.953         2775568.255           1191         108+770         530108.044         2775577.732           1192         108+780         530102.098         2775585.747           1193         108+790         530095.345         2775593.122           1194         108+800         530081.809         2775607.845           1195         108+810         530081.809         2775607.845           1196         108+820         530075.04         2775615.207           1197         108+830         530068.272         2775622.568           1198         108+840         530061.504         2775629.93           1199         108+850         530054.739         2775637.294           1200         108+860         530048.086         2775644.759           1201         108+870         530041.76         2775652.503           1202         108+880         530035.83         2775668.89           1204         108+990         530030.309         2775668.89           1204         108+900         530025.212         2775695.404           1207         108+930         530016.332 <td></td> <td></td> <td></td> <td></td>        |      |          |            |             |
| 1190         108+760         530110.953         2775568.255           1191         108+770         530108.044         2775577.732           1192         108+780         530102.098         2775585.747           1193         108+790         530095.345         2775593.122           1194         108+800         530081.809         2775607.845           1195         108+810         530081.809         2775607.845           1196         108+820         530075.04         2775615.207           1197         108+830         530068.272         2775622.568           1198         108+840         530061.504         2775622.568           1199         108+850         530054.739         2775637.294           1200         108+860         530048.086         2775644.759           1201         108+870         530041.76         2775652.503           1202         108+880         530035.83         2775660.553           1203         108+890         530030.309         2775668.389           1204         108+900         530025.212         2775677.492           1205         108+910         530020.551         2775686.338           1206         108+920         530016.332<  |      |          |            |             |
| 1191         108+770         530108.044         2775577.732           1192         108+780         530102.098         2775585.747           1193         108+790         530095.345         2775593.122           1194         108+800         530088.577         2775600.484           1195         108+810         530081.809         2775607.845           1196         108+820         530075.04         2775615.207           1197         108+830         530068.272         2775622.568           1198         108+840         530061.504         2775629.93           1199         108+850         530054.739         2775637.294           1200         108+860         530048.086         2775644.759           1201         108+870         530041.76         2775652.503           1202         108+880         530035.83         2775660.553           1203         108+890         530030.309         2775668.89           1204         108+90         530020.551         2775686.338           1205         108+910         530020.551         2775686.338           1206         108+920         530016.332         2775704.605           1208         108+940         530008.555 <td></td> <td></td> <td></td> <td></td>        |      |          |            |             |
| 1192         108+780         530102.098         2775585.747           1193         108+790         530095.345         2775593.122           1194         108+800         530088.577         2775600.484           1195         108+810         530081.809         2775607.845           1196         108+820         530075.04         2775615.207           1197         108+830         530068.272         2775622.568           1198         108+840         530061.504         2775629.93           1199         108+850         530054.739         2775637.294           1200         108+860         530048.086         2775644.759           1201         108+870         530041.76         2775652.503           1202         108+880         530035.83         2775660.553           1203         108+890         530030.309         2775668.89           1204         108+900         530025.212         2775677.492           1205         108+910         530020.551         2775686.338           1206         108+920         530016.332         2775695.404           1207         108+930         530012.416         2775704.605           1208         108+940         530008.555 <td></td> <td></td> <td></td> <td></td>       |      |          |            |             |
| 1193         108+790         530095.345         2775593.122           1194         108+800         530088.577         2775600.484           1195         108+810         530081.809         2775607.845           1196         108+820         530075.04         2775615.207           1197         108+830         530068.272         2775622.568           1198         108+840         530061.504         2775629.93           1199         108+850         530054.739         2775637.294           1200         108+860         530048.086         2775644.759           1201         108+870         530041.76         2775652.503           1202         108+880         530035.83         2775660.553           1203         108+890         530030.309         2775668.89           1204         108+900         530025.212         2775677.492           1205         108+910         530020.551         2775686.338           1206         108+920         530016.332         2775695.404           1207         108+930         530016.332         2775746.605           1208         108+940         530008.555         2775713.829           1209         108+950         5300004.693 </td <td></td> <td></td> <td></td> <td></td> |      |          |            |             |
| 1194         108+800         530088.577         2775600.484           1195         108+810         530081.809         2775607.845           1196         108+820         530075.04         2775615.207           1197         108+830         530068.272         2775622.568           1198         108+840         530061.504         2775629.93           1199         108+850         530054.739         2775637.294           1200         108+860         530048.086         2775644.759           1201         108+870         530041.76         2775652.503           1202         108+880         530035.83         2775660.553           1203         108+890         5300303.309         2775668.89           1204         108+900         530025.212         2775677.492           1205         108+910         530020.551         2775686.338           1206         108+920         530016.332         2775695.404           1207         108+930         530012.416         2775704.605           1208         108+940         530008.555         2775713.829           1210         108+960         530004.693         2775732.29           1211         108+970         529998.108 <td></td> <td></td> <td></td> <td></td>       |      |          |            |             |
| 1195         108+810         530081.809         2775607.845           1196         108+820         530075.04         2775615.207           1197         108+830         530068.272         2775622.568           1198         108+840         530061.504         2775629.93           1199         108+850         530054.739         2775637.294           1200         108+860         530048.086         2775644.759           1201         108+870         530041.76         2775652.503           1202         108+880         530035.83         2775660.553           1203         108+890         530030.309         2775668.89           1204         108+900         530025.212         2775677.492           1205         108+910         530020.551         2775686.338           1206         108+920         530012.416         2775704.605           1208         108+940         530008.555         2775713.829           1209         108+950         530000.86         2775732.29           1211         108+960         530000.86         2775732.29           1211         108+980         529998.834         2775764.912           1213         108+990         530004.135   |      |          |            |             |
| 1196         108+820         530075.04         2775615.207           1197         108+830         530068.272         2775622.568           1198         108+840         530061.504         2775629.93           1199         108+850         530054.739         2775637.294           1200         108+860         530048.086         2775644.759           1201         108+870         530041.76         2775652.503           1202         108+880         530035.83         2775660.553           1203         108+890         530030.309         2775668.89           1204         108+900         530025.212         2775677.492           1205         108+910         530020.551         2775686.338           1206         108+920         530016.332         2775695.404           1207         108+930         530012.416         2775704.605           1208         108+940         530008.555         2775713.829           1209         108+950         530004.693         2775732.29           1211         108+960         530000.86         2775732.29           1211         108+980         529998.834         2775760.12           1214         109+000         530012.794   |      |          |            |             |
| 1197         108+830         530068.272         2775622.568           1198         108+840         530061.504         2775629.93           1199         108+850         530054.739         2775637.294           1200         108+860         530048.086         2775644.759           1201         108+870         530041.76         2775652.503           1202         108+880         530035.83         2775660.553           1203         108+890         530030.309         2775668.89           1204         108+900         530025.212         2775677.492           1205         108+910         530020.551         2775686.338           1206         108+920         530016.332         2775695.404           1207         108+930         530012.416         2775704.605           1208         108+940         530008.555         2775713.829           1209         108+950         530004.693         2775723.054           1210         108+960         530000.86         2775732.29           1211         108+970         529998.834         2775760.12           1213         108+990         530012.794         2775764.912           1215         109+010         530022.69  |      |          |            |             |
| 1198         108+840         530061.504         2775629.93           1199         108+850         530054.739         2775637.294           1200         108+860         530048.086         2775644.759           1201         108+870         530041.76         2775652.503           1202         108+880         530035.83         2775660.553           1203         108+890         530030.309         2775668.89           1204         108+900         530025.212         2775677.492           1205         108+910         530020.551         2775686.338           1206         108+920         530016.332         2775695.404           1207         108+930         530012.416         2775704.605           1208         108+940         530008.555         2775713.829           1209         108+950         530004.693         2775732.29           1211         108+960         530000.86         2775732.29           1211         108+980         529998.108         2775741.88           1212         108+980         529998.834         2775760.12           1213         108+990         530012.794         2775760.12           1214         109+000         530022.69   | -    |          |            |             |
| 1199108+850530054.7392775637.2941200108+860530048.0862775644.7591201108+870530041.762775652.5031202108+880530035.832775660.5531203108+890530030.3092775668.891204108+900530025.2122775677.4921205108+910530020.5512775686.3381206108+920530016.3322775695.4041207108+930530012.4162775704.6051208108+940530008.5552775713.8291209108+950530004.6932775723.0541210108+960530000.862775732.291211108+960530000.862775741.881212108+980529998.1082775761.7631213108+990530004.1352775760.121214109+000530012.7942775764.9121215109+010530022.692775764.9661216109+020530031.4542775760.3391217109+030530044.0312775744.8551218109+040530049.882775736.744   |      |          |            |             |
| 1200         108+860         530048.086         2775644.759           1201         108+870         530041.76         2775652.503           1202         108+880         530035.83         2775660.553           1203         108+890         530030.309         2775668.89           1204         108+900         530025.212         2775677.492           1205         108+910         530020.551         2775686.338           1206         108+920         530016.332         2775695.404           1207         108+930         530012.416         2775704.605           1208         108+940         530008.555         2775713.829           1209         108+950         530004.693         2775723.054           1210         108+960         530000.86         2775732.29           1211         108+970         529998.108         2775741.88           1212         108+980         529998.834         2775750.12           1213         108+990         530004.135         2775764.912           1214         109+000         530031.454         2775760.339           1215         109+010         530038.161         2775752.95           1218         109+040         530044.031  | -    | 108+840  |            | 2775629.93  |
| 1201         108+870         530041.76         2775652.503           1202         108+880         530035.83         2775660.553           1203         108+890         530030.309         2775668.89           1204         108+900         530025.212         2775677.492           1205         108+910         530020.551         2775686.338           1206         108+920         530016.332         2775695.404           1207         108+930         530012.416         2775704.605           1208         108+940         530008.555         2775713.829           1209         108+950         530004.693         2775723.054           1210         108+960         530000.86         2775732.29           1211         108+970         529998.108         2775741.88           1212         108+980         529998.834         2775751.763           1213         108+990         530004.135         2775764.912           1214         109+000         530012.794         2775764.912           1215         109+010         530031.454         2775760.339           1217         109+030         530038.161         2775752.95           1218         109+040         530049.88  | 1199 | 108+850  | 530054.739 |             |
| 1202         108+880         530035.83         2775660.553           1203         108+890         530030.309         2775668.89           1204         108+900         530025.212         2775677.492           1205         108+910         530020.551         2775686.338           1206         108+920         530016.332         2775695.404           1207         108+930         530012.416         2775704.605           1208         108+940         530008.555         2775713.829           1209         108+950         530004.693         2775723.054           1210         108+960         530000.86         2775732.29           1211         108+970         529998.108         2775741.88           1212         108+980         529998.834         2775751.763           1213         108+990         530004.135         2775760.12           1214         109+000         530012.794         2775764.966           1215         109+010         530031.454         2775760.339           1217         109+030         530034.031         2775744.855           1218         109+040         530049.88         2775736.744   |      | 108+860  |            |             |
| 1203         108+890         530030.309         2775668.89           1204         108+900         530025.212         2775677.492           1205         108+910         530020.551         2775686.338           1206         108+920         530016.332         2775695.404           1207         108+930         530012.416         2775704.605           1208         108+940         530008.555         2775713.829           1209         108+950         530004.693         2775723.054           1210         108+960         530000.86         2775732.29           1211         108+970         529998.108         2775741.88           1212         108+980         529998.834         2775751.763           1213         108+990         530004.135         2775764.912           1214         109+000         530012.794         2775764.966           1215         109+010         530031.454         2775760.339           1217         109+030         530038.161         2775752.95           1218         109+040         530044.031         2775744.855           1219         109+050         530049.88         2775736.744  | 1201 | 108+870  | 530041.76  | 2775652.503 |
| 1204         108+900         530025.212         2775677.492           1205         108+910         530020.551         2775686.338           1206         108+920         530016.332         2775695.404           1207         108+930         530012.416         2775704.605           1208         108+940         530008.555         2775713.829           1209         108+950         530004.693         2775723.054           1210         108+960         530000.86         2775732.29           1211         108+970         529998.108         2775741.88           1212         108+980         529998.834         2775751.763           1213         108+990         530004.135         2775760.12           1214         109+000         530012.794         2775764.912           1215         109+010         530022.69         2775764.966           1216         109+020         530031.454         2775760.339           1217         109+030         530038.161         2775752.95           1218         109+040         530044.031         2775744.855           1219         109+050         530049.88         2775736.744   |      | 108+880  | 530035.83  | 2775660.553 |
| 1205         108+910         530020.551         2775686.338           1206         108+920         530016.332         2775695.404           1207         108+930         530012.416         2775704.605           1208         108+940         530008.555         2775713.829           1209         108+950         530004.693         2775723.054           1210         108+960         530000.86         2775732.29           1211         108+970         529998.108         2775741.88           1212         108+980         529998.834         2775751.763           1213         108+990         530004.135         2775760.12           1214         109+000         530012.794         2775764.912           1215         109+010         530022.69         2775764.966           1216         109+020         530031.454         2775760.339           1217         109+030         530038.161         2775752.95           1218         109+040         530044.031         2775744.855           1219         109+050         530049.88         2775736.744   | 1203 | 108+890  | 530030.309 | 2775668.89  |
| 1206         108+920         530016.332         2775695.404           1207         108+930         530012.416         2775704.605           1208         108+940         530008.555         2775713.829           1209         108+950         530004.693         2775723.054           1210         108+960         530000.86         2775732.29           1211         108+970         529998.108         2775741.88           1212         108+980         529998.834         2775751.763           1213         108+990         530004.135         2775760.12           1214         109+000         530012.794         2775764.912           1215         109+010         530022.69         2775764.966           1216         109+020         530031.454         2775760.339           1217         109+030         530038.161         2775752.95           1218         109+040         530044.031         2775744.855           1219         109+050         530049.88         2775736.744   | 1204 | 108+900  | 530025.212 | 2775677.492 |
| 1207         108+930         530012.416         2775704.605           1208         108+940         530008.555         2775713.829           1209         108+950         530004.693         2775723.054           1210         108+960         530000.86         2775732.29           1211         108+970         529998.108         2775741.88           1212         108+980         529998.834         2775751.763           1213         108+990         530004.135         2775760.12           1214         109+000         530012.794         2775764.912           1215         109+010         530022.69         2775764.966           1216         109+020         530031.454         2775760.339           1217         109+030         530038.161         2775752.95           1218         109+040         530044.031         2775744.855           1219         109+050         530049.88         2775736.744   | 1205 | 108+910  | 530020.551 | 2775686.338 |
| 1208         108+940         530008.555         2775713.829           1209         108+950         530004.693         2775723.054           1210         108+960         530000.86         2775732.29           1211         108+970         529998.108         2775741.88           1212         108+980         529998.834         2775751.763           1213         108+990         530004.135         2775760.12           1214         109+000         530012.794         2775764.912           1215         109+010         530022.69         2775764.966           1216         109+020         530031.454         2775760.339           1217         109+030         530038.161         2775752.95           1218         109+040         530044.031         2775744.855           1219         109+050         530049.88         2775736.744   | 1206 | 108+920  | 530016.332 | 2775695.404 |
| 1209         108+950         530004.693         2775723.054           1210         108+960         530000.86         2775732.29           1211         108+970         529998.108         2775741.88           1212         108+980         529998.834         2775751.763           1213         108+990         530004.135         2775760.12           1214         109+000         530012.794         2775764.912           1215         109+010         530022.69         2775764.966           1216         109+020         530031.454         2775760.339           1217         109+030         530038.161         2775752.95           1218         109+040         530044.031         2775744.855           1219         109+050         530049.88         2775736.744   | 1207 | 108+930  | 530012.416 | 2775704.605 |
| 1210         108+960         530000.86         2775732.29           1211         108+970         529998.108         2775741.88           1212         108+980         529998.834         2775751.763           1213         108+990         530004.135         2775760.12           1214         109+000         530012.794         2775764.912           1215         109+010         530022.69         2775764.966           1216         109+020         530031.454         2775760.339           1217         109+030         530038.161         2775752.95           1218         109+040         530044.031         2775744.855           1219         109+050         530049.88         2775736.744   | 1208 | 108+940  | 530008.555 | 2775713.829 |
| 1211         108+970         529998.108         2775741.88           1212         108+980         529998.834         2775751.763           1213         108+990         530004.135         2775760.12           1214         109+000         530012.794         2775764.912           1215         109+010         530022.69         2775764.966           1216         109+020         530031.454         2775760.339           1217         109+030         530038.161         2775752.95           1218         109+040         530044.031         2775744.855           1219         109+050         530049.88         2775736.744   | 1209 | 108+950  | 530004.693 | 2775723.054 |
| 1212     108+980     529998.834     2775751.763       1213     108+990     530004.135     2775760.12       1214     109+000     530012.794     2775764.912       1215     109+010     530022.69     2775764.966       1216     109+020     530031.454     2775760.339       1217     109+030     530038.161     2775752.95       1218     109+040     530044.031     2775744.855       1219     109+050     530049.88     2775736.744  | 1210 | 108+960  | 530000.86  | 2775732.29  |
| 1213     108+990     530004.135     2775760.12       1214     109+000     530012.794     2775764.912       1215     109+010     530022.69     2775764.966       1216     109+020     530031.454     2775760.339       1217     109+030     530038.161     2775752.95       1218     109+040     530044.031     2775744.855       1219     109+050     530049.88     2775736.744  | 1211 | 108+970  | 529998.108 | 2775741.88  |
| 1214     109+000     530012.794     2775764.912       1215     109+010     530022.69     2775764.966       1216     109+020     530031.454     2775760.339       1217     109+030     530038.161     2775752.95       1218     109+040     530044.031     2775744.855       1219     109+050     530049.88     2775736.744   | 1212 | 108+980  | 529998.834 | 2775751.763 |
| 1215     109+010     530022.69     2775764.966       1216     109+020     530031.454     2775760.339       1217     109+030     530038.161     2775752.95       1218     109+040     530044.031     2775744.855       1219     109+050     530049.88     2775736.744   | 1213 | 108+990  | 530004.135 | 2775760.12  |
| 1216     109+020     530031.454     2775760.339       1217     109+030     530038.161     2775752.95       1218     109+040     530044.031     2775744.855       1219     109+050     530049.88     2775736.744  | 1214 | 109+000  | 530012.794 | 2775764.912 |
| 1217     109+030     530038.161     2775752.95       1218     109+040     530044.031     2775744.855       1219     109+050     530049.88     2775736.744  | 1215 | 109+010  | 530022.69  | 2775764.966 |
| 1218     109+040     530044.031     2775744.855       1219     109+050     530049.88     2775736.744   | 1216 | 109+020  | 530031.454 | 2775760.339 |
| 1219 109+050 530049.88 2775736.744   | 1217 | 109+030  | 530038.161 | 2775752.95  |
|  | 1218 | 109+040  | 530044.031 | 2775744.855 |
| 1220 109+060 530055.729 2775728.632  | 1219 | 109+050  | 530049.88  | 2775736.744 |
| <u> </u>   | 1220 | 109+060  | 530055.729 | 2775728.632 |





| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 1221 | 109+070  | 530061.577 | 2775720.521 |
| 1222 | 109+080  | 530067.426 | 2775712.409 |
| 1223 | 109+090  | 530073.274 | 2775704.298 |
| 1224 | 109+100  | 530079.123 | 2775696.187 |
| 1225 | 109+110  | 530085.035 | 2775688.121 |
| 1226 | 109+120  | 530091.233 | 2775680.275 |
| 1227 | 109+130  | 530097.813 | 2775672.746 |
| 1228 | 109+140  | 530104.761 | 2775665.556 |
| 1229 | 109+150  | 530112.046 | 2775658.707 |
| 1230 | 109+160  | 530119.507 | 2775652.049 |
| 1231 | 109+170  | 530126.986 | 2775645.411 |
| 1232 | 109+180  | 530134.465 | 2775638.773 |
| 1233 | 109+190  | 530141.944 | 2775632.135 |
| 1234 | 109+200  | 530149.423 | 2775625.497 |
| 1235 | 109+210  | 530156.891 | 2775618.846 |
| 1236 | 109+220  | 530164.173 | 2775611.993 |
| 1237 | 109+230  | 530170.944 | 2775604.639 |
| 1238 | 109+240  | 530176.83  | 2775596.564 |
| 1239 | 109+250  | 530181.594 | 2775587.78  |
| 1240 | 109+260  | 530185.148 | 2775578.441 |
| 1241 | 109+270  | 530187.429 | 2775568.712 |
| 1242 | 109+280  | 530188.396 | 2775558.767 |
| 1243 | 109+290  | 530188.047 | 2775548.78  |
| 1244 | 109+300  | 530186.627 | 2775538.884 |
| 1245 | 109+310  | 530184.58  | 2775529.096 |
| 1246 | 109+320  | 530182.333 | 2775519.352 |
| 1247 | 109+330  | 530180.08  | 2775509.609 |
| 1248 | 109+340  | 530177.827 | 2775499.866 |
| 1249 | 109+350  | 530175.574 | 2775490.123 |
| 1250 | 109+360  | 530173.321 | 2775480.381 |
| 1251 | 109+370  | 530171.084 | 2775470.634 |
| 1252 | 109+380  | 530169.07  | 2775460.84  |
| 1253 | 109+390  | 530167.517 | 2775450.962 |
| 1254 | 109+400  | 530166.459 | 2775441.019 |
| 1255 | 109+410  | 530165.9   | 2775431.036 |
| 1256 | 109+420  | 530165.84  | 2775421.037 |
| 1257 | 109+430  | 530166.28  | 2775411.048 |
| 1258 | 109+440  | 530167.219 | 2775401.093 |
| 1259 | 109+450  | 530168.654 | 2775391.198 |
| 1260 | 109+460  | 530170.581 | 2775381.386 |
| 1261 | 109+470  | 530172.886 | 2775371.655 |
| 1262 | 109+480  | 530175.288 | 2775361.948 |
| 1263 | 109+490  | 530177.69  | 2775352.241 |
| 1264 | 109+500  | 530180.093 | 2775342.534 |

| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 1265 | 109+510  | 530182.495 | 2775332.827 |
| 1266 | 109+520  | 530184.898 | 2775323.12  |
| 1267 | 109+530  | 530187.301 | 2775313.413 |
| 1268 | 109+540  | 530189.703 | 2775303.706 |
| 1269 | 109+550  | 530192.106 | 2775293.998 |
| 1270 | 109+560  | 530194.508 | 2775284.291 |
| 1271 | 109+570  | 530197.414 | 2775274.732 |
| 1272 | 109+580  | 530202.732 | 2775266.341 |
| 1273 | 109+590  | 530211.228 | 2775261.267 |
| 1274 | 109+600  | 530221.117 | 2775260.888 |
| 1275 | 109+610  | 530229.977 | 2775265.296 |
| 1276 | 109+620  | 530235.64  | 2775273.412 |
| 1277 | 109+630  | 530237.038 | 2775283.247 |
| 1278 | 109+640  | 530235.75  | 2775293.155 |
| 1279 | 109+650  | 530233.94  | 2775302.989 |
| 1280 | 109+660  | 530232.129 | 2775312.824 |
| 1281 | 109+670  | 530230.318 | 2775322.659 |
| 1282 | 109+680  | 530228.507 | 2775332.493 |
| 1283 | 109+690  | 530226.696 | 2775342.328 |
| 1284 | 109+700  | 530224.885 | 2775352.163 |
| 1285 | 109+710  | 530223.08  | 2775361.998 |
| 1286 | 109+720  | 530221.44  | 2775371.863 |
| 1287 | 109+730  | 530220.236 | 2775381.789 |
| 1288 | 109+740  | 530219.53  | 2775391.763 |
| 1289 | 109+750  | 530219.324 | 2775401.76  |
| 1290 | 109+760  | 530219.617 | 2775411.754 |
| 1291 | 109+770  | 530220.41  | 2775421.722 |
| 1292 | 109+780  | 530221.699 | 2775431.637 |
| 1293 | 109+790  | 530223.483 | 2775441.476 |
| 1294 | 109+800  | 530225.756 | 2775451.213 |
| 1295 | 109+810  | 530228.513 | 2775460.824 |
| 1296 | 109+820  | 530231.734 | 2775470.291 |
| 1297 | 109+830  | 530235.228 | 2775479.66  |
| 1298 | 109+840  | 530238.756 | 2775489.017 |
| 1299 | 109+850  | 530242.285 | 2775498.374 |
| 1300 | 109+860  | 530245.814 | 2775507.731 |
| 1301 | 109+870  | 530249.342 | 2775517.087 |
| 1302 | 109+880  | 530252.871 | 2775526.444 |
| 1303 | 109+890  | 530256.4   | 2775535.801 |
| 1304 | 109+900  | 530259.928 | 2775545.157 |
| 1305 | 109+910  | 530263.457 | 2775554.514 |
| 1306 | 109+920  | 530266.986 | 2775563.871 |
| 1307 | 109+930  | 530270.515 | 2775573.228 |
| 1308 | 109+940  | 530274.023 | 2775582.592 |





| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 1309 | 109+950  | 530277.228 | 2775592.063 |
| 1310 | 109+960  | 530279.668 | 2775601.757 |
| 1311 | 109+970  | 530281.132 | 2775611.645 |
| 1312 | 109+980  | 530281.601 | 2775621.63  |
| 1313 | 109+990  | 530281.071 | 2775631.611 |
| 1314 | 110+000  | 530279.548 | 2775641.49  |
| 1315 | 110+010  | 530277.048 | 2775651.169 |
| 1316 | 110+020  | 530273.759 | 2775660.611 |
| 1317 | 110+030  | 530270.138 | 2775669.932 |
| 1318 | 110+040  | 530266.49  | 2775679.243 |
| 1319 | 110+050  | 530262.842 | 2775688.554 |
| 1320 | 110+060  | 530259.194 | 2775697.865 |
| 1321 | 110+070  | 530255.546 | 2775707.176 |
| 1322 | 110+080  | 530251.898 | 2775716.486 |
| 1323 | 110+090  | 530248.25  | 2775725.797 |
| 1324 | 110+100  | 530244.602 | 2775735.108 |
| 1325 | 110+110  | 530240.954 | 2775744.419 |
| 1326 | 110+120  | 530237.306 | 2775753.73  |
| 1327 | 110+130  | 530233.658 | 2775763.04  |
| 1328 | 110+140  | 530230.009 | 2775772.351 |
| 1329 | 110+150  | 530226.361 | 2775781.662 |
| 1330 | 110+160  | 530222.713 | 2775790.973 |
| 1331 | 110+170  | 530219.065 | 2775800.284 |
| 1332 | 110+180  | 530215.417 | 2775809.595 |
| 1333 | 110+190  | 530211.769 | 2775818.905 |
| 1334 | 110+200  | 530208.121 | 2775828.216 |
| 1335 | 110+210  | 530204.473 | 2775837.527 |
| 1336 | 110+220  | 530200.733 | 2775846.8   |
| 1337 | 110+230  | 530195.632 | 2775855.382 |
| 1338 | 110+240  | 530188.928 | 2775862.779 |
| 1339 | 110+250  | 530180.888 | 2775868.697 |
| 1340 | 110+260  | 530171.832 | 2775872.899 |
| 1341 | 110+270  | 530162.224 | 2775875.666 |
| 1342 | 110+280  | 530152.587 | 2775878.334 |
| 1343 | 110+290  | 530142.95  | 2775881.006 |
| 1344 | 110+300  | 530133.373 | 2775883.881 |
| 1345 | 110+310  | 530124.019 | 2775887.405 |
| 1346 | 110+320  | 530115.054 | 2775891.828 |
| 1347 | 110+330  | 530106.533 | 2775897.056 |
| 1348 | 110+340  | 530098.286 | 2775902.712 |
| 1349 | 110+350  | 530090.089 | 2775908.439 |
| 1350 | 110+360  | 530081.891 | 2775914.166 |
| 1351 | 110+370  | 530073.694 | 2775919.893 |
| 1352 | 110+380  | 530065.496 | 2775925.621 |

| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 1353 | 110+390  | 530057.299 | 2775931.348 |
| 1354 | 110+400  | 530049.101 | 2775937.075 |
| 1355 | 110+410  | 530040.904 | 2775942.802 |
| 1356 | 110+420  | 530032.725 | 2775948.556 |
| 1357 | 110+430  | 530024.71  | 2775954.534 |
| 1358 | 110+440  | 530016.993 | 2775960.893 |
| 1359 | 110+450  | 530009.604 | 2775967.629 |
| 1360 | 110+460  | 530002.56  | 2775974.726 |
| 1361 | 110+470  | 529995.881 | 2775982.167 |
| 1362 | 110+480  | 529989.581 | 2775989.932 |
| 1363 | 110+490  | 529983.662 | 2775997.991 |
| 1364 | 110+500  | 529977.957 | 2776006.204 |
| 1365 | 110+510  | 529972.276 | 2776014.433 |
| 1366 | 110+520  | 529966.594 | 2776022.663 |
| 1367 | 110+530  | 529960.913 | 2776030.892 |
| 1368 | 110+540  | 529955.232 | 2776039.121 |
| 1369 | 110+550  | 529949.55  | 2776047.351 |
| 1370 | 110+560  | 529943.869 | 2776055.58  |
| 1371 | 110+570  | 529938.187 | 2776063.809 |
| 1372 | 110+580  | 529932.506 | 2776072.039 |
| 1373 | 110+590  | 529926.85  | 2776080.285 |
| 1374 | 110+600  | 529922.164 | 2776089.094 |
| 1375 | 110+610  | 529920.804 | 2776098.91  |
| 1376 | 110+620  | 529924.234 | 2776108.193 |
| 1377 | 110+630  | 529931.696 | 2776114.694 |
| 1378 | 110+640  | 529941.36  | 2776116.822 |
| 1379 | 110+650  | 529950.871 | 2776114.074 |
| 1380 | 110+660  | 529958.624 | 2776107.811 |
| 1381 | 110+670  | 529965.294 | 2776100.363 |
| 1382 | 110+680  | 529971.885 | 2776092.842 |
| 1383 | 110+690  | 529978.476 | 2776085.322 |
| 1384 | 110+700  | 529985.067 | 2776077.801 |
| 1385 | 110+710  | 529991.659 | 2776070.281 |
| 1386 | 110+720  | 529998.25  | 2776062.76  |
| 1387 | 110+730  | 530004.841 | 2776055.24  |
| 1388 | 110+740  | 530011.432 | 2776047.719 |
| 1389 | 110+750  | 530018.023 | 2776040.199 |
| 1390 | 110+760  | 530024.614 | 2776032.678 |
| 1391 | 110+770  | 530031.206 | 2776025.158 |
| 1392 | 110+780  | 530037.88  | 2776017.712 |
| 1393 | 110+790  | 530044.843 | 2776010.536 |
| 1394 | 110+800  | 530052.156 | 2776003.717 |
| 1395 | 110+810  | 530059.801 | 2775997.272 |
| 1396 | 110+820  | 530067.758 | 2775991.217 |





| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 1397 | 110+830  | 530076.008 | 2775985.568 |
| 1398 | 110+840  | 530084.53  | 2775980.337 |
| 1399 | 110+850  | 530093.26  | 2775975.461 |
| 1400 | 110+860  | 530102.051 | 2775970.695 |
| 1401 | 110+870  | 530110.843 | 2775965.93  |
| 1402 | 110+880  | 530119.635 | 2775961.166 |
| 1403 | 110+890  | 530128.427 | 2775956.402 |
| 1404 | 110+900  | 530137.219 | 2775951.637 |
| 1405 | 110+910  | 530146.011 | 2775946.873 |
| 1406 | 110+920  | 530154.804 | 2775942.108 |
| 1407 | 110+930  | 530163.596 | 2775937.344 |
| 1408 | 110+940  | 530172.39  | 2775932.583 |
| 1409 | 110+950  | 530181.376 | 2775928.205 |
| 1410 | 110+960  | 530190.928 | 2775925.318 |
| 1411 | 110+970  | 530200.878 | 2775925.233 |
| 1412 | 110+980  | 530210     | 2775929.1   |
| 1413 | 110+990  | 530216.204 | 2775936.81  |
| 1414 | 111+000  | 530217.954 | 2775946.551 |
| 1415 | 111+010  | 530215.124 | 2775956.067 |
| 1416 | 111+020  | 530209.152 | 2775964.044 |
| 1417 | 111+030  | 530201.51  | 2775970.475 |
| 1418 | 111+040  | 530193.234 | 2775976.087 |
| 1419 | 111+050  | 530184.891 | 2775981.601 |
| 1420 | 111+060  | 530176.549 | 2775987.115 |
| 1421 | 111+070  | 530168.206 | 2775992.629 |
| 1422 | 111+080  | 530159.864 | 2775998.143 |
| 1423 | 111+090  | 530151.521 | 2776003.656 |
| 1424 | 111+100  | 530143.179 | 2776009.17  |
| 1425 | 111+110  | 530134.836 | 2776014.684 |
| 1426 | 111+120  | 530126.494 | 2776020.198 |
| 1427 | 111+130  | 530118.151 | 2776025.712 |
| 1428 | 111+140  | 530109.809 | 2776031.226 |
| 1429 | 111+150  | 530101.475 | 2776036.752 |
| 1430 | 111+160  | 530093.264 | 2776042.459 |
| 1431 | 111+170  | 530085.328 | 2776048.542 |
| 1432 | 111+180  | 530077.705 | 2776055.013 |
| 1433 | 111+190  | 530070.416 | 2776061.858 |
| 1434 | 111+200  | 530063.478 | 2776069.058 |
| 1435 | 111+210  | 530056.908 | 2776076.595 |
| 1436 | 111+220  | 530050.65  | 2776084.394 |
| 1437 | 111+230  | 530044.485 | 2776092.268 |
| 1438 | 111+240  | 530038.322 | 2776100.144 |
| 1439 | 111+250  | 530032.159 | 2776108.019 |
| 1440 | 111+260  | 530025.996 | 2776115.894 |

| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 1441 | 111+270  | 530019.833 | 2776123.769 |
| 1442 | 111+280  | 530013.67  | 2776131.644 |
| 1443 | 111+290  | 530007.507 | 2776139.519 |
| 1444 | 111+300  | 530001.344 | 2776147.394 |
| 1445 | 111+310  | 529995.189 | 2776155.275 |
| 1446 | 111+320  | 529989.187 | 2776163.273 |
| 1447 | 111+330  | 529983.556 | 2776171.536 |
| 1448 | 111+340  | 529978.344 | 2776180.069 |
| 1449 | 111+350  | 529973.565 | 2776188.852 |
| 1450 | 111+360  | 529969.133 | 2776197.816 |
| 1451 | 111+370  | 529964.796 | 2776206.826 |
| 1452 | 111+380  | 529960.46  | 2776215.837 |
| 1453 | 111+390  | 529956.124 | 2776224.848 |
| 1454 | 111+400  | 529951.787 | 2776233.859 |
| 1455 | 111+410  | 529947.451 | 2776242.87  |
| 1456 | 111+420  | 529943.115 | 2776251.881 |
| 1457 | 111+430  | 529938.779 | 2776260.892 |
| 1458 | 111+440  | 529934.443 | 2776269.903 |
| 1459 | 111+450  | 529930.107 | 2776278.914 |
| 1460 | 111+460  | 529925.77  | 2776287.925 |
| 1461 | 111+470  | 529921.434 | 2776296.936 |
| 1462 | 111+480  | 529917.098 | 2776305.947 |
| 1463 | 111+490  | 529912.762 | 2776314.958 |
| 1464 | 111+500  | 529908.401 | 2776323.957 |
| 1465 | 111+510  | 529903.806 | 2776332.838 |
| 1466 | 111+520  | 529898.79  | 2776341.488 |
| 1467 | 111+530  | 529893.348 | 2776349.876 |
| 1468 | 111+540  | 529887.493 | 2776357.982 |
| 1469 | 111+550  | 529881.241 | 2776365.785 |
| 1470 | 111+560  | 529874.627 | 2776373.285 |
| 1471 | 111+570  | 529867.841 | 2776380.629 |
| 1472 | 111+580  | 529861.04  | 2776387.961 |
| 1473 | 111+590  | 529854.24  | 2776395.293 |
| 1474 | 111+600  | 529847.44  | 2776402.625 |
| 1475 | 111+610  | 529840.639 | 2776409.956 |
| 1476 | 111+620  | 529833.839 | 2776417.288 |
| 1477 | 111+630  | 529827.038 | 2776424.62  |
| 1478 | 111+640  | 529820.238 | 2776431.952 |
| 1479 | 111+650  | 529813.482 | 2776439.324 |
| 1480 | 111+660  | 529807.063 | 2776446.989 |
| 1481 | 111+670  | 529801.401 | 2776455.224 |
| 1482 | 111+680  | 529796.988 | 2776464.185 |
| 1483 | 111+690  | 529794.336 | 2776473.809 |
| 1484 | 111+700  | 529793.65  | 2776483.769 |





| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 1485 | 111+710  | 529794.955 | 2776493.667 |
| 1486 | 111+720  | 529798.201 | 2776503.108 |
| 1487 | 111+730  | 529803.219 | 2776511.741 |
| 1488 | 111+740  | 529809.543 | 2776519.478 |
| 1489 | 111+750  | 529816.673 | 2776526.486 |
| 1490 | 111+760  | 529824.203 | 2776533.065 |
| 1491 | 111+770  | 529831.822 | 2776539.542 |
| 1492 | 111+780  | 529839.441 | 2776546.018 |
| 1493 | 111+790  | 529847.061 | 2776552.495 |
| 1494 | 111+800  | 529854.68  | 2776558.972 |
| 1495 | 111+810  | 529862.236 | 2776565.522 |
| 1496 | 111+820  | 529869.436 | 2776572.458 |
| 1497 | 111+830  | 529875.961 | 2776580.03  |
| 1498 | 111+840  | 529881.697 | 2776588.217 |
| 1499 | 111+850  | 529886.587 | 2776596.935 |
| 1500 | 111+860  | 529890.582 | 2776606.097 |
| 1501 | 111+870  | 529893.643 | 2776615.613 |
| 1502 | 111+880  | 529895.738 | 2776625.387 |
| 1503 | 111+890  | 529896.847 | 2776635.321 |
| 1504 | 111+900  | 529896.959 | 2776645.316 |
| 1505 | 111+910  | 529896.073 | 2776655.273 |
| 1506 | 111+920  | 529894.228 | 2776665.098 |
| 1507 | 111+930  | 529891.766 | 2776674.789 |
| 1508 | 111+940  | 529889.169 | 2776684.446 |
| 1509 | 111+950  | 529886.884 | 2776694.18  |
| 1510 | 111+960  | 529885.35  | 2776704.058 |
| 1511 | 111+970  | 529884.993 | 2776714.044 |
| 1512 | 111+980  | 529885.966 | 2776723.989 |
| 1513 | 111+990  | 529888.251 | 2776733.717 |
| 1514 | 112+000  | 529891.809 | 2776743.054 |
| 1515 | 112+010  | 529896.487 | 2776751.888 |
| 1516 | 112+020  | 529901.885 | 2776760.304 |
| 1517 | 112+030  | 529907.608 | 2776768.504 |
| 1518 | 112+040  | 529913.371 | 2776776.676 |
| 1519 | 112+050  | 529919.088 | 2776784.881 |
| 1520 | 112+060  | 529924.435 | 2776793.329 |
| 1521 | 112+070  | 529928.963 | 2776802.239 |
| 1522 | 112+080  | 529932.161 | 2776811.701 |
| 1523 | 112+090  | 529933.529 | 2776821.59  |
| 1524 | 112+100  | 529932.906 | 2776831.554 |
| 1525 | 112+110  | 529930.316 | 2776841.195 |
| 1526 | 112+120  | 529925.862 | 2776850.13  |
| 1527 | 112+130  | 529919.721 | 2776858.001 |
| 1528 | 112+140  | 529912.144 | 2776864.502 |

| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 1529 | 112+150  | 529903.541 | 2776869.581 |
| 1530 | 112+160  | 529894.358 | 2776873.53  |
| 1531 | 112+170  | 529884.895 | 2776876.76  |
| 1532 | 112+180  | 529875.345 | 2776879.725 |
| 1533 | 112+190  | 529865.791 | 2776882.676 |
| 1534 | 112+200  | 529856.249 | 2776885.668 |
| 1535 | 112+210  | 529846.835 | 2776889.038 |
| 1536 | 112+220  | 529837.747 | 2776893.198 |
| 1537 | 112+230  | 529829.118 | 2776898.245 |
| 1538 | 112+240  | 529821.037 | 2776904.128 |
| 1539 | 112+250  | 529813.583 | 2776910.788 |
| 1540 | 112+260  | 529806.832 | 2776918.16  |
| 1541 | 112+270  | 529800.85  | 2776926.168 |
| 1542 | 112+280  | 529795.588 | 2776934.669 |
| 1543 | 112+290  | 529790.691 | 2776943.388 |
| 1544 | 112+300  | 529785.839 | 2776952.132 |
| 1545 | 112+310  | 529780.987 | 2776960.876 |
| 1546 | 112+320  | 529776.135 | 2776969.62  |
| 1547 | 112+330  | 529771.283 | 2776978.364 |
| 1548 | 112+340  | 529766.431 | 2776987.108 |
| 1549 | 112+350  | 529761.578 | 2776995.852 |
| 1550 | 112+360  | 529756.726 | 2777004.596 |
| 1551 | 112+370  | 529751.874 | 2777013.34  |
| 1552 | 112+380  | 529747.022 | 2777022.084 |
| 1553 | 112+390  | 529742.17  | 2777030.828 |
| 1554 | 112+400  | 529737.31  | 2777039.567 |
| 1555 | 112+410  | 529732.25  | 2777048.192 |
| 1556 | 112+420  | 529726.628 | 2777056.458 |
| 1557 | 112+430  | 529720.135 | 2777064.054 |
| 1558 | 112+440  | 529712.696 | 2777070.726 |
| 1559 | 112+450  | 529704.437 | 2777076.351 |
| 1560 | 112+460  | 529695.564 | 2777080.954 |
| 1561 | 112+470  | 529686.356 | 2777084.851 |
| 1562 | 112+480  | 529677.02  | 2777088.434 |
| 1563 | 112+490  | 529667.685 | 2777092.018 |
| 1564 | 112+500  | 529658.478 | 2777095.917 |
| 1565 | 112+510  | 529649.606 | 2777100.523 |
| 1566 | 112+520  | 529641.35  | 2777106.151 |
| 1567 | 112+530  | 529633.914 | 2777112.827 |
| 1568 | 112+540  | 529627.374 | 2777120.385 |
| 1569 | 112+550  | 529621.53  | 2777128.497 |
| 1570 | 112+560  | 529616.051 | 2777136.863 |
| 1571 | 112+570  | 529610.634 | 2777145.269 |
| 1572 | 112+580  | 529605.218 | 2777153.675 |





| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 1573 | 112+590  | 529599.801 | 2777162.08  |
| 1574 | 112+600  | 529594.343 | 2777170.46  |
| 1575 | 112+610  | 529588.541 | 2777178.602 |
| 1576 | 112+620  | 529582.056 | 2777186.208 |
| 1577 | 112+630  | 529574.844 | 2777193.129 |
| 1578 | 112+640  | 529566.976 | 2777199.296 |
| 1579 | 112+650  | 529558.569 | 2777204.706 |
| 1580 | 112+660  | 529549.886 | 2777209.665 |
| 1581 | 112+670  | 529541.154 | 2777214.538 |
| 1582 | 112+680  | 529532.421 | 2777219.411 |
| 1583 | 112+690  | 529523.689 | 2777224.285 |
| 1584 | 112+700  | 529514.957 | 2777229.158 |
| 1585 | 112+710  | 529506.225 | 2777234.032 |
| 1586 | 112+720  | 529497.493 | 2777238.905 |
| 1587 | 112+730  | 529488.761 | 2777243.778 |
| 1588 | 112+740  | 529480.029 | 2777248.652 |
| 1589 | 112+750  | 529471.296 | 2777253.525 |
| 1590 | 112+760  | 529462.564 | 2777258.398 |
| 1591 | 112+770  | 529453.832 | 2777263.272 |
| 1592 | 112+780  | 529445.1   | 2777268.145 |
| 1593 | 112+790  | 529436.368 | 2777273.018 |
| 1594 | 112+800  | 529427.636 | 2777277.892 |
| 1595 | 112+810  | 529418.904 | 2777282.765 |
| 1596 | 112+820  | 529410.171 | 2777287.639 |
| 1597 | 112+830  | 529401.439 | 2777292.512 |
| 1598 | 112+840  | 529392.707 | 2777297.385 |
| 1599 | 112+850  | 529383.956 | 2777302.223 |
| 1600 | 112+860  | 529375.065 | 2777306.8   |
| 1601 | 112+870  | 529365.963 | 2777310.938 |
| 1602 | 112+880  | 529356.682 | 2777314.66  |
| 1603 | 112+890  | 529347.331 | 2777318.206 |
| 1604 | 112+900  | 529337.978 | 2777321.743 |
| 1605 | 112+910  | 529328.624 | 2777325.28  |
| 1606 | 112+920  | 529319.271 | 2777328.818 |
| 1607 | 112+930  | 529309.917 | 2777332.355 |
| 1608 | 112+940  | 529300.564 | 2777335.892 |
| 1609 | 112+950  | 529291.21  | 2777339.429 |
| 1610 | 112+960  | 529281.857 | 2777342.966 |
| 1611 | 112+970  | 529272.503 | 2777346.504 |
| 1612 | 112+980  | 529263.15  | 2777350.041 |
| 1613 | 112+990  | 529253.796 | 2777353.578 |
| 1614 | 113+000  | 529244.443 | 2777357.115 |
| 1615 | 113+010  | 529235.051 | 2777360.548 |
| 1616 | 113+020  | 529225.487 | 2777363.459 |

| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 1617 | 113+030  | 529215.693 | 2777365.458 |
| 1618 | 113+040  | 529205.749 | 2777366.471 |
| 1619 | 113+050  | 529195.753 | 2777366.485 |
| 1620 | 113+060  | 529185.805 | 2777365.501 |
| 1621 | 113+070  | 529176.006 | 2777363.531 |
| 1622 | 113+080  | 529166.401 | 2777360.751 |
| 1623 | 113+090  | 529156.904 | 2777357.621 |
| 1624 | 113+100  | 529147.417 | 2777354.459 |
| 1625 | 113+110  | 529137.759 | 2777351.921 |
| 1626 | 113+120  | 529127.794 | 2777351.313 |
| 1627 | 113+130  | 529117.901 | 2777352.669 |
| 1628 | 113+140  | 529108.109 | 2777354.701 |
| 1629 | 113+150  | 529098.318 | 2777356.733 |
| 1630 | 113+160  | 529088.46  | 2777358.355 |
| 1631 | 113+170  | 529078.478 | 2777358.126 |
| 1632 | 113+180  | 529068.529 | 2777357.116 |
| 1633 | 113+190  | 529058.575 | 2777356.17  |
| 1634 | 113+200  | 529048.937 | 2777358.414 |
| 1635 | 113+210  | 529041.555 | 2777365.005 |
| 1636 | 113+220  | 529038.236 | 2777374.328 |
| 1637 | 113+230  | 529039.793 | 2777384.101 |
| 1638 | 113+240  | 529045.799 | 2777391.984 |
| 1639 | 113+250  | 529053.136 | 2777398.779 |
| 1640 | 113+260  | 529060.473 | 2777405.573 |
| 1641 | 113+270  | 529067.811 | 2777412.368 |
| 1642 | 113+280  | 529075.148 | 2777419.162 |
| 1643 | 113+290  | 529082.485 | 2777425.956 |
| 1644 | 113+300  | 529089.597 | 2777432.967 |
| 1645 | 113+310  | 529093.421 | 2777442.095 |
| 1646 | 113+320  | 529092.402 | 2777451.938 |
| 1647 | 113+330  | 529086.788 | 2777460.088 |
| 1648 | 113+340  | 529077.954 | 2777464.548 |
| 1649 | 113+350  | 529068.079 | 2777466.124 |
| 1650 | 113+360  | 529058.198 | 2777467.661 |
| 1651 | 113+370  | 529048.317 | 2777469.198 |
| 1652 | 113+380  | 529038.436 | 2777470.734 |
| 1653 | 113+390  | 529028.554 | 2777472.271 |
| 1654 | 113+400  | 529018.629 | 2777472.513 |
| 1655 | 113+410  | 529009.745 | 2777468.152 |
| 1656 | 113+420  | 529004.038 | 2777460.067 |
| 1657 | 113+430  | 529000.366 | 2777450.766 |
| 1658 | 113+440  | 528995.007 | 2777442.439 |
| 1659 | 113+450  | 528986.332 | 2777437.676 |
| 1660 | 113+460  | 528976.473 | 2777436.018 |





| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 1661 | 113+470  | 528966.597 | 2777434.449 |
| 1662 | 113+480  | 528956.914 | 2777432.073 |
| 1663 | 113+490  | 528948.479 | 2777426.789 |
| 1664 | 113+500  | 528941.126 | 2777420.011 |
| 1665 | 113+510  | 528933.778 | 2777413.229 |
| 1666 | 113+520  | 528926.429 | 2777406.447 |
| 1667 | 113+530  | 528918.224 | 2777400.872 |
| 1668 | 113+540  | 528908.387 | 2777399.787 |
| 1669 | 113+550  | 528899.235 | 2777403.551 |
| 1670 | 113+560  | 528893.007 | 2777411.242 |
| 1671 | 113+570  | 528891.229 | 2777420.977 |
| 1672 | 113+580  | 528894.336 | 2777430.373 |
| 1673 | 113+590  | 528900.753 | 2777438.031 |
| 1674 | 113+600  | 528907.154 | 2777445.701 |
| 1675 | 113+610  | 528910.204 | 2777455.115 |
| 1676 | 113+620  | 528908.367 | 2777464.84  |
| 1677 | 113+630  | 528902.093 | 2777472.492 |
| 1678 | 113+640  | 528893.004 | 2777476.528 |
| 1679 | 113+650  | 528883.505 | 2777479.656 |
| 1680 | 113+660  | 528874.475 | 2777483.855 |
| 1681 | 113+670  | 528867.289 | 2777490.744 |
| 1682 | 113+680  | 528862.753 | 2777499.604 |
| 1683 | 113+690  | 528861.366 | 2777509.46  |
| 1684 | 113+700  | 528863.28  | 2777519.228 |
| 1685 | 113+710  | 528868.28  | 2777527.837 |
| 1686 | 113+720  | 528874.511 | 2777535.657 |
| 1687 | 113+730  | 528880.743 | 2777543.478 |
| 1688 | 113+740  | 528886.975 | 2777551.299 |
| 1689 | 113+750  | 528893.206 | 2777559.12  |
| 1690 | 113+760  | 528899.458 | 2777566.925 |
| 1691 | 113+770  | 528905.918 | 2777574.558 |
| 1692 | 113+780  | 528912.629 | 2777581.971 |
| 1693 | 113+790  | 528919.583 | 2777589.156 |
| 1694 | 113+800  | 528926.773 | 2777596.106 |
| 1695 | 113+810  | 528934.132 | 2777602.876 |
| 1696 | 113+820  | 528941.5   | 2777609.638 |
| 1697 | 113+830  | 528948.868 | 2777616.399 |
| 1698 | 113+840  | 528956.236 | 2777623.16  |
| 1699 | 113+850  | 528963.603 | 2777629.922 |
| 1700 | 113+860  | 528969.662 | 2777637.819 |
| 1701 | 113+870  | 528972.803 | 2777647.265 |
| 1702 | 113+880  | 528972.68  | 2777657.218 |
| 1703 | 113+890  | 528969.308 | 2777666.583 |
| 1704 | 113+900  | 528963.058 | 2777674.329 |

| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 1705 | 113+910  | 528954.616 | 2777679.604 |
| 1706 | 113+920  | 528944.914 | 2777681.826 |
| 1707 | 113+930  | 528935.018 | 2777680.752 |
| 1708 | 113+940  | 528926.013 | 2777676.507 |
| 1709 | 113+950  | 528917.657 | 2777671.014 |
| 1710 | 113+960  | 528909.301 | 2777665.52  |
| 1711 | 113+970  | 528900.906 | 2777660.09  |
| 1712 | 113+980  | 528891.535 | 2777656.732 |
| 1713 | 113+990  | 528881.57  | 2777656.494 |
| 1714 | 114+000  | 528871.589 | 2777657.113 |
| 1715 | 114+010  | 528861.605 | 2777657.369 |
| 1716 | 114+020  | 528851.987 | 2777654.805 |
| 1717 | 114+030  | 528843.328 | 2777649.814 |
| 1718 | 114+040  | 528834.767 | 2777644.645 |
| 1719 | 114+050  | 528826.206 | 2777639.477 |
| 1720 | 114+060  | 528817.645 | 2777634.309 |
| 1721 | 114+070  | 528809.084 | 2777629.141 |
| 1722 | 114+080  | 528800.523 | 2777623.972 |
| 1723 | 114+090  | 528791.963 | 2777618.804 |
| 1724 | 114+100  | 528783.176 | 2777614.066 |
| 1725 | 114+110  | 528773.413 | 2777612.124 |
| 1726 | 114+120  | 528763.553 | 2777613.483 |
| 1727 | 114+130  | 528754.68  | 2777617.994 |
| 1728 | 114+140  | 528747.757 | 2777625.149 |
| 1729 | 114+150  | 528741.829 | 2777633.203 |
| 1730 | 114+160  | 528735.902 | 2777641.257 |
| 1731 | 114+170  | 528729.513 | 2777648.933 |
| 1732 | 114+180  | 528721.762 | 2777655.225 |
| 1733 | 114+190  | 528712.916 | 2777659.852 |
| 1734 | 114+200  | 528703.484 | 2777663.173 |
| 1735 | 114+210  | 528694.032 | 2777666.437 |
| 1736 | 114+220  | 528684.579 | 2777669.701 |
| 1737 | 114+230  | 528675.127 | 2777672.965 |
| 1738 | 114+240  | 528665.675 | 2777676.229 |
| 1739 | 114+250  | 528656.046 | 2777678.777 |
| 1740 | 114+260  | 528646.326 | 2777676.914 |
| 1741 | 114+270  | 528638.69  | 2777670.62  |
| 1742 | 114+280  | 528635.005 | 2777661.436 |
| 1743 | 114+290  | 528635.882 | 2777651.533 |
| 1744 | 114+300  | 528637.812 | 2777641.721 |
| 1745 | 114+310  | 528639.662 | 2777631.896 |
| 1746 | 114+320  | 528638.224 | 2777622.105 |
| 1747 | 114+330  | 528632.267 | 2777614.202 |
| 1748 | 114+340  | 528623.251 | 2777610.122 |





| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 1749 | 114+350  | 528613.321 | 2777610.573 |
| 1750 | 114+360  | 528603.437 | 2777612.093 |
| 1751 | 114+370  | 528593.553 | 2777613.612 |
| 1752 | 114+380  | 528583.669 | 2777615.132 |
| 1753 | 114+390  | 528573.785 | 2777616.651 |
| 1754 | 114+400  | 528563.901 | 2777618.17  |
| 1755 | 114+410  | 528554.122 | 2777620.202 |
| 1756 | 114+420  | 528544.916 | 2777624.065 |
| 1757 | 114+430  | 528536.661 | 2777629.679 |
| 1758 | 114+440  | 528529.685 | 2777636.821 |
| 1759 | 114+450  | 528524.268 | 2777645.207 |
| 1760 | 114+460  | 528520.624 | 2777654.501 |
| 1761 | 114+470  | 528518.9   | 2777664.335 |
| 1762 | 114+480  | 528519.164 | 2777674.315 |
| 1763 | 114+490  | 528521.216 | 2777684.095 |
| 1764 | 114+500  | 528523.57  | 2777693.814 |
| 1765 | 114+510  | 528525.925 | 2777703.533 |
| 1766 | 114+520  | 528527.328 | 2777713.417 |
| 1767 | 114+530  | 528526.74  | 2777723.383 |
| 1768 | 114+540  | 528524.184 | 2777733.033 |
| 1769 | 114+550  | 528519.882 | 2777742.051 |
| 1770 | 114+560  | 528515.224 | 2777750.9   |
| 1771 | 114+570  | 528510.566 | 2777759.749 |
| 1772 | 114+580  | 528504.871 | 2777767.884 |
| 1773 | 114+590  | 528496.096 | 2777772.46  |
| 1774 | 114+600  | 528486.202 | 2777772.269 |
| 1775 | 114+610  | 528477.61  | 2777767.358 |
| 1776 | 114+620  | 528471.323 | 2777759.592 |
| 1777 | 114+630  | 528465.185 | 2777751.697 |
| 1778 | 114+640  | 528459.048 | 2777743.802 |
| 1779 | 114+650  | 528452.562 | 2777736.22  |
| 1780 | 114+660  | 528443.623 | 2777731.975 |
| 1781 | 114+670  | 528433.742 | 2777732.535 |
| 1782 | 114+680  | 528425.34  | 2777737.764 |
| 1783 | 114+690  | 528420.157 | 2777746.251 |
| 1784 | 114+700  | 528415.763 | 2777755.232 |
| 1785 | 114+710  | 528408.821 | 2777762.286 |
| 1786 | 114+720  | 528399.348 | 2777765.148 |
| 1787 | 114+730  | 528389.385 | 2777764.611 |
| 1788 | 114+740  | 528380.042 | 2777767.874 |
| 1789 | 114+750  | 528373.407 | 2777775.216 |
| 1790 | 114+760  | 528371.104 | 2777784.84  |
| 1791 | 114+770  | 528373.368 | 2777794.526 |
| 1792 | 114+780  | 528376.576 | 2777803.997 |

| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 1793 | 114+790  | 528379.784 | 2777813.469 |
| 1794 | 114+800  | 528382.992 | 2777822.94  |
| 1795 | 114+810  | 528386.199 | 2777832.412 |
| 1796 | 114+820  | 528389.407 | 2777841.884 |
| 1797 | 114+830  | 528392.615 | 2777851.355 |
| 1798 | 114+840  | 528395.822 | 2777860.827 |
| 1799 | 114+850  | 528399.03  | 2777870.298 |
| 1800 | 114+860  | 528402.238 | 2777879.77  |
| 1801 | 114+870  | 528405.445 | 2777889.241 |
| 1802 | 114+880  | 528408.653 | 2777898.713 |
| 1803 | 114+890  | 528411.861 | 2777908.184 |
| 1804 | 114+900  | 528415.069 | 2777917.656 |
| 1805 | 114+910  | 528418.276 | 2777927.128 |
| 1806 | 114+920  | 528421.484 | 2777936.599 |
| 1807 | 114+930  | 528424.691 | 2777946.071 |
| 1808 | 114+940  | 528427.778 | 2777955.582 |
| 1809 | 114+950  | 528430.31  | 2777965.253 |
| 1810 | 114+960  | 528431.913 | 2777975.12  |
| 1811 | 114+970  | 528432.523 | 2777985.097 |
| 1812 | 114+980  | 528432.134 | 2777995.085 |
| 1813 | 114+990  | 528430.753 | 2778004.985 |
| 1814 | 115+000  | 528428.566 | 2778014.742 |
| 1815 | 115+010  | 528426.04  | 2778024.417 |
| 1816 | 115+020  | 528423.487 | 2778034.086 |
| 1817 | 115+030  | 528420.934 | 2778043.755 |
| 1818 | 115+040  | 528418.382 | 2778053.424 |
| 1819 | 115+050  | 528415.829 | 2778063.092 |
| 1820 | 115+060  | 528413.277 | 2778072.761 |
| 1821 | 115+070  | 528410.734 | 2778082.432 |
| 1822 | 115+080  | 528408.646 | 2778092.208 |
| 1823 | 115+090  | 528408.078 | 2778102.173 |
| 1824 | 115+100  | 528410.12  | 2778111.92  |
| 1825 | 115+110  | 528415.199 | 2778120.481 |
| 1826 | 115+120  | 528422.771 | 2778126.951 |
| 1827 | 115+130  | 528431.77  | 2778131.27  |
| 1828 | 115+140  | 528441.326 | 2778134.205 |
| 1829 | 115+150  | 528451.004 | 2778136.723 |
| 1830 | 115+160  | 528460.683 | 2778139.234 |
| 1831 | 115+170  | 528470.363 | 2778141.745 |
| 1832 | 115+180  | 528479.983 | 2778144.46  |
| 1833 | 115+190  | 528488.989 | 2778148.767 |
| 1834 | 115+200  | 528496.96  | 2778154.778 |
| 1835 | 115+210  | 528503.578 | 2778162.253 |
| 1836 | 115+220  | 528508.67  | 2778170.847 |





| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 1837 | 115+230  | 528513.363 | 2778179.678 |
| 1838 | 115+240  | 528518.055 | 2778188.509 |
| 1839 | 115+250  | 528522.786 | 2778197.319 |
| 1840 | 115+260  | 528527.773 | 2778205.986 |
| 1841 | 115+270  | 528533.046 | 2778214.482 |
| 1842 | 115+280  | 528538.599 | 2778222.798 |
| 1843 | 115+290  | 528544.426 | 2778230.924 |
| 1844 | 115+300  | 528550.521 | 2778238.851 |
| 1845 | 115+310  | 528556.877 | 2778246.571 |
| 1846 | 115+320  | 528563.398 | 2778254.153 |
| 1847 | 115+330  | 528569.921 | 2778261.732 |
| 1848 | 115+340  | 528576.445 | 2778269.311 |
| 1849 | 115+350  | 528582.969 | 2778276.89  |
| 1850 | 115+360  | 528589.344 | 2778284.585 |
| 1851 | 115+370  | 528592.49  | 2778293.968 |
| 1852 | 115+380  | 528590.751 | 2778303.71  |
| 1853 | 115+390  | 528585.664 | 2778312.314 |
| 1854 | 115+400  | 528582.412 | 2778321.664 |
| 1855 | 115+410  | 528584.027 | 2778331.427 |
| 1856 | 115+420  | 528590.126 | 2778339.221 |
| 1857 | 115+430  | 528599.196 | 2778343.218 |
| 1858 | 115+440  | 528608.89  | 2778345.672 |
| 1859 | 115+450  | 528618.585 | 2778348.125 |
| 1860 | 115+460  | 528628.279 | 2778350.578 |
| 1861 | 115+470  | 528637.421 | 2778354.427 |
| 1862 | 115+480  | 528643.68  | 2778362.092 |
| 1863 | 115+490  | 528645.498 | 2778371.82  |
| 1864 | 115+500  | 528642.43  | 2778381.228 |
| 1865 | 115+510  | 528635.689 | 2778388.579 |
| 1866 | 115+520  | 528628.72  | 2778395.744 |
| 1867 | 115+530  | 528623.097 | 2778403.993 |
| 1868 | 115+540  | 528619.224 | 2778413.195 |
| 1869 | 115+550  | 528617.257 | 2778422.983 |
| 1870 | 115+560  | 528617.274 | 2778432.966 |
| 1871 | 115+570  | 528619.274 | 2778442.747 |
| 1872 | 115+580  | 528623.177 | 2778451.936 |
| 1873 | 115+590  | 528628.767 | 2778460.213 |
| 1874 | 115+600  | 528634.788 | 2778468.197 |
| 1875 | 115+610  | 528640.81  | 2778476.181 |
| 1876 | 115+620  | 528646.831 | 2778484.165 |
| 1877 | 115+630  | 528652.852 | 2778492.149 |
| 1878 | 115+640  | 528658.874 | 2778500.133 |
| 1879 | 115+650  | 528665.273 | 2778507.794 |
| 1880 | 115+660  | 528673.622 | 2778513.214 |


| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 1881 | 115+670  | 528683.285 | 2778515.604 |
| 1882 | 115+680  | 528693.197 | 2778514.701 |
| 1883 | 115+690  | 528702.269 | 2778510.604 |
| 1884 | 115+700  | 528710.597 | 2778505.068 |
| 1885 | 115+710  | 528718.925 | 2778499.533 |
| 1886 | 115+720  | 528727.253 | 2778493.997 |
| 1887 | 115+730  | 528735.581 | 2778488.462 |
| 1888 | 115+740  | 528743.657 | 2778482.574 |
| 1889 | 115+750  | 528750.894 | 2778475.683 |
| 1890 | 115+760  | 528757.15  | 2778467.892 |
| 1891 | 115+770  | 528762.32  | 2778459.34  |
| 1892 | 115+780  | 528767.002 | 2778450.504 |
| 1893 | 115+790  | 528771.895 | 2778441.791 |
| 1894 | 115+800  | 528778.904 | 2778434.723 |
| 1895 | 115+810  | 528787.84  | 2778430.339 |
| 1896 | 115+820  | 528797.718 | 2778429.119 |
| 1897 | 115+830  | 528807.453 | 2778431.198 |
| 1898 | 115+840  | 528815.97  | 2778436.348 |
| 1899 | 115+850  | 528823.161 | 2778443.296 |
| 1900 | 115+860  | 528830.309 | 2778450.289 |
| 1901 | 115+870  | 528837.458 | 2778457.282 |
| 1902 | 115+880  | 528844.607 | 2778464.274 |
| 1903 | 115+890  | 528852.207 | 2778470.751 |
| 1904 | 115+900  | 528860.926 | 2778475.613 |
| 1905 | 115+910  | 528870.341 | 2778478.973 |
| 1906 | 115+920  | 528879.817 | 2778482.17  |
| 1907 | 115+930  | 528889.158 | 2778485.715 |
| 1908 | 115+940  | 528897.681 | 2778490.914 |
| 1909 | 115+950  | 528905.002 | 2778497.702 |
| 1910 | 115+960  | 528910.828 | 2778505.809 |
| 1911 | 115+970  | 528914.93  | 2778514.911 |
| 1912 | 115+980  | 528918.218 | 2778524.355 |
| 1913 | 115+990  | 528921.505 | 2778533.799 |
| 1914 | 116+000  | 528924.793 | 2778543.243 |
| 1915 | 116+010  | 528928.08  | 2778552.688 |
| 1916 | 116+020  | 528931.368 | 2778562.132 |
| 1917 | 116+030  | 528934.656 | 2778571.576 |
| 1918 | 116+040  | 528937.943 | 2778581.02  |
| 1919 | 116+050  | 528941.231 | 2778590.464 |
| 1920 | 116+060  | 528944.518 | 2778599.908 |
| 1921 | 116+070  | 528947.644 | 2778609.404 |
| 1922 | 116+080  | 528949.161 | 2778619.271 |
| 1923 | 116+090  | 528948.687 | 2778629.243 |
| 1924 | 116+100  | 528946.266 | 2778638.931 |





| S.N.ChainageNorthingEasting1925116+110528943.1692778648.4391926116+120528940.6882778658.1021927116+130528941.2612778668.041928116+140528945.0532778677.2421929116+150528951.6492778684.6981930116+160528960.2182778694.371931116+170528969.1162778694.371932116+180528977.4432778699.8761933116+190528984.5112778706.9271934116+200528990.0382778715.2411935116+210528993.8022778724.4881936116+220528996.0872778734.2211937116+230528998.2622778743.9821938116+240529000.4372778753.7421939116+250529002.6122778763.5031940116+260529004.792778773.2631941116+270529007.3182778782.9351942116+280529011.1622778792.1491943116+290529017.1572778800.1051944116+300529025.3762778805.721945116+310529034.982778808.3361946116+320529044.9112778807.6671947116+330529054.0782778803.788   |      | i i      |            |             |
|---|------|----------|------------|-------------|
| 1926         116+120         528940.688         2778658.102           1927         116+130         528941.261         2778668.04           1928         116+140         528945.053         2778677.242           1929         116+150         528951.649         2778684.698           1930         116+160         528960.218         2778689.805           1931         116+170         528969.116         2778699.876           1932         116+180         528977.443         2778699.876           1933         116+190         528984.511         2778706.927           1934         116+200         528990.038         2778715.241           1935         116+210         528993.802         2778724.488           1936         116+220         528996.087         2778734.221           1937         116+230         528998.262         2778743.982           1938         116+240         529002.612         2778763.503           1940         116+260         529002.612         2778763.503           1941         116+270         529007.318         2778782.149           1943         116+290         529017.157         2778800.105           1944         116+300         529025.37   | S.N. | Chainage | Northing   | Easting     |
| 1927         116+130         528941.261         2778668.04           1928         116+140         528945.053         2778677.242           1929         116+150         528951.649         2778684.698           1930         116+160         528960.218         2778689.805           1931         116+170         528969.116         2778694.37           1932         116+180         528977.443         2778699.876           1933         116+190         528984.511         2778706.927           1934         116+200         528990.038         2778715.241           1935         116+210         528993.802         2778724.488           1936         116+220         528996.087         2778734.221           1937         116+230         528998.262         2778743.982           1938         116+240         529000.437         2778753.742           1939         116+250         529002.612         2778763.503           1940         116+260         529007.318         2778782.935           1941         116+270         529007.318         2778792.149           1943         116+290         529017.157         2778800.105           1944         116+300         529025.376   | 1925 | 116+110  | 528943.169 | 2778648.439 |
| 1928         116+140         528945.053         2778677.242           1929         116+150         528951.649         2778684.698           1930         116+160         528960.218         2778689.805           1931         116+170         528969.116         2778694.37           1932         116+180         528977.443         2778699.876           1933         116+190         528984.511         2778706.927           1934         116+200         528990.038         2778715.241           1935         116+210         528993.802         2778724.488           1936         116+220         528996.087         2778734.221           1937         116+230         528998.262         2778743.982           1938         116+240         529000.437         2778753.742           1939         116+250         529002.612         2778763.503           1940         116+260         529004.79         2778773.263           1941         116+270         529007.318         2778792.149           1943         116+290         529017.157         2778805.72           1945         116+310         529034.98         2778805.72           1945         116+320         529044.911 <td>1926</td> <td>116+120</td> <td>528940.688</td> <td>2778658.102</td>      | 1926 | 116+120  | 528940.688 | 2778658.102 |
| 1929         116+150         528951.649         2778684.698           1930         116+160         528960.218         2778689.805           1931         116+170         528969.116         2778694.37           1932         116+180         528977.443         2778699.876           1933         116+190         528984.511         2778706.927           1934         116+200         528990.038         2778715.241           1935         116+210         528993.802         2778724.488           1936         116+220         528996.087         2778734.221           1937         116+230         528998.262         2778743.982           1938         116+240         529000.437         2778753.742           1939         116+250         529002.612         2778763.503           1940         116+260         529004.79         2778773.263           1941         116+270         529007.318         2778782.935           1942         116+280         529011.162         2778792.149           1943         116+290         529017.157         2778805.72           1945         116+310         529034.98         2778808.336           1946         116+320         529044.911 </td <td>1927</td> <td>116+130</td> <td>528941.261</td> <td>2778668.04</td> | 1927 | 116+130  | 528941.261 | 2778668.04  |
| 1930         116+160         528960.218         2778689.805           1931         116+170         528969.116         2778694.37           1932         116+180         528977.443         2778699.876           1933         116+190         528984.511         2778706.927           1934         116+200         528990.038         2778715.241           1935         116+210         528993.802         2778724.488           1936         116+220         528996.087         2778734.221           1937         116+230         528998.262         2778743.982           1938         116+240         529000.437         2778753.742           1939         116+250         529002.612         2778763.503           1940         116+260         529004.79         2778773.263           1941         116+270         529007.318         2778782.935           1942         116+280         529011.162         2778792.149           1943         116+290         529017.157         2778805.72           1945         116+310         529034.98         2778808.336           1946         116+320         529044.911         2778807.667   | 1928 | 116+140  | 528945.053 | 2778677.242 |
| 1931         116+170         528969.116         2778694.37           1932         116+180         528977.443         2778699.876           1933         116+190         528984.511         2778706.927           1934         116+200         528990.038         2778715.241           1935         116+210         528993.802         2778724.488           1936         116+220         528996.087         2778734.221           1937         116+230         528998.262         2778743.982           1938         116+240         529000.437         2778753.742           1939         116+250         529002.612         2778763.503           1940         116+260         529004.79         2778773.263           1941         116+270         529007.318         2778782.935           1942         116+280         529011.162         2778792.149           1943         116+290         529017.157         2778800.105           1944         116+300         529025.376         2778805.72           1945         116+310         529034.98         2778807.667   | 1929 | 116+150  | 528951.649 | 2778684.698 |
| 1932         116+180         528977.443         2778699.876           1933         116+190         528984.511         2778706.927           1934         116+200         528990.038         2778715.241           1935         116+210         528993.802         2778724.488           1936         116+220         528996.087         2778734.221           1937         116+230         528998.262         2778743.982           1938         116+240         529000.437         2778753.742           1939         116+250         529002.612         2778763.503           1940         116+260         529004.79         2778773.263           1941         116+270         529007.318         2778782.935           1942         116+280         529011.162         2778792.149           1943         116+290         529017.157         2778800.105           1944         116+300         529025.376         2778805.72           1945         116+310         529034.98         2778808.336           1946         116+320         529044.911         2778807.667  | 1930 | 116+160  | 528960.218 | 2778689.805 |
| 1933         116+190         528984.511         2778706.927           1934         116+200         528990.038         2778715.241           1935         116+210         528993.802         2778724.488           1936         116+220         528996.087         2778734.221           1937         116+230         528998.262         2778743.982           1938         116+240         529000.437         2778753.742           1939         116+250         529002.612         2778763.503           1940         116+260         529004.79         2778773.263           1941         116+270         529007.318         2778782.935           1942         116+280         529011.162         2778792.149           1943         116+290         529017.157         2778800.105           1944         116+300         529025.376         2778805.72           1945         116+310         529034.98         2778808.336           1946         116+320         529044.911         2778807.667  | 1931 | 116+170  | 528969.116 | 2778694.37  |
| 1934         116+200         528990.038         2778715.241           1935         116+210         528993.802         2778724.488           1936         116+220         528996.087         2778734.221           1937         116+230         528998.262         2778743.982           1938         116+240         529000.437         2778753.742           1939         116+250         529002.612         2778763.503           1940         116+260         529004.79         2778773.263           1941         116+270         529007.318         2778782.935           1942         116+280         529011.162         2778792.149           1943         116+290         529017.157         2778800.105           1944         116+300         529025.376         2778805.72           1945         116+310         529034.98         2778808.336           1946         116+320         529044.911         2778807.667  | 1932 | 116+180  | 528977.443 | 2778699.876 |
| 1935         116+210         528993.802         2778724.488           1936         116+220         528996.087         2778734.221           1937         116+230         528998.262         2778743.982           1938         116+240         529000.437         2778753.742           1939         116+250         529002.612         2778763.503           1940         116+260         529004.79         2778773.263           1941         116+270         529007.318         2778782.935           1942         116+280         529011.162         2778792.149           1943         116+290         529017.157         2778800.105           1944         116+300         529025.376         2778805.72           1945         116+310         529034.98         2778808.336           1946         116+320         529044.911         2778807.667  | 1933 | 116+190  | 528984.511 | 2778706.927 |
| 1936         116+220         528996.087         2778734.221           1937         116+230         528998.262         2778743.982           1938         116+240         529000.437         2778753.742           1939         116+250         529002.612         2778763.503           1940         116+260         529004.79         2778773.263           1941         116+270         529007.318         2778782.935           1942         116+280         529011.162         2778792.149           1943         116+290         529017.157         2778800.105           1944         116+300         529025.376         2778805.72           1945         116+310         529034.98         2778808.336           1946         116+320         529044.911         2778807.667  | 1934 | 116+200  | 528990.038 | 2778715.241 |
| 1937         116+230         528998.262         2778743.982           1938         116+240         529000.437         2778753.742           1939         116+250         529002.612         2778763.503           1940         116+260         529004.79         2778773.263           1941         116+270         529007.318         2778782.935           1942         116+280         529011.162         2778792.149           1943         116+290         529017.157         2778800.105           1944         116+300         529025.376         2778805.72           1945         116+310         529034.98         2778808.336           1946         116+320         529044.911         2778807.667  | 1935 | 116+210  | 528993.802 | 2778724.488 |
| 1938         116+240         529000.437         2778753.742           1939         116+250         529002.612         2778763.503           1940         116+260         529004.79         2778773.263           1941         116+270         529007.318         2778782.935           1942         116+280         529011.162         2778792.149           1943         116+290         529017.157         2778800.105           1944         116+300         529025.376         2778805.72           1945         116+310         529034.98         2778808.336           1946         116+320         529044.911         2778807.667  | 1936 | 116+220  | 528996.087 | 2778734.221 |
| 1939         116+250         529002.612         2778763.503           1940         116+260         529004.79         2778773.263           1941         116+270         529007.318         2778782.935           1942         116+280         529011.162         2778792.149           1943         116+290         529017.157         2778800.105           1944         116+300         529025.376         2778805.72           1945         116+310         529034.98         2778808.336           1946         116+320         529044.911         2778807.667  | 1937 | 116+230  | 528998.262 | 2778743.982 |
| 1940         116+260         529004.79         2778773.263           1941         116+270         529007.318         2778782.935           1942         116+280         529011.162         2778792.149           1943         116+290         529017.157         2778800.105           1944         116+300         529025.376         2778805.72           1945         116+310         529034.98         2778808.336           1946         116+320         529044.911         2778807.667  | 1938 | 116+240  | 529000.437 | 2778753.742 |
| 1941     116+270     529007.318     2778782.935       1942     116+280     529011.162     2778792.149       1943     116+290     529017.157     2778800.105       1944     116+300     529025.376     2778805.72       1945     116+310     529034.98     2778808.336       1946     116+320     529044.911     2778807.667   | 1939 | 116+250  | 529002.612 | 2778763.503 |
| 1942     116+280     529011.162     2778792.149       1943     116+290     529017.157     2778800.105       1944     116+300     529025.376     2778805.72       1945     116+310     529034.98     2778808.336       1946     116+320     529044.911     2778807.667   | 1940 | 116+260  | 529004.79  | 2778773.263 |
| 1943     116+290     529017.157     2778800.105       1944     116+300     529025.376     2778805.72       1945     116+310     529034.98     2778808.336       1946     116+320     529044.911     2778807.667   | 1941 | 116+270  | 529007.318 | 2778782.935 |
| 1944     116+300     529025.376     2778805.72       1945     116+310     529034.98     2778808.336       1946     116+320     529044.911     2778807.667   | 1942 | 116+280  | 529011.162 | 2778792.149 |
| 1945     116+310     529034.98     2778808.336       1946     116+320     529044.911     2778807.667  | 1943 | 116+290  | 529017.157 | 2778800.105 |
| 1946 116+320 529044.911 2778807.667   | 1944 | 116+300  | 529025.376 | 2778805.72  |
|   | 1945 | 116+310  | 529034.98  | 2778808.336 |
| 1947         116+330         529054.078         2778803.788   | 1946 | 116+320  | 529044.911 | 2778807.667 |
|   | 1947 | 116+330  | 529054.078 | 2778803.788 |

| S.N. | Chainage | Northing   | Easting     |
|------|----------|------------|-------------|
| 1948 | 116+340  | 529061.735 | 2778797.395 |
| 1949 | 116+350  | 529068.048 | 2778789.649 |
| 1950 | 116+360  | 529073.721 | 2778781.415 |
| 1951 | 116+370  | 529079.337 | 2778773.141 |
| 1952 | 116+380  | 529084.969 | 2778764.878 |
| 1953 | 116+390  | 529091.044 | 2778756.941 |
| 1954 | 116+400  | 529098.318 | 2778750.108 |
| 1955 | 116+410  | 529107.142 | 2778745.495 |
| 1956 | 116+420  | 529116.982 | 2778743.997 |
| 1957 | 116+430  | 529126.771 | 2778745.801 |
| 1958 | 116+440  | 529135.458 | 2778750.672 |
| 1959 | 116+450  | 529142.596 | 2778757.648 |
| 1960 | 116+460  | 529148.6   | 2778765.641 |
| 1961 | 116+470  | 529154.207 | 2778773.921 |
| 1962 | 116+480  | 529159.576 | 2778782.356 |
| 1963 | 116+490  | 529164.662 | 2778790.966 |
| 1964 | 116+500  | 529169.457 | 2778799.741 |
| 1965 | 116+510  | 529173.958 | 2778808.67  |
| 1966 | 116+520  | 529178.158 | 2778817.745 |
| 1967 | 116+530  | 529182.054 | 2778826.954 |
| 1968 | 116+540  | 529185.767 | 2778836.24  |
| 1969 | 116+550  | 529189.478 | 2778845.525 |







**Technical Schedule** 

#### Schedule-B

(SeeClause2.1)

# Development of the Project Highway

# 1. Development of the Project Highway

Development of the Project Highway shall include design and construction of the Project Highway as described in this Schedule-B and in Schedule-C.

# 2. [Rehabilitation and augmentation]

[Rehabilitation and augmentation] shall include [Two-Laning and Strengthening] of the Project Highway as described in Annex-I of this Schedule-B and in Schedule-C.

# 3. Specifications and Standards

The Project Highway shall be designed and constructed in conformity with the Specifications and Standards specified in Annex-I of Schedule-D.





**Technical Schedule** 

#### Annex- I

(Schedule-B)

# Description of [Two-Laning]

[Note: Description of the Project Highway shall be given by the Authority in detail together with explanatory drawings (where necessary) to explain the Authority's requirements precisely in order to avoid subsequent changes in the Scope of the Project. The particulars that must be specified in this Schedule-B are listed below as per the requirements of the Manual of Specifications and Standards for [Two Laning of Highways (IRC: SP:73-2018)], referred to as the Manual. If any standards, specifications or details are not given in the Manual, the minimum design/construction requirements shall be specified in this Schedule. In addition to these particulars, all other essential project specific details, as required, should be provided in order to define the Scope of the Project clearly and precisely.]

# 1. Widening of the Existing Highway

(i) The Project Highway shall follow the existing alignment unless otherwise specified by the Authority and shown in the alignment plans specified in Annex-III of Schedule-A. Geometric deficiencies, if any, in the existing horizontal and vertical profiles shall be corrected as per the prescribed standards for [plain/rolling] terrain to the extent land is available.

## (ii) Width of Carriageway

a) Two Lane Road with Paved shoulders in Hilly Terrain with Hill side drain & without Retaining Wall: - The Carriageway shall be 7.0 m wide with 1.5 m paved shoulder both side and 1.0 m earthen shoulder valley side shall be provided. The width of carriageway specified following table-

| S. No. | Built-up<br>stretch<br>(Township) | Design Chainage |        | Width (m)        | Length<br>(km) | Typical<br>cross<br>section<br>(Ref. to<br>Manual) |
|--------|-----------------------------------|-----------------|--------|------------------|----------------|--|
| 1.     | -                                 | 97500           | 97700  | 7+1.5x2+1x1=11 m | 0.200          | 2.9  |
| 2.     | -                                 | 97900           | 98000  | 7+1.5x2+1x1=11 m | 0.100          | 2.9  |
| 3.     | -                                 | 99000           | 99100  | 7+1.5x2+1x1=11 m | 0.100          | 2.9  |
| 4.     | -                                 | 99200           | 99300  | 7+1.5x2+1x1=11 m | 0.100          | 2.9  |
| 5.     | -                                 | 99700           | 99800  | 7+1.5x2+1x1=11 m | 0.100          | 2.9  |
| 6.     | -                                 | 101300          | 101400 | 7+1.5x2+1x1=11 m | 0.100          | 2.9  |
| 7.     | -                                 | 101700          | 101900 | 7+1.5x2+1x1=11 m | 0.200          | 2.9  |





**Technical Schedule** 

| S. No. | Built-up<br>stretch<br>(Township) | Design ( | Chainage | Width (m)        | Length<br>(km) | Typical<br>cross<br>section<br>(Ref. to<br>Manual) |
|--------|-----------------------------------|----------|----------|------------------|----------------|--|
| 8.     | -                                 | 102100   | 102200   | 7+1.5x2+1x1=11 m | 0.100          | 2.9  |
| 9.     | -                                 | 103700   | 103900   | 7+1.5x2+1x1=11 m | 0.200          | 2.9  |
| 10.    | -                                 | 104000   | 104500   | 7+1.5x2+1x1=11 m | 0.500          | 2.9  |
| 11.    | -                                 | 104900   | 105100   | 7+1.5x2+1x1=11 m | 0.200          | 2.9  |
| 12.    | -                                 | 106000   | 106200   | 7+1.5x2+1x1=11 m | 0.200          | 2.9  |
| 13.    | -                                 | 106400   | 106600   | 7+1.5x2+1x1=11 m | 0.200          | 2.9  |
| 14.    | -                                 | 111700   | 113200   | 7+1.5x2+1x1=11 m | 1.500          | 2.9  |
| 15.    | -                                 | 114000   | 114100   | 7+1.5x2+1x1=11 m | 0.100          | 2.9  |
| 16.    | -                                 | 114150   | 114350   | 7+1.5x2+1x1=11 m | 0.200          | 2.9  |
| 17.    | -                                 | 114400   | 114650   | 7+1.5x2+1x1=11 m | 0.250          | 2.9  |
| 18.    | -                                 | 114800   | 115100   | 7+1.5x2+1x1=11 m | 0.300          | 2.9  |
| 19.    | -                                 | 115150   | 115350   | 7+1.5x2+1x1=11 m | 0.200          | 2.9  |
| 20.    | -                                 | 115750   | 116000   | 7+1.5x2+1x1=11 m | 0.250          | 2.9  |
| 21.    | -                                 | 116350   | 116550   | 7+1.5x2+1x1=11 m | 0.200          | 2.9  |
|        |                                   |          | Total    | Length           | 5.300 km       |  |

b) Two-Lane with paved shoulder in Hilly Terrain with Hill side Drain on Both sides in open Country area (Box cut): - The Carriageway shall be 7.0 m wide with 1.5 m. paved shoulder both sides shall be provided. The width of carriage way shall be specified in following table:

| S.No. | Built-up<br>stretch<br>(Township) | Design Chainage |        | Width (m)    | Length<br>(km) | Typical<br>cross<br>section<br>(Ref. to<br>Manual) |
|-------|-----------------------------------|-----------------|--------|--------------|----------------|--|
| 1.    | -                                 | 96870           | 97100  | 7+1.5x2=10 m | 0.230          | 2.11(new)  |
| 2.    | -                                 | 97300           | 97500  | 7+1.5x2=10 m | 0.200          | 2.11(new)  |
| 3.    | -                                 | 97800           | 97900  | 7+1.5x2=10 m | 0.100          | 2.11(new)  |
| 4.    | -                                 | 98100           | 98250  | 7+1.5x2=10 m | 0.150          | 2.11(new)  |
| 5.    | -                                 | 98500           | 98650  | 7+1.5x2=10 m | 0.150          | 2.11(new)  |
| 6.    | -                                 | 98750           | 98900  | 7+1.5x2=10 m | 0.150          | 2.11(new)  |
| 7.    | -                                 | 99100           | 99200  | 7+1.5x2=10 m | 0.100          | 2.11(new)  |
| 8.    | -                                 | 99300           | 99700  | 7+1.5x2=10 m | 0.400          | 2.11(new)  |
| 9.    | -                                 | 99800           | 100100 | 7+1.5x2=10 m | 0.300          | 2.11(new)  |
| 10.   | -                                 | 100200          | 100300 | 7+1.5x2=10 m | 0.100          | 2.11(new)  |
| 11.   | -                                 | 100800          | 101100 | 7+1.5x2=10 m | 0.300          | 2.11(new)  |





**Technical Schedule** 

| S.No. | Built-up<br>stretch<br>(Township) | Design Chainage |        | Width (m)    | Length<br>(km) | Typical<br>cross<br>section<br>(Ref. to<br>Manual) |
|-------|-----------------------------------|-----------------|--------|--------------|----------------|--|
| 12.   | -                                 | 102400          | 102600 | 7+1.5x2=10 m | 0.200          | 2.11(new)  |
| 13.   | -                                 | 102800          | 102950 | 7+1.5x2=10 m | 0.150          | 2.11(new)  |
| 14.   | -                                 | 103150          | 103500 | 7+1.5x2=10 m | 0.350          | 2.11(new)  |
| 15.   | -                                 | 103600          | 103700 | 7+1.5x2=10 m | 0.100          | 2.11(new)  |
| 16.   | -                                 | 103900          | 104000 | 7+1.5x2=10 m | 0.100          | 2.11(new)  |
| 17.   | -                                 | 104500          | 104900 | 7+1.5x2=10 m | 0.400          | 2.11(new)  |
| 18.   | -                                 | 105200          | 105500 | 7+1.5x2=10 m | 0.300          | 2.11(new)  |
| 19.   | -                                 | 105600          | 106000 | 7+1.5x2=10 m | 0.400          | 2.11(new)  |
| 20.   | -                                 | 109900          | 110300 | 7+1.5x2=10 m | 0.400          | 2.11(new)  |
| 21.   | -                                 | 113200          | 114000 | 7+1.5x2=10 m | 0.800          | 2.11(new)  |
|       |                                   |                 | Total  | Length       | 5.380km        |  |

c) Two Lane Road with Paved shoulders in Hilly Terrain with Hill side drain& Retaining Wall: - The Carriageway shall be 7.0 m wide with 1.5 m paved shoulder both side and 1.0 m earthen shoulder valley side shall be provided. The width of carriageway specified following table-

| S.No. | Built-up<br>stretch<br>(Township) | _      | Chainage | Width (m)        | Length<br>(km) | Typical<br>cross<br>section<br>(Ref. to<br>Manual) |
|-------|-----------------------------------|--------|----------|------------------|----------------|--|
| 1.    | -                                 | 97100  | 97300    | 7+1.5x2+1x1=11 m | 0.200          | 2.8  |
| 2.    | -                                 | 97700  | 97800    | 7+1.5x2+1x1=11 m | 0.100          | 2.8  |
| 3.    | -                                 | 98000  | 98100    | 7+1.5x2+1x1=11 m | 0.100          | 2.8  |
| 4.    | -                                 | 98250  | 98500    | 7+1.5x2+1x1=11 m | 0.250          | 2.8  |
| 5.    | -                                 | 98650  | 98750    | 7+1.5x2+1x1=11 m | 0.100          | 2.8  |
| 6.    | -                                 | 98900  | 99000    | 7+1.5x2+1x1=11 m | 0.100          | 2.8  |
| 7.    | -                                 | 100100 | 100200   | 7+1.5x2+1x1=11 m | 0.100          | 2.8  |
| 8.    | -                                 | 100300 | 100800   | 7+1.5x2+1x1=11 m | 0.500          | 2.8  |
| 9.    | -                                 | 101100 | 101300   | 7+1.5x2+1x1=11 m | 0.200          | 2.8  |
| 10.   | -                                 | 101400 | 101700   | 7+1.5x2+1x1=11 m | 0.300          | 2.8  |
| 11.   | -                                 | 101900 | 102100   | 7+1.5x2+1x1=11 m | 0.200          | 2.8  |
| 12.   | -                                 | 102200 | 102400   | 7+1.5x2+1x1=11 m | 0.200          | 2.8  |
| 13.   | -                                 | 102600 | 102800   | 7+1.5x2+1x1=11 m | 0.200          | 2.8  |
| 14.   | -                                 | 102950 | 103150   | 7+1.5x2+1x1=11 m | 0.200          | 2.8  |
| 15.   | -                                 | 103500 | 103600   | 7+1.5x2+1x1=11 m | 0.100          | 2.8  |
| 16.   | -                                 | 105100 | 105200   | 7+1.5x2+1x1=11 m | 0.100          | 2.8  |





**Technical Schedule** 

| S.No. | Built-up<br>stretch<br>(Township) | Design ( | Chainage | Width (m)        | Length<br>(km) | Typical<br>cross<br>section<br>(Ref. to<br>Manual) |
|-------|-----------------------------------|----------|----------|------------------|----------------|--|
| 17.   | -                                 | 105500   | 105600   | 7+1.5x2+1x1=11 m | 0.100          | 2.8  |
| 18.   | -                                 | 106200   | 106400   | 7+1.5x2+1x1=11 m | 0.200          | 2.8  |
| 19.   | -                                 | 106600   | 109900   | 7+1.5x2+1x1=11 m | 3.300          | 2.8  |
| 20.   | -                                 | 110300   | 111700   | 7+1.5x2+1x1=11 m | 1.400          | 2.8  |
| 21.   | -                                 | 114100   | 114150   | 7+1.5x2+1x1=11 m | 0.050          | 2.8  |
| 22.   | -                                 | 114350   | 114400   | 7+1.5x2+1x1=11 m | 0.050          | 2.8  |
| 23.   | -                                 | 114650   | 114800   | 7+1.5x2+1x1=11 m | 0.150          | 2.8  |
| 24.   | -                                 | 115100   | 115150   | 7+1.5x2+1x1=11 m | 0.050          | 2.8  |
| 25.   | -                                 | 115350   | 115750   | 7+1.5x2+1x1=11 m | 0.400          | 2.8  |
| 26.   | -                                 | 116000   | 116350   | 7+1.5x2+1x1=11 m | 0.350          | 2.8  |
|       |                                   |          | Tota     | l Length         | 9.000 km       |  |

- \$ The contents of this Annex-I may be modified in accordance with the structure of the Project.
  - d) Except as otherwise provided in this Agreement, the width of the paved carriageway and cross-sectional features shall conform to paragraph 1.1 above.

# 2. Geometric Design and General Features

## (i) General

Geometric design and general features of the Project Highway shall be in accordance with Section 2 of the Manual.

# (ii) Design speed

The design speed shall be the minimum design speed of [40 km per hr for Mountainous terrain] with some restrictions mentioned in Clause 2(iii).

#### (iii) Improvement of the existing road geometrics

[Refer to paragraph 2.1 (v) of the Manual and provide details]

In the following sections, where improvement of the existing road geometrics to the prescribed standards is not possible, the existing road geometrics shall be improved to the extent possible within the given right of way and proper road signs and safety measures shall be provided:

| S. No.         | Stre       | tch        | Radius (m)   | Speed(km/h)    |  |
|----------------|------------|------------|--------------|----------------|--|
| <i>5.</i> 110. | From To    |            | Radias (III) | Speed(Kill/II) |  |
| 1.             | 106704.838 | 106827.994 | 30           | 30             |  |





**Technical Schedule** 

| S. No. | Stre       | tch        | Radius (m) | Speed(km/h) |
|--------|------------|------------|------------|-------------|
| 2.     | 107289.488 | 107318.810 | 30         | 30          |
|        |            | 107386.096 | 30         | 30          |
| 4.     | 107466.887 | 107547.933 | 20         | 20          |
| 5.     | 108010.610 | 108092.474 | 20         | 20          |
| 6.     | 108702.551 | 108783.705 | 20         | 20          |
| 7.     | 108955.764 | 109034.032 | 20         | 20          |
| 8.     | 109559.204 | 109640.825 | 20         | 20          |
| 9.     | 110585.834 | 110666.358 | 20         | 20          |
| 10.    | 110957.204 | 111018.287 | 20         | 20          |
| 11.    | 113188.401 | 113238.316 | 20         | 20          |
| 12.    | 113296.460 | 113341.267 | 20         | 20          |
| 13.    | 113392.789 | 113419.771 | 20         | 20          |
| 14.    | 113431.146 | 113451.890 | 20         | 20          |
| 15.    | 113472.940 | 113490.571 | 30         | 30          |
| 16.    | 113522.291 | 113583.015 | 20         | 20          |
| 17.    | 113596.863 | 113636.319 | 20         | 20          |
| 18.    | 113651.615 | 113709.379 | 30         | 30          |
| 19.    | 113849.782 | 113939.204 | 30         | 30          |
| 20.    | 113967.874 | 113987.182 | 30         | 30          |
| 21.    | 114005.326 | 114023.480 | 30         | 30          |
| 22.    | 114094.597 | 114138.981 | 30         | 30          |
| 23.    | 114244.564 | 114286.514 | 20         | 20          |
| 24.    | 114308.198 | 114346.549 | 20         | 20          |
| 25.    | 114572.889 | 114612.814 | 20         | 20          |
| 26.    | 114645.667 | 114686.305 | 20         | 20          |
| 27.    | 114698.431 | 114723.519 | 20         | 20          |
| 28.    | 114725.630 | 114766.228 | 20         | 20          |
| 29.    | 115066.191 | 115143.445 | 30         | 30          |
| 30.    | 115357.254 | 115382.447 | 20         | 20          |

Note:- At above locations Safety features like Traffic Sign boards, Crash Barrier, Road Delineators, etc. as per IRC 67: 2022 shall be provided.

# (iv) Right of Way

[Refer to paragraph 2.3 of the Manual]. Details of the Right of Way are given in Annex II of Schedule-A.

# (v) Type of shoulders

[Refer to paragraph 2.5.2of the Manual and specify]

(a) In open country paved shoulder of 1.5m both side & earthen shoulder of 1.0m width on valley side shall be provided (Hilly terrain).





**Technical Schedule** 

|        | Design C | hainage | Length (in | Paved      | Earthen  | Reference to  |
|--------|----------|---------|------------|------------|----------|---------------|
| S. No. | From     | То      | m)         | Shoulder   | Shoulder | cross section |
| 1.     | 96870    | 97100   | 230        | 2x1.5=3.0m | -        | Fig 2.11(new) |
| 2.     | 97100    | 97300   | 200        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 3.     | 97300    | 97500   | 200        | 2x1.5=3.0m | -        | Fig 2.11(new) |
| 4.     | 97500    | 97700   | 200        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.9       |
| 5.     | 97700    | 97800   | 100        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 6.     | 97800    | 97900   | 100        | 2x1.5=3.0m | -        | Fig 2.11(new) |
| 7.     | 97900    | 98000   | 100        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.9       |
| 8.     | 98000    | 98100   | 100        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 9.     | 98100    | 98250   | 150        | 2x1.5=3.0m | -        | Fig 2.11(new) |
| 10.    | 98250    | 98500   | 250        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 11.    | 98500    | 98650   | 150        | 2x1.5=3.0m | -        | Fig 2.11(new) |
| 12.    | 98650    | 98750   | 100        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 13.    | 98750    | 98900   | 150        | 2x1.5=3.0m | -        | Fig 2.11(new) |
| 14.    | 98900    | 99000   | 100        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 15.    | 99000    | 99100   | 100        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.9       |
| 16.    | 99100    | 99200   | 100        | 2x1.5=3.0m | -        | Fig 2.11(new) |
| 17.    | 99200    | 99300   | 100        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.9       |
| 18.    | 99300    | 99700   | 400        | 2x1.5=3.0m | -        | Fig 2.11(new) |
| 19.    | 99700    | 99800   | 100        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.9       |
| 20.    | 99800    | 100100  | 300        | 2x1.5=3.0m | -        | Fig 2.11(new) |
| 21.    | 100100   | 100200  | 100        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 22.    | 100200   | 100300  | 100        | 2x1.5=3.0m | -        | Fig 2.11(new) |
| 23.    | 100300   | 100800  | 500        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 24.    | 100800   | 101100  | 300        | 2x1.5=3.0m | -        | Fig 2.11(new) |
| 25.    | 101100   | 101300  | 200        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 26.    | 101300   | 101400  | 100        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.9       |
| 27.    | 101400   | 101700  | 300        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |





**Technical Schedule** 

|        | Design C | hainage | Length (in | Paved      | Earthen  | Reference to  |
|--------|----------|---------|------------|------------|----------|---------------|
| S. No. | From     | То      | m)         | Shoulder   | Shoulder | cross section |
| 28.    | 101700   | 101900  | 200        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.9       |
| 29.    | 101900   | 102100  | 200        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 30.    | 102100   | 102200  | 100        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.9       |
| 31.    | 102200   | 102400  | 200        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 32.    | 102400   | 102600  | 200        | 2x1.5=3.0m | -        | Fig 2.11(new) |
| 33.    | 102600   | 102800  | 200        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 34.    | 102800   | 102950  | 150        | 2x1.5=3.0m | -        | Fig 2.11(new) |
| 35.    | 102950   | 103150  | 200        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 36.    | 103150   | 103500  | 350        | 2x1.5=3.0m | -        | Fig 2.11(new) |
| 37.    | 103500   | 103600  | 100        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 38.    | 103600   | 103700  | 100        | 2x1.5=3.0m | -        | Fig 2.11(new) |
| 39.    | 103700   | 103900  | 200        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.9       |
| 40.    | 103900   | 104000  | 100        | 2x1.5=3.0m | -        | Fig 2.11(new) |
| 41.    | 104000   | 104500  | 500        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.9       |
| 42.    | 104500   | 104900  | 400        | 2x1.5=3.0m | -        | Fig 2.11(new) |
| 43.    | 104900   | 105100  | 200        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.9       |
| 44.    | 105100   | 105200  | 100        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 45.    | 105200   | 105500  | 300        | 2x1.5=3.0m | -        | Fig 2.11(new) |
| 46.    | 105500   | 105600  | 100        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 47.    | 105600   | 106000  | 400        | 2x1.5=3.0m | -        | Fig 2.11(new) |
| 48.    | 106000   | 106200  | 200        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.9       |
| 49.    | 106200   | 106400  | 200        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 50.    | 106400   | 106600  | 200        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.9       |
| 51.    | 106600   | 109900  | 3300       | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 52.    | 109900   | 110300  | 400        | 2x1.5=3.0m | -        | Fig 2.11(new) |
| 53.    | 110300   | 111700  | 1400       | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 54.    | 111700   | 113200  | 1500       | 2x1.5=3.0m | 1x1=1.0m | Fig 2.9       |





**Technical Schedule** 

|        | Design C | hainage | Length (in | Paved      | Earthen  | Reference to  |
|--------|----------|---------|------------|------------|----------|---------------|
| S. No. | From     | То      | m)         | Shoulder   | Shoulder | cross section |
| 55.    | 113200   | 114000  | 800        | 2x1.5=3.0m | -        | Fig 2.11(new) |
| 56.    | 114000   | 114100  | 100        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.9       |
| 57.    | 114100   | 114150  | 50         | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 58.    | 114150   | 114350  | 200        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.9       |
| 59.    | 114350   | 114400  | 50         | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 60.    | 114400   | 114650  | 250        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.9       |
| 61.    | 114650   | 114800  | 150        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 62.    | 114800   | 115100  | 300        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.9       |
| 63.    | 115100   | 115150  | 50         | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 64.    | 115150   | 115350  | 200        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.9       |
| 65.    | 115350   | 115750  | 400        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 66.    | 115750   | 116000  | 250        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.9       |
| 67.    | 116000   | 116350  | 350        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.8       |
| 68.    | 116350   | 116550  | 200        | 2x1.5=3.0m | 1x1=1.0m | Fig 2.9       |
|        | Tot      | tal     | =19680m    |            |          |               |

# (vi) Lateral and vertical clearances at underpasses

- (a) Lateral and vertical clearance at underpasses and provision of guardrails/ crash barriers shall be as per the provision of relevant Manual.
- (b) Lateral clearance: The width of the opening at the under passes shall be as follows:

| S. No. | Location (Chainage)<br>(from km to km) | Span/opening<br>(m) | Remarks |
|--------|--|---------------------|---------|
|        |  | Nil                 |         |

# (vii) Lateral and vertical clearances at overpasses

- (a) Lateral and vertical clearances at overpasses shall be as the provision of relevant Manual.
- (b) Lateral clearance: The width of the opening at the overpasses shall be as





**Technical Schedule** 

#### follows:

| S. No. | Location (Chainage)<br>(from km to km) | Span/opening<br>(m) | Remarks |  |  |
|--------|--|---------------------|---------|--|--|
| Nil    |  |                     |         |  |  |

# (viii) Service roads

Service roads shall be constructed at the locations and for the lengths indicated below: [Refer to the provision of relevant Manual and provided details]

| S. No. | Location of service road<br>(From km to km) | Right hand<br>side(RHS)/Left hand<br>side(LHS)/or Both sides | Length(km)of<br>service road |  |  |
|--------|---|--|------------------------------|--|--|
| Nil    |   |  |                              |  |  |

# (ix) Grade separated structures

(a) Grade separated structures shall be provided as per provision of the relevant Manual. The requisite particulars are given below:

[Refer to the provision of relevant Manual and provide details]

| S. No. | Location of structure | Length<br>(m) | Number and length<br>of spans (m) | Approach gradient | * |
|--------|-----------------------|---------------|-----------------------------------|-------------------|---|
| Nil    |                       |               |                                   |                   |   |

(b) In the case of grade separated structures, the type of structure and the level of the Project Highway and the cross roads shall be as follows: [Refer to the provision of relevant Manual and specify the type of vehicular underpass/ overpass structure and whether the cross road is to be carried at the existing level, raised or lowered]

| SI         |          | Type of                | Cı                | ross road a     | t                | Remarks            |  |
|------------|----------|------------------------|-------------------|-----------------|------------------|--------------------|--|
| SI.<br>No. | Location | structure<br>Length(m) | Existing<br>Level | Raised<br>Level | Lowered<br>Level | Remarks,<br>if any |  |
|            | Nil      |                        |                   |                 |                  |                    |  |





**Technical Schedule** 

# (x) Cattle and pedestrian underpass /overpass

Cattle and pedestrian underpass/overpass shall be constructed as follows: [Refer to provision of relevant Manual and specify the requirements of cattle and pedestrian underpass/overpass]

| S. No. | Location | Type of crossing |  |
|--------|----------|------------------|--|
| Nil    |          |                  |  |

# (xi) Typical cross-sections of the Project Highway

[Givetypicalcross-sectionsoftheProjectHighwaybyreferencetotheManual]

As per attached Drawings

| Sr. No. | Description  | Design Length (Km.) | Proposed TCS<br>Type |
|---------|--|---------------------|----------------------|
| 1       | Reconstruction in Two-Lane Carriageway with Paved Shoulder in Hilly Terrain with both side drain on hill side  | 5.380               | TCS-2.11(new)        |
| 2       | Two Lane Road with Paved shoulders in Hilly<br>Terrain with Trapezoidal Drains on Hill side<br>and Retaining wall on Valley Side in open<br>country area | 9.000               | TCS-2.8              |
| 3       | Reconstruction in Two-Lane Carriageway with Paved Shoulder in Hilly Terrain without retaining wall   | 5.300               | TCS-2.9              |
|         | Total  | 19.680km            |                      |

| S.no. | Des Ch<br>from (m) | Des Ch<br>to (m) | Length<br>(km) | TCS type      | Remarks      |
|-------|--------------------|------------------|----------------|---------------|--------------|
| 1.    | 96870              | 97100            | 0.230          | Fig 2.11(new) | Open Country |
| 2.    | 97100              | 97300            | 0.200          | Fig 2.8       | Open Country |
| 3.    | 97300              | 97500            | 0.200          | Fig 2.11(new) | Open Country |
| 4.    | 97500              | 97700            | 0.200          | Fig 2.9       | Open Country |
| 5.    | 97700              | 97800            | 0.100          | Fig 2.8       | Open Country |
| 6.    | 97800              | 97900            | 0.100          | Fig 2.11(new) | Open Country |
| 7.    | 97900              | 98000            | 0.100          | Fig 2.9       | Open Country |
| 8.    | 98000              | 98100            | 0.100          | Fig 2.8       | Open Country |
| 9.    | 98100              | 98250            | 0.150          | Fig 2.11(new) | Open Country |
| 10.   | 98250              | 98500            | 0.250          | Fig 2.8       | Open Country |





**Technical Schedule** 

| S.no. | Des Ch<br>from (m) | Des Ch<br>to (m) | Length<br>(km) | TCS type      | Remarks      |
|-------|--------------------|------------------|----------------|---------------|--------------|
| 11.   | 98500              | 98650            | 0.150          | Fig 2.11(new) | Open Country |
| 12.   | 98650              | 98750            | 0.100          | Fig 2.8       | Open Country |
| 13.   | 98750              | 98900            | 0.150          | Fig 2.11(new) | Open Country |
| 14.   | 98900              | 99000            | 0.100          | Fig 2.8       | Open Country |
| 15.   | 99000              | 99100            | 0.100          | Fig 2.9       | Open Country |
| 16.   | 99100              | 99200            | 0.100          | Fig 2.11(new) | Open Country |
| 17.   | 99200              | 99300            | 0.100          | Fig 2.9       | Open Country |
| 18.   | 99300              | 99700            | 0.400          | Fig 2.11(new) | Open Country |
| 19.   | 99700              | 99800            | 0.100          | Fig 2.9       | Open Country |
| 20.   | 99800              | 100100           | 0.300          | Fig 2.11(new) | Open Country |
| 21.   | 100100             | 100200           | 0.100          | Fig 2.8       | Open Country |
| 22.   | 100200             | 100300           | 0.100          | Fig 2.11(new) | Open Country |
| 23.   | 100300             | 100800           | 0.500          | Fig 2.8       | Open Country |
| 24.   | 100800             | 101100           | 0.300          | Fig 2.11(new) | Open Country |
| 25.   | 101100             | 101300           | 0.200          | Fig 2.8       | Open Country |
| 26.   | 101300             | 101400           | 0.100          | Fig 2.9       | Open Country |
| 27.   | 101400             | 101700           | 0.300          | Fig 2.8       | Open Country |
| 28.   | 101700             | 101900           | 0.200          | Fig 2.9       | Open Country |
| 29.   | 101900             | 102100           | 0.200          | Fig 2.8       | Open Country |
| 30.   | 102100             | 102200           | 0.100          | Fig 2.9       | Open Country |
| 31.   | 102200             | 102400           | 0.200          | Fig 2.8       | Open Country |
| 32.   | 102400             | 102600           | 0.200          | Fig 2.11(new) | Open Country |
| 33.   | 102600             | 102800           | 0.200          | Fig 2.8       | Open Country |
| 34.   | 102800             | 102950           | 0.150          | Fig 2.11(new) | Open Country |
| 35.   | 102950             | 103150           | 0.200          | Fig 2.8       | Open Country |
| 36.   | 103150             | 103500           | 0.350          | Fig 2.11(new) | Open Country |
| 37.   | 103500             | 103600           | 0.100          | Fig 2.8       | Open Country |





**Technical Schedule** 

| S.no. | Des Ch<br>from (m) | Des Ch<br>to (m) | Length<br>(km) | TCS type      | Remarks      |
|-------|--------------------|------------------|----------------|---------------|--------------|
| 38.   | 103600             | 103700           | 0.100          | Fig 2.11(new) | Open Country |
| 39.   | 103700             | 103900           | 0.200          | Fig 2.9       | Open Country |
| 40.   | 103900             | 104000           | 0.100          | Fig 2.11(new) | Open Country |
| 41.   | 104000             | 104500           | 0.500          | Fig 2.9       | Open Country |
| 42.   | 104500             | 104900           | 0.400          | Fig 2.11(new) | Open Country |
| 43.   | 104900             | 105100           | 0.200          | Fig 2.9       | Open Country |
| 44.   | 105100             | 105200           | 0.100          | Fig 2.8       | Open Country |
| 45.   | 105200             | 105500           | 0.300          | Fig 2.11(new) | Open Country |
| 46.   | 105500             | 105600           | 0.100          | Fig 2.8       | Open Country |
| 47.   | 105600             | 106000           | 0.400          | Fig 2.11(new) | Open Country |
| 48.   | 106000             | 106200           | 0.200          | Fig 2.9       | Open Country |
| 49.   | 106200             | 106400           | 0.200          | Fig 2.8       | Open Country |
| 50.   | 106400             | 106600           | 0.200          | Fig 2.9       | Open Country |
| 51.   | 106600             | 109900           | 3.300          | Fig 2.8       | Open Country |
| 52.   | 109900             | 110300           | 0.400          | Fig 2.11(new) | Open Country |
| 53.   | 110300             | 111700           | 1.400          | Fig 2.8       | Open Country |
| 54.   | 111700             | 113200           | 1.500          | Fig 2.9       | Open Country |
| 55.   | 113200             | 114000           | 0.800          | Fig 2.11(new) | Open Country |
| 56.   | 114000             | 114100           | 0.100          | Fig 2.9       | Open Country |
| 57.   | 114100             | 114150           | 0.050          | Fig 2.8       | Open Country |
| 58.   | 114150             | 114350           | 0.200          | Fig 2.9       | Open Country |
| 59.   | 114350             | 114400           | 0.050          | Fig 2.8       | Open Country |
| 60.   | 114400             | 114650           | 0.250          | Fig 2.9       | Open Country |
| 61.   | 114650             | 114800           | 0.150          | Fig 2.8       | Open Country |
| 62.   | 114800             | 115100           | 0.300          | Fig 2.9       | Open Country |
| 63.   | 115100             | 115150           | 0.050          | Fig 2.8       | Open Country |
| 64.   | 115150             | 115350           | 0.200          | Fig 2.9       | Open Country |





**Technical Schedule** 

| S.no. | Des Ch<br>from (m)  | Des Ch<br>to (m) | Length<br>(km) | TCS type | Remarks      |
|-------|---------------------|------------------|----------------|----------|--------------|
| 65.   | 115350              | 115750           | 0.400          | Fig 2.8  | Open Country |
| 66.   | 115750              | 116000           | 0.250          | Fig 2.9  | Open Country |
| 67.   | 116000              | 116350           | 0.350          | Fig 2.8  | Open Country |
| 68.   | 116350              | 116550           | 0.200          | Fig 2.9  | Open Country |
|       | Fotal Design Length |                  | 19.680 km      |          |              |

# 3. Intersections and Grade Separators

All intersections and grade separators shall be as per the provision of relevant Manual. Existing intersections which are deficient shall be improved to the prescribed standards. [Refer to the provision of relevant Manual and specify the requirements. Explain where necessary with drawings/sketches/general arrangement]

Properly designed intersections shall be provided at the locations and of the types and features given in the tables below:

# (i) At-grade intersections

# a. Major Intersections

| S. No. | Intersection at km | Type of intersection | Other features |  |
|--------|--------------------|----------------------|----------------|--|
| NIL    |                    |                      |                |  |

## b. Minor Intersections

| S.No. | Intersection at km | Type of intersection | Other features        |
|-------|--------------------|----------------------|-----------------------|
| 1     | 106+830            | 3 legged             | To N. Sonkhai Village |

# (ii) Grade separated intersection with/without ramps

| S. No. | Location<br>(km) | Salient<br>features | Minimum length of viaduct to be provided | Road to be carried over/under the structures |  |  |
|--------|------------------|---------------------|--|--|--|--|
| Nil    |                  |                     |  |  |  |  |





**Technical Schedule** 

#### 4. Road Embankment and Cut Section

(i) Widening and improvement of the existing road embankment/cuttings and construction of new road embankment/cuttings shall conform to the Specifications and Standards given in Section4 of the Manual and the specified cross-sectional details. Deficiencies in the plan and profile of the existing road shall be corrected.

#### Note: -

- 1. Disposal of extra earth (Muck) obtained by cutting is sole responsibility of contractor.
- 2. Identification & finalization of muck disposal site is sole responsibility of contractor in consultation with Authority Engineer & without violating Guidelines of MoEFCC.
- 3. Any financial implication related to the muck disposal & muck disposal site will not be considered as Change of Scope.
- (ii) Raising of the existing road [Refer to the provision of relevant Manual and specify sections to be raised]

The existing road shall be raised in the following sections:

| S. No. | Section<br>(From km to km) | Length | Extent of raising [Top of finished road level] |  |  |  |
|--------|----------------------------|--------|--|--|--|--|
| Nil    |                            |        |  |  |  |  |

# 5. Pavement Design

(i) Pavement design shall be carried out in accordance with Section 5 of the Manual.

| Homogenous<br>Section (Km) |         |                | CBR<br>(%) | MSA     |    | Adopted Pavement Composition In Widening Position (mm) |     |      |
|----------------------------|---------|----------------|------------|---------|----|--|-----|------|
| From                       | То      | Length (in Km) |            | Adopted | ВС | DBM  | WMM | CTSB |
| 96+870                     | 116+550 | 19.68          | 10         | 20      | 30 | 50   | 150 | 200  |

#### (ii) Type of pavement

[Refer to paragraph 5.1 of the Manual and state specific requirement, if any, of providing cement concrete pavement.]

| Н      | T (5)   |       |                   |
|--------|---------|-------|-------------------|
| From   | From To |       | Type of Pavement  |
| 96+870 | 116+550 | 19.68 | Flexible Pavement |

# (i) Design requirements





**Technical Schedule** 

[Refer to the provision of relevant Manual and specify design requirements and strategy]

# a) Design Period and strategy

Flexible pavement for new pavement or for widening and strengthening of the existing pavement shall be designed for a minimum design period of 20 years. Stage construction shall not be permitted.

# b) Design Traffic

Notwithstanding anything to the contrary contained in this Agreement or the Manual, the Contractor shall design the pavement for design traffic of 20 million standard axles.

# (ii) Reconstruction of stretches

[Refer to the provision of relevant Manual and specify the stretches, if any, tobe reconstructed.]

The following stretches of the existing road shall be reconstructed. These shall be designed as new pavement.

|   | S. No. | Stre    | Remark  |                |
|---|--------|---------|---------|----------------|
|   | 5. NO. | From km | To km   | Remark         |
| Ī | 1.     | 96+870  | 116+550 | Reconstruction |

#### 6. Roadside Drainage

Drainage system including surface and subsurface drains for the Project Highway shall be provided as per the provision of relevant Manual.

## a) PCC Catch water drain: 45480 m

| S.  | ,     | ainage | Length | Catch Water<br>Drain at no. of | Catch Water Drain at | Total Length |
|-----|-------|--------|--------|--------------------------------|----------------------|--------------|
| No. | From  | То     | (in m) | bench (LHS)                    | no. of bench (RHS)   | (in m)       |
| 1.  | 96870 | 97100  | 230    | 2.000                          | 4.000                | 1380         |
| 2.  | 97100 | 97300  | 200    | 0.000                          | 1.000                | 200          |
| 3.  | 97300 | 97500  | 200    | 1.000                          | 2.000                | 600          |
| 4.  | 97500 | 97700  | 200    | 0.000                          | 2.000                | 400          |
| 5.  | 97700 | 97800  | 100    | 0.000                          | 1.000                | 100          |
| 6.  | 97800 | 97900  | 100    | 1.000                          | 3.000                | 400          |
| 7.  | 97900 | 98000  | 100    | 0.000                          | 2.000                | 200          |
| 8.  | 98000 | 98100  | 100    | 0.000                          | 1.000                | 100          |
| 9.  | 98100 | 98250  | 150    | 1.000                          | 8.000                | 1350         |
| 10. | 98250 | 98500  | 250    | 0.000                          | 3.000                | 750          |
| 11. | 98500 | 98650  | 150    | 1.000                          | 3.000                | 600          |
| 12. | 98650 | 98750  | 100    | 0.000                          | 3.000                | 300          |
| 13. | 98750 | 98900  | 150    | 1.000                          | 6.000                | 1050         |





**Technical Schedule** 

| S.<br>No. | Cha    | inage  | Length<br>(in m) | Catch Water<br>Drain at no. of | Catch Water Drain at no. of bench (RHS) | Total Length<br>(in m) |
|-----------|--------|--------|------------------|--------------------------------|---|------------------------|
| 14.       | 98900  | 99000  | 100              | 0.000                          | 3.000                                   | 300                    |
| 15.       | 99000  | 99100  | 100              | 0.000                          | 3.000                                   | 300                    |
| 16.       | 99100  | 99200  | 100              | 1.000                          | 3.000                                   | 400                    |
| 17.       | 99200  | 99300  | 100              | 0.000                          | 3.000                                   | 300                    |
| 18.       | 99300  | 99700  | 400              | 1.000                          | 4.000                                   | 2000                   |
| 19.       | 99700  | 99800  | 100              | 0.000                          | 2.000                                   | 200                    |
| 20.       | 99800  | 100100 | 300              | 1.000                          | 3.000                                   | 1200                   |
| 21.       | 100100 | 100100 | 100              | 0.000                          | 3.000                                   | 300                    |
| 22.       | 100100 | 100300 | 100              | 1.000                          | 3.000                                   | 400                    |
| 23.       | 100200 | 100300 | 500              | 0.000                          | 2.000                                   | 1000                   |
| 24.       | 100800 | 101100 | 300              | 0.000                          | 1.000                                   | 300                    |
| 25.       | 101100 | 101100 | 200              | 0.000                          | 1.000                                   | 200                    |
| 26.       | 101300 | 101400 | 100              | 0.000                          | 1.000                                   | 100                    |
| 27.       | 101400 | 101700 | 300              | 0.000                          | 1.000                                   | 300                    |
| 28.       | 101700 | 101700 | 200              | 0.000                          | 2.000                                   | 400                    |
| 29.       | 101700 | 102100 | 200              | 0.000                          | 2.000                                   | 400                    |
| 30.       | 102100 | 102200 | 100              | 0.000                          | 3.000                                   | 300                    |
| 31.       | 102200 | 102400 | 200              | 0.000                          | 1.000                                   | 200                    |
| 32.       | 102400 | 102600 | 200              | 1.000                          | 2.000                                   | 600                    |
| 33.       | 102600 | 102800 | 200              | 0.000                          | 1.000                                   | 200                    |
| 34.       | 102800 | 102950 | 150              | 1.000                          | 1.000                                   | 300                    |
| 35.       | 102950 | 103150 | 200              | 0.000                          | 1.000                                   | 200                    |
| 36.       | 103150 | 103500 | 350              | 1.000                          | 1.000                                   | 700                    |
| 37.       | 103500 | 103600 | 100              | 0.000                          | 1.000                                   | 100                    |
| 38.       | 103600 | 103700 | 100              | 1.000                          | 1.000                                   | 200                    |
| 39.       | 103700 | 103900 | 200              | 0.000                          | 1.000                                   | 200                    |
| 40.       | 103900 | 104000 | 100              | 1.000                          | 3.000                                   | 400                    |
| 41.       | 104000 | 104500 | 500              | 0.000                          | 2.000                                   | 1000                   |
| 42.       | 104500 | 104900 | 400              | 1.000                          | 3.000                                   | 1600                   |
| 43.       | 104900 | 105100 | 200              | 0.000                          | 2.000                                   | 400                    |
| 44.       | 105100 | 105200 | 100              | 0.000                          | 1.000                                   | 100                    |
| 45.       | 105200 | 105500 | 300              | 1.000                          | 3.000                                   | 1200                   |
| 46.       | 105500 | 105600 | 100              | 0.000                          | 1.000                                   | 100                    |
| 47.       | 105600 | 106000 | 400              | 1.000                          | 2.000                                   | 1200                   |
| 48.       | 106000 | 106200 | 200              | 0.000                          | 1.000                                   | 200                    |
| 49.       | 106200 | 106400 | 200              | 0.000                          | 1.000                                   | 200                    |
| 50.       | 106400 | 106600 | 200              | 0.000                          | 1.000                                   | 200                    |
| 51.       | 106600 | 109900 | 3300             | 0.000                          | 2.000                                   | 6600                   |
| 52.       | 109900 | 110300 | 400              | 1.000                          | 3.000                                   | 1600                   |
| 53.       | 110300 | 111700 | 1400             | 0.000                          | 2.000                                   | 2800                   |
| 54.       | 111700 | 113200 | 1500             | 0.000                          | 2.000                                   | 3000                   |
| 55.       | 113200 | 114000 | 800              | 1.000                          | 3.000                                   | 3200                   |
| 56.       | 114000 | 114100 | 100              | 0.000                          | 1.000                                   | 100                    |
| 57.       | 114100 | 114150 | 50               | 0.000                          | 1.000                                   | 50                     |
| 58.       | 114150 | 114350 | 200              | 0.000                          | 2.000                                   | 400                    |
| 59.       | 114350 | 114400 | 50               | 0.000                          | 1.000                                   | 50                     |





**Technical Schedule** 

| S.  | Cha       | inage    | Length | Catch Water     | Catch Water Drain at | Total Length |
|-----|-----------|----------|--------|-----------------|----------------------|--------------|
| No. |           | <u> </u> | (in m) | Drain at no. of | no. of bench (RHS)   | (in m)       |
| 60. | 114400    | 114650   | 250    | 0.000           | 1.000                | 250          |
| 61. | 114650    | 114800   | 150    | 0.000           | 1.000                | 150          |
| 62. | 114800    | 115100   | 300    | 0.000           | 1.000                | 300          |
| 63. | 115100    | 115150   | 50     | 0.000           | 1.000                | 50           |
| 64. | 115150    | 115350   | 200    | 0.000           | 1.000                | 200          |
| 65. | 115350    | 115750   | 400    | 0.000           | 1.000                | 400          |
| 66. | 115750    | 116000   | 250    | 0.000           | 1.000                | 250          |
| 67. | 116000    | 116350   | 350    | 0.000           | 1.000                | 350          |
| 68. | 116350    | 116550   | 200    | 0.000           | 3.000                | 600          |
| Tot | al Length | (in m)   |        |                 |                      | 45480        |

b) Hill Side Drain: 25060m

| SI. No. | Type of TCS   | Location  | stretches | Side      | Total Length |
|---------|---------------|-----------|-----------|-----------|--------------|
| 51. NO. | Type of TCS   | From (km) | To (km)   | Side      | (m)          |
| 1.      | Fig 2.11(new) | 96870     | 97100     | Both Side | 460          |
| 2.      | Fig 2.8       | 97100     | 97300     | One side  | 200          |
| 3.      | Fig 2.11(new) | 97300     | 97500     | Both Side | 400          |
| 4.      | Fig 2.9       | 97500     | 97700     | One side  | 200          |
| 5.      | Fig 2.8       | 97700     | 97800     | One side  | 100          |
| 6.      | Fig 2.11(new) | 97800     | 97900     | Both Side | 200          |
| 7.      | Fig 2.9       | 97900     | 98000     | One side  | 100          |
| 8.      | Fig 2.8       | 98000     | 98100     | One side  | 100          |
| 9.      | Fig 2.11(new) | 98100     | 98250     | Both Side | 300          |
| 10.     | Fig 2.8       | 98250     | 98500     | One side  | 250          |
| 11.     | Fig 2.11(new) | 98500     | 98650     | Both Side | 300          |
| 12.     | Fig 2.8       | 98650     | 98750     | One side  | 100          |
| 13.     | Fig 2.11(new) | 98750     | 98900     | Both Side | 300          |
| 14.     | Fig 2.8       | 98900     | 99000     | One side  | 100          |
| 15.     | Fig 2.9       | 99000     | 99100     | One side  | 100          |
| 16.     | Fig 2.11(new) | 99100     | 99200     | Both Side | 200          |
| 17.     | Fig 2.9       | 99200     | 99300     | One side  | 100          |
| 18.     | Fig 2.11(new) | 99300     | 99700     | Both Side | 800          |
| 19.     | Fig 2.9       | 99700     | 99800     | One side  | 100          |
| 20.     | Fig 2.11(new) | 99800     | 100100    | Both Side | 600          |
| 21.     | Fig 2.8       | 100100    | 100200    | One side  | 100          |
| 22.     | Fig 2.11(new) | 100200    | 100300    | Both Side | 200          |
| 23.     | Fig 2.8       | 100300    | 100800    | One side  | 500          |
| 24.     | Fig 2.11(new) | 100800    | 101100    | Both Side | 600          |
| 25.     | Fig 2.8       | 101100    | 101300    | One side  | 200          |
| 26.     | Fig 2.9       | 101300    | 101400    | One side  | 100          |
| 27.     | Fig 2.8       | 101400    | 101700    | One side  | 300          |
| 28.     | Fig 2.9       | 101700    | 101900    | One side  | 200          |
| 29.     | Fig 2.8       | 101900    | 102100    | One side  | 200          |
| 30.     | Fig 2.9       | 102100    | 102200    | One side  | 100          |
| 31.     | Fig 2.8       | 102200    | 102400    | One side  | 200          |





**Technical Schedule** 

| Sl. No. | Type of TCS   | Location     | stretches | Side      | Total Length |
|---------|---------------|--------------|-----------|-----------|--------------|
| 31. NO. | Type of TCS   | From (km)    | To (km)   | Side      | (m)          |
| 32.     | Fig 2.11(new) | 102400       | 102600    | Both Side | 400          |
| 33.     | Fig 2.8       | 102600       | 102800    | One side  | 200          |
| 34.     | Fig 2.11(new) | 102800       | 102950    | Both Side | 300          |
| 35.     | Fig 2.8       | 102950       | 103150    | One side  | 200          |
| 36.     | Fig 2.11(new) | 103150       | 103500    | Both Side | 700          |
| 37.     | Fig 2.8       | 103500       | 103600    | One side  | 100          |
| 38.     | Fig 2.11(new) | 103600       | 103700    | Both Side | 200          |
| 39.     | Fig 2.9       | 103700       | 103900    | One side  | 200          |
| 40.     | Fig 2.11(new) | 103900       | 104000    | Both Side | 200          |
| 41.     | Fig 2.9       | 104000       | 104500    | One side  | 500          |
| 42.     | Fig 2.11(new) | 104500       | 104900    | Both Side | 800          |
| 43.     | Fig 2.9       | 104900       | 105100    | One side  | 200          |
| 44.     | Fig 2.8       | 105100       | 105200    | One side  | 100          |
| 45.     | Fig 2.11(new) | 105200       | 105500    | Both Side | 600          |
| 46.     | Fig 2.8       | 105500       | 105600    | One side  | 100          |
| 47.     | Fig 2.11(new) | 105600       | 106000    | Both Side | 800          |
| 48.     | Fig 2.9       | 106000       | 106200    | One side  | 200          |
| 49.     | Fig 2.8       | 106200       | 106400    | One side  | 200          |
| 50.     | Fig 2.9       | 106400       | 106600    | One side  | 200          |
| 51.     | Fig 2.8       | 106600       | 109900    | One side  | 3300         |
| 52.     | Fig 2.11(new) | 109900       | 110300    | Both Side | 800          |
| 53.     | Fig 2.8       | 110300       | 111700    | One side  | 1400         |
| 54.     | Fig 2.9       | 111700       | 113200    | One side  | 1500         |
| 55.     | Fig 2.11(new) | 113200       | 114000    | Both Side | 1600         |
| 56.     | Fig 2.9       | 114000       | 114100    | One side  | 100          |
| 57.     | Fig 2.8       | 114100       | 114150    | One side  | 50           |
| 58.     | Fig 2.9       | 114150       | 114350    | One side  | 200          |
| 59.     | Fig 2.8       | 114350       | 114400    | One side  | 50           |
| 60.     | Fig 2.9       | 114400       | 114650    | One side  | 250          |
| 61.     | Fig 2.8       | 114650       | 114800    | One side  | 150          |
| 62.     | Fig 2.9       | 114800       | 115100    | One side  | 300          |
| 63.     | Fig 2.8       | 115100       | 115150    | One side  | 50           |
| 64.     | Fig 2.9       | 115150       | 115350    | One side  | 200          |
| 65.     | Fig 2.8       | 115350       | 115750    | One side  | 400          |
| 66.     | Fig 2.9       | 115750       | 116000    | One side  | 250          |
| 67.     | Fig 2.8       | 116000       | 116350    | One side  | 350          |
| 68.     | Fig 2.9       | 116350       | 116550    | One side  | 200          |
|         | ·             | Total Length |           | •         | = 25060 m    |

# 7. Design of Structures

# (i) General

(a) All bridges, culverts and structures shall be designed and constructed in accordance with the provision of relevant Manual and shall conform to the cross-





**Technical Schedule** 

sectional features and other details specified therein.

(b) Width of the carriageway of new bridges and structures shall be asfollows:

[Refer to the provision of relevant Manual and specify the width of carriageway of new bridges and structures of more than 60(sixty) metre length, if the carriageway width is different from 7.5(seven point five) metres in the table below.]

| SI.<br>No. | Bridge at km | Width of carriageway and cross-sectional features* |
|------------|--------------|--|
|            |              | NIL  |

(c) The following structures shall be provided with footpaths:

[Refer to the provision of relevant Manual and provide details of new Structures with footpath.]

| S.<br>No. | Bridge at km | Width of carriageway and cross-sectional features*                   |
|-----------|--------------|--|
| 1.        | 97+220       | Carriageway Width = 11.0 m Footpath width= 3.0m (2x1.5m)             |
| 2.        | 113+315      | Width of Crash Barrier = 2.0m (2x1m) Width of Railings = 2.0m (2x1m) |
| 3.        | 116+435      | Overall width = 18 m   |

- (d) All bridges shall be high-level bridges.[Refer to the provision of relevant Manual and state if there is any exception]
- (e) The following structures shall be designed to carry utility services specified in table below:

[Refer to the provision of relevant Manual and provide details]

| S.No. | Bridge at km | Utility service to be carried | Remarks |
|-------|--------------|-------------------------------|---------|
|       |              | Nil                           |         |

(f) Cross-section of the new culverts and bridges at deck level for the Project Highway shall confirm to the typical cross-sections given in the provision of relevant Manual.

#### (ii) Culverts

(a) Overall width of all culverts should not be less than the roadway width of





**Technical Schedule** 

the approaches.

# (b) Reconstruction of existing culverts:

The existing culverts at the following locations shall be re-constructed as new culverts:

[Refer to the provision of relevant Manual and provide details]

| Sl.No. | Culvert location (km) | Span/Opening(m) | Remarks, if any* |
|--------|-----------------------|-----------------|------------------|
| 1.     | 107115                | 1X2X2           | Box Culvert      |
| 2.     | 107240                | 1X2X2           | Box Culvert      |
| 3.     | 107300                | 1X2X2           | Box Culvert      |
| 4.     | 107665                | 1X2X2           | Box Culvert      |
| 5.     | 107785                | 1X2X2           | Box Culvert      |
| 6.     | 108345                | 1X2X2           | Box Culvert      |
| 7.     | 109275                | 1X2X2           | Box Culvert      |
| 8.     | 109750                | 1X2X2           | Box Culvert      |
| 9.     | 110250                | 1X3X3           | Box Culvert      |
| 10.    | 110715                | 1X2X2           | Box Culvert      |
| 11.    | 110855                | 1X2X2           | Box Culvert      |
| 12.    | 111520                | 1X2X2           | Box Culvert      |
| 13.    | 111925                | 1X3X3           | Box Culvert      |
| 14.    | 112090                | 1X3X3           | Box Culvert      |
| 15.    | 112170                | 1X3X3           | Box Culvert      |
| 16.    | 112420                | 1X3X3           | Box Culvert      |
| 17.    | 112680                | 1X3X3           | Box Culvert      |
| 18.    | 112820                | 1X2X2           | Box Culvert      |
| 19.    | 112935                | 1X3X3           | Box Culvert      |
| 20.    | 113405                | 1X2X2           | Box Culvert      |
| 21.    | 113615                | 1X3X3           | Box Culvert      |
| 22.    | 113800                | 1X2X2           | Box Culvert      |
| 23.    | 113935                | 1X3X3           | Box Culvert      |
| 24.    | 114010                | 1X2X2           | Box Culvert      |
| 25.    | 114180                | 1X2X2           | Box Culvert      |
| 26.    | 114265                | 1X2X2           | Box Culvert      |
| 27.    | 114600                | 1X2X2           | Box Culvert      |
| 28.    | 114700                | 1X2X2           | Box Culvert      |
| 29.    | 114970                | 1X3X3           | Box Culvert      |
| 30.    | 115155                | 1X2X2           | Box Culvert      |





**Technical Schedule** 

| SI.No. | Culvert location (km) | Span/Opening(m) | Remarks, if any* |
|--------|-----------------------|-----------------|------------------|
| 31.    | 115320                | 1X2X2           | Box Culvert      |
| 32.    | 115480                | 1X3X3           | Box Culvert      |
| 33.    | 116100                | 1X3X3           | Box Culvert      |
| 34.    | 116180                | 1X2X2           | Box Culvert      |

#### Note:-

- 1. The cushion over the culverts should be aligned symmetrically on both sides of road along the road way width.
- 2. Minimum Width of Culvert should be 12.0m & Maximum Width should be calculated as per applicable TCS, Earth Cushion & Site conditions.
- 3. Proposed Span Arrangement of Culverts mentioned above may vary as per site conditions. All Culverts shall be designed and provided as per the technical requirement in consultation with the Authority Engineer.

# (c) Widening of existing culverts:

All existing culverts which are not to be reconstructed shall be widened to the roadway width of the Project Highway as per the typical cross section given in the provision of relevant Manual. Repairs and strengthening of existing structures where required shall be carried out.

| SI. No. | Culvert location | Type, span, height and width of existing culvert (m) | Repairs to be carried out [specify] |
|---------|------------------|--|-------------------------------------|
|         |                  |  |                                     |

# (d) Additional new culverts shall be constructed as per particulars given in the table below:

| SI. No. | Culvert location (km) | Span/Opening(m) | Remarks, if any* |
|---------|-----------------------|-----------------|------------------|
| 1.      | 97530                 | 1X2X2           | Box Culvert      |
| 2.      | 97650                 | 1X2X2           | Box Culvert      |
| 3.      | 97850                 | 1X2X2           | Box Culvert      |
| 4.      | 98060                 | 1X2X2           | Box Culvert      |
| 5.      | 98170                 | 1X3X3           | Box Culvert      |
| 6.      | 98650                 | 1X2X2           | Box Culvert      |
| 7.      | 98800                 | 1X2X2           | Box Culvert      |
| 8.      | 99050                 | 1X2X2           | Box Culvert      |
| 9.      | 99300                 | 1X3X3           | Box Culvert      |
| 10.     | 99650                 | 1X2X2           | Box Culvert      |





**Technical Schedule** 

| Sl. No. | Culvert location (km) | \nan/()nening(m) |             |
|---------|-----------------------|------------------|-------------|
| 11.     | 99750                 | 1X2X2            | Box Culvert |
| 12.     | 99900                 | 1X2X2            | Box Culvert |
| 13.     | 100040                | 1X2X2            | Box Culvert |
| 14.     | 100250                | 1X2X2            | Box Culvert |
| 15.     | 100465                | 1X2X2            | Box Culvert |
| 16.     | 100570                | 1X3X3            | Box Culvert |
| 17.     | 100750                | 1X2X2            | Box Culvert |
| 18.     | 101080                | 1X2X2            | Box Culvert |
| 19.     | 101270                | 1X2X2            | Box Culvert |
| 20.     | 101390                | 1X2X2            | Box Culvert |
| 21.     | 101520                | 1X2X2            | Box Culvert |
| 22.     | 101680                | 1X2X2            | Box Culvert |
| 23.     | 101850                | 1X2X2            | Box Culvert |
| 24.     | 102010                | 1X2X2            | Box Culvert |
| 25.     | 102420                | 1X2X2            | Box Culvert |
| 26.     | 102680                | 1X2X2            | Box Culvert |
| 27.     | 102850                | 1X2X2            | Box Culvert |
| 28.     | 103100                | 1X2X2            | Box Culvert |
| 29.     | 103300                | 1X2X2            | Box Culvert |
| 30.     | 103550                | 1X2X2            | Box Culvert |
| 31.     | 103750                | 1X2X2            | Box Culvert |
| 32.     | 103950                | 1X2X2            | Box Culvert |
| 33.     | 104150                | 1X2X2            | Box Culvert |
| 34.     | 104380                | 1X2X2            | Box Culvert |
| 35.     | 104600                | 1X2X2            | Box Culvert |
| 36.     | 104830                | 1X2X2            | Box Culvert |
| 37.     | 105050                | 1X2X2            | Box Culvert |
| 38.     | 105350                | 1X3X3            | Box Culvert |
| 39.     | 105550                | 1X2X2            | Box Culvert |
| 40.     | 105750                | 1X2X2            | Box Culvert |
| 41.     | 105810                | 1X2X2            | Box Culvert |
| 42.     | 106080                | 1X3X3            | Box Culvert |
| 43.     | 106320                | 1X2X2            | Box Culvert |
| 44.     | 106500                | 1X2X2            | Box Culvert |
| 45.     | 106650                | 1X2X2            | Box Culvert |
| 46.     | 107975                | 1X2X2            | Box Culvert |





**Technical Schedule** 

| SI. No. | Culvert location<br>(km) | Span/Opening(m) | Remarks, if any* |
|---------|--------------------------|-----------------|------------------|
| 47.     | 108130                   | 1X2X2           | Box Culvert      |
| 48.     | 108660                   | 1X2X2           | Box Culvert      |
| 49.     | 108825                   | 1X2X2           | Box Culvert      |
| 50.     | 109130                   | 1X2X2           | Box Culvert      |
| 51.     | 109455                   | 1X2X2           | Box Culvert      |
| 52.     | 109900                   | 1X2X2           | Box Culvert      |
| 53.     | 110400                   | 1X2X2           | Box Culvert      |
| 54.     | 110510                   | 1X2X2           | Box Culvert      |
| 55.     | 111115                   | 1X2X2           | Box Culvert      |
| 56.     | 111220                   | 1X2X2           | Box Culvert      |
| 57.     | 115815                   | 1X2X2           | Box Culvert      |

#### Note:-

- 1. The cushion over the culverts should be aligned symmetrically on both sides of road along the road way width.
- 2. Minimum Width of Culvert should be 12.0m & Maximum Width should be calculated as per applicable TCS, Earth Cushion & Site conditions.
- 3. Proposed Span Arrangement of Culverts mentioned above may vary as per site conditions. All Culverts shall be designed and provided as per the technical requirement in consultation with the Authority Engineer.
  - (e) Repairs/replacements of railing/parapets, flooring and protection works of the existing culverts shall be undertaken as follows:

[Refer to the provision of relevant Manual and provide details]

| S.No. | Location at km | Type of repair required |
|-------|----------------|-------------------------|
|       | N              | IL                      |

(f) Floor protection works shall be as specified in the relevant IRC Codes and Specifications.

#### (iii) Bridges

- (a) Existing bridges to be re-constructed/widened
- (i) The existing bridges at the following locations shall be re-constructed as new Structures]

[Refer to the provision of relevant Manual and provide details]





**Technical Schedule** 

# a. Major Bridge - NIL

|  | Dridge     | Salient deta               | ils of existing bridge | Adequacy or otherwise of the                                 | Proposed           |      |
|--|------------|----------------------------|------------------------|--|--------------------|------|
|  | SI.<br>No. | Bridge<br>location<br>(km) | Type of<br>Structures  | Span Arrangement and<br>Total Vent way (No. x<br>Length) (m) | existing waterway, | Span |
|  | NIL        |                            |                        |  |                    |      |

# b. Minor Bridges - 2nos.

|            |                            | Salient details of existing bridge |  | Adequacy or  |  |
|------------|----------------------------|------------------------------------|--|--|--|
| SI.<br>No. | Bridge<br>location<br>(km) | Type of Structures                 | Span Arrangement and Total Vent way (No. x Length) (m) | otherwise of the existing waterway, vertical clearance, etc* | Proposed<br>Span<br>Arrangement<br>(m) |
| 1          | 113315                     | Bailey Bridge                      | 1x19   | -  | 1x16                                   |
| 2          | 116435                     | Slab                               | 1x3  | -  | 2X3X3                                  |

<sup>\*</sup>Attach GAD

#### Note: -

- 1. During reconstruction of existing bridges, traffic movement should not be obstructed. Hence for movement of traffic, diversions shall be constructed as per site conditions.
- 2. Proposed Span Arrangement of Bridges mentioned above may vary as per site conditions. All Minor Bridges shall be designed and provided as per the technical requirement in consultation with the Authority Engineer.

The following narrow bridges shall be widened:

| S. No. | Location (km) | Existing width(m) | Extent of widening(m) | Cross-section at deck level for widening@ |
|--------|---------------|-------------------|-----------------------|---|
|        |               | NIL               |                       |   |

# @ Attach cross-section

#### (b) Additional new bridges

[Specify additional new bridges if required, and attach GAD]

New bridges at the following locations on the Project Highway shall be constructed. GADs for the new bridges are attached in the drawings folder.





**Technical Schedule** 

Minor Bridge - 1 Nos.

| S.No. | Location (km) | Span Arrangements | Remarks, if any |
|-------|---------------|-------------------|-----------------|
| 1.    | 97+220        | 3x16m             | T- Beam Girder  |

Major Bridge - 0 Nos.

| S.No. | Location (km) | Span Arrangements | Remarks, if any |
|-------|---------------|-------------------|-----------------|
|       |               | NIL               |                 |

(c) The railings of existing bridges shall be replaced by crash barriers at the following locations:

[Refer to the provision of relevant Manual and provide details:]

| SI. No. | Location at km | Remarks |
|---------|----------------|---------|
| NIL     |                |         |

(d) Repairs/replacements of railing/parapets of the existing bridges shall be undertaken as follows:

[Refer to the provision of relevant Manual and provide details]

| SI. No. Location at km |     | Remarks |
|------------------------|-----|---------|
|                        | NIL |         |

(e) Drainage system for bridge decks

An effective drainage system for bridge decks shall be provided as specified in the provision of relevant Manual.

(f) Structures in marine environment

[Refer to the provision of relevant Manual and specify the necessary measures/treatments for protecting structures in marine environment, where applicable]

#### (iv) Rail-road bridges

- (a) Design, construction and detailing of ROB/RUB shall be as specified in the provision of relevant Manual. [Refer to the provision of relevant Manual and specify modification, if any]
- (b) Road over-bridges

Road over-bridges (road over rail) shall be provided at the following level





**Technical Schedule** 

crossings, as per GAD drawings attached:

| S. No.  Location of Level crossing (Chainage km) |     | Length of bridge (m) |
|--|-----|----------------------|
|  | NIL |                      |

# (c) Road under-bridges

Road under-bridges (road under railway line) shall be provided at the following level crossings, as per GAD drawings attached:

| S. No. | Location of Level crossing (Chainage km) | Number and length of span(m) |
|--------|--|------------------------------|
|        | Nil                                      |                              |

### (v) Grade separated structures

[Refer to the provision of relevant Manual]

The grade separated structures shall be provided at the locations and of the type and length specified in paragraphs 2 (ix) and 3 of this Annex-I.

# (vi) Repairs and strengthening of bridges and structures

[Refer to the provision of relevant Manual and provide details] The existing bridges and structures to be repaired /strengthened, and the nature and extent of repairs /strengthening required are given below:

(a) Bridges

| S. No. | Location ofbridge (km) | Nature and extent of repairs/ strengthening to be carried out |  |
|--------|------------------------|---|--|
| NIL    |                        |   |  |

# (b) ROB / RUB

| S. No. | Location of<br>ROB/RUB (km) | Nature and extent of repairs/ strengthening to be carried out |  |  |  |
|--------|-----------------------------|---|--|--|--|
|        | Nil                         |   |  |  |  |

# (c) Overpasses/Underpasses and others structures

| S. No. | Location of<br>Structure(km) | Nature and extent of repairs/ Strengthening to be carried out |
|--------|------------------------------|---|
|--------|------------------------------|---|





**Technical Schedule** 

Nil

# (vii) List of Major Bridges

The following is the list of the Major Bridges:

| S.No. | Location (Km) |  |
|-------|---------------|--|
|       | NIL           |  |

## 8. Traffic Control Devices and Road Safety Works

- i. Traffic control devices and road safety works shall be provided in accordance with the provision of relevant Manual.
- ii. Specifications of the reflective sheeting. [Refer to the provision of relevant Manual and specify]

#### 9. Roadside Furniture

- (i) Road side furniture shall be provided in accordance with the provisions of the relevant Manual.
- (ii) Overhead traffic signs: at each village start and end border, etc.

[Refer to the provision of relevant Manual and provide details]

# 10. Compulsory Afforestation

[Refer to the provision of relevant Manual and specify the number of trees which are required to be planted by the Contractor as compensatory afforestation.]

## 11. Hazardous Locations

THRIE- Beam crash barriers shall also be provided at the following hazardous locations:

| S. No. | Type of TCS | Location | n stretch | Side     | Total Length |
|--------|-------------|----------|-----------|----------|--------------|
| 3. NO. | Type of TCS | From (m) | To (m)    | Side     | (m)          |
| 1.     | Fig 2.8     | 97100    | 97300     | One Side | 200          |
| 2.     | Fig 2.9     | 97500    | 97700     | One Side | 200          |
| 3.     | Fig 2.8     | 97700    | 97800     | One Side | 100          |
| 4.     | Fig 2.9     | 97900    | 98000     | One Side | 100          |
| 5.     | Fig 2.8     | 98000    | 98100     | One Side | 100          |
| 6.     | Fig 2.8     | 98250    | 98500     | One Side | 250          |
| 7.     | Fig 2.8     | 98650    | 98750     | One Side | 100          |
| 8.     | Fig 2.8     | 98900    | 99000     | One Side | 100          |
| 9.     | Fig 2.9     | 99000    | 99100     | One Side | 100          |
| 10.    | Fig 2.9     | 99200    | 99300     | One Side | 100          |
| 11.    | Fig 2.9     | 99700    | 99800     | One Side | 100          |
| 12.    | Fig 2.8     | 100100   | 100200    | One Side | 100          |





**Technical Schedule** 

| C No   | Type of TCS | Location stretch    |        | Side     | Total Length |
|--------|-------------|---------------------|--------|----------|--------------|
| S. No. | Type of TCS | From (m)            | To (m) | Side     | (m)          |
| 13.    | Fig 2.8     | 100300              | 100800 | One Side | 500          |
| 14.    | Fig 2.8     | 101100              | 101300 | One Side | 200          |
| 15.    | Fig 2.9     | 101300              | 101400 | One Side | 100          |
| 16.    | Fig 2.8     | 101400              | 101700 | One Side | 300          |
| 17.    | Fig 2.9     | 101700              | 101900 | One Side | 200          |
| 18.    | Fig 2.8     | 101900              | 102100 | One Side | 200          |
| 19.    | Fig 2.9     | 102100              | 102200 | One Side | 100          |
| 20.    | Fig 2.8     | 102200              | 102400 | One Side | 200          |
| 21.    | Fig 2.8     | 102600              | 102800 | One Side | 200          |
| 22.    | Fig 2.8     | 102950              | 103150 | One Side | 200          |
| 23.    | Fig 2.8     | 103500              | 103600 | One Side | 100          |
| 24.    | Fig 2.9     | 103700              | 103900 | One Side | 200          |
| 25.    | Fig 2.9     | 104000              | 104500 | One Side | 500          |
| 26.    | Fig 2.9     | 104900              | 105100 | One Side | 200          |
| 27.    | Fig 2.8     | 105100              | 105200 | One Side | 100          |
| 28.    | Fig 2.8     | 105500              | 105600 | One Side | 100          |
| 29.    | Fig 2.9     | 106000              | 106200 | One Side | 200          |
| 30.    | Fig 2.8     | 106200              | 106400 | One Side | 200          |
| 31.    | Fig 2.9     | 106400              | 106600 | One Side | 200          |
| 32.    | Fig 2.8     | 106600              | 109900 | One Side | 3300         |
| 33.    | Fig 2.8     | 110300              | 111700 | One Side | 1400         |
| 34.    | Fig 2.9     | 111700              | 113200 | One Side | 1500         |
| 35.    | Fig 2.9     | 114000              | 114100 | One Side | 100          |
| 36.    | Fig 2.8     | 114100              | 114150 | One Side | 50           |
| 37.    | Fig 2.9     | 114150              | 114350 | One Side | 200          |
| 38.    | Fig 2.8     | 114350              | 114400 | One Side | 50           |
| 39.    | Fig 2.9     | 114400              | 114650 | One Side | 250          |
| 40.    | Fig 2.8     | 114650              | 114800 | One Side | 150          |
| 41.    | Fig 2.9     | 114800              | 115100 | One Side | 300          |
| 42.    | Fig 2.8     | 115100              | 115150 | One Side | 50           |
| 43.    | Fig 2.9     | 115150              | 115350 | One Side | 200          |
| 44.    | Fig 2.8     | 115350              | 115750 | One Side | 400          |
| 45.    | Fig 2.9     | 115750              | 116000 | One Side | 250          |
| 46.    | Fig 2.8     | 116000              | 116350 | One Side | 350          |
| 47.    | Fig 2.9     | 116350<br>Total Ler | 116550 | One Side | 200          |
|        | = 14300 m   |                     |        |          |              |

# 12. SPECIAL REQUIREMENT FOR HILL ROADS

[Refer to paragraphs 14.5 and 14.8 of the Manual and provide details where relevant and required.]

Special requirement for hill roads in accordance with the provisions of section 14 of the manual shall be provided in the following locations: -

# a) RCC Retaining Wall

| Sl. No. | Location | n stretch | Side | Total Length (m) |
|---------|----------|-----------|------|------------------|
| 31. NO. | From (m) | To (m)    | Side |                  |





Technical Schedule

| SI. No. | Location                 | stretch         | Side     | Total Length (m) |
|---------|--------------------------|-----------------|----------|------------------|
| 31. NO. | From (m)                 | To (m)          | Side     |                  |
| 1.      | 97100                    | 97300           | One side | 200              |
| 2.      | 97700                    | 97800           | One side | 100              |
| 3.      | 98000                    | 98100           | One side | 100              |
| 4.      | 98250                    |                 |          | 250              |
| 5.      | 98650                    | 98750           | One side | 100              |
| 6.      | 98900                    | 99000           | One side | 100              |
| 7.      | 100100                   | 100200          | One side | 100              |
| 8.      | 100300                   | 100800          | One side | 500              |
| 9.      | 101100                   | 101300          | One side | 200              |
| 10.     | <b>10.</b> 101400 101700 |                 | One side | 300              |
| 11.     |                          |                 | One side | 200              |
| 12.     | 102200                   | 102400          | One side | 200              |
| 13.     | 102600                   | 102800          | One side | 200              |
| 14.     | 102950                   | 103150          | One side | 200              |
| 15.     | 103500                   | 103600 One side |          | 100              |
| 16.     | 105100                   | 105200          | One side | 100              |
| 17.     | 105500                   | 105600          | One side | 100              |
| 18.     | 106200                   | 106400          | One side | 200              |
| 19.     | 106600                   | 109900          | One side | 3300             |
| 20.     | 110300                   | 111700          | One side | 1400             |
| 21.     | 114100                   | 114150 One sid  |          | 50               |
| 22.     | 114350                   | 114400          | One side | 50               |
| 23.     | 114650                   | 114800          | One side | 150              |
| 24.     | 115100                   | 115150          | One side | 50               |
| 25.     | 115350                   | 115750          | One side | 400              |
| 26.     | 116000                   | 116350          | One side | 350              |
|         | <u>.</u>                 | =9000 m         |          |                  |

**Note: - Retaining wall** shall be designed and provided as per the technical requirement in consultation with the Authority Engineer subject to minimum length of 9000 meter. Increase in length of Retaining wall will not be treated as change of Scope.

# b) PCC/RCC Breast wall

| S. No. | Location stretch |                | Side     | Total Length (m) |
|--------|------------------|----------------|----------|------------------|
| 5. NO. | From (m) To (m)  |                | - Side   |                  |
| 1      | 96870            | 97100          | One Side | 230              |
| 2      | 97300            | 101100         | One Side | 3800             |
| 3      | 101600           | 102600         | One Side | 1000             |
| 4      | 103200           | 104100         | One Side | 900              |
| 5      | 104300           | 105000         | One Side | 700              |
| 6      | 105200           | 105500         | One Side | 300              |
| 7      | 105700           | 106000         | One Side | 300              |
| 8      | 106300           | 111300         | One Side | 5000             |
| 9      | 111700           | 1700 114000 On |          | 2300             |
|        |                  |                | Total    | =14530m          |

**Note: - 1.** Breast wallshall be designed and provided as per the technical requirement in consultation with the Authority Engineer subject to minimum length of 14530 meter. Increase in length of Breast wall will not be treated as change of Scope.





**Technical Schedule** 

- 2. For Height of Breast Wall following parameters shall be adopted: -
- (a) For cutting height of hill side slopes till 10m minimum height of breast wall should be 2.0m above GL.
- (b) For cutting height of hill side slopes 10-20m minimum height of breast wall should be 3.0m above GL.
- (c) For cutting height of hill side slopes 20-30m minimum height of breast wall should be 4.0mabove GL.
- (d) For cutting height of hill side slopes above 30m minimum height of breast wall should be 5.0m above GL.

## c) Hydroseeding & Mulching

| S No   | Locatio  | Total Length (m) |          |
|--------|----------|------------------|----------|
| S. No. | From (m) | To (m)           |          |
| 1      | 96870    | 97100            | 230      |
| 2      | 97300    | 97600            | 300      |
| 3      | 97800    | 98000            | 200      |
| 4      | 98100    | 100300           | 2200     |
| 5      | 100500   | 100700           | 200      |
| 6      | 100800   | 101100           | 300      |
| 7      | 101700   | 101900           | 200      |
| 8      | 102100   | 102600           | 500      |
| 9      | 103200   | 103500           | 300      |
| 10     | 103900   | 104100           | 200      |
| 11     | 104300 1 | 105000           | 700      |
| 12     | 105200   | 105500           | 300      |
| 13     | 105700   | 106000           | 300      |
| 14     | 106300   | 111300           | 5000     |
|        |          |                  | = 10930m |

**Note:** - Hydroseeding & Mulching are provided as per the technical requirement in consultation with the Authority Engineer subject to minimum length of 10930 meter. Increase in length of Hydroseeding & Mulching shall not be treated as change of Scope.





**Technical Schedule** 

d) Special Protection for Sinking Zone

| d) Special Protection for Sinking Zone |           |        |                         |         |   |
|--|-----------|--------|-------------------------|---------|---|
| S.                                     | Tentative |        | Length                  | Area in | Detail of Special Protection  |
| No.                                    | From (m)  | To (m) | (in m)                  | Sq.m.   | •   |
| 1                                      | 114450    | 116550 | 2100                    | 126000  | Supply and installation of rock fall mitigation system comprising of steel wire grid/mesh Geo-composite made of mechanically woven Double twisted Hexagonal shaped steel wire mesh (wire dia. 2.7mm, Class A Zn-Al5% coated, Type 8 x 10, D=80mm) interlaced during manufacturing with 8mm (construction type-6x7+WSC and of rope grade 1770MPa) in longitudinal direction at 0.3m spacing, with longitudinal tensile strength of 165KN/m and punch resistance of 140 KN and rhomboidal shaped Cable Panel/Net of 10mm diameter of steel wire rope of size 300 mm x 300 mm with suitable connection at each intermediate and end junctions having minimum tear resistance of 15kN with tensile strength of 230kN/m and punch strength of 370kN, wherever applicable along with top anchoring using anchor trench filled with concrete or top nails, bottom nails and surface nails of CTA 32mm dia. and suitable corrosion protection coating of lengths and spacing, including top and bottom support rope, lacing wire or rope required to connect the nets and all accessories such as U-clamps, turn buckles, thimbles, including safety, all other ancillary works, material, machinery, labour etc. complete including preparatory works of loose scaling, vegetation removal etc. as per technical specifications attached and as directed by Engineer-in -charge. The System should be tailor made according to the site conditions and requirements with accessories. Equivalent / Higher Protection system will be Technically Evaluated by Approving Authority. The Final Type of product to be used shall be decided upon approval of final design / drawing as per |
| Total                                  |           | 126000 | IRC & BS specification. |         |   |

**Note: - Special Protection for Sinking Zone** shall be provided as per the technical requirement in consultation with the Authority Engineer subject to minimum area of 126000 Sq.m. Increase in Area will not be treated as change of Scope. The specification and methodology adopted for special protection works on sinking zone should be as per Annexure D2 of Schedule D.





**Technical Schedule** 

# 13. Change of Scope

The length of Structures and bridges specified here in above shall be treated as an approximate assessment. The actual lengths as required on the basis of detailed investigations shall be determined by the Contractor in accordance with the Specifications and Standards. Any variations in the lengths specified in this Schedule-B shall not constitute a Change of Scope, save and except any variations in the length arising out of a Change of Scope expressly undertaken in accordance with the provisions of Article 13.





**Technical Schedule** 

# 14. Utility Shifting

Shifting of obstructing existing utilities indicated in Schedule A to an appropriate location in accordance with the standards and specification of concerned Utility Owning Department is part of the scope of work of the Contractor/Concessionaire\*. The bidders may visit the site and assess the quantum of shifting of utilities for the projects before submission of their bid. Copy of utility relocation plan is enclosed. The specification of concerned Utility Owning Department shall be applicable and followed.

#### Notes:

- The type/spacing/size/specifications of poles/towers/lines/cables to be used in a) shifting work shall be as per the guidelines of utility owning department and it is to be agreed solely between the contractor/Concessionaire\* and the utility owning department. No change of scope shall be admissible and no cost shall be paid for using different type/spacing/size/specifications in shifted work in comparison to those in the existing work or for making any overhead crossing to underground as per requirement of utility construction owning department and/or of project highway. The contractor/concessionaire\* shall carry out joint inspection with utility owning department and get the estimates from the utility owning department. The assistance of the Authority is limited to giving forwarding letter on the proposal of contractor/concessionaire\* to utility owning department whenever asked by the contractor/concessionaire\*. The decision/ approval utility owning department shall be on the contractor/concessionaire\*.
- b) The supervision charges at the rates/charges applicable of the utility owning department shall be paid directly by the Authority to the utility Owning department as and when contractor/concessionaire\*furnishes demand of utility Owning Department along with a copy of estimated cost given by later.
- c) The dismantled material/scrap of existing Utility to be shifted/Dismantled shall belong to the contractor/concessionaire\* who would be free to dispose-off the dismantled material as deemed fit by them unless the contractor/concessionaire\* is required to deposit the dismantled material may be availed by the contractor/concessionaire\* as per estimate agreed between them.
- d) The utilities shall be handed over after shifting work is completed to utility Owning Department to their entire satisfaction. The maintenance liability shall rest with the Utility Owning Department after Handing over Process is complete as far as utility shifting works are concerned.






**Technical Schedule** 

# Schedule B-1

| Sr. | No  | Type of Utility                                | Unit | Quantity | Remarks   |
|-----|-----|--|------|----------|---|
| Α   |     | Electrical Utilities                           |      |          |   |
| Α1  |     | Items for 11KV Line                            |      |          | The details of  |
|     |     | GI Steel SP 66 tubular pole                    | Nos  | 44       | items/quantities/works to                               |
|     |     | 11KV GI Channel cross arm<br>(100x50x6x2200)mm | Nos  | 104      | be executed for shifting of utilities is tentative. All |
|     | 3.  | GI 11 kv T cross arm (50x50x6)mm               | Nos  | 7        | works/quantities/                                       |
|     | 4.  | GI Channel (150x75x6)mm                        | Nos  | 55       | miscellaneous items to be                               |
|     | 5.  | 11 kv Pin insulator-polymeric                  | Nos  | 75       | executed at site as per                                 |
|     | 6.  | 11KV Polymeric Disc insulator - 70kN           | Nos  | 90       | - 1   |
|     | 7.  | H/W fitting for 11 KV DISC 70 KN               | Nos  | 90       | detailed estimate of utility                            |
|     | 8.  | ACSR Raccoon conductor                         | Km   | 6        | owning department,                                      |
|     | 9.  | HT stay set                                    | Nos  | 40       | without any additional                                  |
|     | 10. | HT Guy Insulator                               | Nos  | 40       | claim/COS.  |
|     | 11. | GI Stay Wire 7/10 SWG                          | Kg   | 120      |   |
|     | 12. | pole clamp for GI flat, 50x6mm                 | Nos  | 230      |   |
|     | 13. | GI wire for earthing, 6 SWG                    | Kg   | 25       |   |
|     | 14. | GI pipe 50 mm dia 3 mtr length                 | Nos  | 22       |   |
|     | 15. | GI nuts-bolts & GI washer(assorted)            | Kg   | 25       |   |
|     | 16. | PG clamp for ACSR Racoon                       | No.  | 90       |   |
|     | 17. | GI Barbered Wire Type A                        | Kg   | 44       |   |
|     | 18. | GI Channel (75x40x6) mm                        | Mtr  | 5        |   |
|     | 19. | Stay grouting                                  | No.  | 44       |   |
|     | 20. | Grouting and steel Tubular Poles               | No.  | 40       |   |

| Sr. No | Type of Utility   | Unit | Quantity | Remarks   |  |
|--------|---|------|----------|---|--|
| В      | Water/Sewage pipeline   |      |          |   |  |
|        | Water supply pipeline<br>(Drinking & Water Supply Dept.,<br>PHED)                   |      |          | The details of items/quantities/works to be executed for shifting   |  |
| 1.     | GI Pipes (CWGM) 40mm  | m    | 100      | of utilities is tentative.  |  |
| 2.     | HDPE Pipes 50mm Dia   | m    | 160      | All works/quantities/   |  |
| B2     | Other Items   |      |          | miscellaneous items to be   |  |
| 1.     | TP of RSF 2.00m <sup>2</sup> with internal connection, Back wash with Solar Pannels | No.  | 1        | executed at site as per detailed estimate of utility owning department, without any additional claim/COS. |  |
| L Z.   | CWR 15KL Cap. With Chemical dosing pump   | No.  | 1        |   |  |







**Technical Schedule** 

#### Schedule-C

(SeeClause2.1)

## **Project Facilities**

# 1. Project Facilities

The Contractor shall construct the Project Facilities in accordance with the provisions of this Agreement. Such Project Facilities shall include:

- (a) Toll plaza[s];
- (b) Roadsidefurniture;
- (c) Pedestrianfacilities;
- (d) Treeplantation;
- (e) Truck lay-byes;
- (f) Bus-bays and bus shelters;
- (g) Rest areas; and
- (h) Others to be specified

# 2. Description of Project Facilities

Each of the Project Facilities is described below:

- (a) Toll Plaza: Nil
- (b) Roadside Furniture:

| S.<br>No. | ProjectFacility  | Location      | Design<br>Requirements | Otheressential details |
|-----------|--|---------------|------------------------|------------------------|
| 1         | Traffic Sign & Pavement marking                                | Entire Length | As per Schedule D      |                        |
| 2         | Km stone, Hectometer<br>Stone, 5 <sup>th</sup> kilometre stone | Entire Length | As per Schedule D      |                        |
| 3         | Boundary Stone   | Entire Length | As per Schedule D      |                        |
| 4         | Roadside Delineator,<br>marker & Road Stud                     | As per manual | As per Schedule D      |                        |

**Note:** Provide adequate details of each Project Facility to ensure their design and completion in accordance with the project- specific requirements and the provisions of

SCHEDULE-C 74





**Technical Schedule** 

the Manual.

## (c) Pedestrian Facilities:

Pedestrian facilities in the form of footpath cum drain shall be provided in the built-up area (refer typical cross-section drawing). Pedestrian facilities shall be provided at the locations of urban sections in order to ensure safety of pedestrians while crossing in consultation with Authority.

(d) Tree Plantation: 4922 nos. of trees should be planted & maintained by EPC Contractor @4mc/c in Single ROW within Proposed ROW as per IRC: SP:21-2009

# (e) Truck Lay Byes: 1no.

| S.<br>No. | Project<br>Facility | Location (km)   | Design<br>Requirements | Other Essential Details |
|-----------|---------------------|-----------------|------------------------|-------------------------|
| 1         | Truck Lay<br>Bye    | 104+300-104+400 | One side               | -                       |

Note:- The Design & Specifications of Truck Lay-bye shall follow IRC: SP-73:2018 & finalized in consultation with Authority Engineer.

# (f) Bus Bay & Shelter: 1no(Both Side).

| S.<br>No. | Project<br>Facility  | Location (km)                  | Design Requirements              | Other Essential Details                                 |
|-----------|----------------------|--------------------------------|----------------------------------|---|
| 1         | Bus Bay &<br>Shelter | 106+200-106+300<br>(LHS & RHS) | Separation from main carriageway | Start Taper-100 m,<br>Straight-30 m,<br>End Taper-100 m |

Note:- The Design & Specifications of Bus Bay & Shelter shall follow IRC: SP-73:2018 & finalized in consultation with Authority Engineer.

## (g) Rest areas: 1no.

| S.<br>No. | Project<br>Facility                | Location (km)   | Design Requirements | Other Essential Details |
|-----------|------------------------------------|-----------------|---------------------|-------------------------|
| 1         | Rest Area<br>with Public<br>Toilet | 104+300-104+400 | One side            | •                       |

Note:- The Design & Specifications of Rest Area with Public Toilet shall follow IRC: SP-73:2018 & finalized in consultation with Authority Engineer.

## (h) Others:

## (i) Street Lighting

Street lighting shall be provided in the built-up area, bus bay, truck lay bye and

SCHEDULE-C 75






**Technical Schedule** 

major junction location.

# (j) Environment

The Project Highway during design, construction and maintenance during implementation period shall conform to the environmental rules and regulations in force. The Construction Contractor shall be responsible for the same.

SCHEDULE-C 76







**Technical Schedule** 

# Schedule-D

(SeeClause2.1)

# Specifications and Standards

## 1. Construction

The Contractor shall comply with the Specifications and Standards set forth in Annex-I of this Schedule-D for construction of the Project Highway.

# 2. Design Standards

The Project Highway including Project Facilities shall conform to design requirements set out in the following documents:

[Manual of Specifications and Standards for Two Laning of Highways (IRC: SP: 73-2018), referred to herein as the Manual]

[Note: Specify the relevant Manual, Specifications and Standards]





**Technical Schedule** 

#### Annex- I

(Schedule-D)

# Specifications and Standards for Construction

# 1. SpecificationsandStandards

All Materials, works and construction operations shall conform to the Manual of Specifications and Standards for [Two-Laning of Highways (IRC: SP:73-2018)], referred to as the Manual, and MORTH Specifications for Road and Bridge Works. Where the specification for a work is not given, Good Industry Practice shall be adopted to the satisfaction of the Authority's Engineer.

# 2. Deviations from the Specifications and Standards

- (i) The terms "Concessionaire", "Independent Engineer" and "Concession Agreement" used in the Manual shall be deemed to be substituted by the terms "Contractor", "Authority's Engineer" and "Agreement" respectively.
- (ii) [Not withstanding anything to the contrary contained in Paragraph-1 above, the following Specifications and Standards shall apply to the Project Highway, and for purposes of this Agreement, the aforesaid Specifications and Standards shall be deemed to be amended to the extentset forthbelow:]
- (iii) [Note1: Deviations fromtheaforesaidSpecifications and Standards shallbe listedout here. Suchdeviations shall be pecified only if they are considered essential in viewof project-specific requirements.]

| Sr.<br>No. | Cl. No.           | Provisions in Clause      | Deviation from Manual   |
|------------|-------------------|---------------------------|---|
| 1          | TCS-2.11<br>(New) | New Typical Cross Section | Two-Lane with paved shoulder in Hilly<br>Terrain with Hill side Drain on Both sides<br>in open Country area (Box cut) |

(iv) Locations where Speed is less than 40km/hr.

| S. No.  | Stretch    |            | Radius (m)   | Speed(km/h)    |  |
|---------|------------|------------|--------------|----------------|--|
| J. 140. | From       | То         | Nadius (III) | Speed(kiii/ii) |  |
| 1.      | 106704.838 | 106827.994 | 30           | 30             |  |
| 2.      | 107289.488 | 107318.810 | 30           | 30             |  |
| 3.      | 107341.478 | 107386.096 | 30           | 30             |  |
| 4.      | 107466.887 | 107547.933 | 20           | 20             |  |
| 5.      | 108010.610 | 108092.474 | 20           | 20             |  |
| 6.      | 108702.551 | 108783.705 | 20           | 20             |  |
| 7.      | 108955.764 | 109034.032 | 20           | 20             |  |





**Technical Schedule** 

| S. No. | Stretch    |            | Radius (m) | Speed(km/h) |
|--------|------------|------------|------------|-------------|
| 8.     | 109559.204 | 109640.825 | 20         | 20          |
| 9.     | 110585.834 | 110666.358 | 20         | 20          |
| 10.    | 110957.204 | 111018.287 | 20         | 20          |
| 11.    | 113188.401 | 113238.316 | 20         | 20          |
| 12.    | 113296.460 | 113341.267 | 20         | 20          |
| 13.    | 113392.789 | 113419.771 | 20         | 20          |
| 14.    | 113431.146 | 113451.890 | 20         | 20          |
| 15.    | 113472.940 | 113490.571 | 30         | 30          |
| 16.    | 113522.291 | 113583.015 | 20         | 20          |
| 17.    | 113596.863 | 113636.319 | 20         | 20          |
| 18.    | 113651.615 | 113709.379 | 30         | 30          |
| 19.    | 113849.782 | 113939.204 | 30         | 30          |
| 20.    | 113967.874 | 113987.182 | 30         | 30          |
| 21.    | 114005.326 | 114023.480 | 30         | 30          |
| 22.    | 114094.597 | 114138.981 | 30         | 30          |
| 23.    | 114244.564 | 114286.514 | 20         | 20          |
| 24.    | 114308.198 | 114346.549 | 20         | 20          |
| 25.    | 114572.889 | 114612.814 | 20         | 20          |
| 26.    | 114645.667 | 114686.305 | 20         | 20          |
| 27.    | 114698.431 | 114723.519 | 20         | 20          |
| 28.    | 114725.630 | 114766.228 | 20         | 20          |
| 29.    | 115066.191 | 115143.445 | 30         | 30          |
| 30.    | 115357.254 | 115382.447 | 20         | 20          |

Note:- At above locations Safety features like Traffic Sign boards, Crash Barrier, Road Delineators, etc. as per IRC 67: 2022 shall be provided.







**Technical Schedule** 

# Annexure- D-I

# **Typical Cross Sections**






SCHEDULE-D 81

(Open Country - Mountainous Terrain)





**Technical Schedule** 







**Technical Schedule** 

**Annexure D-II** 

# Specification & Methodology for Special Protection (Rock fall Mitigation)

Providing and spreading steel wire grid/mesh consisting of hexagonal double twisted wire mesh type 8x10 woven with steel wire with a diameter of 2.70 mm (EN 10223-3; EN 10218), Zn-5%Al coated (EN 10244 - class A), interlaced during manufacturing with 8mm (construction type-6x7+WSC and of rope grade 1770MPa) in longitudinal direction at 0.3m spacing Zl-5%Al coated (EN 10244 - class A)(specifications as per clause 5.3.3 of IRC HRB Special Report 23), meeting the minimum requirements: Longitudinal Tensile Strength of High Resistance Steel Wire mesh /Grid Geo-composite: 165 kN/m (minimum); Puncture Resistance of High Resistance steel wire mesh/grid Geo-composite: 140kN minimum at maximum displacement of 46cm as per UNI 11437; including top and bottom support rope, lateral wire rope cable anchors at top and bottom, lacing wire rope or links required to connect the nets and all accessories such as U-clamps, thimbles, including safety, all other ancillary works, material, machinery, labour, etc., with all leads and lifts and as per technical specifications attached and as directed by Engineer - In - Charge.

The Steel wire grid/mesh geo-composite shall be time tested proven CE certified system as per IRC Highway Research Board Special Report-23 and should meet the minimum requirements of Mechanically woven double twisted (DT) hexagonal shaped Class AZn+Al5% Coated wire interlaced with 8 mm steel wire rope during manufacturing in longitudinally and transversal direction as per IRC Highway Research Board Special Report-23.

## **Material Specifications:**

The Steel wire mesh geo composite shall be mechanically prefabricated to become a uniform hexagonal woven wire mesh wherein joints are formed by twisting each pair of wires through two half turns commonly known as Double Twisted, in such a manner that unravelling is prevented. The longitudinal selvedge steel ropes and the intermediate steel ropes of 8mm are inserted during the process of manufacture to form a cohesive and monolithic geocomposite product.

All steel wires used in the manufacturing of Steel wire mesh geocomposite and in the lacing operation during construction shall confirm to EN 10223 - 3. The wire used for the manufacture of double twisted wire mesh shall have a tensile strength in the range of 380-500N/mm2 and elongation shall not be less than 10%. Test must be carried out on a sample of at least 25 cm length. DT mesh shall confirm properties indicated in table. All tests on the mesh and lacing wire must be performed prior to manufacturing the mesh

Required Properties of Mechanically Woven DT shaped mesh

| tequired i ropercies of meenameany wovem by shaped mesh |            |  |  |
|---|------------|--|--|
| Property  | Value      |  |  |
| Mesh Type   | 8x10       |  |  |
| Mesh Opening "D"(mm)(maximum)                           | 80         |  |  |
| Tolerance - Mesh Opening(%)                             | +16 to - 4 |  |  |
| Mesh Wire Diameter (mm)                                 | 2.7mm      |  |  |





**Technical Schedule** 

| Property                        | Value  |
|---------------------------------|--------|
| Tolerance - Mesh Wire           | 0.07   |
| Diameter(+/)(mm)                |        |
| Mesh Wire Zinc- Al alloyCoating | 240min |
| (gm/sqm)                        |        |

# High Resistance Steel wire mesh Geo-composite should meet the following minimum strength requirements:

The longitudinal steel rope should meet the requirement as per IS 2266 / ISO 2408/ EN 12385-22008 / EN 12385-4 2008 and have a nominal diameter of 8.00 mm. They shall be made from galvanized (Zn-Al alloy) steel in accordance with 10244-2. The rope shall be of grade 1770 N/sq mm and with a minimum breaking load of the rope as 40 KN. The longitudinal steel ropes are spaced at 1m. Tensile test & zinc mass test on steel ropes must be performed prior to manufacturing the High Resistance steel wire mesh geo-composite.

The diameter of the lacing wire rope shall be of required diameter as suggested by the supplier but shall not be less than 8 mm and shall have same characteristics as the mesh wire rope. Typically, lacing wire rope is supplied at 3% of the total weight of High Resistance Steel wire mesh geo-composite to enable the lacing to be undertaken in an adequate manner. Alternatively, if required as per site conditions and suggested by the Manufacturer, lacing wire ropes or lap links could be used for joining of adjacent nets.

The Strength Properties of Geo-composite shall be as below:

| S/No | Property                      | Value (Minimum)  |
|------|-------------------------------|--|
| (a)  | Longitudinal Tensile strength | 165 kN/m   |
| (b)  | Punch Resistance              | 140 kN(min) at maximum displacement of 46cm tested inaccordance with UNI 11437 |

Lacing wire ropes or links shall be used for joining of adjacent nets.

Installation Method: The rolls of Steel wire mesh geocomposite should be rolled down the surface from Top anchoring system as per the contract drawings. New Roll shall be placed side by side of adjacent roll in the same manner such that longitudinal ropes of both the rolls can be laced together by hand. Lacing shall commence by twisting end of the lacing wire tightly the two selvedges. It shall then pass round the two edges being joined using alternate single and double loops at approximately 100 mm intervals. The lacing wire shall be securely tied off at the bottom of the roll. The Bottom anchoring and surficial anchoring shall be done as per the contract drawings or as per standard system.

**Testing and acceptance criteria for Quality Control:** Material shall be approved by engineer-in-charge before supply. Testing on mesh wire & rope shall be performed prior to manufacturing the Steel wire mesh Geocomposite as mentioned in Table 5. Table 5 showing Testing Plans:





**Technical Schedule** 

| Sr.<br>No. | Type of Test                        | Frequency of testing & minimum of samples | Test Location  | Reference<br>Code      | Remarks, if any  |
|------------|-------------------------------------|---|--|------------------------|--|
| 1          | Tensile test on<br>Wire Rope        | 01 sample per<br>8000 sqm                 | Supplier of Wire ropes factory/Independent laboratory        | IS<br>2266/ISO<br>2408 | Can be certified through supplier MTC, else the testing can be |
| 2          | Zinc Mass of Wires<br>used for Rope | 01 sample per<br>8000 sqm                 | Supplier of Wire ropes<br>factory/ Independent<br>laboratory | IS 1835                | done at Supplier location                                      |
| 3          | Properties of GI<br>Wire            |   |  |                        |  |
|            | b. Zinc Mass &Zinc<br>Adhesion      | 01 sample per<br>800 sqm                  | Manufacturers Lab/<br>Independent laboratory                 | EN 10244               |  |

#### TECHNICAL SPECIFICATION FOR FULLY THREADED ANCHOR BARS

#### Scope:

The fully threaded anchor bars shall be designed and arranged in order to stabilize the fractured or jointed rock mass to induce homogeneity in the behavior. The anchor bars shall have the required grip length in rock. The grout shall have characteristic strength of 200kg/cm2. The fully threaded anchor bars, nuts, washer plates shall be provided.

Drilling shall be carried out by DTH machine or Top Hammer or any other suitable equipment. Size of the hole shall be minimum 51 mm and 76mm for nail diameters of 32mm. The Anchor Bar shall be high strength continuously threadedbar of tensile strength more than 400 KN with hexagonal nut and plate. If there are difficult ground and rock conditions resulting into unstable drill holes which can collapse, the Anchor Bar shall be replaced with Self-drilling anchor of tensile strength >400 KN with attached sacrificial drill bit with hexagonal nut and plate For convenience of installation, appropriate arrangement (coupler) shall be made to connect two smaller lengths of anchor bars to achieve the required length. However, the strength of the bar with coupler should be same as that of single bar.

## Installation Guideline:

- i. Anchor bars of 32mm diameter and required length along with washer plate, nut shall be installed along with drilling activity.
- ii. Grouting Drilled Holes: Grouting of the drilled holes shall be done by using OPC Grade 43 along with Suitable admixture. Mixing shall be done along with potable water





**Technical Schedule** 

so as to form the Cementous paste.

- iii. The grouting material should not shrink after final setting.
- iv. The grouting pressure shall be kept such that the drill hole shall be 100% filled after installation of anchor bar. The bidder shall maintain record of grout material consumed for each hole and submit to Engineer.

# <u>Material Technical Performance Requirements:</u>

- The EPC Contractor should provide past performance for successful completion of similar works using "Protection/Mitigation works using Rhomboidal shape steel cable panels having suitable connection at each intermediate and end junctions of the cable panel and/or High Resistance Steel wire mesh Geocomposite system" along with the bid.
- 2. The EPC Contractor shall provide the Test certificates from independent Laboratories / agencies of repute have established system performance meeting the requirements for Rhomboidal cable panels with suitable connection at each intermediate and end junction and High Resistance Steel wire Mesh Geo-composite with the bid as below:

# (A) For Rhomboidal Cable Panels with suitable connection at each intermediate and end junction:

- a. The established system should able to increase the bearing capacity during punch test / any accepted method of testing material. Under punch test with the standard / established procedure the system of Rhomboidal Cable Panel with suitable connection at each intermediate and end junction should be able to bear minimum resistance of 370 KN with maximum displacement up to 33cm as per the test procedures defined in ISO 17746.
- b. The Rhomboidal Cable Panel with suitable connection at each intermediate and end junction should have minimum tensile strength of 230kN/m as per the test procedures defined in ISO 17746.
- c. The connection at each intermediate and end junction of Rhomboidal cable Panels should have static tear minimum 15kN as per the test procedures defined in ISO 17746.

# (B) For High Resistance steel wire Mesh Geo-composite:

- a. The High Resistance steel wire Mesh Geo-composite should have minimum tensile strength of 170kN/m in longitudinal direction.
- b. Under punch test with the standard / established procedure the system of High





**Technical Schedule** 

Resistance Steel wire mesh Geo-composite should be able to bear minimum resistance of 140 KN with maximum displacement up to 45cm.

# SPECIFICATION OF THE MATERIALS TO BE USED:

#### SPECIFICATION FOR RHOMBOIDAL CABLE PANEL FOR ROCK FALL PROTECTION:

The rockfall protection system shall be as per IRC Highway Research Board Special Report-23 to be used for high hazard locations and shall be Rhomboidal in shape and should have corrosion protection coating, to prevent corrosion effect at rockfall protection system (Square /rectangular/diamond shape cable panel will not be preferred as per technical requirement of the site condition). Each Rhomboidal Cable panel should be made of one single cable having all the intermediate and end junctions of the Rhomboidal cable panel should have suitable connection as defined in IRC Highway Research Board Special Report-23 having minimum tear capacity of 15 kN and should have minimum pull apart of 9kN. The diameter of the cable should be 10mm and must have tensile strength of 1770N/mm². The loose end of cable knotted using similar / equivalent material for suage/sleeve having fastening resistance, should not be less than 90% of breaking load of the cable.

The Edge / Perimetral rope of diameter same or higher than the wrapping rope shall be used to secure the Mesh panel /cable net and should have sleeves of suitable material.

Table 1 showing specification for Wrapping Rope and Edge / Perimetral rope

| Diameter(mm)            | 10mm                |  |
|-------------------------|---------------------|--|
| Rope grade of cable net | 1770N/mm2           |  |
| Zinc coating(IS 1835)   | Class A minimum and |  |
|                         | above               |  |

Table - 2: The Rhomboidal Cable Panel should meet the following minimum strength requirements:

| Sr. | Strength Parameter  | Value (minimum)                       |
|-----|---|---------------------------------------|
| No. |   |                                       |
| 1   | Tensile Strength of cable Panel                           | 230kN/m                               |
| 2   | Puncture Strength of Cable Panel                          | 370kN at maximum displacement of 33cm |
| 3   | Tear Resistance at Junctions of cable intersections       | 15kN                                  |
| 4   | Pull Apart Resistance at Junctions of cable intersections | 9kN                                   |





**Technical Schedule** 

\*\*\* The Above parameters shall meet the requirements as per the test procedures defined in ISO 17746.

## Installation Procedure and Safety:

The rhomboidal shaped Cable panels should be used in combination with appropriate rock bolting. The rhomboidal shaped cable panels shall carefully be unrolled over the slope and the rock bolts shall be installed, keeping the rock bolt under the mesh intersection. Wherever this is not possible, the rock bolt shall be enclosed within an additional steel cable provided. Care should be taken to tighten the rhomboidal shaped cable panels around the rock bolt by pulling manually. Adjacent panel junction connection strength with cable net should not be less than 35-40KN.

**Note:** Self Drilling Anchors can be used in place of continuously threaded anchor bars depending on the strata at installation location and as directed by Engineer. In case of use of Self Drilling anchors, the contractor shall execute the job at the same rate as defined in the schedule for continuously threaded anchor bars.

After completion of rhomboidal shaped cable panel installation, base plate of a suitable size shall be tightened on the rock/soil nail, taking care that the base plate maintains a tight contact with as much with the Rhomboidal cable panel, as possible.

## Testing and Acceptance criteria for Quality control:

Testing shall be done on raw material as per testing plan indicated in Table 3. The material should get approved from the client before the actual start of supply. The manufacturer of the rhomboidal shaped cable panels shall provide Manufacturers Test Certificate for the material with every lot/shipment. The Manufacturers Test Certificate shall be provided for certifying that rhomboidal shaped cable panel rock fall protection system conforms to all the technical and special requirements.

Table 3 showing Testing Plan:

| Sr.<br>No | Test                      | Specificatio<br>n   | Number<br>of | Lot size             | Comments                      |
|-----------|---------------------------|---------------------|--------------|----------------------|-------------------------------|
| 110       |                           |                     | Testing      |                      |                               |
|           | ROPE                      |                     |              |                      |                               |
| 1         | Tensile test on wire rope | IS 2266/ISO<br>2048 | 01           | Minimum<br>8000 Sq.m | At wire rope<br>manufacturer  |
|           |                           |                     |              |                      | lab/independent<br>laboratory |
| 2         | Zinc mass of wire used    | IS 1835             | 01           | Minimum              | At wire rope                  |
|           | inrope                    |                     |              | 8000                 | manufacturer                  |
|           |                           |                     |              | Sq.m                 | lab/independent               |





**Technical Schedule** 

| Sr.<br>No | Test                          | Specificatio<br>n         | Number<br>of<br>Testing | Lot size                | Comments  |
|-----------|-------------------------------|---------------------------|-------------------------|-------------------------|---|
|           | CONNECTION AT                 | JUNCTION                  |                         |                         | laboratory  |
| 3         | Tear resistance               | Manufacturer<br>procedure | 01                      | Minimum<br>8000<br>Sq.m | At cable panel<br>manufacturer<br>lab/independent<br>laboratory |
| 4         | Pull Apart resistance         | Manufacturer<br>procedure | 01                      | Minimum<br>8000<br>Sq.m | At cable panel<br>manufacturer<br>lab/independent<br>laboratory |
| NoTe:     | Testing of rope shall be carr | ried out on the sam       | ple collected a         | fter receipt of         | material on work site.  |

## Special requirements:

- 1. The Manufacturer / Supplier should have production facility for manufacturing wire rope net panel in India. Manufacturing facility shall be certified for ISO 9001: 2015 Quality Management System certification
- 2. The wire rope net panel rock fall protection system shall have demonstrated satisfactory performance in similar applications and capacities in India or abroad. Valid documentary proof showing the supply of wire rope net panel to at least one project in India / abroad in the form of case study / Certificate from client shall be submitted.
- 3. The Manufacturer / supplier shall have a demonstrated capability of providing technical support and design assistance for rock fall protection works.
- 4. The Manufacturer / Supplier should have in-house testing facility to conduct the key testing on wire rope net panels.
- 5. The Manufacturer / Supplier should have supplied Rhomboidal wire rope panels with double knot connection at junctions not less than 18000 Sq.m for a single project in India.
- 6. The Manufacturer / Supplier shall submit documentary proof of adoption of the proposed technology on at least one project in India along with proposal.
- 7. The Manufacturer / Supplier should not have a history of poor performance such as abandoning the works, financial failures, blacklisting. If it is observed, Manufacturer / Supplier will be automatically disqualified






**Technical Schedule** 

\*\*\*\*\*The EPC Contractor shall provide sample of rhomboidal steel cable panel with suitable connection at each intermediate and end junction and as per technical specifications of size 3m X 3m of along with the bid during physical submission.

**Mode of Measurements:** The mode of measurement shall be based on Sq.m of Area of Rhomboidal Steel Cable Panels supplied.







**Technical Schedule** 

SCHEDULE - E (See Clauses 2.1 and 14.2)

## MAINTENANCE REQUIREMENTS

## 1 Maintenance Requirements

- (i) The Contractor shall, at all times maintain the Project Highway in accordance with the provisions of this Agreement, Applicable Laws and Applicable Permits.
- (ii) The Contractor shall repair or rectify any Defect or deficiency set forth in Paragraph 2 of this Schedule-E within the time limit specified therein and any failure in this behalf shall constitute non-fulfillment of the Maintenance obligations by the Contractor. Upon occurrence of any breach hereunder, the Authority shall be entitled to effect reduction in monthly lump sum payment as set forth in Clause 14.6 of this Agreement, without prejudice to the rights of the Authority under this Agreement, including Termination thereof.
- (iii) All Materials, works and construction operations shall conform to the MORTH Specifications for Road and Bridge Works, and the relevant IRC publications. Where the specifications for a work are not given, Good Industry Practice shall be adopted.

[Specify all the relevant documents]

## 2. Repair/rectification of Defects and deficiencies

The obligations of the Contractor in respect of Maintenance Requirements shall include repair and rectification of the Defects and deficiencies specified in Annex - I of this Schedule-E within the time limit set forth therein.

### 3. Other Defects and deficiencies

In respect of any Defect or deficiency not specified in Annex - I of this Schedule-E, the Authority's Engineer may, in conformity with Good Industry Practice, specify the permissible limit of deviation or deterioration with reference to the Specifications and Standards, and any deviation or deterioration beyond the permissible limit shall be repaired or rectified by the Contractor within the time limit specified by the Authority's Engineer.

#### 4. Extension of time limit

Notwithstanding anything to the contrary specified in this Schedule-E, if the nature and extent of any Defect or deficiency justifies more time for its repair or rectification than the time specified herein, the Contractor shall be entitled to additional time in conformity with Good Industry Practice. Such additional time shall be determined by the Authority's Engineer and conveyed to the Contractor and the Authority with reasons thereof.

# 5. Emergency repairs/restoration





**Technical Schedule** 

Notwithstanding anything to the contrary contained in this Schedule-E, if any Defect, deficiency or deterioration in the Project Highway poses a hazard to safety or risk of damage to property, the Contractor shall promptly take all reasonable measures for eliminating or minimizing such danger.

# 6. Daily inspection by the Contractor

The Contractor shall, through its engineer, undertake a daily visual inspection of the Project Highway and maintain a record thereof in a register to be kept in such form and manner as the Authority's Engineer may specify. Such record shall be kept in safe custody of the Contractor and shall be open to inspection by the Authority and the Authority's Engineer at any time during office hours.

## 7. Pre-monsoon inspection / Post-monsoon inspection

The Contractor shall carry out a detailed pre-monsoon inspection of all bridges, culverts and drainage system before [1st June] every year in accordance with the guidelines contained in IRC: SP35. Report of this inspection together with details of proposed maintenance works as required on the basis of this inspection shall be sent to the Authority's Engineer before the [10th June] every year. The Contractor shall complete the required repairs before the onset of the monsoon and send to the Authority's Engineer a compliance report. Post monsoon inspection shall be done by the [30th September] and the inspection report together with details of any damages observed and proposed action to remedy the same shall be sent to the Authority's Engineer.

## 8. Repairs on account of natural calamities

All damages occurring to the Project Highway on account of a Force Majeure Event or default or neglect of the Authority shall be undertaken by the Authority at its own cost. The Authority may instruct the Contractor to undertake the repairs at the rates agreed between the Parties.





**Technical Schedule** 

|  | Performan                       |                  | f Service<br>OS)  | Frequen cy of  | Tools/Equipm  | Standards and References for       | Time limit<br>for                  | Maintenanc<br>e                    |
|--|---------------------------------|------------------|---|--|---|------------------------------------|------------------------------------|------------------------------------|
| Asset Type   | ce<br>Parameter                 | Desirabl<br>e    | Acceptab<br>le  | Inspectio<br>n   | ent   | Inspection and Data Analysis       | Rectificatio<br>n/<br>Repair       | Specificatio<br>ns                 |
| Flexible<br>Pavement   | Potholes                        | Nil              | < 0.1 % of<br>area and<br>subject<br>to<br>limit of<br>10 mm<br>indepth | Daily  | Length Measurement Unit like Scale, Tape, odometer etc. |                                    | 24-48 hours                        | MORT&H<br>Specificatio<br>n 3004.2 |
| (Pavement<br>of MCW,<br>Service<br>Road,<br>approaches<br>of Grade<br>structure,<br>approaches | Cracking                        | < 5 % subject to |   | IRC 82: 2015 and Distress Identification Manual for Long Term Pavement Performance Program, FHWA 2003 (http://www.tfhrc.com/pavement | 7-15 days   | MORT&H<br>Specificatio<br>n 3004.3 |                                    |                                    |
| of<br>connecting<br>roads, slip<br>roads, lay  | Rutting                         | Nil              | < 5 mm  | mm Straight Edge / LLTD  | reports/03031/)   | 15 -30 days                        | MORT&H<br>Specificatio<br>n 3004.2 |                                    |
| byes etc. as applicable)   | Corrugation<br>s and<br>Shoving | Nil              | < 0.1 %<br>of area  | Daily  | Length<br>Measurement<br>Unit like                      |                                    | 2-7 days                           | IRC:82-<br>2015                    |
| applicable)  | Bleeding                        | Nil              | < 0.1 %<br>of area  | Daily  | Scale, Tape, odometer etc.                              |                                    | 3-7 days                           | MORT&H<br>Specificatio<br>n 3004.4 |
|  | Raveling /<br>Stripping         | Nil              | < 0.1 % of area   | Daily  |   |                                    | 7-15 days                          | IRC:82-<br>2015 read               |





**Technical Schedule** 

| Asset Type | Performan<br>ce                      |               | of Service<br>.OS)   | Frequen<br>cy of | Tools/Equipm<br>ent  | Standards and References for<br>Inspection and Data Analysis  | Time limit for | Maintenanc<br>e     |
|------------|--------------------------------------|---------------|--|------------------|--|---|----------------|---------------------|
|            |                                      |               |  | -                |  |   |                | with IRC SP<br>81   |
|            | Edge<br>Deformatio<br>n/<br>Breaking | Nil           | < 1 m for<br>any 100<br>m section<br>and width<br>< 0.1 m at<br>any<br>location,<br>restricted<br>to 30 cm<br>from<br>the edge | Daily            | Scale, Tape,<br>odometer<br>etc.                                     |   |                | IRC:82-<br>2015     |
|            | Roughness<br>BI                      | 2000<br>mm/km | 2400<br>mm/km  | Bi-<br>Annually  | Class I<br>Profilometer  | Class I Profilometer: ASTM E950 (98)  | 180 days       | IRC:82-2015         |
|            | Skid<br>Number                       | 60SN          | 50SN   | Bi-<br>Annually  | SCRIM<br>(Sideway-force  | :2004 -Standard Test Method for measuring Longitudinal Profile of   | 180 days       | BS: 7941-1:<br>2006 |
|            | Pavement<br>Condition<br>Index       | 3             | 2.1  | Bi-<br>Annually  | Coefficient<br>Routine<br>Investigation<br>Machine or<br>equivalent) | Travelled Surfaces with Accelerometer Established Inertial Profiling Reference ASTM E1656 -94: 2000- Standard Guide for Classification of Automatic Pavement Condition Survey Equipment | 180 days       | IRC:82-<br>2015     |
|            | Other<br>Pavement                    |               |  | Bi-<br>Annually  |  |   | 2-7 days       | IRC:82-<br>2015     |





**Technical Schedule** 

| Asset Type   | Performan<br>ce                  |  | of Service<br>.OS)         | Frequen<br>cy of | Tools/Equipm<br>ent                    | Standards and References for<br>Inspection and Data Analysis | Time limit for | Maintenanc<br>e    |
|--|----------------------------------|--|----------------------------|------------------|--|--|----------------|--------------------|
|  | Distresses Deflection/ Remaining |  |                            | Annually         | Falling<br>Weight                      | IRC 115: 2014  | 180 days       | IRC:115-           |
|  | Life                             |  |                            | Aillidatty       | Deflect meter                          | INC 113. 2014  | 100 days       | 2014               |
| Rigid Pavement (Pavement of MCW, Service Road, Grade Structure, approaches of connecting roads, slip roads, lay byes etc. as applicable) | Roughness<br>BI                  | 2200m<br>m/km                                      | 2400mm<br>/km              | Bi-<br>Annually  | Class I<br>Profilometer                | 180 days   |                | IRC:SP:83-<br>2008 |
|  | Skid                             | Skid Resistance no. at different speed of vehicles |                            | Bi-<br>Annually  | SCRIM<br>(Sideway-force<br>Coefficient | RC:SP:83-2008  | 180 days       | IRC:SP:83-         |
|  |                                  | Minimu<br>m<br>SN                                  | Traffic<br>Speed<br>(Km/h) |                  | Routine<br>Investigation<br>Machine or |  | ,              | 2008               |





**Technical Schedule** 

| Asset Type               | Performan<br>ce                   |          | of Service<br>.OS)                                       | Frequen<br>cy of | Tools/Equipm<br>ent                              | Standards and References for<br>Inspection and Data Analysis | Time limit for | Maintenanc<br>e                   |
|--------------------------|-----------------------------------|----------|--|------------------|--|--|----------------|-----------------------------------|
|                          |                                   | 36       | 50   | <b>- 3,</b> 5.   | equivalent)                                      | mopoccion una sucu sucusyon                                  |                |                                   |
|                          |                                   | 33       | 65   |                  |  |  |                |                                   |
|                          | -                                 | 32<br>31 | 80<br>95   |                  |  |  |                |                                   |
|                          |                                   | 31       | 110  |                  |  |  |                |                                   |
|                          |                                   |          |  |                  |  |  |                |                                   |
|                          |                                   |          |  |                  |  |  |                |                                   |
|                          |                                   |          |  |                  | Length   |  |                |                                   |
| Embankmen<br>t/<br>Slope | Edge drop<br>at<br>shoulders      | Nil      | 40 mm  | Daily            | Measurement Unit like Scale, Tape, odometer etc. | IRC  | 7-15 days      | MORT&H<br>Specificatio<br>n 408.4 |
|                          | Slope of<br>camber/cro<br>ss fall | Nil      | <2% variation in prescribe d slope of camber /cross fall | Daily            |  |  | 7-15 days      | MORT&H<br>Specificatio<br>n 408.4 |





Technical Schedule

| Asset Type | Performan<br>ce                   |     | of Service<br>.OS)                    | Frequen cy of                                   | Tools/Equipm<br>ent | Standards and References for<br>Inspection and Data Analysis | Time limit for | Maintenanc<br>e                   |
|------------|-----------------------------------|-----|---------------------------------------|---|---------------------|--|----------------|-----------------------------------|
|            | Embankme<br>nt Slopes             | Nil | <15 % variation in prescribe sidslope | Daily   |                     |  | 7-15 days      | MORT&H<br>Specificatio<br>n 408.4 |
|            | Embankme<br>nt<br>Protection      | Nil | Nil                                   | Daily   | NA                  |  | 7-15 days      | MORT&H<br>Specificatio<br>n       |
|            | Rain Cuts/<br>Gullies in<br>slope | Nil | Nil                                   | Daily<br>Specially<br>During<br>Rainy<br>Season | NA                  |  | 7-15 days      | MORT&H<br>Specificatio<br>n       |

In addition to the above performance criterion, the contractor shall strictly maintain the rigid pavements as per requirements in the following table

Table -2: Maintenance Criteria for Rigid Pavements:

|       | S.No. Type of Distress                           | Measured<br>Parameter                     | Degree   |                         | Repair Action        |                  |  |  |  |  |
|-------|--|---|----------|-------------------------|----------------------|------------------|--|--|--|--|
| S.No. |  |   | of       | Assessment Rating       | For the case d < D/2 | For the case d > |  |  |  |  |
|       |  | raiailletei                               | Severity |                         | Short Term           | D/2 Long Term    |  |  |  |  |
|       | CRACKING   |   |          |                         |                      |                  |  |  |  |  |
| 1.    | Single Discrete Cracks Not intersecting with any | w = width of crack<br>L = length of crack | 0        |                         |                      |                  |  |  |  |  |
|       |  | d = depth of crack<br>D = depth of slab   | 1        | Nil, not discernible    | No Action            | Not applicable   |  |  |  |  |
|       | joint  | 2   |          | w < 0.2 mm. hair cracks |                      |                  |  |  |  |  |





**Technical Schedule** 

|       |  | Measured                                  | Degree         |   | Repair A                            | Action                              |
|-------|--|---|----------------|---|-------------------------------------|-------------------------------------|
| S.No. | Type of Distress                         | Parameter                                 | of<br>Severity | Assessment Rating   | For the case d < D/2<br>Short Term  | For the case d > D/2 Long Term      |
|       |  |   |                | w = 0.2 - 0.5 mm,<br>discernible from<br>slow-moving car  |                                     | Seal, and stitch if<br>L ><br>lm.   |
|       |  |   | 3              | w = 0.5 - 1.5 mm,<br>discernible from fast-<br>moving car | Seal without delay                  | Within 7days                        |
|       |  |   | 4              | w = 1.5 - 3.0 mm  | Seal, and stitch if L > l m.        | Staple or Dowel<br>Bar              |
|       |  |   | 5              | w > 3 mm.   | Within 7 days                       | Retrofit, FDR for affected portion. |
|       |  |   |                |   |                                     | Within 15days                       |
| 2.    | Single Transverse (or                    | w = width of crack                        | 0              | Nil, not discernible                                      | No Action                           | Charle on David                     |
|       | Diagonal) Crack intersecting with one or | L = length of crack<br>d = depth of crack | 1              | w < 0.2 mm, hair cracks                                   | Route and seal with epoxy.          | Staple or Dowel<br>Bar              |
|       | more joints                              | D = depth of slab                         | 2              | w = 0.2 - 0.5 mm,   | сролу.                              | Retrofit.                           |
|       |  | ,   |                | discernible from slow                                     | Within 7 days                       |                                     |
|       |  |   |                | vehicle   |                                     | Within 15 days                      |
|       |  |   | 3              | w = 0.5 - 3.0 mm,<br>discernible from fast<br>vehicle     | Route, seal and stitch, if L > 1 m. |                                     |
|       |  |   |                |   | Within 7 days                       |                                     |
|       |  |   | 4              | w = 3.0 - 6.0 mm  | Dowel Bar Retrofit.                 | Full Depth Repair Dismantle and     |
|       |  |   |                |   | Within 15 days                      | reconstruct affected.               |
|       |  |   |                |   |                                     | Portion with norms                  |





**Technical Schedule** 

|       |                                      | Measured   | Degree         |   | Repair /  | Action   |
|-------|--------------------------------------|--|----------------|---|---|--|
| S.No. | Type of Distress                     | Parameter  | of<br>Severity | Assessment Rating   | For the case d < D/2<br>Short Term  | For the case d > D/2 Long Term                             |
|       |                                      |  | 5              | w > 6 mm, usually associated with spelling, and/or slab rocking under traffic                     | Not Applicable, as it may be full depth   | and specifications - See Para 5.5 & 9.2 Within 15days      |
| 3     | Single Longitudinal Crack            | w = width of crack   | 0              | Nil, not discernible  | No Action   |  |
|       | intersecting with one or more joints | L = length of crack<br>d = depth of crack<br>D = depth of slab | 2              | w < 0.5 mm, discernable from slow moving vehicle  w = 0.5 - 3.0 mm, discernible from fast vehicle | Seal with epoxy, if L > 1 m.  Within 7 days  Route seal and stitch, if L > 1 m.  Within 15 days | Staple or dowel<br>bar<br>retrofit.<br>Within 15days       |
|       |                                      |  | 3              | w = 3.0 - 6.0 mm<br>w = 6.0 - 12.0 mm, usually<br>associated with spalling                        | Staple, if L > 1 m. Within 15 days  | Partial Depth<br>Repair<br>with stapling.<br>Within 15days |
|       |                                      |  |                |   | Not Applicable, as it<br>  may<br>  be full   |  |
|       |                                      |  | 5              | w > 12 mm, usually  | De Tutt   | Full Depth Repair  |





**Technical Schedule** 

|       |  | Measured           | Degree         |   | Repair /                                    | Action  |
|-------|--|--------------------|----------------|---|---|---|
| S.No. | Type of Distress                                     | Parameter          | of<br>Severity | Assessment Rating   | For the case d < D/2<br>Short Term          | For the case d > D/2 Long Term  |
|       |  |                    |                | associated with spalling, and/or slab rocking under traffic   | depth                                       | Dismantle and reconstruct affected portion as per norms and specifications - See Para 5.6.4 |
| 4     | Multiple Cracks intersecting                         | w = width of crack | 0              | Nil, not discernible  | No Action                                   | Within 15days   |
| 4     | Multiple Cracks intersecting with one or more joints | w - width of crack | 1 2            | w < 0.2 mm, hair cracks  w = 0.2 - 0.5 mm. discernible from slow vehicle                                | Seal, and stitch if L > l m. Within 15 days |   |
|       |  |                    | 3              | w = 0.5 - 3.0 mm,<br>discernible from fast<br>vehicle   | Full depth repair<br>within 15 days         | Dismantle,<br>Reinstate<br>Sub-base,  |
|       |  |                    | 4<br>5         | w = 3.0 - 6.0 mm panel<br>broken into 2 or 3 pieces<br>w > 6 mm and/or panel<br>broken into more than 4 |   | Reconstruct whole<br>slab as per<br>specifications<br>within<br>30 days                     |





**Technical Schedule** 

|       |   | Measured                                  | Degree         |   | Repair A                              | Action   |
|-------|---|---|----------------|---|---------------------------------------|--|
| S.No. | Type of Distress                              | Parameter                                 | of<br>Severity | Assessment Rating                             | For the case d < D/2<br>Short Term    | For the case d > D/2 Long Term   |
|       |   |   |                | pieces  |                                       |  |
| 5     | Corner Break                                  | w = width of crack<br>L = length of crack | 0              | Nil, not discernible                          | No Action                             |  |
|       |   |   | 1              | w < 0.5 mm; only 1 corner<br>broken           | Seal with low viscosity epoxy to      | Seal with epoxy<br>seal  |
|       |   |   | 2              | w < 1.5 mm; L < 0.6 m, only one corner broken | secure broken parts                   | with epoxy Within 7 days   |
|       |   |   | 3              | w < 1.5 mm; L < 0.6 m,<br>two corners broken  | Within 7 days                         | Within 7 days  |
|       |   |   | 4              | w > 1.5 mm; L > 0.6 m or three                | Partial Depth (Refer<br>Figure 8.3 of | Full depth repair  |
|       |   |   |                | corners broken                                | IRC:SP: 83-2008)                      |  |
|       |   |   | 5              | three or four corners<br>broken               | Within 15 days                        | Reinstate sub-<br>base, and<br>reconstruct the<br>slab as per norms<br>and specifications<br>within 30days |
| 6     | Punchout (Applicable to Continuous Reinforced |   | 0              | Nil, not discernible                          |                                       | No Action  |





**Technical Schedule** 

|       |                                | Measured<br>Parameter  | Degree         | Assessment Rating                    | Repair Action                           |   |
|-------|--------------------------------|--|----------------|--------------------------------------|---|---|
| S.No. | Type of Distress               |  | of<br>Severity |                                      | For the case d < D/2<br>Short Term      | For the case d > D/2 Long Term                                    |
|       | Concrete Pavement (CRCP) only) |  | 1              | w < 0.5 mm; L < 3 m/m2               |   | Seal with low   |
|       |                                |  | 2              | either w > 0.5 mm or L < 3 m/m2      | Not Applicable, as it may be full depth | viscosity epoxy to secure broken parts.                           |
|       |                                |  | 3              | w > 1.5 mm and L < 3<br>m/m2         |   | Within 15 days  |
|       |                                |  | 4              | w > 3 mm, L < 3 m/m2 and deformation |   | Full depth repair -<br>Cut out and<br>replace                     |
|       |                                |  | 5              | w > 3 mm, L > 3 m/m2 and deformation |   | damaged area<br>taking<br>care not to<br>damage<br>Reinforcement. |
|       |                                |  |                |                                      |   | Within 30days   |
| 7     | type surface                   | r = area damaged 0 surface/total surface of slab (%) h = maximum depth 1 of damage | 0              | Nil, not discernible                 | No Action                               |   |
|       |                                |  | 1              | r < 2 %                              | Local repair of areas<br>Damaged        |   |





**Technical Schedule** 

|       |   | Measured Degree   |                | Repair A                         | Action   |                                |
|-------|---|---|----------------|----------------------------------|--|--------------------------------|
| S.No. | Type of Distress  | Parameter   | of<br>Severity | Assessment Rating                | For the case d < D/2<br>Short Term               | For the case d > D/2 Long Term |
|       |   |   | 2              | r = 2 - 10 %                     | and liable to be damaged.  Within 15 days        |                                |
|       |   |   | 3              | r = 10-25%                       | Bonded Inlay, 2 or 3 slabs if                    |                                |
|       |   |   | 4              | r = 25 - 50 %                    | Affecting  |                                |
|       |   |   |                |                                  | Within 30 days                                   |                                |
|       |   |   | 5              | r > 50% and h > 25 mm            | Reconstruct slabs, 4 or more slabs if affecting. |                                |
|       |   |   |                |                                  | Within 30 days                                   |                                |
| 8     | Scaling r = damaged surface/total surface of slab (%) h = maximum depth of damage | surface/total<br>surface of slab (%)<br>h = maximum depth | 0              | Nil, not discernible             | Short Term No Action                             | Long Term                      |
|       |   | 1   | r < 2 %        | Local repair of areas<br>Damaged |  |                                |





**Technical Schedule** 

|       |                  | Measured           | Degree         |                    | Repair A                              | Action                         |
|-------|------------------|--------------------|----------------|--------------------|---------------------------------------|--------------------------------|
| S.No. | Type of Distress | Parameter          | of<br>Severity | Assessment Rating  | For the case d < D/2<br>Short Term    | For the case d > D/2 Long Term |
|       |                  |                    | 2              | r = 2 - 10 %       | and liable to be damaged.             |                                |
|       |                  |                    |                |                    | Within 7days                          |                                |
|       |                  |                    | 3              | r = 10 - 20%       | Bonded Inlay within<br>15             |                                |
|       |                  |                    | 4              | r = 10 - 30%       | Days                                  |                                |
|       |                  |                    | 5              | r>30 % and h> 25mm | Reconstruct slab<br>within<br>30 days |                                |
| 9     | Polished         | t = texture depth, | 0              |                    |                                       |                                |
|       | Surface/Glazing  | sand patch test    | 1              | t > 1 mm           | No action                             |                                |
|       |                  |                    | 2              | t = 1 - 0.6 mm     |                                       | Not Applicable                 |
|       |                  |                    | 3              | t = 0.6 - 0.3 mm   | Monitor rate of deterioration         |                                |
|       |                  |                    | 4              | t = 0.3 - 0.1 mm   | Diamond Grinding if<br>Affecting      |                                |





**Technical Schedule** 

|       |  | Measured   | Degree         |   | Repair A   | Action                         |  |
|-------|--|--|----------------|---|--|--------------------------------|--|
| S.No. | Type of Distress                               | Parameter  | of<br>Severity | Assessment Rating                               | For the case d < D/2<br>Short Term   | For the case d > D/2 Long Term |  |
|       |  |  | 5              | t < 0.1 mm                                      | 50% or more slabs in a  Continuous stretch of minimum  5 km.  Within 30 days |                                |  |
|       |  |  |                |   | Within 30 days   |                                |  |
| 10    | Popout (Small Hole),<br>Pothole Refer Para 8.4 | n = number/m2<br>d = diameter<br>h = maximum depth | 0              | d < 50 mm; h < 25 mm; n < 1 per 5 m2            | No action.   | Not Applicable                 |  |
|       |  | in maximum depth                                   | 1              | d = 50 - 100 mm; h < 50<br>mm; n < 1 per 5 m2   | Partial depth repair<br>65 mm deep.  |                                |  |
|       |  |  | 2              | d = 50 - 100 mm; h > 50<br>mm; n < 1 per 5 m2   | Within 15 days  Partial depth repair  110mm                                  |                                |  |
|       |  |  | 3              | d = 100 - 300 mm; h < 100<br>mm n < 1 per 5 m2  | i.e.10 mm more than  |                                |  |
|       |  |  | 4              | d = 100 - 300 mm; h > 100<br>mm; n < 1 per 5 m2 | the depth of the hole.   |                                |  |





**Technical Schedule** 

|       |                    | Measured<br>Parameter                   | Degree         |  | Repair Action  |                                |  |
|-------|--------------------|---|----------------|--|--|--------------------------------|--|
| S.No. | Type of Distress   |   | of<br>Severity | Assessment Rating  | For the case d < D/2<br>Short Term                             | For the case d > D/2 Long Term |  |
|       |                    |   | 5              | d > 300 mm; h > 100 mm:<br>n > 1 per 5 m2  | Within 30 days Full depth repair. Within 30 days               |                                |  |
| 11    | Joint Seal Defects | loss or damage<br>L = Length as % total | 0              | Difficult to discern.  | No action.   |                                |  |
|       |                    | joint length                            | 1              | Discernible, L< 25% but of little immediate consequence with regard to ingress of water or trapping incompressible material. | Clean joint, inspect<br>later.                                 | Not Applicable                 |  |
|       |                    |   | 2              | Notable. L > 25% insufficient protection against ingress of water and trapping incompressible material.                      | Clean and reapply sealant in Selected locations. Within 7 days |                                |  |
|       |                    |   | 4              | Severe; w > 3 mm<br>negligible protection<br>against ingress of water<br>and trapping  | Clean, widen and reseal the joint. Within 7 days               |                                |  |





**Technical Schedule** 

|       |  | Measured                                      | Degree         | Assessment Rating F      | Repair Action   |                                |
|-------|--|---|----------------|--------------------------|---|--------------------------------|
| S.No. | Type of Distress                           | Parameter                                     | of<br>Severity |                          | For the case d < D/2<br>Short Term                          | For the case d > D/2 Long Term |
|       |  |   |                | incompressible material. |   |                                |
| 12    | Spalling of Joints                         | w = width on either<br>side of the joint L =  | 0              | Nil, not discernible     | No action.  | For the case d >               |
|       |  | length of spalled portion (as % joint length) | 1              | w < 10 mm                | Apply low viscosity epoxy resin/ mortar in cracked portion. |                                |
|       |  |   | 2              | w = 10 - 20 mm, L < 25%  | Within 7 days   |                                |
|       |  |   | 3              | w = 20 - 40 mm, L > 25%  | Partial Depth Repair.                                       | Not Applicable                 |
|       |  |   |                | W = 20 40 Hill, E > 25%  |   | Not Applicable                 |
|       |  |   | 4              | w = 40 - 80 mm, L > 25%  | 30 - 50 mm deep, h<br>= w + 20% of<br>w, within 30 days     |                                |
|       |  |   | 5              | w > 80 mm, and L > 25%   | 50 - 100 mm deep repair.                                    |                                |
|       |  |   |                |                          | H = w + 20% of w.   |                                |
|       |  |   |                |                          | Within 30 days  |                                |
| 13    | Faulting (or Stepping) in Cracks or Joints | f = difference of level                       | 0              | not discernible, < 1 mm  | No action.  | No action.                     |





**Technical Schedule** 

|       |                    | Measured                          | Degree         |                      | Repair /  |                                  |
|-------|--------------------|-----------------------------------|----------------|----------------------|---|----------------------------------|
| S.No. | Type of Distress   | Parameter                         | of<br>Severity | Assessment Rating    | For the case d < D/2<br>Short Term  | For the case d > D/2 Long Term   |
|       |                    |                                   | 1              | f < 3 mm             |   |                                  |
|       |                    |                                   | 2              | f = 3 - 6 mm         | Determine cause and observe, take action for diamond grinding                   | Replace the slab as appropriate. |
|       |                    |                                   | 3              | f = 6 - 12 mm        | Diamond Grinding  | Within 30days                    |
|       |                    |                                   | 4              | f= 12 - 18 mm        | Raise sunken slab.  | Replace the slab                 |
|       |                    |                                   | 5              | f> 18 mm             | Strengthen sub-<br>grade and sub-base<br>by grouting and<br>raising sunken slab | as appropriate.                  |
|       |                    |                                   |                |                      | Taising sunich stab   | Within 30days                    |
| 14    | Blowup or Buckling | h = vertical<br>displacement from | 0              | Nil, not discernible | No Action   |                                  |
|       |                    | normal profile                    | 1              | h < 6 mm             |   |                                  |
|       |                    |                                   | 2              | h = 6 - 12 mm        | Install Signs to Warn   |                                  |





**Technical Schedule** 

|       |                  | Measured   | Degree         |   | Repair A  | Action                         |
|-------|------------------|--|----------------|---|---|--------------------------------|
| S.No. | Type of Distress | Parameter  | of<br>Severity | Assessment Rating   | For the case d < D/2<br>Short Term  | For the case d > D/2 Long Term |
|       |                  |  | 3 4            | h = 12 - 25 mm h > 25 mm shattered slabs, ie 4 or more pieces | Traffic within 7 days  Full Depth Repair. Within 30 days  Replace broken slabs.  Within 30 days |                                |
| 15    | Depression       | h = negative vertical<br>displacement from<br>normal profile L =length | 0              | Not discernible, h < 5 mm                                     | No action.  |                                |
|       |                  |  | 2              | h = 5 - 15 mm<br>h = 15-30 mm, Nos <20%<br>joints             | Install Signs to Warn<br>Traffic<br>within 7 days   | Not Applicable                 |
|       |                  |  | 3              | h = 30 - 50 mm  |   |                                |





**Technical Schedule** 

|       |                  | Measured                                   | Degree         |                                 | Repair A  | ction                          |
|-------|------------------|--|----------------|---------------------------------|---|--------------------------------|
| S.No. | Type of Distress | Parameter                                  | of<br>Severity | Assessment Rating               | For the case d < D/2<br>Short Term                    | For the case d > D/2 Long Term |
|       |                  |  | 4              | h > 50 mm or > 20% joints       | Strengthen subgrade.                                  |                                |
|       |                  |  | 5              | h > 100 mm                      | Reinstate pavement<br>at normal level if L <<br>20 m. |                                |
|       |                  |  |                |                                 | Within 30 days  |                                |
| 16    | Heave            | h = positive vertical<br>displacement from | 0              | Not discernible. h < 5 mm       | No action.  |                                |
|       |                  | normal profile.  L = length                | 1              | h = 5 - 15 mm                   | Follow up.  |                                |
|       |                  |  | 2              | h = 15 - 30 mm, Nos <20% joints | Install Signs to Warn<br>Traffic                      |                                |
|       |                  |  | 3              | h = 30 - 50 mm                  | within 7 days   | scrabble                       |
|       |                  |  | 4              | h > 50 mm or > 20% joints       | Stabilise subgrade.<br>Reinstate pavement             |                                |
|       |                  |  | 5              | h > 100 mm                      | at normal level if length < 20 m.                     |                                |
|       |                  |  |                |                                 | Within 30 days  |                                |





**Technical Schedule** 

|       |                          | Measured                          | Degree         |                            | Repair /   |  |
|-------|--------------------------|-----------------------------------|----------------|----------------------------|--|--|
| S.No. | Type of Distress         | Parameter                         | of<br>Severity | Assessment Rating          | For the case d < D/2<br>Short Term               | For the case d > D/2 Long Term           |
|       |                          |                                   |                |                            |  |  |
| 17    | Bump                     | h = vertical<br>displacement from | 0              | h < 4 mm                   | No action  |  |
|       |                          | normal profile                    | 1              | h = 4 - 7 mm               | Grind, in case of new construction within 7 days | Construction Limit for New Construction. |
|       |                          |                                   |                |                            | within 7 days                                    |  |
|       |                          |                                   | 3              | h = 7 - 15 mm              | Grind, in case of ongoing Maintenance            | Replace in case of new construction.     |
|       |                          |                                   |                |                            | within 15 days                                   | Within 30days                            |
|       |                          |                                   | 4              | h > 15 mm                  | Full Depth Repair.                               | Full Depth Repair.                       |
|       |                          |                                   |                |                            | Within 30 days                                   | Within 30days                            |
|       |                          |                                   |                |                            | Short Term                                       | Long Term                                |
|       |                          |                                   | 0              | Nil, not discernible < 3mm | No Action  |  |
| 18    | Lane to Shoulder Dropoff | f = difference of level           | 1              | f = 3 - 10 mm              | Spot repair of shoulder                          |  |





**Technical Schedule** 

|       |                  | Manageral  | Degree         |                                   | Repair /                                | Action   |
|-------|------------------|--|----------------|-----------------------------------|---|--|
| S.No. | Type of Distress | Measured<br>Parameter  | of<br>Severity | Assessment Rating                 | For the case d < D/2<br>Short Term      |  |
|       |                  |  | 2              | f = 10 - 25 mm                    | within 7 days                           |  |
|       |                  |  | 3              | f = 25 - 50 mm                    | Fill up shoulder                        | For any 100 m<br>Stretch   |
|       |                  |  | 4              | f = 50 - 75 mm                    | within 7 dayss                          | Reconstruct<br>shoulder, if<br>affecting 25% or                      |
|       |                  |  | 5              | f > 75 mm                         |   | more of stretch. Within 30days                                       |
|       |                  |  | Drair          | nage                              |   |  |
| 19    | Pumping          | quantity of fines and<br>water expelled through<br>open joints and cracks<br>Nos | 0              | not discernible                   | No Action                               |  |
|       |                  |  | 1 to 2         | slight/ occasional Nos < 10%      | Repair cracks and joints Without delay. | Inspect and repair sub-drainage at distressed sections and upstream. |
|       |                  |  | 3 to 4         | appreciable/ Frequent<br>10 - 25% | Lift or jack slab within 30 days.       | and appercam.  |
|       |                  |  |                |                                   |   |  |





**Technical Schedule** 

|       |                  | Measured                                   | Degree         |   | Repair A  | Action                                 |
|-------|------------------|--|----------------|---|---|--|
| S.No. | Type of Distress | Parameter                                  | of<br>Severity | Assessment Rating                               | For the case d < D/2<br>Short Term  | For the case d > D/2 Long Term         |
|       |                  |  | 5              | abundant, crack<br>development > 25%            | Repair distressed pavement sections. Strengthen subgrade and subbase. Replace slab.  Within 30 days |  |
| 20    | Ponding          | Ponding on slabs due to blockage of drains | 0-2            | No discernible problem                          | No action.  |  |
|       |                  |  | 3 to 4         | Blockages observed in drains, but water flowing | Clean drains etc<br>within 7 days, Follow<br>up   | Action required to stop water damaging |
|       |                  |  | 5              | Ponding, accumulation of water observed         | -do   | foundation within 30 days.             |

Table -3: Maintenance Criteria for Safety Related Items and Other Furniture Items:

| Asset<br>Type | Performance<br>Parameter   | Level of Service (LOS)                                  | Frequency of Measurement | Testing<br>Method      | Recommended<br>Remedial<br>measures   | Time limit for Rectification    | Specifications<br>and<br>Standards |
|---------------|----------------------------|---|--------------------------|------------------------|---------------------------------------|---------------------------------|------------------------------------|
| Highway       | Availability of Safe Sight | As per IRC SP:84-2014, a minimum of safe stopping sight | Monthly                  | Manual<br>Measurements | Removal of obstraction hours, in case | ruction within 24 of sight line | IRC:SP<br>84-2014                  |





**Technical Schedule** 

| Asset<br>Type       | Performance<br>Parameter | Level                                | l of Service                                     | (LOS)  | Frequency of Measurement | Testing<br>Method                                   | Recommended<br>Remedial<br>measures  | Time limit for Rectification   | Specifications<br>and<br>Standards |  |
|---------------------|--------------------------|--------------------------------------|--|--|--------------------------|---|--|--|------------------------------------|--|
|                     | Distance                 | distance<br>throughou                | shall be<br>t.                                   | available                                    |                          | with 0 dometer                                      | _  | such as trees, temporary   |                                    |  |
|                     |                          | Design<br>Speed,<br>kmph             | Desirable<br>Minimum<br>Sight<br>Distance<br>(m) | Safe<br>Stopping<br>Sight<br>Distance<br>(m) |                          | along with<br>video/ image<br>backup                | encroachments. In case of permanent structure or design deficiency: Removal of obstruction/improvement of deficiency at the earliest Speed Restriction boards and suitable |  |                                    |  |
|                     |                          | 100                                  | 360  | 180  |                          |   | traffic calming transverse bar   |  |                                    |  |
|                     |                          | 80                                   | 260  | 130  |                          |   | etc. shall be applied during the period of rectification.  |  |                                    |  |
| Pavement<br>Marking | Wear                     | <70% of                              | marking rer                                      | maining                                      | Bi-<br>Annually          | Visual Assessment as per Annexure-F of IRC:35- 2015 | Re - painting  | Cat-1 Defect -<br>within 24 hours<br>Cat-2 Defect -<br>within 2 months | IRC:35-<br>2015                    |  |
|                     | Day time<br>Visibility   | Time<br>130mcd/m                     | Bituminous F                                     | d -  | Monthly                  | As per<br>Annexure-D<br>of<br>IRC:35-2015           | Re - painting  Cat-1 Defect - within 24 hours Cat-2 Defect - within 2 months   |  | IRC:35-<br>2015                    |  |
|                     | Night Time<br>Visibility | Initial<br>Performan<br>reflectivity | and<br>ce for D<br>y during nigh                 | Minimum<br>ry Retro<br>at time:              | Bi-Annually              | As per<br>Annexure-E of<br>IRC:35-2015              | Re - painting  | Cat-1 Defect -<br>within 24 hours<br>Cat-2 Defect -                    | IRC:35-2015                        |  |





**Technical Schedule** 

| Asset<br>Type | Performance<br>Parameter | Level  | of Service   | (LOS)      | Frequency of Measurement | Testing<br>Method  | Recommended<br>Remedial<br>measures   | Time limit for Rectification   | Specifications<br>and<br>Standards |
|---------------|--------------------------|--|--|------------|--------------------------|--|---|--|------------------------------------|
|               |                          | Design<br>Speed                              | (RL)<br>Reflectivit<br>(mcd/m2/  |            |                          |  |   | within 2 months  |                                    |
|               |                          | Up to 65                                     | 200  | 80         |                          |  |   |  |                                    |
|               |                          | 65-100                                       | 250  | 120        |                          |  |   |  |                                    |
|               |                          | Above<br>100                                 | 350  | 150        |                          |  |   |  |                                    |
|               |                          |  | and<br>ce for Nigh<br>et condition   |            |                          |  |   |  |                                    |
| Signs         | Shape and<br>Position    | IRC:67-<br>2012.<br>Signboard<br>visible for | Position as positi | early      | Daily                    | Visual with<br>video/image<br>backup                         | Improvement of shape, in case if shape is damaged.  Relocation as Per requirement |  | IRC:67-2012                        |
|               | Retro<br>reflectivity    | As per spe                                   | ecifications i<br>2012   | in IRC:67- | Bi-Annually              | Testing of Each signboard using Retro Reflectivity Measuring | Change of signboard   | 48 hours in case of Mandatory Signs, Cautionary and Informatory Signs (Single and Dual post signs) 1 | IRC:67-2012                        |





**Technical Schedule** 

| Asset<br>Type     | Performance<br>Parameter                             | Level of Service (LOS)   | Frequency of Measurement | Testing<br>Method                          | Recommended<br>Remedial<br>measures | Rectification                                   | Specifications<br>and<br>Standards   |
|-------------------|--|--|--------------------------|--|-------------------------------------|---|--------------------------------------|
|                   |  |  |                          | Device. In accordance with ASTM D 4956-09. |                                     | Month in case of Gantry/ Cantilever Sign boards |                                      |
| Kerb              | Kerb Height  | As per IRC 86:1983 depending upon type of Kerb   | Bi-Annually              | Use of<br>distance<br>measuring<br>tape    | Raising Kerb<br>Height              | Within 1 Month                                  | IRC 86:1983                          |
|                   | Kerb Painting  | Functionality: Functioning of Kerb painting as intended  | Daily                    | Visual with video/image backup             | Kerb<br>Repainting                  | Within 7-days                                   | IRC 35:2015                          |
|                   | Reflective<br>Pavement<br>Markers<br>(Road<br>Studs) | Numbers and Functionality as per specifications in IRC:SP:84-2014 and IRC:35-2015, unless specified in Schedule-B. | Daily                    | Counting                                   | New<br>Installation                 | Within 2 months                                 | IRC:SP:84-<br>2014, IRC:35-<br>2015  |
| Other             | Pedestrian<br>Guardrail                              | Functionality: Functioning of guardrail as intended  | Daily                    | Visual with video/image backup             | Rectification                       | Within 15 days                                  | IRC:SP:84-<br>2014                   |
| Road<br>Furniture | Traffic<br>Safety<br>Barriers                        | Functionality: Functioning of Safety Barriers as intended  | Daily                    | Visual with video/image backup             | Rectification                       | Within 7 days                                   | IRC:SP:84-<br>2014,<br>IRC:119- 2015 |
|                   | End<br>Treatment of<br>Traffic<br>Safety<br>Barriers | Functionality: Functioning of End Treatment as intended  | Daily                    | Visual with video/image backup             | Rectification                       | Within 7 days                                   | IRC:SP:84-<br>2014,<br>IRC:119- 2015 |





**Technical Schedule** 

| Asset<br>Type      | Performance<br>Parameter          | Level of Service (LOS)  | Frequency of Measurement | Testing<br>Method                                      | Recommended<br>Remedial<br>measures  | Time limit for Rectification | Specifications<br>and<br>Standards |
|--------------------|-----------------------------------|---|--------------------------|--|--------------------------------------|------------------------------|------------------------------------|
|                    | Attenuators                       | Functionality: Functioning of Attenuators as intended                 | Daily                    | Visual with video/image backup                         | Rectification                        | Within 7 days                | IRC:SP-2014,<br>IRC:119- 2015      |
|                    | Guard Posts<br>and<br>Delineators | Functionality: Functioning of Guard Posts and Delineators as intended | Daily                    | Visual with video/image backup                         | Rectification                        | Within 15 days               | IRC: 79 - 1981                     |
|                    | Overhead<br>Sign<br>Structure     | Overhead sign structure shall be structurally adequate                | Daily                    | Visual with video/image backup                         | Rectification                        | Within 15 days               | IRC:67-2012                        |
|                    | Traffic<br>Blinkers               | Functionality: Functioning of Traffic Blinkers as intended            | Daily                    | Visual with video/image backup                         | Rectification                        | Within 7 days                | IRC:SP:84-<br>2014                 |
| Highway            | Highway<br>Lights                 | Illumination: Minimum 40 Lux illumination on the road surface         | Daily                    | The illumination level shall be measured with luxmeter | Improvement<br>in Lighting<br>System | 24 hours                     | IRC:SP:84-<br>2014                 |
| Lighting<br>System |                                   | No major failure in the lighting system                               | Daily                    | -  | Rectification of failure             | 24 hours                     | IRC:SP:84-<br>2014                 |
|                    |                                   | No minor failure in the lighting system                               | Monthly                  | -  | Rectification of failure             | 8 hours                      | IRC:SP:84-<br>2014                 |
|                    | Toll Plaza<br>Canopy<br>Lights    | Minimum 40 Lux illumination on the road surface                       | Daily                    | The illumination level shall be measured with luxmeter | Improvement<br>in Lighting<br>System | 24 hours                     | IRC:SP:84-<br>2014                 |





**Technical Schedule** 

| Asset<br>Type                         | Performance<br>Parameter   | Level of Service (LOS)  | Frequency of Measurement | Testing<br>Method                    | Recommended<br>Remedial<br>measures                                | Rectification  | Specifications<br>and<br>Standards |
|---------------------------------------|--|---|--------------------------|--------------------------------------|--|----------------|------------------------------------|
|                                       |  | No major/minor failure in the lighting system   | Daily                    | -                                    | Rectification of failure   | 8 hours        | IRC:SP:84-<br>2014                 |
| Trees and<br>Plantation               | Obstruction in a minimum head-room of 5.5 m above carriageway or obstruction in visibility of road signs | No obstruction due to trees   | Monthly                  | Visual with<br>video/image<br>backup | Removal of trees   | Immediate      | IRC:SP:84-<br>2014                 |
| including<br>median<br>plantatio<br>n | Deterioration<br>in health of<br>trees and<br>bushes   | Health of plantation shall be as per requirement of specifications & instructions issued by Authority from time to time | Daily                    | Visual with<br>video/image<br>backup | Timely watering and treatment. Or Replacement of Trees and Bushes. | Within 90 days | IRC:SP:84-<br>2014                 |
|                                       | Vegetation<br>affecting<br>sight line and<br>road<br>structures  | Sight line shall be free from obstruction by vegetation   | Daily                    | Visual with<br>video/image<br>backup | Removal of trees   | Immediate      | IRC:SP 84-<br>2014                 |
| Rest<br>Areas                         | Cleaning of toilets  | -   | Daily                    | -                                    | -  | Every 4 hours  |                                    |





**Technical Schedule** 

| Asset<br>Type                                | Performance<br>Parameter                                | Level of Service (LOS)   | Frequency of Measurement | Testing<br>Method | Recommended<br>Remedial<br>measures | Time limit for Rectification | Specifications<br>and<br>Standards |
|--|---|--|--------------------------|-------------------|-------------------------------------|------------------------------|------------------------------------|
|  | Defects in electrical, water and sanitary installations | -  | Daily                    | -                 | Rectification                       | 24 hours                     |                                    |
| Other Project Facilities and Approac h roads | pedestrian factorists, can                              | eterioration in Approach Roads, cilities, truck lay-bys, bus-bays, attle crossings, Traffic Aid Posts, sts and other works | Daily                    | -                 | Rectification                       | 15 days                      | IRC:SP 84-<br>2014                 |

| Asset<br>Type             | Performance<br>Parameter                       | Level of<br>Service (LOS)                              | Frequency of<br>Measurement                                | Testing Method   | Recommended<br>Remedial<br>measures  | Time limit for Rectification  | Specifications and Standards                                |
|---------------------------|--|--|--|--|--|---|---|
| Pipe/box/slab<br>culverts | Free waterway/<br>unobstructed<br>flow section | 85% of culvert<br>normal flow<br>area to<br>available. | 2 times in a<br>year (before<br>and after<br>rainy season) | Inspection by Bridge Engineer as per IRC SP: 35-1990 and recording of depth of silting and area of vegetation. | Cleaning silt up soils and debris in culvert barrel after rainy season, removal of bushes and vegetation, U/s of barrel, under barrel and D/s of barrel before rainy season. | 15 days before onset of monsoon and within 30 days after end of rainy season. | IRC 5-2015,<br>IRC SP:40-<br>1993 and<br>IRC SP:13-<br>2004 |





**Technical Schedule** 

| Asset<br>Type | Performance<br>Parameter                 | Level of<br>Service (LOS)   | Frequency of<br>Measurement                                | Testing Method   | Recommended<br>Remedial<br>measures   | Time limit for Rectification  | Specifications and Standards   |
|---------------|--|---|--|--|---|---|--|
|               | Leak-proof<br>expansion<br>joints if any | No leakage<br>through<br>expansion joints   | Bi-Annually  | Physical inspection of expansion joints as per IRC SP: 35-1990 if any, for leakage strains on walls at joints. | Fixing with sealant suitably  | 30 days or<br>before onset<br>of rains<br>whichever<br>comes<br>earlier                 | IRC SP:40-<br>1993 and IRC<br>SP:69-2011                             |
|               | Structurally sound                       | Spalling of concrete not more than 0.25 sqm  Delamination of concrete not more than 0.25 sq.m.  Cracks wider than 0.3 mm not more than 1m aggregatelength | Bi-Annually  | Detailed inspection of all components of culvert as per IRC SP:35-1990 and recording the defects               | Repairs to<br>spalling,<br>cracking,<br>delamination,<br>rusting shall be<br>followed<br>as per IRC:SP:40-<br>1993. | 15 days   | IRC SP 40-<br>1993 and<br>MORTH<br>Specification<br>s clause<br>2800 |
|               | Protection<br>works in<br>good condition | Damaged of<br>rough stone<br>apron or bank<br>revetment not<br>more than 3<br>sqm, damage to  | 2 times in a<br>year (before<br>and after<br>rainy season) | Condition<br>survey as<br>per IRC SP:35-<br>1990   | Repairs to<br>damaged<br>aprons and<br>pitching   | 30 days<br>after defect<br>observation<br>or 2 weeks<br>before onset<br>of rainy season | IRC: SP 40-<br>1993 and<br>IRC:SP:13-<br>2004.                       |





**Technical Schedule** 

| Asset<br>Type  | Performance<br>Parameter   | Level of<br>Service (LOS)   | Frequency of<br>Measurement | Testing Method  | Recommended<br>Remedial<br>measures   | Time limit for Rectification | Specifications and Standards                                    |
|--|--|---|-----------------------------|---|---|------------------------------|---|
|  |  | solid apron<br>(concreteapron)<br>not more than 1<br>sqm                              |                             |   |   | whichever is earlier.        |   |
| Bridges<br>including ROBs<br>Flyover etc. as<br>applicable | Riding<br>quality or<br>user<br>comfort                          | No pothole in<br>wearing coat on<br>bridge deck                                       | Daily                       | Visual<br>inspection as<br>per IRC SP:35-<br>1990                       | Repairs to BC or<br>wearing<br>coat   | 15 days                      | MORT&H<br>Specification<br>2811                                 |
| Bridge -Super  | Bumps  | No bump at expansion joint  | Daily                       | Visual<br>inspection as<br>per IRC SP:35-<br>1990                       | Repairs to BC on either side of expansion joints, profile correction course on approach slab in case of settlement to approach embankment | 15 days                      | MORT&H<br>Specification<br>3004.2 &<br>2811.                    |
| Structure  | User safety<br>(condition of<br>crash barrier<br>and guard rail) | No damaged or<br>missing stretch<br>of crash barrier<br>or pedestrian<br>hand railing | Daily                       | Visual inspection and detailed condition survey as per IRC SP: 35-1990. | Repairs and replacement of safety barriers as the case may be   | 3 days                       | IRC: 5-1998,<br>IRC SP: 84-<br>2014 and<br>IRC SP: 40-<br>1993. |
|  | Rusted reinforcement   | Not more than 0.25 sq.m   | Bi- Annually                | Detailed<br>condition<br>survey as per                                  | All the corroded reinforcement shall need to be   | 15 days                      | IRC SP: 40-<br>1993 and<br>MORTH                                |





**Technical Schedule** 

| Asset<br>Type | Performance<br>Parameter                     | Level of<br>Service (LOS)        | Frequency of<br>Measurement | Testing Method   | Recommended<br>Remedial<br>measures  | Time limit for Rectification | Specifications and Standards                               |
|---------------|--|----------------------------------|-----------------------------|--|--|------------------------------|--|
|               | Spalling of concrete                         | Not more than 0.50 sq.m          |                             | IRC SP: 35-1990<br>using Mobile<br>Bridge  | thoroughly<br>cleaned from<br>rusting and  |                              | Specification 1600.  |
|               | Delamination                                 | Not more than 0.50 sq.m          |                             | Inspection Unit  | applied with anti-<br>corrosive coating<br>before carrying<br>out the repairs to<br>affected concrete<br>portion with<br>epoxy mortar /<br>concrete. |                              |  |
|               | Cracks<br>wider than<br>0.30 mm              | Not more than<br>1m total length | Bi-<br>Annually             | Detailed condition survey as per IRC SP: 35-1990 using Mobile Bridge Inspection Unit                   | Grouting with epoxy mortar, investigating causes for cracks development and carry out necessary rehabilitation                                       | 48 Hours                     | IRC SP: 40-<br>1993 and<br>MORTH<br>Specification<br>2800. |
|               | Rainwater<br>seepage<br>through<br>deck slab | Leakage - nil                    | Quarterly                   | Detailed<br>condition<br>survey as per<br>IRC SP: 35-1990<br>using Mobile<br>Bridge<br>Inspection Unit | Grouting of deck<br>slab at<br>leakage areas,<br>waterproofing,<br>repairs to<br>drainage spouts   | 1 months                     | MORTH specifications 2600 & 2700                           |
|               | Deflection due to                            | Within design limits.            | Once in every 10            | Load test<br>method  | Carry out major rehabilitation   | 6 months                     | IRC SP: 51-<br>1999.                                       |





**Technical Schedule** 

| Asset<br>Type | Performance<br>Parameter                                | Level of<br>Service (LOS)   | Frequency of<br>Measurement   | Testing Method  | Recommended<br>Remedial<br>measures                               | Time limit for Rectification | Specifications and Standards                   |
|---------------|---|---|---|---|---|------------------------------|--|
|               | permanent<br>loads and live<br>loads                    |   | years for<br>spans more<br>than 40 m  |   | works on bridge<br>to retain original<br>design loads<br>capacity |                              |  |
|               | Vibrations<br>in bridge<br>deck due to<br>moving trucks | Frequency of<br>vibrations shall<br>not be more<br>than 5 Hz  | Once in every 5 years for spans more than 30m and every 10 years for spans between 15 to 30 m | Laser<br>displacement<br>sensors or laser<br>vibro-meters                           | Strengthening of super structure                                  | 4 months                     | AASHTO<br>LRFD<br>specifications               |
|               | Leakage in Expansion joints                             | No damage to elastomeric sealant compound in strip seal expansion joint, no leakage of rain water through expansion joint in case of buried and asphalt plug and copper strip joint | Bi-<br>Annually   | Detailed condition survey as per IRC SP:35-1990 using Mobile Bridge Inspection Unit | Replace of seal in expansion joint                                | 15 days                      | MORTH specifications 2600 and IRC SP: 40-1993. |
|               | Debris and dust in                                      | No dust or<br>debris in   | Monthly   | Detailed condition  | Cleaning of expansion   | 3 days                       | MORTH specification                            |





**Technical Schedule** 

| Asset<br>Type           | Performance<br>Parameter                         | Level of<br>Service (LOS)   | Frequency of<br>Measurement | Testing Method   | Recommended<br>Remedial<br>measures   | Time limit for Rectification | Specifications and Standards                               |
|-------------------------|--|---|-----------------------------|--|---|------------------------------|--|
|                         | strip seal<br>expansion<br>joint                 | expansion joint gap.  |                             | survey as per<br>IRC SP:35-1990<br>using Mobile<br>Bridge<br>Inspection Unit         | joint gaps<br>thoroughly  |                              | s 2600 and IRC<br>SP: 40-<br>1993.                         |
|                         | Drainage<br>spouts                               | No down take pipe missing/broken below soffit of the deck slab. No silt, debris, clogging of drainage spout collection chamber. | Bi-<br>Annually             | Detailed condition survey as per IRC SP: 35-1990 using Mobile Bridge Inspection Unit | Cleaning of drainage spouts thoroughly. Replacement of missing/broken down take pipes with a minimum pipe extension of 500mm below soffit of slab. Providing sealant around the drainage spout if any leakages observed | 3 days                       | MORTH specification 2700.                                  |
| Bridge-<br>substructure | Cracks/ spalling<br>of concrete/<br>Rusted steel | No cracks,<br>spalling of<br>concrete and<br>rusted steel   | Bi-Annually                 | Detailed condition survey as per IRC SP: 35-1990 using Mobile Bridge Inspection Unit | All the corroded reinforcement shall need to be thoroughly cleaned from rusting and applied with anticorrosive coating  | 30 days                      | IRC SP: 40-<br>1993 and<br>MORTH<br>specification<br>2800. |





**Technical Schedule** 

| Asset<br>Type         | Performance<br>Parameter          | Level of<br>Service (LOS)   | Frequency of<br>Measurement | Testing Method   | Recommended<br>Remedial<br>measures  | Time limit for<br>Rectification | Specifications and Standards   |
|-----------------------|-----------------------------------|---|-----------------------------|--|--|---------------------------------|--|
|                       | Bearings                          | Delaminating of bearing reinforcement not more than 5%, cracking or tearing of rubber not more than 2 locations per side, no rupture of | Bi-Annually                 | Detailed<br>condition<br>survey as per<br>IRC SP: 35-1990<br>using Mobile<br>Bridge<br>Inspection Unit | before carrying out repairs to substructure by grouting/guniting and micro concreting depending on type of defect noticed  In case of failure of even one bearing on any pier/abutment, all the bearings on that pier/abutment shall be replaced, in order to get uniform load | 3 months                        | MORTH<br>specificatio<br>n 2810 and<br>IRC SP: 40-<br>199.             |
| Bridge<br>Foundations | Scouring<br>around<br>foundations | reinforcement or rubber  Scouring shall not be lower than maximum scour level for the bridge  | Bi-Annually                 | Condition<br>survey<br>and visual<br>Inspection as<br>per IRC SP:35-<br>1990 using                     | transfer on<br>to bearings.<br>suitable<br>protection<br>works around<br>pier/abutment   | 1 months                        | IRC SP: 40-<br>1993, IRC<br>83-2014,<br>MORTH<br>specification<br>2500 |





**Technical Schedule** 

| Asset<br>Type | Performance<br>Parameter                 | Level of<br>Service (LOS)  | Frequency of<br>Measurement                       | Testing Method  | Recommended<br>Remedial<br>measures     | Time limit for Rectification   | Specifications and Standards               |
|---------------|--|--|---|---|---|--|--|
|               | Protection<br>works in good<br>condition | Damaged of rough stone apron or bank revetment not more than 3 sq.m, damage to solid apron (concrete apron) not more than 1 sq.m | 2 times in a year (before and after rainy season) | Mobile Bridge Inspection Unit. In case of oubt, use Underwater camera for inspection of deep wells in major Rivers.  Condition survey as per IRC SP:35-1990 | Repairs to damaged aprons and pitching. | 30 days After defect observation or 2 weeks before onset of rainy season whichever is earlier. | IRC: SP 40-<br>1993 and<br>IRC:SP:13-2004. |

**Note:** Any Structure during the entire contract period which is found that does not complies with all requirements of this Table will be prepared, rehabilitated or even reconstructed under the scope of the contractor.





Time limit for repair/

**Technical Schedule** 

Table 4: Maintenance Criteria for Structures and Culverts:

Table 5: Maintenance Criteria for Hill Roads

In addition to above, for hill roads the following provisions for maintenance is also to done.

| ,          |                                       |                        |  |  |  |  |  |
|------------|---------------------------------------|------------------------|--|--|--|--|--|
| Hill Roads |                                       |                        |  |  |  |  |  |
| (i)        | Damage to Retaining wall/ Breast wall | 7 (Seven) days         |  |  |  |  |  |
| (ii)       | Landslides requiring clearance        | 12 (Twelve) hours      |  |  |  |  |  |
| (iii)      | Snow requiring clearance              | 24 (Twenty Four) hours |  |  |  |  |  |

Note: For all tables 1 to 5 above, latest BIS & IRC standards (even those not indicated herewith)

along with MoRTH specifications shall be binding for all maintenance activities.

# A. Flexible Pavement

|               | Nature of Defect or deficiency  | rectification                      |
|---------------|---|------------------------------------|
| (b) Cr        | anular earth choulders, side clanes, drains and   |                                    |
| (b) Gr<br>(i) | anular earth shoulders, side slopes, drains and of Variation by more than 1 % in the prescribed | 7 (seven) days                     |
| (1)           | slope of camber/cross fall (shall not be less   | 7 (seven) days                     |
|               | than the camber on the main carriageway)  |                                    |
| (;;)          |   | 7 (sayan) days                     |
| (ii)          | Edge drop at shoulders exceeding 40 mm  Variation by more than 15% in the prescribed            | 7 (seven) days<br>30 (thirty) days |
| (iii)         | ·   | 30 (thirty) days                   |
| (3.4)         | side (embankment) slopes  | 7 (20)(20) dove                    |
| (iv)          | Rain cuts/gullies in slope  | 7 (seven) days                     |
| (v)           | Damage to or silting of culverts and side drains  | 7 (seven) days                     |
| (vi)          | Desilting of drains in urban/semi- urban areas  | 24 (twenty four) hours             |
| (vii)         | Railing, parapets, crash barriers   | 7 (seven) days (Restore            |
|               |   | immediately if causing safety      |
|               |   | hazard)                            |
|               | nd side furniture including road sign and paveme  |                                    |
| (i)           | Damage to shape or position, poor visibility or   | 48 (forty eight) hours             |
|               | loss of retro- reflectivity   |                                    |
| (ii)          | Painting of km stone, railing, parapets, crash  | As and when required/ Once         |
|               | barriers  | every year                         |
| (iii)         | Damaged/missing signs road requiring  | 7 (seven) days                     |
|               | replacement   |                                    |
| (vi)          | Damage to road mark ups   | 7 (seven) days                     |
|               | nd lighting   |                                    |
| (i)           | Any major failure of the system   | 24 (twenty four) hours             |
| (ii)          | Faults and minor failures   | 8 (eight) hours                    |
| (e) Tre       | es and plantation   |                                    |
| (i)           | Obstruction in a minimum head- room of 5 m  | 24 (twenty four)hours              |
|               | above carriageway or obstruction in visibility  |                                    |
|               | of  |                                    |
|               | road signs  |                                    |
| (ii)          | Removal of fallen trees from carriageway  | 4 (four) hours                     |
| (iii)         | Deterioration in health of trees and bushes   | Timely watering and treatment      |
| (vi)          | Trees and bushes requiring replacement  | 30 (thirty) days                   |
| (v)           | Removal of vegetation affecting sight line and road structures                                  | 15 (fifteen) days                  |
| (f) Res       | t area  |                                    |
|               |   |                                    |






**Technical Schedule** 

| (i)      | Cleaning of toilets   | Every 4 (four) hours  |
|----------|---|---|
| (ii)     | Defects in electrical, water and sanitary   | 24 (twenty four) hours  |
| ( )      | installations   | (3.7.5)   |
| (g) [To  | ll Plaza]   |   |
| (h)      | Other Project Facilities and Approach roads   |   |
| (i)      | Damage in approach roads, pedestrian facilities, truck lay- byes, bus-bays, bus-shelters, cattle crossings, [Traffic Aid Posts, Medical Aid | 15 (fifteen) days   |
| (::)     | Posts] and service roads  | 4 (fa.m) haves  |
| (ii)     | Damaged vehicles or debris on the road  | 4 (four) hours  |
| (iii)    | Malfunctioning of the mobile crane  | 4 (four) hours  |
| Bridges  |   |   |
|          | erstructure   | within 40 (forty sight) hours   |
| (i)      | Any damage, cracks, spalling/scaling Temporary measures Permanent measures  | within 48 (forty eight) hours<br>within 15 (fifteen) days or as<br>specified by the Authority's<br>Engineer |
| _ ` '    | indations indations   |   |
| (i)      | Scouring and/or cavitation  | 15 (fifteen) days   |
|          | rs, abutments, return walls and wing walls  |   |
| (i)      | Cracks and damages including settlement and tilting, spalling, scaling  | 30 (thirty) days  |
|          | rings (metallic) of bridges   |   |
| (i)      | Deformation, damages, tilting or shifting of bearings   | 15 (fifteen) days Greasing of metallic bearings once in a year  |
| (e) Joi  |   |   |
| (i)      | Malfunctioning of joints  | 15 (fifteen) days   |
| (f) Oth  | er items  |   |
| (i)      | Deforming of pads in elastomeric bearings   | 7 (seven) days  |
| (ii)     | Gathering of dirt in bearings and joints; or clogging of spouts, weep holes and vent-holes  | 3 (three) days  |
| (iii)    | Damage or deterioration in kerbs, parapets, handrails and crash barriers  | 3 (three) days (immediately within 24 hours if posing danger to safety)                                     |
| (vi)     | Rain-cuts or erosion of banks of the side slopes of approaches  | 7 (seven) days  |
| (v)      | Damage to wearing coat  | 15 (fifteen) days   |
| (vi)     | Damage or deterioration in approach slabs, pitching, apron, toes, floor or guide bunds  | 30 (thirty) days  |
| (vii)    | Growth of vegetation affecting the structure or obstructing the waterway  | 15 (fifteen) days   |
| (g) Hill |   | •   |
| (i)      | Damage to retaining wall/breast wall  | 7 (seven) days  |
| (ii)     | Landslides requiring clearance  | 12 (twelve) hours   |
| (iii)    | Snow requiring clearance  | 24 (twenty four) hours  |
|          | Where necessary, the Authority may modify th  | , ,   |

or add to the nature of Defect or deficiency before issuing the bidding document, with the approval of the competent authority.]







**Technical Schedule** 

SCHEDULE - F (See Clause 3.1.7(a))


## APPLICABLE PERMITS

## 1 Applicable Permits

The Contractor shall obtain, as required under the Applicable Laws, the following Applicable Permits:

- a) Permission of the State Government for extraction of boulders from quarry;
- b) Permission of Village Panchayats and Pollution Control Board for installation of crushers;
- c) License for use of explosives;
- d) Permission of the State Government for drawing water from river/reservoir;
- e) License from inspector of factories or other competent Authority for setting up batching plant;
- f) Clearance of Pollution Control Board for setting up batching plant;
- g) Clearance of Village Panchayats and Pollution Control Board for setting up asphalt plant;
- h) Permission of Village Panchayats and State Government for borrow earth; and
- i) Any other permits or clearances required under Applicable Laws
- j) Applicable Permits, as required, relating to environmental protection and conservation shall have been procured by the Authority in accordance with the provisions of this Agreement.

SCHEDULE-F 141







**Technical Schedule** 

#### SCHEDULE - G

(See Clauses 7.1 and 19.2)

## FORM OF BANK GUARANTEE

Annex-I (See Clause 7.1)

#### [Performance Security/Additional Performance Security]

To National Highway & Highway Development Corporation Ltd. PTI Building, 3rd Floor, 4, Parliament Street, New Delhi- 110001

#### WHEREAS:

- [name and address of contractor] (hereinafter called the "Contractor") and [name and address of the authority], (hereinafter called the "Authority") have entered into an agreement (hereinafter called the "Agreement") for the construction of the "Upgradation & Improvement of Tamenglong- Mahur Road (NH-137) to two lane with paved shoulders in the state of Assam on Engineering, Procurement & Construction (EPC) mode Package-7 starting near Jiri River(Assam/Manipur Border) at km 96.870 and ending near Hangrum at km 116.550 (Length-19.68km)" subject to and in accordance with the provisions of the Agreement
- (C) We, ....... through our branch at ....... (the "Bank") have agreed to furnish this bank guarantee (hereinafter called the "Guarantee") by way of Performance Security.
- NOW, THEREFORE, the Bank hereby, unconditionally and irrevocably, guarantees and affirms as follows:
- 1. The Bank hereby unconditionally and irrevocably guarantees the due and faithful performance of the Contractor's obligations during the {Construction Period/Defects Liability Period and Maintenance Period} under and in accordance with the Agreement, and agrees and undertakes to pay to the Authority, upon its mere first written demand, and without any demur, reservation, recourse, contest or protest, and without any reference to the Contractor, such sum or sums up to an aggregate sum of the Guarantee Amount as the Authority shall claim, without the Authority being required to prove or to show grounds or reasons for its demand and/or for the sum specified therein.





**Technical Schedule** 

- 2. A letter from the Authority, under the hand of an officer not below the rank of [General Manager in the National Highways Authority of India], that the Contractor has committed default in the due and faithful performance of all or any of its obligations under and in accordance with the Agreement shall be conclusive, final and binding on the Bank. The Bank further agrees that the Authority shall be the sole judge as to whether the Contractor is in default in due and faithful performance of its obligations during and under the Agreement and its decision that the Contractor is in default shall be final and binding on the Bank, notwithstanding any differences between the Authority and the Contractor, or any dispute between them pending before any court, tribunal, arbitrators or any other authority or body, or by the discharge of the Contractor for any reason whatsoever.
- 3. In order to give effect to this Guarantee, the Authority shall be entitled to act as if the Bank were the principal debtor and any change in the constitution of the Contractor and/or the Bank, whether by their absorption with any other body or corporation or otherwise, shall not in any way or manner affect the liability or obligation of the Bank under this Guarantee.
- 4. It shall not be necessary, and the Bank hereby waives any necessity, for the Authority to proceed against the Contractor before presenting to the Bank its demand under this Guarantee.
- 5. The Authority shall have the liberty, without affecting in any manner the liability of the Bank under this Guarantee, to vary at any time, the terms and conditions of the Agreement or to extend the time or period for the compliance with, fulfillment and/ or performance of all or any of the obligations of the Contractor contained in the Agreement or to postpone for any time, and from time to time, any of the rights and powers exercisable by the Authority against the Contractor, and either to enforce or forbear from enforcing any of the terms and conditions contained in the Agreement and/or the securities available to the Authority, and the Bank shall not be released from its liability and obligation under these presents by any exercise by the Authority of the liberty with reference to the matters aforesaid or by reason of time being given to the Contractor or any other forbearance, indulgence, act or omission on the part of the Authority or of any other matter or thing whatsoever which under any law relating to sureties and guarantors would but for this provision have the effect of releasing the Bank from its liability and obligation under this Guarantee and the Bank hereby waives all of its rights under any such law.
- 6. This Guarantee is in addition to and not in substitution of any other guarantee or security now or which may hereafter be held by the Authority in respect of or relating to the Agreement or for the fulfillment, compliance and/or performance of all or any of the obligations of the Contractor under the Agreement.





**Technical Schedule** 

- 7. Notwithstanding anything contained hereinbefore, the liability of the Bank under this Guarantee is restricted to the Guarantee Amount and this Guarantee will remain in force for the period specified in paragraph 8 below and unless a demand or claim in writing is made by the Authority on the Bank under this Guarantee all rights of the Authority under this Guarantee shall be forfeited and the Bank shall be relieved from its liabilities hereunder.
- 8. The Guarantee shall cease to be in force and effect on \*\*\*\*\$. Unless a demand or claim under this Guarantee is made in writing before expiry of the Guarantee, the Bank shall be discharged from its liabilities hereunder.
- 9. The Bank undertakes not to revoke this Guarantee during its currency, except with the previous express consent of the Authority in writing, and declares and warrants that it has the power to issue this Guarantee and the undersigned has full powers to do so on behalf of the Bank.
- 10. Any notice by way of request, demand or otherwise hereunder may be sent by post addressed to the Bank at its above referred branch, which shall be deemed to have been duly authorized to receive such notice and to effect payment thereof forthwith, and if sent by post it shall be deemed to have been given at the time when it ought to have been delivered in due course of post and in proving such notice, when given by post, it shall be sufficient to prove that the envelope containing the notice was posted and a certificate signed by an officer of the Authority that the envelope was posted shall be conclusive.
- 11. This Guarantee shall come into force with immediate effect and shall remain in force and effect for up to the date specified in paragraph 8 above or until it is released earlier by the Authority pursuant to the provisions of the Agreement.
- 12. This guarantee shall also be operable at our..........Branch at New Delhi, from whom, confirmation regarding the issue of this guarantee or extension / renewal thereof shall be made available on demand. In the contingency of this guarantee being invoked and payment there under claimed, the said branch shall accept such invocation letter and make payment of amounts so demanded under the said invocation.
- 13. The guarantor/bank hereby confirms that it is on the SFMS (Structural Finance Messaging System) platform & shall invariably send an advice of this Bank Guarantee to the designated bank of [MoRT&H/NHAI/NHIDCL/State PWD/BRO], details of which is as under:





**Technical Schedule** 

| Sr. No. | Particulars                      | Details  |
|---------|----------------------------------|--|
| 1.      | Name of Beneficiary              | National Highways & Infrastructure                           |
|         | Hame of Beneficially             | Development Corporation Limited                              |
| 2.      | Beneficiary Bank Account No.     | 90621010002659   |
| 2       | Beneficiary Bank Branch Name and | Canara Bank (erstwhile Syndicate<br>Bank), Transport Bhawan, |
| 3.      | Address                          | 1st Parliament Street, New Delhi-<br>110001                  |
| 4.      | Beneficiary Bank Branch IFSC     | CNRB0019062  |
| 5.      | Swift Code (For Foreign Bidders) | SYNBINBB126  |

Signed and sealed this ....... day of .......... 20....... at .........

SIGNED, SEALED AND DELIVERED

For and on behalf of the Bank by:

(Signature)

(Name)

(Designation)

(Code Number)

(Address)

## **NOTES:**

- (i) The bank guarantee should contain the name, designation and code number of the officer(s) signing the guarantee.
- (ii) The address, telephone number and other details of the head office of the Bank as well as of issuing branch should be mentioned on the covering letter of issuing branch.





**Technical Schedule** 

Annex - II (Schedule - G) (See Clause 19.2)

#### Form for Guarantee for Withdrawal of Retention Money

To National Highway & Highway Development Corporation Ltd. PTI Building, 3rd Floor, 4, Parliament Street, New Delhi- 110001

#### WHEREAS:

- (A) [name and address of contractor] (hereinafter called the "Contractor") has executed an agreement (hereinafter called the "Agreement") with the NHIDCL, (hereinafter called the "Authority") for the construction of the "Upgradation & Improvement of Tamenglong- Mahur Road (NH-137) to two lane with paved shoulders in the state of Assam on Engineering, Procurement & Construction (EPC) mode Package-7 starting near Jiri River(Assam/Manipur Border) at km 96.870 and ending near Hangrum at km 116.550 (Length-19.68km)" subject to and in accordance with the provisions of the Agreement.
- (B) In accordance with Clause 19.2 of the Agreement, the Authority shall make to the Contractor an interest bearing @Bank Rate + 3% advance payment (herein after called "Advance Payment") equal to 10% (ten per cent) of the Contract Price; and that the Advance Payment shall be made in two installments subject to the Contractor furnishing an irrevocable and unconditional guarantee by a scheduled bank for an amount equivalent to 110% (one hundred and ten percent) of such installment to remain effective till the complete and full repayment of the installment of the Advance Payment as security for compliance with its obligations in accordance with the Agreement. The amount of {first/second} installment of the Advance Payment is Rs. ----- cr. (Rupees ----- crore) and the amount of this Guarantee is Rs. ----- cr. (Rupees ----- crore) (the "Guarantee Amount") \$.
- (C) We, ...... through our branch at ...... (the "Bank") have agreed to furnish this bank guarantee (hereinafter called the "Guarantee") for the Guarantee Amount.
- NOW, THEREFORE, the Bank hereby unconditionally and irrevocably guarantees and affirms as follows:
- 1. The Bank hereby unconditionally and irrevocably guarantees the due and faithful repayment on time of the aforesaid instalment of the Advance Payment under and in accordance with the Agreement, and agrees and undertakes to pay to the Authority, upon its mere first written demand, and without any demur, reservation, recourse, contest or protest, and without any reference to the Contractor, such sum or sums up to an aggregate sum of the Guarantee Amount as the Authority shall claim, without the Authority being required to prove or to show grounds or reasons for its demand and/or for the sum specified therein.





**Technical Schedule** 

A letter from the Authority, under the hand of an officer not below the rank of [General Manager in the National Highways Authority of India], that the Contractor has committed default in the due and faithful performance of all or any of its obligations for under and in accordance with the Agreement shall be conclusive, final and binding on the Bank. The Bank further agrees that the Authority shall be the sole judge as to whether the Contractor is in default in due and faithful performance of its obligations during and under the Agreement and its decision that the Contractor is in default shall be final, and binding on the Bank, notwithstanding any differences between the Authority and the Contractor, or any dispute between them pending before any court, tribunal, arbitrators or any other authority or body, or by the discharge of the Contractor for any reason whatsoever.

- 2. In order to give effect to this Guarantee, the Authority shall be entitled to act as if the Bank were the principal debtor and any change in the constitution of the Contractor and/or the Bank, whether by their absorption with any other body or corporation or otherwise, shall not in any way or manner affect the liability or obligation of the Bank under this Guarantee.
- 3. It shall not be necessary, and the Bank hereby waives any necessity, for the Authority to proceed against the Contractor before presenting to the Bank its demand under this Guarantee.
- The Authority shall have the liberty, without affecting in any manner the liability 4. of the Bank under this Guarantee, to vary at any time, the terms and conditions of the Advance Payment or to extend the time or period of its repayment or to postpone for any time, and from time to time, any of the rights and powers exercisable by the Authority against the Contractor, and either to enforce or forbear from enforcing any of the terms and conditions contained in the Agreement and/or the securities available to the Authority, and the Bank shall not be released from its liability and obligation under these presents by any exercise by the Authority of the liberty with reference to the matters aforesaid or by reason of time being given to the Contractor or any other forbearance, indulgence, act or omission on the part of the Authority or of any other matter or thing whatsoever which under any law relating to sureties and guarantors would but for this provision have the effect of releasing the Bank from its liability and obligation under this Guarantee and the Bank hereby waives all of its rights under any such law.
- 5. This Guarantee is in addition to and not in substitution of any other guarantee or security now or which may hereafter be held by the Authority in respect of or relating to the Retention Money.
- 6. Notwithstanding anything contained hereinbefore, the liability of the Bank under this Guarantee is restricted to the Guarantee Amount and this Guarantee will remain in force for the period specified in paragraph 8 below and unless a demand or claim in writing is made by the Authority on the Bank under this Guarantee all rights of the Authority under this Guarantee shall be forfeited and the Bank shall be relieved from its liabilities hereunder.





**Technical Schedule** 

- 7 The Guarantee shall cease to be in force and effect on \*\*\*\*.\$ Unless a demand or claim under this Guarantee is made in writing on or before the aforesaid date, the Bank shall be discharged from its liabilities hereunder.
- 8. The Bank undertakes not to revoke this Guarantee during its currency, except with the previous express consent of the Authority in writing, and declares and warrants that it has the power to issue this Guarantee and the undersigned has full powers to do so on behalf of the Bank.
- 9. Any notice by way of request, demand or otherwise hereunder may be sent by post addressed to the Bank at its above referred branch, which shall be deemed to have been duly authorized to receive such notice and to effect payment thereof forthwith, and if sent by post it shall be deemed to have been given at the time when it ought to have been delivered in due course of post and in proving such notice, when given by post, it shall be sufficient to prove that the envelope containing the notice was posted and a certificate signed by an officer of the Authority that the envelope was so posted shall be conclusive.
- 10. This Guarantee shall come into force with immediate effect and shall remain in force and effect up to the date specified in paragraph 8 above or until it is released earlier by the Authority pursuant to the provisions of the Agreement.
- 11. This guarantee shall also be operatable at our ......... Branch at Guwahati, from whom, confirmation regarding the issue of this guarantee or extension / renewal thereof shall be made available on demand. In the contingency of this guarantee being invoked and payment there under claimed, the said branch shall accept such invocation letter and make payment amounts so demanded under the said invocation.
- 12. Bank Guarantee has been sent to authority's bank through SFMS gateway as per the details below:-

| Sr. No. | Particulars                     | Details  |
|---------|---------------------------------|--|
| 1.      | Name of Beneficiary             | RO NHIDCL PROJECTS   |
| 2.      | Beneficiary Bank Account No.    | 73653210000013   |
| 3.      | Beneficiary Bank Branch IFSC    | CNRB0019062  |
| 4.      | Beneficiary Bank Branch Name    | Canara Bank, Dispur, Guwahati                                    |
| 5.      | Beneficiary Bank Branch Address | Upasana Complex, Dr. R. P. Road,<br>Ganeshguri, Dispur, Guwahati |

Signed and sealed this ....... day of ............ 20........ at ............ SIGNED, SEALED AND DELIVERED

For and on behalf of the Bank by:

(Signature)

(Name)

(Designation)

(Code Number)






**Technical Schedule** 

(Address)

## **NOTES:**

- i. The bank guarantee should contain the name, designation and code number of the officer(s) signing the guarantee.
- ii. The address, telephone number and other details of the head office of the Bank as well as of issuing branch should be mentioned on the covering letter of issuing branch.







**Technical Schedule** 

## Schedule-H

(See Clauses 10.1 (iv) and 19.3)

# 1 Contract Price Weightages

- 1.1 The Contract Price for this Agreement is Rs. 465.84 Cr.
- 1.2 Proportions of the Contract Price for different stages of Construction of the Project Highway shall be as specified below:

| ltem                      | Weightage in percentag e to the Contract Price | Stage for Payment   | Percentag<br>e<br>weightage |
|---------------------------|--|---|-----------------------------|
| 1                         | 2  | 3   | 4                           |
| Road works including      | 45.15%   | A - Widening and strengthening of existing road                           |                             |
| culverts,<br>widening and |  | (1) Earthwork up to Subgrade top  |                             |
| repair of culverts.       |  | (2) Sub base course (GSB/CTSB)  |                             |
|                           |  | (3) Non bituminous base course (WMM)                                      |                             |
|                           |  | (4) Bituminous base (Prime and DBM)                                       |                             |
|                           |  | (5) Wearing coat (Tack coat, BC)  |                             |
|                           |  | (6) widening and repair of culverts                                       |                             |
|                           |  | B.1 - Reconstruction/ New 2/4-lane realignment/bypass (Flexible pavement) |                             |
|                           |  | (1) Earthwork upto Subgrade top   | 60.50%                      |
|                           |  | (2) Subbase course (GSB)  | 8.36%                       |
|                           |  | (3) Non bituminous base course (WMM)                                      | 5.52%                       |
|                           |  | (4) Bituminous base (Prime and DBM)                                       | 6.42%                       |
|                           |  | (5) Wearing coat (Tack coat, BC)  | 2.86%                       |
|                           |  | B.2 - Reconstruction/ New 2/4-lane realignment/bypass (Rigid Pavement)    |                             |
|                           |  | (1) Earthwork upto Subgrade top   |                             |
|                           |  | (2) Subbase course (GSB)  |                             |
|                           |  | (3) Dry lean concrete (DLC)   |                             |
|                           |  | (4) Pavement quality concrete (PQC) course                                |                             |
|                           |  | C.1 - Reconstruction/ New Service road (flexible Pavement)                |                             |
|                           |  | (1) Earthwork upto Subgrade top   |                             |

SCHEDULE-H 150





**Technical Schedule** 

| ltem                       | Weightage in percentag e to the Contract Price | Stage for Payment   | Percentag<br>e<br>weightage |
|----------------------------|--|---|-----------------------------|
| 1                          | 2  | 3   | 4                           |
|                            |  | (2) Subbase course (GSB)  |                             |
|                            |  | (3) Non bituminous base course (WMM)  |                             |
|                            |  | (4) Bituminous base (Prime and DBM)   |                             |
|                            |  | (5) wearing coat (Tack coat, BC)  |                             |
|                            |  | C.2 - Reconstruction/ New Service road (Rigid Pavement)   |                             |
|                            |  | (1) Earthwork upto Subgrade top   |                             |
|                            |  | (2) Subbase course (GSB)  |                             |
|                            |  | (3) Dry lean concrete (DLC)   |                             |
|                            |  | (4) Pavement quality concrete (PQC) course  |                             |
|                            |  | D Reconstruction/ New culverts on existing road and realignments, bypasses  | 16.34%                      |
| Minor Bridges/             |  | A.1 - Widening and repairs of Minor Bridges   |                             |
| Underpasses/<br>Overpasses |  | Widening of existing bridges  |                             |
|                            |  | Rehabilitation of existing bridges  |                             |
|                            |  | A.2 - New of Minor Bridges  |                             |
|                            |  | (1) Foundation: (on completion of the foundation work including foundation for wing wall, return wall, abutments, piers.  | 41.41%                      |
|                            |  | (2) Sub-structure: (on completion of abutments, piers upto abutment/pier cap.)  | 18.48%                      |
|                            |  | (3) Super-structure (on completion of the super structure in all respects including wearing coat, bearings, expansion joints, hand rails, crash barrier road sign, & marking, tests on completion etc. completion in all respect) | 17.28%                      |
|                            |  | <ul> <li>(4) Approaches (on completion of approaches including retaining walls, stone pitching, protection works complete in all respect and fit for use.</li> <li>(5) Guide Bunds and River Training works: (On</li> </ul>       | 22.83%                      |
|                            |  | completion of Guide Bunds and river training works. (On works complete in all respects.)  |                             |
|                            |  | B.1 - Widening and repairs of   |                             |
|                            |  | Underpasses/Overpasses  |                             |
|                            |  | B.2 - New Underpasses/Overpasses  |                             |

SCHEDULE-H 151





**Technical Schedule** 

| Item   | Weightage in percentag e to the Contract Price | Stage for Payment   | Percentag<br>e<br>weightage |
|--|--|---|-----------------------------|
| 1  | 2  | (1) Foundation: on completion of the  | 4                           |
|  |  | (1) Foundation: on completion of the foundation work including foundation for wing wall, return wall, abutments, piers.   |                             |
|  |  | (2) Sub-structure: on completion of abutments, piers upto the abutment/pier cap   |                             |
|  |  | (3) Super-structure: on completion of the super structure in all respects including wearing coat, bearings, expansion joints, hand rails, crash barrier road sign, & marking, tests on completion etc. completion in all respect. |                             |
|  |  | (4) Approaches: on completion of approaches including RE wall, retaining walls stone pitching, protection works complete in all respect and fit for use.  |                             |
| Major Bridge                                   |  | A.1 - Widening and repairs of existing major  |                             |
| works and ROB/RUB/elevate                      |  | (1) Foundation  |                             |
| d sections/flyovers including viaducts, if any |  | (2) Sub structure   |                             |
|  |  | (3) Superstructure (including bearing)  |                             |
|  |  | (4) wearing coat (including expansion joint)  |                             |
|  |  | (5) Miscellaneous items (like hand rails, crash barriers, road markings etc.)   |                             |
|  |  | (6) wing walls/return walls   |                             |
|  |  | (7) Guide bunds, river training works etc.  |                             |
|  |  | (8) Approaches (including retaining walls, stone pitching, protection works).   |                             |
|  |  | A.2 - New/ Reconstruction major bridges   |                             |
|  |  | (1) Foundation  |                             |
|  |  | (2) Sub structure   |                             |
|  |  | (3) Superstructure (including bearing)  |                             |
|  |  | (a) casting of girder   |                             |
|  |  | (b) casting of segments   |                             |
|  |  | (c) erection of girder  |                             |

SCHEDULE-H 152





**Technical Schedule** 

| ltem | Weightage in percentag e to the Contract | Stage for Payment   | Percentag<br>e<br>weightage |
|------|--|---|-----------------------------|
|      | Price                                    |   |                             |
| 1    | 2  | (4) Other ancillary works: wearing coat, including expansion joint, hand rails, crash barriers, tests on completion in all respect.  (5) Miscellaneous works: stone pitching, protection works excluding retaining/ reinforced earth wall etc.  (6) wing walls/return walls upto full height  (7) Guide bunds, river training works etc.  (8) Retaining wall/ Reinforced earth wall etc.  (8.a) Panel casting | 4                           |
|      |  | (8.b) Erection of panel/ construction of retaining wall  B.1 - Widening and repairs of (a) ROB and (b) RUB  (1) Foundation  |                             |
|      |  | (2) Sub structure   |                             |
|      |  | (3) Superstructure (including bearing)  |                             |
|      |  | (4) wearing coat: (a) in case of ROB - wearing coat including expansion joints complete in all respects as specified and (b) in case of RUB - rigid pavement under RUB including drainage facility complete in all respect as specified.  |                             |
|      |  | (5) Miscellaneous items (like hand rails, crash barriers, road markings etc.)   |                             |
|      |  | <ul><li>(6) wing walls/return walls</li><li>(7) Approaches (including retaining walls, stone pitching, protection works).</li></ul>   |                             |
|      |  | B.2 - New ROB / RUB   |                             |
|      |  | (1) Foundation  |                             |
|      |  | (2) Sub structure   |                             |
|      |  | (3) Superstructure (including bearing)  |                             |
|      |  | (a) casting of girder   |                             |
|      |  | (b) casting of segments   |                             |
|      |  | ( C)erection of girder  |                             |





**Technical Schedule** 

| ltem | Weightage in percentag e to the Contract Price | Stage for Payment   | Percentag<br>e<br>weightage |
|------|--|---|-----------------------------|
| 1    | 2  | 3   | 4                           |
|      |  | <ul> <li>(4) Other ancillary works: wearing coat, expansion joint, hand railing, crash barriers tests on completion etc. completion in all respect.</li> <li>(5) Miscellaneous items (like hand rails, crash barriers, road markings etc.)</li> </ul> |                             |
|      |  | (6) wing walls/return walls upto full height  |                             |
|      |  | (7) Retaining wall/ Reinforced earth wall etc.  |                             |
|      |  | (7.a) RE wall Panel casting   |                             |
|      |  | (7.b) Erection of RE wall panel/ construction of retaining wall   |                             |
|      |  | C.1 - Widening and repairs of Elevated section/Flyover/Grade Separators   |                             |
|      |  | (1) Foundation  |                             |
|      |  | (2) Sub structure   |                             |
|      |  | (3) Superstructure (including bearing)  |                             |
|      |  | (4) wearing coat including expansion joint  |                             |
|      |  | (5) Miscellaneous items (like hand rails, crash barriers, road markings etc.)   |                             |
|      |  | (6) wing walls/return walls   |                             |
|      |  | (7) Approaches (including retaining walls/<br>Reinforced earth walls, stone pitching, protection<br>works).   |                             |
|      |  | C.2 - New Elevated section/Flyover/Grade Separators   |                             |
|      |  | (1) Foundation  |                             |
|      |  | (2) Sub structure   |                             |
|      |  | (3) Superstructure: including girder, deck slab, bearing (excluding wearing coat and expansion joints)  |                             |
|      |  | (a) casting of girder   |                             |
|      |  | (b) casting of segments   |                             |
|      |  | (c) erection of girder  |                             |
|      |  | (4) Other ancillary works: wearing coat, expansion joint, hand railing, crash barriers tests on completion etc. completion in all respect.  |                             |





**Technical Schedule** 

| ltem                                   | Weightage in percentag e to the Contract Price | Stage for Payment  | Percentag<br>e<br>weightage |
|--|--|--|-----------------------------|
| 1                                      | 2  | 3  | 4                           |
|  |  | <ul><li>(5) Miscellaneous items (like hand rails, crash barriers, road markings etc.)</li><li>(6) wing walls/return walls upto full height</li></ul> |                             |
|  |  | (7) Retaining wall/ Reinforced earth wall etc.   |                             |
|  |  | (7.a) Panel casting (7.b) Erection of panel/ construction of retaining wall  |                             |
| Other works                            | 52.71%   | (i) Toll plaza including it's approach   |                             |
|  |  | (ii) Road side drains  |                             |
|  |  | a) Hill Side Trapezoidal/V Type Drain  | 1.61%                       |
|  |  | b) Catch Water Drain   | 1.55%                       |
|  |  | (iii) Road signs, markings, km stones, safety devices etc.   | 3.70%                       |
|  |  | (iv) Project facilities  |                             |
|  |  | (a) Bus Bay with Bus Shelter   | 0.13%                       |
|  |  | (b) Truck laybyes  | 0.10%                       |
|  |  | (c) Rest area with Toilet Block  | 0.12%                       |
|  |  | (d) others to specified  |                             |
|  |  | (v) Road side plantation   | 0.35%                       |
|  |  | (vi) Repair of Protection works other than<br>approaches to the bridges, elevated sections,<br>flyovers/ grade separators and ROBs/RUBs.             |                             |
|  |  | (vii) Retaining Wall   | 27.14%                      |
|  |  | (viii) Breast Wall   | 26.94%                      |
|  |  | (ix) Hydro-seeding& Mulching   | 4.00%                       |
|  |  | (x) Special Protection of Sinking Zone   | 34.29%                      |
|  |  | (xi) Junction Improvement  | 0.07%                       |
| Electrical utilities and public Health | 0.16%  | (i) EHT line / (ii) EHT crossings  |                             |
| Utilities (Water                       |  | (iii) HT/ LT line / (iv) HT/ LT crossings over ground  | 86.59%                      |





**Technical Schedule** 

| ltem                         | Weightage in percentag e to the Contract Price | Stage for Payment                                      | Percentag<br>e<br>weightage |
|------------------------------|--|--|-----------------------------|
| 1                            | 2  | 3  | 4                           |
| pipe lines and sewage lines) |  | (iv) HT/ LT line / (vi) HT/ LT crossings Under ground  |                             |
|                              |  | (vii) Water pipeline / (viii) Water pipeline crossings | 13.41%                      |
|                              |  | (ix) Sewage lines / (x) Sewage line crossings          |                             |

1.3 Procedure of estimating the value of work done.

# 1.3.1 Road works

Procedure for estimating the value of road work done shall be as follows:

**Table 1.3.1** 

| Stage of Payment   | Percentage -weightage | Payment Procedure  |
|--|-----------------------|--|
| A - Widening and strengthening of existing road  |                       |  |
| (1) Earthwork upto top of the Subgrade including excavation in Soil, soft rock and hard rock, removal of unserviceable soil etc. |                       | Unit of measurement is linear length. Payment of each stage shall be made on pro rata basis on completion of a stage in a length of not less than 500m. In case of Hill cutting, the payment procedure will be as under:  Hill Cutting: 40% of weightage of A(1)  Preparation of Sub-Grade: 60% of weightage of A(1) |
| (2) Subbase course (GSB)   |                       | Unit of measurement is linear  |
| (3) Non bituminous base course (WMM)   |                       | length. Payment of each stage shall be made on pro rata basis  |
| (4) Bituminous base (Prime and DBM)  |                       | on completion of a stage in a  |
| (5) wearing coat (Tack coat, BC)   |                       | length of not less than 500 m.   |
| (6) widening and repair of culverts  |                       | Cost of ten completed culverts shall be determined pro rata with respect to the total number of culverts. Payment shall be made on the completion of at least five culverts.   |





**Technical Schedule** 

| Stage of Payment   | Percentage -weightage | Payment Procedure  |  |
|--|-----------------------|--|--|
| B.1 - Reconstruction/ New 2/4-lane realignment/bypass (Flexible pavement)  |                       |  |  |
| (1) Earthwork upto top of the Subgrade including excavation in Soil, soft rock and hard rock, removal of unserviceable soil etc. | 60.50%                | Unit of measurement is linear length. Payment of each stage shall be made on pro rata basis on completion of a stage in a length of not less than 500m. In case of Hill cutting, the payment procedure will be as under: Hill Cutting: 40% of weightage of A(1) Preparation of Sub-Grade: 60% of weightage of A(1) |  |
| (2) Subbase course (GSB)   | 8.36%                 | Unit of measurement is   |  |
| (3) Non bituminous base course (WMM)   | 5.52%                 | linear length. Payment of each stage shall be made on pro rata   |  |
| (4) Bituminous base (Prime and DBM)  | 6.42%                 | basis on completion of a stage   |  |
| (5) wearing coat (Tack coat, BC)   | 2.86%                 | in a length of not less than 500 m.  |  |
| B.2 - Reconstruction/ New 2/4-lane realignment/bypass (Rigid Pavement)   |                       |  |  |
| (1) Earthwork upto top of the Subgrade including excavation in Soil, soft rock and hard rock, removal of unserviceable soil etc. |                       | Unit of measurement is linear length. Payment of each stage shall be made on pro rata basis on completion of a stage in a length of not less than 500m.In case of Hill cutting, the payment procedure will be as under:Hill Cutting: 40% of weightage of A(1)Preparation of Sub-Grade: 60% of weightage of A(1)    |  |
| (2) Subbase course (GSB)   |                       | Unit of measurement is linear length. Payment of each stage  |  |
| (3) Dry lean concrete (DLC)  |                       | shall be made on pro rata basis  |  |
| (4) Pavement quality concrete (PQC) course   |                       | on completion of a stage in a length of not less than 500 m.   |  |
| C.1 - Reconstruction/ New Service road/ Slip Road (flexible Pavement)  |                       |  |  |





**Technical Schedule** 

| Stage of Payment   | Percentage -weightage | Payment Procedure  |
|--|-----------------------|--|
| (1) Earthwork upto top of the Subgrade including Shoulder                | Weightage             | Unit of measurement is linear length. Payment of each stage shall be made on pro rata basis on completion of a stage in a length of not less than 500m. In case of Hill cutting, the payment procedure will be as under: Hill Cutting: 40% of weightage of A(1) Preparation of Sub-Grade: 60% of weightage of A(1) |
| (2) Subbase course (GSB)   |                       | Unit of measurement is linear length. Payment of each  |
| (3) Non bituminous base course (WMM)                                     |                       | stage shall be made on pro rata  |
| (4) Bituminous base (Prime and DBM)                                      |                       | basis on completion of a stage   |
| (5) wearing coat (Tack coat, BC)   |                       | in a length of not less than 500 m.  |
| C.2 - Reconstruction/ New Service road/ Slip road (Rigid Pavement)       |                       |  |
| (1) Earthwork upto top of the Subgrade                                   |                       | Unit of measurement is linear length. Payment of each stage shall be made on pro rata basis on completion of a stage in a length of not less than 500m. In case of Hill cutting, the payment procedure will be as under: Hill Cutting: 40% of weightage of A(1) Preparation of Sub-Grade: 60% of weightage of A(1) |
| (2) Subbase course (GSB)   |                       | Unit of measurement is linear length. Payment of each stage  |
| (3) Dry lean concrete (DLC)  |                       | shall be made on pro rata basis  |
| (4) Pavement quality concrete (PQC) course                               |                       | on completion of a stage in a length of not less than 500 m.   |
| D Reconstruction/ New culverts on existing road, Realignments, bypasses: | 16.34%                | Cost of each culvert shall be determined on pro rata basis with respect to the total number of culverts. Payment shall be made on the completion of at least one culvert.  |

<sup>@.</sup> For example, if the total length of bituminous work to be done is 100 km, the cost per km of bituminous work shall be determined as follows:

Cost per km =  $P \times W$  weightage for road work  $\times W$  weightage for bituminous work  $\times W$  (1/L)





**Technical Schedule** 

Where P= Contract Price. And L = Total length in km.

Similarly, the rates per km for other stages shall be worked out accordingly.

Note: The length affected due to law-and-order problems or litigation during execution due to which the Contractor is unable to execute the work, may be deducted from the total project length for payment purposes. The total length calculated here is only for payment purposes and will not affect and referred in other clauses of the Contract Agreement.

## 1.3.2 Minor Bridges and Underpasses/Overpasses.

Procedure for estimating the value of Minor Bridge and underpasses/Overpasses shall be as stated in table 1.3.2:

**Table 1.3.2** 

| Stage of Payment  | Weightage | Payment Procedure   |
|---|-----------|---|
| A.1 - Widening and repairs of Minor Bridges   |           | Cost of each minor bridge shall be determined on pro rata basis with  |
| Widening of existing bridges  |           | respect to the total linear length of the minor bridges. Payment shall be made on   |
| rehabilitation of existing bridges  |           | the completion of widening & repair   |
| A.2 - New of Minor Bridges  |           | works of a minor bridge.  |
| (1) Foundation: on completion of the foundation work including foundation for wing wall, return wall, abutments, piers.   | 41.41%    | (1) Foundation: Payment against foundation shall be made on prorata basis on completion of at least two foundations. In case where load testing is required for foundation, trigger of first payment shall include load testing also where specified. |
| (2) Sub-structure: on completion of abutments, piers upto abutment/pier cap.  | 18.48%    | (2) Substructure: Payment against substructure shall be made on prorata basis on completion of at least two substructures upto abutment/pier cap level of each bridges.   |
| (3) Super-structure: on completion of the super structure in all respects including wearing coat, bearings, expansion joints, hand rails, crash barrier road sign, & marking, tests on completion etc. completion in all respect. | 17.28%    | (3) Super structure: Payment shall be made on prorata basis on completion of a stage i.e., completion of super structure of at least one span in all respects as specified in the column of Stage payment in this sub clause.                         |
| (4) Approaches: on completion of approaches including retaining walls, stone pitching, protection works complete in all respect and fit for use.  | 22.83%    | (4) Approaches: Payment shall be made on prorata basis on completion of a stage i.e., completion of approaches in all respect as specified in the column of "stage Payment" in this sub clause.   |





Technical Schedule

| Stage of Payment   | Weightage | Payment Procedure  |
|--|-----------|--|
| (5) Guide Bunds and River Training works: On completion of Guide Bunds and river training works complete in all respects.  |           | (5) Guide bunds and river training works: Payment shall be made on proratabasison completion of a stage i.e., completion of guide bunds and river training works in all respect as specified.  |
| B.1 - Widening and repairs of Underpasses/Overpasses   |           | Cost of each underpass/overpass shall be determined on pro rata basis with respect to the total linear length of the underpass/overpasses. Payment shall be made on the completion of widening & repair works of a underpass/overpasses.             |
| B.2 - New Underpasses/Overpasses   |           |  |
| (1) Foundation: on completion of the foundation work including foundation for wing wall, return wall, abutments, piers.  |           | (1) Foundation: Payment against foundation shall be made on prorata basis on comletion of at least two foundations. In case where load testing is required for foundation, trigger of fisrt payment shall include load testing also where specified. |
| (2) Sub-structure: on completion of abutments, piers upto the abutment/pier cap  |           | (2) Substructure: Payment against substructure shall be made on prorata basis on comletion of at least two substructures upto abutment/pier cap level of each underpass/overpass.  |
| (3) Super-structure: on completion of the ssuper structure in all respects including wearing coat, bearings, expansion joints, hand rails, crash barrier road sign, & marking, tests on completion etc. completion in all respect) |           | (3) Super structure: Payment shall be made on prorata basis on completion of a stage i.e. completion of super structure of at least one span in all respects as specified in the column of Stage payment in this sub clause.                         |
| (4) Approaches: on completion of approaches including RE wall, retaining walls/ Reinforced earth wall, stone pitching, protection works complete in all respect and fit for use.   |           | (4) Approaches: Payment shall be made on prorata basis on completion of a stage i.e. completion of approaches in all respect as specified in the column of "stage Payment" in this sub clause.   |

# 1.3.3 Major Bridge works, ROB/RUB and Structures

Procedure for estimating the value of major Bridge works, ROB/RUB and structure work shall be as stated in table 1.3.3

**Table 1.3.3** 

| Stage of payment                       | Weightage | Payment procedure |
|--|-----------|-------------------|
| A.1 - Widening and repairs of existing |           |                   |
| major bridges                          |           |                   |





**Technical Schedule** 

| Stage of payment                          | Weightage | Payment procedure                  |
|---|-----------|------------------------------------|
| (1) Foundation                            |           | (1) Foundation: Cost of each       |
| (1) I dulidation                          | -         | ` '                                |
|   |           | , ,                                |
|   |           | determined on pro rata basis       |
|   |           | with respect to the total linear   |
|   |           | length (m) of the major bridges.   |
|   |           | Payment against foundation shall   |
|   |           | be made on prorata basis on        |
|   |           | completion of a stage i.e. not     |
|   |           | less than 25% of the scope of      |
|   |           | foundation of the major bridge     |
|   |           | subject to completion of at least  |
|   |           | two foundations of the major       |
|   |           | bridge.                            |
|   |           | In case where load testing is      |
|   |           | required for foundation, the       |
|   |           | trigger of the first payment shall |
|   |           | include load testing also where    |
|   |           | specified.                         |
| (2) Sub structure                         | -         | (2) Sub structure: Payment         |
|   |           | against sub-structure shall be     |
|   |           | made on prorata basis on           |
|   |           | completion of a stage i.e. not     |
|   |           | less than 25% of the scope of      |
|   |           | sub-structure of the major         |
|   |           | bridge subject to completion of    |
|   |           | at least two substructures of      |
|   |           | abutment/piers upto                |
|   |           | abutment/piers cap level of the    |
|   |           | major bridge.                      |
| (2) Superstructure (including bearing)    |           |                                    |
| (3) Superstructure (including bearing)    | -         | (3) Suer structure: Payment shall  |
|   |           | be made on prorata basis on        |
|   |           | completion of a stage i.e.         |
|   |           | completion of super structure      |
|   |           | including bearings of at least one |
|   |           | span in all respects as specified. |
| (4) wearing coat (including expansion     | -         | (4) wearing coat: Payment shall    |
| joint)                                    |           | be made on completion of           |
|   |           | wearing coat including expansion   |
|   |           | joints complete in all respects    |
|   |           | as specified.                      |
| (5) Miscellaneous items (like hand rails, | -         | (5) Miscellaneous: Payment shall   |
| crash barriers, road markings etc.)       |           | be made on completion of all       |
|   |           | miscellaneous works like hand      |
|   |           | rail, crash barrier, road          |
|   |           | markings, etc. complete in all     |
|   |           | respects as specified.             |
| (6) wing walls/return walls upto top      |           | (6) wing wall/ return wall:        |
| (1) 1 3                                   |           | Payment shall be made on           |
|   |           | completion of wing wall/return     |
|   |           | completion of fing fractifically   |





**Technical Schedule** 

| Stage of payment  | Weightage | Payment procedure  |
|---|-----------|--|
|   | 3 3       | wall complete in all respects as specified.  |
| (7) Guide bunds, river training works etc.  |           | (7) Guide bund, River training works: Payment shall be made on completion of all guide bunds/ river training works etc.complete in all respect as specified.   |
| (8) Approaches (including retaining walls, stone pitching, protection works).         | -         | (8) Approaches: Payment shall be made on prorata basis on completion of both approaches including stone pitching, protection works, etc. complete in all respect as specified.   |
| A.2 - New/ Reconstruction major bridges   |           | Cost of each structure shall be determined on prorata basis with respect to the total linear length (m) of all the structures. Payments shall be made on completion of each stage of structures as per weightage given in this table.  |
| (1) Foundation: foundation of abutment/piers  |           | (1) Foundation: Payment against foundation shall be made on pro rata basis on completion of a stage i.e., not less than 25% of the scope of foundation of a bridge as per weightage given in this table, subject to completion of at least two foundations in all respect.  In case where load testing is required for foundation, the trigger of the first payment shall include load testing also where specified. |
| (2) Sub structure: Substructure for abutment, piers upto the abutment/pier cap level. |           | (2) Substructure: Payment against sub structure shall be made on prorata basis on completion of a stage i.e., not less than 25% of the scope of sub-structure of a bridge as per weightage given in this table, subject to completion of at least two substructure of abutment/piers uptoabutment/piers cap level of a bridge.   |





**Technical Schedule** 

| Stage of payment  | Weightage | Payment procedure   |
|---|-----------|---|
| (3) Superstructure: including girder, deck slab, bearings (excluding wearing coat and expansion joints)                             | <u></u>   | ,   |
| (3.a) Super Structure: Casting of girder/fabrication of girders (steel)   |           | (a) Super structure (casting of girder): Unit of measurement is number. Payment against casting of girder shall be made on prorata basis with respect to total number of girders required in the structure on completion of a stage i.e., not less than completion of casting of at least five girders of the structure.          |
| (3.b) Super structure: casting of segments  |           | (b) Super structure (casting of segment): Unit of measurement is number. Payment against casting of segments shall be made on prorata basis with respect to total number of segments required in the structure on completion of a stage i.e., not less than completion of casting of at least 10 (ten) segments of the structure. |
| (3.c) Super structure: erection of girder, deck slab and bearings   |           | (c) Super structure (erection of girders, deck slab and bearing): Payment shall be made on prorata basis on completion of a stage i.e., completion of super structure including bearings at least one span in all respect as specified.   |
| (4) Other ancillary works: wearing coat, including expansion joint, hand rails, carsh barriers, tests on completion in all respect. |           | (4) Other ancillary work: Payment shall be made on prorata basis on completion of the stage in all respect as specified, for each structure.  |
| (5) Miscellaneous works: stone pitching, protection works excluding retaining/reinforced earth wall etc.                            |           | (5) Miscellaneous works: Payment shall be made on prorata basis on completion of the stage in all respects as specified, for each structure.  |
| (6) wing walls/return walls upto full height  |           | (6) Wing wall/ return wall: Payment shall be made on completion of wing wall/return walls for a bridge as per weightage given in this table   |





**Technical Schedule** 

| Stage of payment  | Weightage | Payment procedure  |
|---|-----------|--|
|   |           | complete in all respects as specified.   |
| (7) Guide bunds, river training works etc.              |           | (7) Guid bund, river training works: Payment shall be made on onprorata basis on completion of the stages in all respect as specified.   |
| (8) Retaining wall/ Reinforced earth wall etc.          |           | Payment shall be made on prorata basis on completion of both approaches including stone pitching, protection works, etc. complete in all respect as specified.   |
| (8.a) Panel casting                                     |           | (a) Panel casting: Unit of measurement is area in Sqm. Payment against casting of panels shall be made on prorata basis with respect to total area panels required for the structure on completion of a stage i.e., not less than completion of casting of 25% of the scope of RE wall panel of each bridge.                                     |
| (8.b) Erection of panel/ construction of retaining wall |           | (b) Erection of panel/Construction of retaining wall: Unit of measurement is area in Sqm. Payment against casting of panels shall be made on prorata basis on completion of a stage i.e. completion of erection of panels/ construction of retaining wall complete in all respect for at least 25% scope of work for each structure.             |
| B.1 - Widening and repairs of (a) ROB and (b) RUB       |           |  |
| (1) Foundation  |           | (1) Foundation: Cost of each ROB/RUB shall be determined on pro rata basis with respect to the total linear length (m) of the ROB/RUBs. Payment against foundation shall be made on prorata basis on completion of a stage i.e. not less than 25% of the scope of foundation of the ROB/RUB subject to completion of at least two foundations of |





**Technical Schedule** 

| Stage of payment   | Weightage | Payment procedure   |
|--|-----------|---|
|  |           | the ROB/RUB. In case where load testing is required for foundation, the trigger of the first payment shall include load testing also where specified.   |
| (2) Sub structure  |           | (2) Substructure: Payment against sub-structure shall be made on prorata basis on completion of a stage i.e., not less than 25% of the scope of sub-structure of the ROB/RUB subject to completion of at least two substructure of abutment/piers upto abutment/piers cap level of the ROB/RUB. |
| (3) Superstructure (including bearing)   |           | (3) Super structure: Payment shall be made on prorata basis on completion of a stage i.e., completion of super structure including bearings of at least one span in all respects as specified.  |
| (4) wearing coat: (a) in case of ROB - wearing coat including expansion joints complete in all respects as specified and (b) in case of RUB - rigid pavement under RUB including drainage facility complete in all respect as specified. |           | (4) wearing coat: Payment shall be made on completion of (a) in case of ROB - wearing coat including expansion joints complete in all respects as specified and (b) in case of RUB - rigid payement under RUB including drainage facility complete in all respect as specified.                 |
| (5) Miscellaneous items (like hand rails, crash barriers, road markings etc.)  |           | (5) Miscellaneous: Payment shall be made on completion of all miscellaneous works like hand rail, crash barrier, road markings, etc. complete in all respects as specified.   |
| (6) wing walls/return walls  |           | (6) Wing wall/return wall: Payment shall be made on completion of wing wall/return wall complete in all respects as specified.  |





**Technical Schedule** 

| Stage of payment   | Weightage | Payment procedure  |
|--|-----------|--|
| (7) Approaches (including retaining walls, stone pitching, protection works).  B.2 - New ROB / RUB     |           | (7) Approaches: Payment shall be made on prorata basis on completion of both approaches including stone pitching, protection works, etc. complete in all respect as specified.  Cost of each structure shall be determined on prorata basis with respect to the total linear length (m) of all the structures. Payments shall be made on completion of each stage of structures as per weightage   |
| (1) Foundation: foundation of abutment/piers   |           | given in this table.  (1) Foundation: Payment against foundation shall be made on prorata basis on completion of a stage i.e., not less than 25% of the scope of foundation of the ROB/RUB as per weightage given in this table, subject to completion of at least two foundations of the ROB/RUB in all respect. In case where load testing is required for foundation, the trigger of the first payment shall include load testing also where specified. |
| (2) Sub structure: Substructure for abutment, piers upto the abutment/pier cap level.                  |           | (2) Substructure: Payment against sub-structure shall be made on prorata basis on completion of a stage i.e., not less than 25% of the scope of sub-structure of the ROB/RUB as per weightage given in tis table, subject to completion of at least two substructures of abutment/piers upto abutment/piers cap level of the ROB/RUB.  |
| (3) Superstructure: including girder, deck slab, bearing (excluding wearing coat and expansion joints) |           |  |





**Technical Schedule** 

| Stage of payment   | Weightage | Payment procedure   |
|--|-----------|---|
| (3.a) Super Structure: Casting of girder/fabrication of girders (steel)  |           | (a) Super structure (casting of girder): Unit of measurement is number. Payment against casting of girder shall be made on prorata basis with respect to total number of girders required in the structure on completion of a stage i.e., not less than completion of casting of at least five girders of the structure.          |
| (3.b) Super structure: casting of segments   |           | (b) Super structure (casting of segment): Unit of measurement is number. Payment against casting of segments shall be made on prorata basis with respect to total number of segments required in the structure on completion of a stage i.e., not less than completion of casting of at least 10 (ten) segments of the structure. |
| (3.c) Super structure: erection of girder, deck dlab and bearings  |           | (c) Super structure (erection of girders, deck slab and bearing): Payment shall be made on prorata basis on completion of a stage i.e. completion of super structure including bearings at least one span in all respect as specified.  |
| (4) Other ancillary works: wearing coat, expansion joint, hand railing, crash barriers tests on completion etc. completion in all respect. |           | (4) Other ancillary works: Payment shall be made on prorata basis on completion of a stage in all respect as specified, for each structure.   |
| (5) Miscellaneous items (like hand rails, crash barriers, road markings etc.)  |           | (5) Miscellaneous: Payment shall be made on completion of all miscellaneous works like hand rail, crash barrier, road markings, etc. complete in all respects as specified.   |
| (6) wing walls/return walls upto full height   |           | (6) wing walls/return walls upto full height: Payment shall be made on completion of wing wall/return wall complete for rach ROB/RUB asper weightage given in the table, completion in all respects as specified.   |





**Technical Schedule** 

| Stage of payment  | Weightage | Payment procedure   |
|---|-----------|---|
| (7) Retaining wall/ Reinforced earth wall etc.  (7.a) Panel casting |           | Payment shall be made on prorata basis on completion of both approaches including stone pitching, protection works, etc. complete in all respect as specified.  (a) Panel casting: Unit of  |
|   |           | measurement is area in Sqm. Payment against casting of panels shall be made on prorata basis with respect to total area panels required for the structure on completion of a stage i.e., not less than completion of casting of 25% of the scope of RE wall panel of each ROB/RUB.  |
| (7.b) Erection of panel/ construction of retaining wall             |           | (b) Erection of panel/Construction of retaining wall: Unit of measurement is area in Sqm. Payment against casting of panels shall be made on prorata basis on completion of a stage i.e., completion of erection of panels/construction of retaining wall complete in all respect for at least 25% scope of work for each ROB/RUB.  |
| C.1 - Widening and repairs of Elevated                              |           |   |
| section/Flyover/Grade Separators                                    |           | (4) 5   |
| (1) Foundation  |           | (1) Foundation: Cost of each structure shall be determined on pro rata basis with respect to the total linear length (m) of the structures. Payment against foundation shall be made on prorata basis on completion of a stage i.e., not less than 25% of the scope of foundation of the structure subject to completion of at least two foundations of the structure. In case where load testing is required for foundation, the trigger of the first payment shall include load testing also where specified. |





**Technical Schedule** 

| Stage of payment  | Weightage | Payment procedure  |
|---|-----------|--|
| (2) Sub structure   |           | (2) Sub structure: Payment against sub-structure shall be made on prorata basis on completion of a stage i.e., not less than 25% of the scope of sub-structure of the structure subject to completion of at least two substructure of abutment/piers upto abutment/piers cap level of the structure. |
| (3) Superstructure (including bearing)  |           | (3) Super Structure: Payment shall be made on prorata basis oncompletion of a stage i.e., completion of super structure including bearings of at least one span in all respects as specified.  |
| (4) wearing coat including expansion joint                                    |           | (4) wearing coat including expansion joint: Payment shall be made on completion of wearing coat including expansion joints complete in all respects as specified.  |
| (5) Miscellaneous items (like hand rails, crash barriers, road markings etc.) |           | (5) Miscellaneous: Payment shall be made on completion of all miscellaneous works like hand rail, crash barrier, road markings, etc. complete in all respects as specified.  |
| (6) wing walls/return walls   |           | (6) wing walls/return walls: Payment shall be made on completion of wing wall/return wall complete in all respects as specified.   |
| (7) Approaches (including retaining walls, stone pitching, protection works). |           | (7) Approaches: Payment shall be made on prorata basis on completion of both approaches including stone pitching, protection works, etc. complete in all respect as specified.   |
| C.2 - New Elevated section/Flyover/Grade<br>Separators                        |           | Cost of each structure shall be determined on prorata basis with respect to the total linear length (m) of all the structures. Payments shall be made on completion of each stage of structures as per weightage given in this table.  |





**Technical Schedule** 

|  | VA/ • • • |   |
|--|-----------|---|
| Stage of payment   | Weightage | Payment procedure   |
| (1) Foundation: foundation of abutment/piers   |           | (1) Foundation: Payment against foundation shall be made on prorata basis on completion of a stage i.e., not less than 25% of the scope of foundation of each structure as per weightage given in this table, subject to completion of at least two foundations in allrespect. In case where load testing is required for foundation, the trigger of the first payment shall include load testing also where specified. |
| (2) Sub structure: Substructure for abutment, piers upto the abutment/pier cap level.                  |           | (2) Substructure: Payment against sub-structure shall be made on prorata basis on completion of a stage i.e., not less than 25% of the scope of sub-structure of each structure as per weightage given in tis table, subject to completion of at least two substructures of abutment/piers upto abutment/piers cap level.   |
| (3) Superstructure: including girder, deck slab, bearing (excluding wearing coat and expansion joints) |           |   |
| (3.a) Super Structure: Casting of girder/fabrication of girders (steel)                                |           | (a) Super structure (casting of girder): Unit of measurement is number. Payment against casting of girder shall be made on prorata basis with respect to total number of girders required in the structure on completion of a stage i.e., not less than completion of casting of at least five girders of the structure.  |
| (3.b) Super structure: casting of segments   |           | (b) Super structure (casting of segment): Unit of measurement is number. Payment against casting of segments shall be made on prorata basis with respect to total number of segments required in the structure on completion of a stage i.e., not less than completion of casting of at least 10 (ten) segments of the  |





**Technical Schedule** 

| Stage of payment   | Weightage | Payment procedure   |
|--|-----------|---|
| Stage of payment   | Weightage | structure.  |
|  |           | structure.  |
|  |           |   |
|  |           |   |
|  |           |   |
|  |           |   |
|  |           |   |
| (3.c) Super structure: erection of girder, deck  |           | (c) Super structure (erection                                       |
| Slab and bearings  |           | of girders, deck slab and   |
|  |           | bearing): Payment shall be made                                     |
|  |           | on prorata basis on completion                                      |
|  |           | of a stage i.e., completion of                                      |
|  |           | super structure including   |
|  |           | bearings at least one span in all                                   |
| (4) Other position would be a second   |           | respect as specified.   |
| (4) Other ancillary works: wearing coat,   |           | (4) Other ancillary works:  |
| expansion joint, hand railing, crash barriers tests on completion etc. completion in all |           | Payment shall be made on  |
| respect.   |           | prorata basis on completion of a stage in all respect as specified, |
| respect.   |           | for each structure.   |
| (5) Miscellaneous items (like hand rails, crash  |           | (5) Miscellaneous: Payment  |
| barriers, road markings etc.)  |           | shall be made on completion of                                      |
| barriers, road markings etc.)  |           | all miscellaneous works like hand                                   |
|  |           | rail, crash barrier, road   |
|  |           | markings, etc. complete in all                                      |
|  |           | respects as specified.  |
| (6) wing walls/return walls upto full height   |           | (6) wing walls/return walls   |
|  |           | upto full height: Payment shall                                     |
|  |           | be made on completion of wing                                       |
|  |           | wall/return wall complete for                                       |
|  |           | rach ROB/RUB asper weightage  |
|  |           | given in the table, completion in                                   |
|  |           | all respects as specified.  |
| (7) Retaining wall/ Reinforced earth wall etc.   |           | Payment shall be made on  |
|  |           | prorata basis on completion of                                      |
|  |           | both approaches including stone                                     |
|  |           | pitching, protection works, etc. complete in all respect as         |
|  |           | complete in all respect as specified.                               |
| (7.a) Panel casting  |           | (a) Panel casting: Unit of  |
| (, , a) i direct custing   |           | measurement is area in Sqm.   |
|  |           | Payment against casting of  |
|  |           | panels shall be made on prorata                                     |
|  |           | basis with respect to total area                                    |
|  |           | panels required for the structure                                   |
|  |           | on completion of a stage i.e.,                                      |
|  |           | not less than completion of   |
|  |           | casting of 25% of the scope of RE                                   |
|  |           | wall panel of each ROB/RUB.   |





Technical Schedule

| Stage of payment  | Weightage | Payment procedure  |
|---|-----------|--|
| (7.b) Erection of panel/ construction of retaining wall |           | (b) Erection of panel/Construction of retaining wall: Unit of measurement is area in Sqm. Payment against casting of panels shall be made on prorata basis on completion of a stage i.e., completion of erection of panels/construction of retaining wall complete in all respect for at least 25% scope of work for each ROB/RUB. |

# 1.3.4 Other works.

Procedure for estimating the value of other works done shall be as stated in table 1.3.4: Table 1.3.4

| Stage of Payment  | Weightage | Payment Procedure  |
|---|-----------|--|
| (i) Toll plaza  |           | Unit of measurement is each completed toll plaza. Payment of each toll plaza shall be made on pro rata basis as per following completed stages:  (i) Rigid pavement upto DLC (LHS) - 12.5% (ii) Rigid pavement upto DLC (RHS) - 12.5% (iii)PQC (LHS) - 25% (iv) PQC (RHS) - 25% (v) Admin Building, Maintenance Building &Misc - 10% (vi) Canopy, Toll Booth, Safety Items & Miscellaneous works - 12.5% (vii) Toll plaza Tunnel/over head bridge - 2.5% |
| (ii) Road side drains   |           | Unit of measurement is linear length in km.  Payment shall be made on pro rata basis on  |
| a) Hill Side Trapezoidal/V<br>Type Drain  | 1.61%     | completion of a stage in a length of not less than 5 % (five per cent) of the total length.  |
| b) Catch Water Drain  | 1.55%     |  |
| (iii) Road signs, markings, km<br>stones, safety devices<br>(iv) Project Facilities | 3.70%     |  |
| . , ,   | 0.430/    |  |
| a) Bus bays& shelter  | 0.13%     | Payment shall be made on pro rata basis for  |
| b) Truck lay-byes   | 0.10%     | completed facilities.  |
| c) Rest areas with toilet Block   | 0.12%     |  |
| d) Others   |           |  |





Technical Schedule

| Stage of Payment   | Weightage | Payment Procedure  |
|--|-----------|--|
| (v) Roadside Plantation  | 0.35%     | Unit of measurement is linear length. Payment shall be made on pro rata basis on completion of a stage in a length of not less than 5% (five percent) of the total length. |
| (vi) Repair of Protection works<br>other than approaches to the<br>bridges, elevated sections,<br>flyovers/ grade separators and<br>ROBs/RUBs. |           |  |
| (a) Retaining wall   | 27.14%    |  |
| (vii) Breast Wall  | 26.94%    |  |
| (ix) Hydro-seeding& Mulching   | 4.00%     |  |
| (x) Special Protection for Sinking Zone  | 34.29%    |  |
| (x) Junction Improvement   | 0.07%     |  |

1.3.5 Electrical utilities and public Health Utilities (Water pipelines and sewage lines)
Procedure for estimating the value of other works done shall be as stated in table 1.3.5:

**Table 1.3.5** 

| Stage of Payment   | Weightage | Payment Procedure   |
|--------------------|-----------|---|
| (i) EHT line       | 0.00%     | Unit of measurement is as per completed activities. Cost per activity shall be determined on pro-rate basis as per its weightage with reference to total cost of EHT line. Payment shall be made for completed activity. (The average weightage of major activities (only for payment purpose) in shifting work is (i)Erection of Poles-20%, (ii) Conductor stringing including laying of cable- 30%, (iii) DTR erection (if involved)-15% and (iv) Charging of line including dismantling and site clearance-35% (with DTR) and 50% without DTR) |
| (ii) EHT crossings |           | Cost of each crossing shall be determined on pro-rata basis with reference to total no. of crossings. Payment shall be made for not less than 25% of the crossings subject to a minimum of 4.   |





**Technical Schedule** 

| Stage of Payment  | Weightage | Payment Procedure   |  |  |
|---|-----------|---|--|--|
| (iii) HTI LT line<br>(including transformers if any)          | 86.59%    | Unit of measurement is as per completed activities. Cost per activity shall be determined on pro-rata basis as per its weightage with reference to total cost of LT/HT line. Payment shall be made for completed activity. (The average weightage of major activities (only for payment purpose) in shifting work is (i) Erection of Poles-20% (ii) Conductor stringing including laying of cable- 30%, (iii) DTR erection (if involved)-10% and (iv) Charging of line including dismantling and site clearance-40% (with DTR) and 50% without DTR) |  |  |
| (iv) HT/ LT crossings/ Under<br>Ground Cable Crossings        |           | Cost of each crossing shall be determined on pro-rata basis with reference to total no. of crossings. Payment shall be made for not less than 25% of the crossings subject to completion of minimum of 1 crossings.   |  |  |
| (v) Water pipeline  | 13.41%    | Unit of measurementis as per completed activities. Cost per activity shall be determined on pro-rata basis as per its weightage with reference to total cost of pipe line. Payment shall be made for completed activity. (The average weightage of major activities (only for payment purpose) in shifting work is laying of pipe-50%, Charging of line including all miscellaneous works and dismantling and site clearance-50%)   |  |  |
| (vi) water pipeline crossings & other Items as per Schedule B |           | Cost of each crossing shall be determined on pro-rata basis with reference to total no. of crossings. Payment shall be made for not less than 25% of the crossings subject to a minimum of 8 crossings.   |  |  |
| (vii) Sewage lines  | 0.00%     | Unit of measurement is as per completed activities. Cost per activity shall be determined on pro-rata basis as per its weightage with reference to total cost of pipe line. Payment shall be made for completed activity. (The average weightage of major activities (only for payment purpose) in shifting work is laying of pipe-50%, Charging of line including all miscellaneous works and dismantling and site clearance-50%)  |  |  |
| (viii) Sewage line crossings                                  |           | Cost of each crossing shall be determined on pro-rata basis with reference to total no. of crossings. Payment shall be made for completed activity. (The average weightage of major activities in shifting work is laying pipe-   |  |  |






**Technical Schedule** 

| 50%, Charging of line including                        |               |
|--|---------------|
| miscellaneous works and dismantling and clearance-50%) | all<br>d site |

- 2 Procedure for payment for Maintenance.
- 2.1 The cost for maintenance shall be as stated in Clause 14.1. (i)
- 2.2 Payment for Maintenance shall be made in quarterly instalments in accordance with the provisions of Clause 19.7.







**Technical Schedule** 

SCHEDULE - I (See Clause 10.2 (iv))

#### **DRAWINGS**

## 1 Drawings

In compliance of the obligations set forth in Clause 10.2 of this Agreement, the Contractor shall furnish to the Authority's Engineer, free of cost, all Drawings listed in Annex-I of this Schedule-I.

## 2 Additional Drawings

If the Authority's Engineer determines that for discharging its duties and functions under this Agreement, it requires any drawings other than those listed in Annex-I, it may by notice require the Contractor to prepare and furnish such drawings forthwith. Upon receiving a requisition to this effect, the Contractor shall promptly prepare and furnish such drawings to the Authority's Engineer, as if such drawings formed part of Annex-I of this Schedule-I.

SCHEDULE-I 177





**Technical Schedule** 


#### Annex - I

# (Schedule - I)

## List of Drawings

- 1. A minimum list of the drawings of the various components/elements of the project highway and project facility required to be submitted by the Contractor is given below:
- (a) Drawing of horizontal alignment & vertical profile and detailed cross sections
- (b) Drawings of cross drainage works i.e. Bridges/Culverts/Flyovers and Other Structures.
- (c) Drawings for River Training works
- (d) Drawings of interchanges, major intersections and underpasses
- (e) Drawing of control centre
- (f) Drawings of road furniture items including traffic signage, marking, safety barriers, etc.
- (g) Drawings of traffic diversions plans and traffic control measures
- (h) Drawings of road drainage measures
- (i) Drawings of typical details slope protection measures
- (j) Drawings of landscaping and horticulture
- (k) Drawings of pedestrian crossing
- (l) Drawings of street lighting
- (m) Any other drawings as per instruction of Authority Engineer
- (m) General Arrangement showing Base Camp and Administrative Block

SCHEDULE-I 178







**Technical Schedule** 

#### Schedule - J

(See Clause 10.3 (ii))

## **Project Completion Schedule**

## 1. Project Completion Schedule

During Construction period, the Contractor shall comply with the requirements set forth in this Schedule-J for each of the Project Milestones and the Scheduled Completion Date. Within 15 (fifteen) days of the date of each Project Milestone, the Contractor shall notify the Authority of such compliance along with necessary particulars thereof.

# 2. Project Milestone-I

- (i) Project Milestone-I shall occur on the date falling on the 256<sup>th</sup> day from then Appointed Date (the "Project Milestone-I").
- (ii) Prior to the occurrence of Project Milestone-I, the Contractor shall have commenced construction of the Project Highway and submitted to the Authority duly and validly prepared Stage Payment Statements for an amount not less than 10% (ten per cent) of the Contract Price.

#### 3. Project Milestone-II

- (i) Project Milestone-II shall occur on the date falling on the 438<sup>th</sup> day from the Appointed Date (the "Project Milestone- II").
- (ii) Prior to the occurrence of Project Milestone-II, the Contractor shall have continued with construction of the Project Highway and submitted to the Authority duly and validly prepared Stage Payment Statements for an amount not less than 35% (thirty five per cent) of the Contract Price and should have started construction of all bridges.

# 4. Project Milestone-III

- (i) Project Milestone-III shall occur on the date falling on the 621<sup>th</sup> day from the Appointed Date (the "Project Milestone-III").
- (ii) Prior to the occurrence of Project Milestone-III, the Contractor shall have continued with construction of the Project Highway and submitted to the Authority duly and validly prepared Stage Payment Statements for an amount not less than 70% (seventy per cent) of the Contract Price and should have started construction of all project facilities.

SCHEDULE-J 180





**Technical Schedule** 


## 5. Scheduled Completion Date

- (i) The Scheduled Completion Date shall occur on the 730<sup>th</sup> day from the Appointed Date.
- (ii) On or before the Scheduled Completion Date, the Contractor shall have completed construction in accordance with this Agreement.

# 6. Extension of time

Upon extension of any or all of the aforesaid Project Milestones or the Scheduled Completion Date, as the case may be, under and in accordance with the provisions of this Agreement, the Project Completion Schedule shall be deemed to have been amended accordingly.

SCHEDULE-J 181







**Technical Schedule** 

## SCHEDULE - K (See Clause 12.1 (ii))

## **Tests on Completion**

#### 1 Schedule for Tests

- (i) The Contractor shall, no later than 30 (thirty) days prior to the likely completion of construction, notify the Authority's Engineer and the Authority of its intent to subject the Project Highway to Tests, and no later than 10 (ten) days prior to the actual date of Tests, furnish to the Authority's Engineer and the Authority detailed inventory and particulars of all works and equipment forming part of Works.
- (ii) The Contractor shall notify the Authority's Engineer of its readiness to subject the Project Highway to Tests at any time after 10 (ten) days from the date of such notice, and upon receipt of such notice, the Authority's Engineer shall, in consultation with the Contractor, determine the date and time for each Test and notify the same to the Authority who may designate its representative to witness the Tests. The Authority's Engineer shall thereupon conduct the Tests itself or cause any of the Tests to be conducted in accordance with Article 12 and this Schedule-K.

#### 2 Tests

- (i) Visual and physical test: The Authority's Engineer shall conduct a visual and physical check of construction to determine that all works and equipment forming part thereof conform to the provisions of this Agreement. The physical tests shall include [\*\*\*].
- (ii) Riding quality test: Riding quality of each lane of the carriageway shall be checked with the help of a Network Survey Vehicle (NSV) fitted with latest equipments and the maximum permissible roughness for purposes of this Test shall be [2,000 (two thousand)] mm for each kilometer.
- (iii) Tests for bridges: All major and minor bridges shall be subjected to the rebound hammer and ultrasonic pulse velocity tests, to be conducted in accordance with the procedure described in Special Report No. 17: 1996 of the IRC Highway Research Board on Nondestructive Testing Techniques, at two spots in every span, to be chosen at random by the Authority's Engineer. Bridges with a span of 15 (fifteen) metres or more shall also be subjected to load testing.
- (iv) Other tests: The Authority's Engineer may require the Contractor to carry out or cause to be carried additional tests, in accordance with Good Industry Practice, for determining the compliance of the Project Highway with Specifications and standards, except tests as specified in clause 5, but shall include measuring the reflectivity of road markings and road signs; and measuring the illumination level (lux) of lighting using requisite testing equipment.

SCHEDULE-K 183





**Technical Schedule** 

- (v) Environmental audit: The Authority's Engineer shall carry out a check to determine conformity of the Project Highway with the environmental requirements set forth in Applicable Laws and Applicable Permits.
- (vi) Safety Audit: The Authority's Engineer shall carry out, or cause to be carried out, a safety audit to determine conformity of the Project Highway with the safety requirements and Good Industry Practice.

## 3 Agency for conducting Tests

All Tests set forth in this Schedule-K shall be conducted by the Authority's Engineer or such other agency or person as it may specify in consultation with the Authority.

## 4 Completion Certificate


Upon successful completion of Tests, the Authority's Engineer shall issue the Completion Certificate in accordance with the provisions of Article 12.

5. The Authority Engineer will carry out tests with following equipment at his own Cost in the presence of contractor's representative.

| S.No. | Key metrics of<br>Asset | Equipment to be used  | Frequency of condition survey        |
|-------|-------------------------|-----------------------|--------------------------------------|
| 1     | Surface                 | Network Survey        | At least twice a year (As per survey |
|       | defects of              | Vehicle (NSV)         | months defined for the state basis   |
|       | pavement                |                       | rainy season)                        |
| 2     | Roughness of            | Network Survey        | At least twice a year (As per survey |
|       | pavement                | Vehicle (NSV)         | months defined for the state basis   |
|       |                         |                       | rainy season)                        |
| 3     | Strength of             | Falling Weight        | At least once a year                 |
|       | pavement                | Deflectometer (FWD)   |                                      |
| 4     | Bridges                 | Mobile Bridge         | At least twice a year (As per survey |
|       |                         | Inspection Unit (MBU) | months defined for the state basis   |
|       |                         |                       | rainy season)                        |
| 5     | Road signs              | Retro-reflectometer   | At least twice a year (As per survey |
|       |                         |                       | months defined for the state basis   |
|       |                         |                       | rainy season)                        |

The first testing with the help of NSV shall be conducted at the time of issue of Completion Certificate.

SCHEDULE-K 184







**Technical Schedule** 

# Schedule - L (See Clause 12.2) Completion Certificate

| 1 | I,  |
|---|---|
|   | "Agreement"), for "Upgradation & Improvement of Tamenglong- Mahur Road (NH-137) to two lane with paved shoulders in the state of Assam on |
|   | Engineering, Procurement & Construction (EPC) mode - Package-7 starting   |
|   | near Jiri River(Assam/Manipur Border) at km 96.870 and ending near  |
|   | Hangrum at km 116.550 (Length-19.68km)" (the "Project Highway") on  |
|   | Engineering, Procurement and Construction (EPC) basis through   |
|   | (Name of Contractor), hereby certify that the Tests in accordance with Article 12   |
|   | of the Agreement have been successfully undertaken to determine compliance of   |
|   | the Project Highway with the provisions of the Agreement, and I am satisfied that   |
|   | the Project Highway can be safely and reliably placed in service of the Users   |
|   | thereof.  |

It is certified that, in terms of the aforesaid Agreement, all works forming part of Project Highway have been completed, and the Project Highway is hereby declared fit for entry into operation on this the ........ day of ........ 20.....

SIGNED, SEALED AND DELIVERED

For and on behalf of

The Authority's Engineer by:


(Signature)

(Name)

(Designation)

(Address)

SCHEDULE-L 186







**Technical Schedule** 

# SCHEDULE - M (See Clauses 14.6, 15.2 and 19.7) PAYMENT REDUCTION FOR NON-COMPLIANCE

- 1. Payment reduction for non-compliance with the Maintenance Requirements
- (i) Monthly lump sum payments for maintenance shall be reduced in the case of noncompliance with the Maintenance Requirements set forth in Schedule-E.
- (ii) Any deduction made on account of non-compliance with the Maintenance Requirements shall not be paid even after compliance subsequently. The deductions shall continue to be made every month until compliance is done.
- (iii) The Authority's Engineer shall calculate the amount of payment reduction on the basis of weightage in percentage assigned to non-conforming items as given in Paragraph 2.
- 2. Percentage reductions in lump sum payments
- The following percentages shall govern the payment reduction:

| S.<br>No. | Item/Defect/Deficiency   | Percentage |
|-----------|--|------------|
| (a)       | Carriageway/Pavement   |            |
| (*)       |  | 4.50/      |
| (i)       | Potholes, cracks, other surface defects  | 15%        |
| (ii)      | Repairs of Edges, Rutting  | 5%         |
| (b)       | Road, Embankment, Cuttings, Shoulders  |            |
| (i)       | Edge drop, inadequate crossfall, undulations, settlement, potholes, ponding, obstructions  | 10%        |
| (ii)      | Deficient slopes, raincuts, disturbed pitching, vegetation growth, pruning of trees  | 5%         |
| (c)       | Bridges and Culverts   |            |
| (i)       | Desilting, cleaning. vegetation growth, damaged pitching, flooring, parapets, wearing course, footpaths, any damage to foundations | 20%        |
| (ii)      | Any Defects in superstructures, bearings and sub-structures  | 10%        |
| (iii)     | Painting, repairs/replacement kerbs, railings, parapets, guideposts/crash barriers   | 5%         |
| (d)       | Roadside Drains  |            |
| (i)       | Cleaning and repair of drains  | 5%         |
| (e)       | Road Furniture   |            |

SCHEDULE-M 188





**Technical Schedule** 

| (i)  | Cleaning, painting, replacement of road signs, delineators, road markings, 200 m/km/5th km stones                        | 5%  |
|------|--|-----|
| (f)  | Miscellaneous Items  |     |
| (i)  | Removal of dead animals, broken down/accidented vehicles, fallen trees, road blockades or malfunctioning of mobile crane | 10% |
| (ii) | Any other Defects in accordance with paragraph 1.  | 5%  |
| (g)  | Defects in Other Project Facilities  | 5%  |

(ii) The amount to be deducted from monthly lump-sum payment for non-compliance of particular item shall be calculated as under:

 $R=P/100 \times (M_1 \text{ or } M_2) \times L1/L$ 

Where P = Percentage of particular item/Defect/deficiency for deduction

M = Monthly lump-sum payment in accordance with the Bid

L1 = Non-complying length


L = Total length of the road,

R = Reduction (the amount to be deducted for non-compliance for a particular item/Defect/deficiency

The total amount of reduction shall be arrived at by summation of reductions for such items/Defects/deficiency or non-compliance.

For any Defect in a part of one kilometer, the non-conforming length shall be taken as one kilometer.

SCHEDULE-M 189







**Technical Schedule** 

# SCHEDULE - N (See Clause 18.1.1)

# SELECTION OF AUTHORITY'S ENGINEER

# 1 Selection of Authority's Engineer

- 1.1 The provisions of the Model Request for Proposal for Selection of Technical Consultants, issued by the Ministry of Finance in May 2009, or any substitute thereof shall apply for selection of an experienced firm to discharge the functions and duties of an Authority's Engineer.
- 1.2 In the event of termination of the Technical Consultants appointed in accordance with the provisions of Paragraph 1.1, the Authority shall appoint another firm of Technical Consultants forthwith and may engage a government-owned entity in accordance with the provisions of Paragraph 3 of this Schedule-N.

#### 2 Terms of Reference

The Terms of Reference for the Authority's Engineer (the "TOR") shall substantially conform with Annex 1 to this Schedule N.

## 3 Appointment of Government entity as Authority's Engineer

Notwithstanding anything to the contrary contained in this Schedule, the Authority may in its discretion appoint a government-owned entity as the Authority's Engineer; provided that such entity shall be a body corporate having as one of its primary functions the provision of consulting, advisory and supervisory services for engineering projects; provided further that a government-owned entity which is owned or controlled by the Authority shall not be eligible for appointment as Authority's Engineer.





**Technical Schedule** 

# Annex - I (Schedule - N)

#### TERMS OF REFERENCE FOR AUTHORITY'S ENGINEER

## 1 Scope

- (ii) The TOR shall apply to construction and maintenance of the Project Highway.

## 2 Definitions and interpretation

- (i) The words and expressions beginning with or in capital letters and not defined herein but defined in the Agreement shall have, unless repugnant to the context, the meaning respectively assigned to them in the Agreement.
- (ii) References to Articles, Clauses and Schedules in this TOR shall, except where the context otherwise requires, be deemed to be references to the Articles, Clauses and Schedules of the Agreement, and references to Paragraphs shall be deemed to be references to Paragraphs of this TOR.
- (iii) The rules of interpretation stated in Article 1 of the Agreement shall apply, mutatis mutandis, to this TOR.

# 3. General

- (i) The Authority's Engineer shall discharge its duties in a fair, impartial and efficient manner, consistent with the highest standards of professional integrity and Good Industry Practice.
- (ii) The Authority's Engineer shall perform the duties and exercise the authority in accordance with the provisions of this Agreement, but subject to obtaining prior written approval of the Authority before determining:
  - (a) any Time Extension;
  - (b) any additional cost to be paid by the Authority to the Contractor;
  - (c) the Termination Payment; or
  - (d) any other matter which is not specified in (a), (b) or (c) above and which





**Technical Schedule** 

creates an obligation or liability on either Party for a sum exceeding Rs. 5,000,000 (Rs. fifty lakh).

- (iii) The Authority's Engineer shall submit regular periodic reports, at least once every month, to the Authority in respect of its duties and functions under this Agreement. Such reports shall be submitted by the Authority's Engineer within 10 (ten) days of the beginning of every month.
- (iv) The Authority's Engineer shall inform the Contractor of any delegation of its duties and responsibilities to its suitably qualified and experienced personnel; provided, however, that it shall not delegate the authority to refer any matter for the Authority's prior approval in accordance with the provisions of Clause 18.2.
- (v) The Authority's Engineer shall aid and advise the Authority on any proposal for Change of Scope under Article 13.
- (vi) In the event of any disagreement between the Parties regarding the meaning, scope and nature of Good Industry Practice, as set forth in any provision of the Agreement, the Authority's Engineer shall specify such meaning, scope and nature by issuing a reasoned written statement relying on good industry practice and authentic literature.

#### 4 Construction Period

- During the Construction Period, the Authority's Engineer shall review and approve the Drawings furnished by the Contractor along with supporting data, including the geotechnical and hydrological investigations, characteristics of materials from borrow areas and quarry sites, topographical surveys, and the recommendations of the Safety Consultant in accordance with the provisions of Clause 10.1 (vi). The Authority's Engineer shall complete such review and approval and send its observations to the Authority and the Contractor within 15 (fifteen) days of receipt of such Drawings; provided, however that in case of a Major Bridge or Structure, the aforesaid period of 15 (fifteen) days may be extended upto 30 (thirty) days. In particular, such comments shall specify the conformity or otherwise of such Drawings with the Scope of the Project and Specifications and Standards.
- (ii) The Authority's Engineer shall review any revised Drawings sent to it by the Contractor and furnish its comments within 10 (ten) days of receiving such Drawings.
- (iii) The Authority's Engineer shall review the Quality Assurance Plan submitted by the Contractor and shall convey its comments to the Contractor within a period of 21 (twenty-one) days stating the modifications, if any, required thereto.
- (iv) The Authority's Engineer shall complete the review and approve of the methodology proposed to be adopted by the Contractor for executing the Works, and convey its comments to the Contractor within a period of 10 (ten) days from the date of receipt of the proposed methodology from the Contractor.
- (v) The Authority's Engineer shall grant written approval to the Contractor, where necessary, for interruption and diversion of the flow of traffic in the existing lane(s) of the Project Highway for purposes of maintenance during the Construction Period in accordance with the provisions of Clause 10.4.





**Technical Schedule** 

- (vi) The Authority's Engineer shall review the monthly progress report furnished by the Contractor and send its comments thereon to the Authority and the Contractor within 7 (seven) days of receipt of such report.
- (vii) The Authority's Engineer shall inspect the Construction Works and the Project Highway and shall submit a monthly Inspection Report bringing out the results of inspections and the remedial action taken by the Contractor in respect of Defects or deficiencies. In particular, the Authority's Engineer shall include in its Inspection Report, the compliance of the recommendations made by the Safety Consultant.
- (viii) The Authority's Engineer shall conduct the pre-construction review of manufacturer's test reports and standard samples of manufactured Materials, and such other Materials as the Authority's Engineer may require.
- (ix) For determining that the Works conform to Specifications and Standards, the Authority's Engineer shall require the Contractor to carry out, or cause to be carried out, tests at such time and frequency and in such manner as specified in the Agreement and in accordance with Good Industry Practice for quality assurance. For purposes of this Paragraph 4.9, the tests specified in the IRC Special Publication-11 (Handbook of Quality Control for Construction of Roads and Runways) and the Specifications for Road and Bridge Works issued by MORTH (the "Quality Control Manuals") or any modification/substitution thereof shall be deemed to be tests conforming to Good Industry Practice for quality assurance.
- (x) The Authority's Engineer shall test check at least 20 (twenty) percent of the quantity or number of tests prescribed for each category or type of test for quality control by the Contractor.
- (xi) The timing of tests referred to in Paragraph 4.9, and the criteria for acceptance/rejection of their results shall be determined by the Authority's Engineer in accordance with the Quality Control Manuals. The tests shall be undertaken on a random sample basis and shall be in addition to, and independent of, the tests that may be carried out by the Contractor for its own quality assurance in accordance with Good Industry Practice.
- (xii) In the event that results of any tests conducted under Clause 11.10 establish any Defects or deficiencies in the Works, the Authority's Engineer shall require the Contractor to carry out remedial measures.
- (xiii) The Authority's Engineer may instruct the Contractor to execute any work which is urgently required for the safety of the Project Highway, whether because of an accident, unforeseeable event or otherwise; provided that in case of any work required on account of a Force Majeure Event, the provisions of Clause 21.6 shall apply.
- (xiv) In the event that the Contractor fails to achieve any of the Project Milestones, the Authority's Engineer shall undertake a review of the progress of construction and identify potential delays, if any. If the Authority's Engineer shall determine that completion of the Project Highway is not feasible within the time specified in the Agreement, it shall require the Contractor to indicate within 15 (fifteen) days





**Technical Schedule** 

the steps proposed to be taken to expedite progress, and the period within which the Project Completion Date shall be achieved. Upon receipt of a report from the Contractor, the Authority's Engineer shall review the same and send its comments to the Authority and the Contractor forthwith.

- (xv) The Authority's Engineer shall obtain from the Contractor a copy of all the Contractor's quality control records and documents before the Completion Certificate is issued pursuant to Clause 12.4.
- (xvi) Authority's Engineer may recommend to the Authority suspension of the whole or part of the Works if the work threatens the safety of the Users and pedestrians. After the Contractor has carried out remedial measure, the Authority's Engineer shall inspect such remedial measures forthwith and make a report to the Authority recommending whether or not the suspension hereunder may be revoked.
- (xvii) In the event that the Contractor carries out any remedial measures to secure the safety of suspended works and Users, and requires the Authority's Engineer to inspect such works, the Authority's Engineer shall inspect the suspended works within 3 (three) days of receiving such notice, and make a report to the Authority forthwith, recommending whether or not such suspension may be revoked by the Authority.
- (xviii) The Authority's Engineer shall carry out, or cause to be carried out, all the Tests specified in Schedule-K and issue a Completion Certificate or Provisional Certificate, as the case may be. For carrying out its functions under this Paragraph 4.18 and all matters incidental thereto, the Authority's Engineer shall act under and in accordance with the provisions of Article 12 and Schedule-K.

## 5. Maintenance Period

- (i) The Authority's Engineer shall aid and advise the Contractor in the preparation of its monthly Maintenance Programme and for this purpose carry out a joint monthly inspection with the Contractor.
- (ii) The Authority's Engineer shall undertake regular inspections, at least once every month, to evaluate compliance with the Maintenance Requirements and submit a Maintenance Inspection Report to the Authority and the Contractor.
- (iii) The Authority's Engineer shall specify the tests, if any, that the Contractor shall carry out, or cause to be carried out, for the purpose of determining that the Project Highway is in conformity with the Maintenance Requirements. It shall monitor and review the results of such tests and the remedial measures, if any, taken by the Contractor in this behalf.
- (iv) In respect of any defect or deficiency referred to in Paragraph 3 of Schedule-E,





**Technical Schedule** 

the Authority's Engineer shall, in conformity with Good Industry Practice, specify the permissible limit of deviation or deterioration with reference to the Specifications and Standards and shall also specify the time limit for repair or rectification of any deviation or deterioration beyond the permissible limit.

- (v) The Authority's Engineer shall examine the request of the Contractor for closure of any lane(s) of the Project Highway for undertaking maintenance/repair thereof, and shall grant permission with such modifications, as it may deem necessary, within 5 (five) days of receiving a request from the Contractor. Upon expiry of the permitted period of closure, the Authority's Engineer shall monitor the reopening of such lane(s), and in case of delay, determine the Damages payable by the Contractor to the Authority under Clause 14.5.
- 6 Determination of costs and time
- (i) The Authority's Engineer shall determine the costs, and/or their reasonableness, that are required to be determined by it under the Agreement.
- (ii) The Authority's Engineer shall determine the period of Time Extension that is required to be determined by it under the Agreement.
- (iii) The Authority's Engineer shall consult each Party in every case of determination in accordance with the provisions of Clause 18.5.

## 7. Payments

- (i) The Authority's Engineer shall withhold payments for the affected works for which the Contractor fails to revise and resubmit the Drawings to the Authority's Engineer in accordance with the provisions of Clause 10.2.4 (d).
- (ii) Authority's Engineer shall -
- (a) within 10 (ten) days of receipt of the Stage Payment Statement from the Contractor pursuant to Clause 19.4, determine the amount due to the Contractor and recommend the release of 90 (ninety) percent of the amount so determined as part payment, pending issue of the Interim Payment Certificate; and
- (b) within 15 (fifteen) days of the receipt of the Stage Payment Statement referred to in Clause 19.4, deliver to the Authority and the Contractor an Interim Payment Certificate certifying the amount due and payable to the Contractor, after adjustments in accordance with the provisions of Clause 19.10.
- (iii) The Authority's Engineer shall, within 15 (fifteen) days of receipt of the Monthly Maintenance Statement from the Contractor pursuant to Clause 19.6, verify the Contractor's monthly statement and certify the amount to be paid to the Contractor in accordance with the provisions of the Agreement.
- (iv) The Authority's Engineer shall certify final payment within 30 (thirty) days of the





Technical Schedule


receipt of the final payment statement of Maintenance in accordance with the provisions of Clause 19.16.

## 8. Other duties and functions

The Authority's Engineer shall perform all other duties and functions as specified in the Agreement.

## 9 Miscellaneous

- (i) A copy of all communications, comments, instructions, Drawings or Documents sent by the Authority's Engineer to the Contractor pursuant to this TOR, and a copy of all the test results with comments of the Authority's Engineer thereon, shall be furnished by the Authority's Engineer to the Authority forthwith.
- (ii) The Authority's Engineer shall retain at least one copy each of all Drawings and Documents received by it, including "as-built" Drawings, and keep them in its safe custody.
- (iii) Within 90 (ninety) days of the Project Completion Date, the Authority's Engineer shall obtain a complete set of as-built Drawings, in 2 (two) hard copies and in micro film form or in such other medium as may be acceptable to the Authority, reflecting the Project Highway as actually designed, engineered and constructed, including an as-built survey illustrating the layout of the Project Highway and setback lines, if any, of the buildings and structures forming part of Project Facilities; and shall hand them over to the Authority against receipt thereof.
- (iv) The Authority's Engineer, if called upon by the Authority or the Contractor or both, shall mediate and assist the Parties in arriving at an amicable settlement of any Dispute between the Parties.
- (v) The Authority's Engineer shall inform the Authority and the Contractor of any event of Contractor's Default within one week of its occurrence.







**Technical Schedule** 

## **SCHEDULE - 0**

(See Clauses 19.4.1, 19.6.1, and 19.8.1)

# Forms of Payment Statements

## 1. Stage Payment Statement for Works

The Stage Payment Statement for Works shall state:

- (a) the estimated amount for the Works executed in accordance with Clause 19.3(i) subsequent to the last claim;
- (b) amounts reflecting adjustments in price for the aforesaid claim;
- (c) the estimated amount of each Change of Scope Order executed subsequent to the last claim;
- (d) amounts reflecting adjustment in price, if any, for (c) above in accordance with the provisions of Clause 13.2(iii) (a);
- (e) total of (a), (b), (c) and (d) above;
- (f) Deductions:
  - (i) Any amount to be deducted in accordance with the provisions of the Agreement except taxes;
  - (ii) Any amount towards deduction of taxes; and
  - (iii) Total of (i) and (ii) above.
- (g) Net claim: (e) (f) (iii);
- (h) The amounts received by the Contractor upto the last claim:
  - (i) For the Works executed (excluding Change of Scope orders);
  - (ii) For Change of Scope Orders, and
  - (iii) Taxes deducted

## 2. Monthly Maintenance Payment Statement


The monthly Statement for Maintenance Payment shall state:

- (a) The monthly payment admissible in accordance with the provisions of the Agreement;
- (b) The deductions for maintenance work not done;
- (c) Net payment for maintenance due, (a) minus (b);
- (d) Amounts reflecting adjustments in price under Clause 19.12; and
- (e) Amount towards deduction of taxes.

## 3. Contractor's claim for Damages

Note: The Contractor shall submit its claims in a form acceptable to the Authority.

SCHEDULE-O 199







**Technical Schedule** 

# SCHEDULE - P (See Clause 20.1)

## **INSURANCE**

# 1. Insurance during Construction Period

- (i) The Contractor shall effect and maintain at its own cost, from the Appointed Date till the date of issue of the Completion Certificate, the following insurances for any loss or damage occurring on account of Non Political Event of Force Majeure, malicious act, accidental damage, explosion, fire and terrorism:
  - Insurance of Works, Plant and Materials and an additional sum of [15 (fifteen)] per cent of such replacement cost to cover any additional costs of and incidental to the rectification of loss or damage including professional fees and the cost of demolishing and removing any part of the Works and of removing debris of whatsoever nature; and
  - (b) Insurance for the Contractor's equipment and Documents brought onto the Site by the Contractor, for a sum sufficient to provide for their replacement at the Site.
- (ii) The insurance under sub para (a) and (b) of paragraph 1(i) above shall cover the Authority and the Contractor against all loss or damage from any cause arising under Paragraph 1.1 other than risks which are not insurable at commercial terms.

# 2. Insurance for Contractor's Defects Liability

The Contractor shall effect and maintain insurance cover of not less than 15% of the Contract Price for the Works from the date of issue of the Completion Certificate until the end of the Defects Liability Period for any loss or damage for which the Contractor is liable and which arises from a cause occurring prior to the issue of the Completion Certificate. The Contractor shall also maintain other insurances for maximum sums as may be required under the Applicable Laws and in accordance with Good Industry Practice.

## 3. Insurance against injury to persons and damage to property

(i) The Contractor shall insure against its liability for any loss, damage, death or bodily In jury, or damage to any property (except things insured under Paragraphs 1 and 2 of this Schedule or to any person (except persons insured under Clause 20.9), which may arise out of the Contractor's performance of this Agreement. This insurance shall be for a limit per occurrence of not less than the amount stated below with no limit on the number of occurrences.

The insurance cover shall be not less than: Rs. [\*\*\*\*\*]

- (ii) The insurance shall be extended to cover liability for all loss and damage to the Authority's property arising out of the Contractor's performance of this Agreement excluding:
  - (a) the Authority's right to have the construction works executed on, over, under, in or through any land, and to occupy this land for the Works; and
  - (b) Damage which is an unavoidable result of the Contractor's obligations to execute the Works.

SCHEDULE-P 201






**Technical Schedule** 

# 4. Insurance to be in joint names

The insurance under paragraphs 1 to 3 above shall be in the joint names of the Contractor and the Authority.

SCHEDULE-P 202







**Technical Schedule** 

## Schedule-Q

(See Clause 14.10)

## Tests on Completion of Maintenance Period


# 1. Riding Quality test:

Riding quality test: Riding quality of each lane of the carriageway shall be checked with the help of a calibrated bump integrator and the maximum permissible roughness for purposes of this Test shall be [2,200 (two thousand and two hundred only)] mm for each kilometer.

# 2. Visual and physical test:

The Authority's Engineer shall conduct a visual and physical check of construction to determine that all works and equipment forming part thereof conform to the provisions of this Agreement. The physical tests shall include measurement of cracking, rutting, stripping and potholes and shall be as per the requirement of maintenance mentioned in Schedule-E.

SCHEDULE-Q 204







**Technical Schedule** 

## Schedule-R

(See Clause 14.10)

# Taking Over Certificate

| I, (Name and designation of the Authority's Representative) under and in                  |
|---|
| accordance with the Agreement dated (the "Agreement"), "Upgradation &                     |
| Improvement of Tamenglong- Mahur Road (NH-137) to two lane with paved shoulders in        |
| the state of Assam on Engineering, Procurement & Construction (EPC) mode - Package-7      |
| starting near Jiri River(Assam/Manipur Border) at km 96.870 and ending near Hangrum at    |
| km 116.550 (Length-19.68km)" (the "Project Highway") on Engineering, Procurement and      |
| Construction (EPC) basis through (Name of Contractor), hereby certify that the            |
| Tests on completion of Maintenance Period in accordance with Article 14 of the Agreement  |
| have been successfully undertaken to determine compliance of the Project Highway with the |
| provisions of the Agreement and I hereby certify that the Authority has taken over the    |
| Project highway from the Contractor on this day   |
|   |
|   |
|   |
|   |
|   |
|   |
|   |
| CICNED CEALED AND DELIVEDED   |
| SIGNED, SEALED AND DELIVERED  |
|   |
|   |
|   |
|   |
| (Signature)   |
| (Name and designation of Authority's Popuseentative)                                      |
| (Name and designation of Authority's Representative)                                      |
| (Address)   |

SCHEDULE-R 206