# **SCHEDULES**

[CONSTRUCTION OF BALANCE WORK OF TWO – LANE WITH HARD SHOULDERS OF EXISTING HAYULIANG – HAWAI ROAD (NH-113) FROM DESIGN KM 51.825 TO KM 63.131 (EXISTING KM 45.050 OF HAYULIANG – HAWAI ROAD TO HAWAI TOWN)(11.306 KM) ON EPC BASIS IN THE STATE OF ARUNACHAL PRADESH PACKAGE OF SARDP –NE (GREEN FIELD ALIGNMENT)]

### SCHEDULE - A

(See Clauses 2.1 and 8.1)

### SITE OF THE PROJECT

### 1 The Site

- 1.1 Site of the Two-Laning of Hayuliang— Hawai Road on EPC basis from design Km. 51.825 to Km. 63.131 [Existing Km 45.050 (Hayuliang Hawai road) to Hawai Town] in the state of Arunachal Pradesh under SARDP-NE, Project Highway shall include the land, buildings, structures and road works as described in Annex-I of this Schedule-A.
  - The Project alignment is approachable only from Hawai town (End of Project Road) for execution works.
- 1.2 The dates of handing over the Right of Way to the Contractor are specified in Annex-II of this Schedule-A.
- 1.3 AninventoryoftheSiteincludingtheland,buildings,structures,roadworks,trees and any other immovable property on, or attached to, the Site shall be prepared jointly by the Authority Representative and the Contractor, and such inventory shall form part of the memorandum referred to in Clause 8.2.1of this Agreement.
- The alignment plans of the Project Highway are specified in Annex-III. In the case of sections where no modification in the existing alignment of the Project Highway is contemplated, the alignment plan has not been provided. Alignment plans have only been given for sections where the existing alignment is proposed to be modified.
- The status of the environment clearances obtained or awaited is given in Annex IV.

# Annex - I (Schedule-A)

### 1. Site

The site of the two lane Project Highway comprises the section of Hawai bypass road commencing from existing Km 45.050 (Hayuliang – Hawai road) to Hawai Town [from Km 51.825 to Km 63.131, Design] in the State of Arunachal Pradesh. The land, carriageway and structures comprising the Site are described below.

### 2. Chainage References (Topographical vsDesign)

"Topographical Chainage" means survey done at site on final approved alignment because no any alignment exists there presently". After finalization of alignment by improving the existing geometry the Chainage has been referred to "Design Chainage". The relationship between the "Topographical Chainage" and the "Design Chainage" as per field surveys for the "Project Highway" is given below.

Sl. No.	Topo / Existing Chainage	Design Chainage (km)
1	0	51.825
2	500	52.335
3	1000	52.845
4	1500	53.365
5	2000	53.855
6	2500	54.355
7	3000	54.855
8	3500	55.410
9	4000	55.905
10	4500	56.425
11	5000	56.895
12	5500	57.385
13	6000	58.055
14	6500	58.580
15	7000	59.065
16	7500	59.545
17	8000	60.040
18	8500	60.525
19	9000	61.025
20	9500	61.515
21	10000	62.025
22	10500	62.525
23	11000	63.025
24	11112	63.131

### 3. Land

The Site of the Project Highway comprises the land described below:

Sl. No.	Existing Chainage (Km)		(8111)		Length in Km (Design)	ROW	Remarks
	From	To	From	To	Kili (Desigli)	( <b>m</b> )	
1	0.000	0.230	51.825	52.055	0.230	24	
2	0.550	1.000	52.375	52.825	0.450	18	
3	2.500	2.600	54.325	54.425	0.100	24	
4	2.950	3.340	54.775	55.165	0.390	24	
6	5.040	5.160	56.865	56.985	0.120	16	
7	5.160	5.390	56.985	57.215	0.230	24	
8	5.800	5.830	57.625	57.655	0.030	24	
9	6.800	11.306	58.625	63.131	4.506	24	
				Total	6.056		

### 4. Carriageway

The present carriageway detail is shown in the table below:

Sl.	Existing Chainage (Km)		S S Elligh III	Lane Width	Remarks		
No.	From	To	From	To			TCIIIII INS
1	0.000	6.800	51825	58455	6800	Nil	
2	6.800	11.112	58455	63131	4676	3-8	Non-motorized Earthen track

# **5.** Earthwork done as per 2Laning in following stretches upto top of Subgrade (Rectification work needs to be carried out in some chainages vide Schedule-B).

Cha	ninage (km)	a	Formation	
From	То	Side	Width available	Length (Km)
62+590	62+900	B/S		0.310
62+120	62+590	B/S		0.470
62+000	62+120	B/S		0.120
61+850	62+000	B/S		0.150
61+550	61+850	B/S	12m	0.300
61+420	61+550	B/S		0.130
61+180	61+420	B/S	] [	0.240
59+000	59+300	B/S	] [	0.300
58+750	59+000	B/S		0.250

62+900	63+000	B/S		0.100
63+000	63+080	B/S		0.080
61+050	61+180	B/S		0.130
59+580	59+740	B/S		0.160
58+660	58+740	B/S		0.080
59+310	59+430	B/S		0.120
			Total =	2.94 Km

# 6. Major Bridges

The Site includes the following Major Bridges:

		Type of Structure			No. of Spans	
Sl. No.	Existing Chainage (km)	Foundation	Sub- structure	Superstr ucture	with span length (m)	Width (m)
NIL						

# 7. Road over-bridges(ROB)

The Site includes the following ROB (road over railway line)

Sl. No.	Chainage (km)	Type of Structure		No. of Spans with span length (m)	Width (m)	ROB		
1,00	()	Foundation	Superstructure		(===)			
	NIL							

# 8. Grade separators

The Site includes the following grade separators:

Sl.		Type of Structure		No. of Spans	Width		
No.	Chainage (km)	Foundation	Superstructure	with span length (m)	(m)		
	NIL						

# 9. Minor bridges

The Site includes the following minor bridges:

Sl. No.	Existing (m)	Type of Structure		ıre	Span	Width			
		_			Foundation	RAHNASHAN I	Super	length (m)	( <b>m</b> )
		Foundation	structure	Structure					
1			NIL						

# 10. Railway level crossings / Railway Track

The Site includes the following railway level crossings / Track:

Sl. No.	Location (km)	Remarks
	NIL	

# 11. Underpasses (Vehicular, Non Vehicular)

The Site includes the following underpasses:

Sl. No.	Chainage (km)	Type of Structure	No. of Spans with	Width (m)			
NIL							

### 12. Culverts

The Site has the following culverts falling in Non-motorized earthen track (As shown in clause 4 of Schedule A:

Sl. NO	Existing Chainage	Design Chainage	Span
1	6+670	58+725	1x1.5
2	6+930	59+000	1x2.1
3	7+010	59+075	1x2.0
4	7+180	59+225	1x3.0
5	7+275	59+335	1x2.0
6	7+350	59+410	1x2.0
7	7+480	59+525	1x1.5
8	7+600	59+640	1x2.0
9	7+810	59+850	1x3.0
10	8+305	60+335	1x2.1
11	8+840	60+870	1x2.8
12	8+955	60+985	1x2.4
13	10+755	62+775	1x1.5
14	10+850	62+865	1x1.6
15	10+905	62+925	1x1.5

### 13. Bus bays

The details of bus bays on the Site are as follows:

Sl. No.	Chainage (km)	Length (m)	Left Hand Side	Right Hand Side
		NIL		

# 14. Truck Lay byes

The details of truck lay byes are as follows:

Sl. No.	Chainage (km)	Length (m)	Left Hand Side	Right Hand Side		
	NIL					

### 15. Road side drains

The details of the roadside drains are as follows:

	Locatio	on (km)		Туре	
Sl.			Side	Masonry/cc	Earthen
No.	From	То		(Pucca)	(Kutcha)
NIL					

### 16. Major junctions

The details of major junctions are as follows:

S.	Location		At	Separated	Category of Cross Road			
No	Existing Ch.	Design Ch.	Grade	Separateu	NH	SH	MDR	Others
	NIL							

(NH: National Highway, SH: State Highway, MDR: Major District Road)

### 17. Minor junctions

The details of the minor junctions are as follows:

Sl. No.	Existing Chainage (Km)	Design Chainage (m)	Type of Junction	Side	Remarks
NIL					

# 18. Bypass

The details of Bypasses on the Site are as follows:

Sl. I	No.	Chainage (m)	Length (m)	Left Hand Side	Right Hand Side
		This complete	e alignment is prop	osed as bypass.	

### 19. Other structures / Details

The details are:

Sl.	Existing Chainage (m)		Design Chainage (m)		Length in m	Remarks
No.	From	То	From	То	(Design)	Kemarks
			NiL			

Dec 2020

# Annex - II

(Schedule-A)

# **Dates for providing Right of Way**

The dates on which the Authority shall provide Right of Way to the Contractor on Different stretches of the Site are stated below:

Sl. No	Design Chaina	ge	Length	Width (m)	Date of Providing ROW
	From	То			
(i) Full Right of way (full width)	51.825	63.131	11.306	16-24 (as shown in Schedule B, clause 2.4)	90% at appointed date
(ii) Balance Right of way (width)	51.825	63.131	11.306	24 (as shown in Schedule B, clause 2.4)	100% Within 90 days after the appointed Date as per clause 8.2 of DCA

Construction of Balance work of Two – Lane with hard shoulders of Existing Hayuliang – Hawai Road (NH-113) from design km 51.825 to km 63.131 (Existing km 45.050 of Hayuliang – Hawai Road to Hawai town)(11.306 km) on EPC basis in the state of Arunachal Pradesh Package of SARDP –NE (Green Field Alignment)

Dec 2020

Annex - III (Schedule-A)

# **Alignment Plans**

The proposed alignment of the Project Highway is indicated below:

Dec 2020

Annex - IV (Schedule-A)

## **Environment Clearances**

The Project Highway does not required Environment Clearance as per MoEF corrigendum dated 22 Aug 2013.

In addition, the AIP for the project has been received. The Final approval is yet to be received through temporary working provision will be ensured before appointed date. FC final approved conditions and AIP conditions are to be compliance in totality during construction stage and after construction stage.

The muck dumping sites in forest area stand identified and freezed by Forest department to be abided by agency during dumping of muck as stated in Schedule "F"

# SCHEDULE -B (See Clause 2.1)

# **Development of the Project Highway**

# 1 Development of the Project Highway

Development of the Project Highway shall include design and construction of the Project Highway as described in this Schedule-B and in Schedule-C.

# 2 Rehabilitation and augmentation

Rehabilitation and augmentation shall include Two-Laning of the Project Highway as described in Annex-I of this Schedule-B and in Schedule-C.

# 3 Specifications and Standards

The Project Highway shall be designed and constructed in conformity with the Specifications and Standards specified in Annex-I of Schedule-D.

#### Annex - I

### (SCHEDULE-B)

### **DESCRIPTION OF TWO-LANING**

### 1 WIDENING OF THE EXISTINGHIGHWAY

1.1 The Project Highway shall follow the proposed alignment as specified by the Authority and shown in the alignment plans specified in Annex III of Schedule-A. Geometric deficiencies, if any, in the existing horizontal and vertical profiles shall be corrected as per the prescribed standards for hilly terrain to the extent land is available.

### 1.2 WIDTH OFCARRIAGEWAY

- 1.2.1 Construction of Two-Lane pavement without paved shoulders shall be undertaken. The paved carriageway shall be 7 m wide with hard shoulders in accordance with the typical cross sections drawings.
- 1.2.2 Except as otherwise provided in this Agreement, the width of the paved carriageway and cross-sectional features shall conform to paragraph1.1above.

### 2 GEOMETRIC DESIGN AND GENERALFEATURES

### 2.1 General

Geometric design and general features of the Project Highway shall be in accordance with Section 2 of the Two Lane Manual (IRC : SP 73 -2018).

### 2.2 Design speed

The design speed shall be the minimum design speed of 30 km per hour and ruling design speed of 50 km / per hour for hilly terrain.

### 2.3 Improvement of the existing road geometrics

Improvement of the existing alignment geometrics shall be carried out as per section 2 of the Two Lane Manual (IRC : SP 73 -2018).

### 2.4 Right of Way

Details of Right of way are given in Annex-II of Schedule-A.

# 2.5 Rectification of earthwork including subgrade required in following chainages.

Chainage	Chainage (Km)		Y 41 (YZ )	
From	To	Side	Length (Km)	
59+310	59+430	B/S	0.120	
59+716	59+740	B/S	0.024	
59+580	59+620	B/S	0.040	
62+300	62+520	B/S	0.220	
58+6	72	LHS		
58+6	80	LHS		
58+7	00	LHS		
58+7	20	LHS		
58+7	25	LHS		
58+7	33	LHS		
58+7	40	LHS		
58+7	60	LHS		
58+7	75	LHS		
58+8	30	LHS		
58+8	60	LHS		
58+8	73	LHS		
58+8	83	LHS		
58+8	85	LHS		
58+9	00	LHS		
58+9	75	LHS		
58+9	87	LHS		
58+9	90	LHS	0.057	
58+9	95	LHS	0.037	
59+0	05	LHS		
59+0	10	LHS		
59+0	18	LHS		
59+0	20	LHS		
59+0	25	LHS		
59+1	85	LHS		
59+1	90	LHS		
59+2	00	LHS		
59+2	80	LHS		
59+2	90	LHS		
59+3	00	LHS		
61+1	90	LHS		
61+4	50	LHS		
61+6	60	LHS		
61+7	20	LHS		
61+7	60	LHS		
61+8	20	LHS		

Total=		0.461
62+790	LHS	
62+775	LHS	
62+670	LHS	
62+620	LHS	
62+600	LHS	
62+590	LHS	
62+570	LHS	
62+239	LHS	
62+190	LHS	
62+180	LHS	
62+175	LHS	
62+170	LHS	
62+150	LHS	
62+145	LHS	
62+100	LHS	
62+050	LHS	
61+980	LHS	
61+970	LHS	
61+840	LHS	
61+830	LHS	

### 2.5 Type of shoulder

The shoulder shall be hard granular shoulder on both sides of the carriageway as per typical Cross Sections provided in para 2.11 of this Schedule B.

### 2.6 Lateral and vertical clearances at underpasses

- 2.6.1 Lateral and vertical clearances at underpasses and provision of guardrails / crash barriers shall be as per paragraph 2.11 of the Two Lane Manual (IRC : SP 73-2018).
- 2.6.2 Lateral clearance: The width of the opening at the Vehicle Underpasses shall be as follows.

Sl. No.	Location (Chainage)	Span/opening (m)	Remarks			
	NIL					

### 2.7 Lateral and vertical clearances at overpasses

- 2.7.1 Lateral and vertical clearances at overpasses shall be as per paragraph 2.12 of the Two Lane Manual (IRC : SP 73-2018).
- 2.7.2 Lateral clearance: The width of the opening at the overpasses shall be as follows:

Sl. No.	Location (Chainage)	Span/opening (m)	Remarks			
	NIL					

# 2.8 Service Roads

Service roads shall be constructed at the locations and for the lengths indicated below:

Sl. No.	Existing Location of Service road (from km to km)	Proposed Location of Service road (from km to km)	Right hand side (RHS)/Left hand side (LHS)/ or Both sides	Length (km) of Service road				
	NIL							

## 2.9 Grade separated structures

2.9.1 Grade separated structures shall be provided as per paragraph 2.14 of the Two Lane Manual (IRC: SP 73 -2015). The requisite particulars are given below and GADs are annexed at Annexure "D":

Sl. No.	Existing Chainage of the structure	Design Chainage of structure	Length (m)	Number and length of spans (m)	Approach gradient	Remarks, if any	
NiL							

# 2.10 Cattle and Pedestrian Underpass/Overpass

Cattle and pedestrian underpass/ overpass shall be constructed as follows: [Refer to paragraphs 2.14.3 of the Two Lane Manual (IRC: SP 73 -2015) and specify the requirements of cattle and pedestrian underpass/ overpass]

Sl.	Location	Span/opening (m)	Type of crossing
No.			
	N	NiL	

### 2.11 Typical cross-sections of the Project Highway

Typical Cross-Sections of the Project Highway are tabulated below -

Sl. No.		Chainage m)	nage Length (in m, after structure length TCS Type Widening Details		m, after structure TCS Type Widening Details Shoulder		
	From	То	deduction)				
1	51.825	63.131	10.846	TCS I	New Two lane in Open areas	1.5 m Hard Shoulder on hill side and 1.9 m on Valley side	

### 3 INTERSECTIONS AND GRADESEPARATORS

All intersections and grade separators shall be as per Section 3 of the Two Lane Manual (IRC: SP 73 - 2015).

Existing intersections which are deficient shall be improved to the prescribed standards.

Properly designed intersections shall be provided at *the* locations and of the types and features given in the tables below:

### (a) At-gradeintersections

Sl. No.	Existing Chainage (Km)	Design Chainage (m)	Type of Junction	Side	Remarks
1	0.00	51825	T	RHS	Start of Bypass
2	6.400	58455	Y	LHS	
3	10.900	62925	Y	LHS	
4	11.112	63131	T	LHS	End of Bypass

(b) Grade separated intersection with/without ramps

Sl. No.	Location	Salient Features	Minimum length of Viaduct to be Provided	Road to be carried over / under the structures	
NIL					

#### 4 ROAD EMBANKMENT AND CUTSECTION

- 4.1 Widening of the existing alignment and construction of new road embankment/ cuttings shall conform to the Specifications and Standards given in section 4 of the Two Lane Manual (IRC: SP 73 -2015) and the specified cross sectional details. Deficiencies in the plan and profile of the existing road shall be corrected.
- 4.2 The proposed road including raising shall be constructed as per FRL mentioned in Plan & Profile as attached in annex 3 of schedule A.

### 5 PAVEMENTDESIGN

5.1 Pavement design shall be carried out in accordance with Section 5 of the Two Lane Manual (IRC: SP 73-2015).

### 5.2 Type of pavement

Flexible pavement shall be adopted for Project Highway in accordance with Clause 2.2 of IRC:37-2012 identifies four type of flexible pavements. The estimated cost of civil works is based on flexible pavements consisting of Granular base, Sub base, DBM and BC. Since, the successful bidders under EPC mode can use any type of four flexible pavements mentioned Clause 2.2 of IRC:37-2012, they may carry out their own diligence to arrive at project cost before submitting bids.

# 5.3 Design requirements

### 5.3.1 Design Period and Strategy

The pavement shall be designed for a minimum design period of 15 years. Stage construction shall not be permitted.

### 5.3.2 Design Traffic

Notwithstanding anything to the contrary contained in this Agreement or the Two Lane Manual (IRC: SP 73-2015), the Contractor shall design the pavement for entire Project Highway for design traffic of not less than 20 million standards axles (msa).

### 5.4 Reconstruction / Realignment / Bypass of stretches

5.4.1 The following stretches of the existing road shall be realigned. These shall be designed as new pavement.

Sl.	Existing Chainage (m)		Design Chainage (m)		Design Length	Remarks
No.	From	To	From	To	( <b>m</b> )	
1	0	11112	51825	63131	11306	Complete alignment is proposed as Bypass

5.4.2 The existing alignment shall be constructed as per FRL mentioned in Plan & Profile (Annex III of Schedule A).

### 6 ROADSIDEDRAINAGE

Drainage system including surface and subsurface drains for the Project Highway shall be provided as per Section 6 of the Two Lane Manual (IRC : SP 73 -2015). How above, Line drains shall be provided in the following stretches –

Sl.	Design Chainage (Km)		Length (in m, after	TCS Type	Drain Type
No.	From	То	structure length deduction)	1CS Type	Diam Type
1	51.825	63.131	10846	TCS I	Rectangular drain on HillSide

### 7 DESIGN OFSTRUCTURES

### 7.1 General

- 7.1.1 All bridges, culverts and structures shall be designed and constructed in accordance with section 7 of the Two Lane Manual (IRC : SP 73 -2015) and shall conform to the cross- sectional features and other details specified therein.
- 7.1.2 Width of the carriageway of new bridges and structures shall be as per figure 7.2 and figure 7.3 of the Two Lane Manual (IRC: SP 73-2015).
- 7.1.3 The following structures shall be provided with footpaths:
  NIL
- 7.1.4 All bridges shall be high-level bridges.
- 7.1.5 The following structures shall be designed to carry utility services specified in tablebelow:

Sl. No.	Bridge at Design km	Utility service to be carried	Remarks
1	51.825 (start of Hawai Bypass)	Water Pipe	Nil

7.1.6 Cross-section of the new culverts and bridges at deck level for the Project Highway shall conform to the typical cross-sections given in section 7 of the Two Lane Manual (IRC : SP 73-2018).

### 7.2 Culverts

- 7.2.1 Overall width of all culverts shall be equal to the roadway width of the approaches.
- 7.2.2 Reconstruction of existing culverts:

Existing Culverts at the following locations shall be re-constructed as new culverts:

Sl. No.	Existing Chainage	Design Chainage	Type of Culvert	Width (m)
1	6+670	58+725	Slab/Box	3
2	6+930	59+000	Slab/Box	3
3	7+010	59+075	Slab/Box	3
4	7+180	59+225	Slab/Box	3
5	7+275	59+335	Slab/Box	3
6	7+350	59+410	Slab/Box	3
7	7+480	59+525	Slab/Box	3
8	7+600	59+640	Slab/Box	3
9	7+810	59+850	Slab/Box	3
10	8+305	60+335	Slab/Box	3
11	8+840	60+870	Slab/Box	3

Sl. No.	Existing Chainage	Design Chainage	Type of Culvert	Width (m)
12	8+955	60+985	Slab/Box	3
13	10+755	62+775	Slab/Box	3
14	10+850	62+865	Slab/Box	3
15	10+905	62+925	Slab/Box	3

# 7.2.3 Widening of existing culverts -NIL

# 7.2.4 Additional new culverts shall be constructed as per particulars given in the table below:

Sl. No.	Design Chainage	Type of Culvert	Width (m)
1	52135	Slab/Box	3
2	52435	Slab/Box	3
3	52570	Slab/Box	3
4	52760	Slab/Box	3
5	53015	Slab/Box	3
6	53170	Slab/Box	3
7	53320	Slab/Box	3
8	53515	Slab/Box	3
9	53775	Slab/Box	3
10	53995	Slab/Box	3
11	54095	Slab/Box	3
12	54255	Slab/Box	3
13	54575	Slab/Box	3
14	54705	Slab/Box	3
15	54800	Slab/Box	3
16	55090	Slab/Box	3
17	55220	Slab/Box	3

Sl. No.	Design Chainage	Type of Culvert	Width (m)
18	55445	Slab/Box	3
19	55575	Slab/Box	3
20	55705	Slab/Box	3
21	55800	Slab/Box	3
22	56035	Slab/Box	3
23	56145	Slab/Box	3
24	56365	Slab/Box	3
25	56530	Slab/Box	3
26	56640	Slab/Box	3
27	56750	Slab/Box	3
28	56865	Slab/Box	3
29	56980	Slab/Box	3
30	57145	Slab/Box	3
31	57285	Slab/Box	3
32	57440	Slab/Box	3
33	57610	Slab/Box	3
34	57750	Slab/Box	3
35	57910	Slab/Box	3
36	58335	Slab/Box	3
37	58620	Slab/Box	3
38	59335	Slab/Box	3
39	59530	Slab/Box	3
40	59850	Slab/Box	3
41	59990	Slab/Box	3
42	60335	Slab/Box	3
43	60440	Slab/Box	3

Sl. No.	Design Chainage	Type of Culvert	Width (m)
44	60870	Slab/Box	3
45	60990	Slab/Box	3
46	61170	Slab/Box	3
47	61365	Slab/Box	3
48	61485	Slab/Box	3
49	61640	Slab/Box	3
50	61750	Slab/Box	3
51	61850	Slab/Box	3
52	61970	Slab/Box	3
53	62160	Slab/Box	3
54	62440	Slab/Box	3
55	62865	Slab/Box	3

7.2.5 Repairs/replacements of railing/parapets, flooring and protection works of the existing culverts shall be undertaken as follows:

NIL

7.2.6 Floor protection works shall be as specified in the relevant IRC Codes and Specifications.

# 7.3 Minor Bridges

- 7.3.1 Existing bridges to be re-constructed/widened
  - (i) The existing bridges at the following locations shall be reconstructed as new structures (Minor Bridges)—

Sl. No.	Existing Chainage (Km)	Design Chainage (m)	Proposed Span in m	Proposed Width in m	Remark
		N	iL		

GAD is attached at Annex B of annex 1 of this Schedule.

(ii) The following bridges shall bewidened:

NIL

### 7.3.2 Additional New MinorBridges

New minor bridges at the following locations on the Project Highway shall be constructed

S	Sl. No.	Existing Chainage (Km)	Design Chainage (m)	Proposed Span in mt	Proposed Width in mt	Proposed / Remark
			N	iL		

7.3.3 The railings of existing bridges shall be replaced by crash barriers at the following locations

Sl. No.	Location at km	Remarks
	Nil	

7.3.4 Repairs/replacement of railing/parapets of the existing bridges shall be undertaken as follows:

Sl. No.	Location at km	Remarks
	Nil	

7.3.5 Drainage system for bridge decks

An effective drainage system for bridge decks shall be provided as specified in the Two Lane Manual (IRC : SP 73 -2018)

7.3.6 Structures in marine environment

**NIL** 

### 7.4. Rail-road bridges

7.4.1 Design, construction and detailing of ROB/RUB shall be as specified in section 7 of the Two Lane Manual (IRC : SP 73-2018).

**NIL** 

### 7.4.2 Roadover-bridges

Road over-bridges (road over rail) shall be provided at the following level crossings, as per GAD drawings attached at Annexure – "C" to this schedule:

Sl. No.	Existing Location of Level crossing / Railway Track (Chainage km)	Proposed Location of Level crossing / Railway Track (Chainage km)	Length of bridge (m)
		NiL	

# 7.4.3 Roadunder-bridges

Road under-bridges (road under railway line) shall be provided at the following level crossings, as per GAD drawings attached:

Sl. No.	Location of Level Crossing (Chainage km)	Number and length of span (m)
	NIL	

### 7.5 Grade separated structures

NiL

### 7.6 Repairs and strengthening of bridges and structures

### A. Bridges

The existing bridges and structures to be repaired/strengthened are given below:

NiL

#### B. ROB/RUB

Nil

### C. Overpasses/Underpasses and other structures

Nil

### 7.7 List of Major Bridges and Structures

- 7.7.1 The following is the list of the **Major Bridges** and Structures:
- (i) The existing bridges at the following locations shall be constructed as new structures (Major Bridges) -

Sl. No.	Existing Chainage (Km)	Design Chainage (m)	Proposed Span in m	Proposed Width in m	Proposed/Re mark
NiL					

### 7.7.2 Additional **New Major Bridges**

New major bridges at the following locations on the Project Highway shall be constructed as per 2 Laning Manual Section 7 of the Two Lane Manual (IRC: SP 73 -2018)

Sl. No.	Design Chainage (m)	Proposed Span in m	Proposed Width in m	Proposed/Remark
1	51825	230	As per IRC :SP 73-2018	Steel/RCC /Box String Girder / Suspended Superstructure with well/pile/rock bolt foundation

# 8 TRAFFIC CONTROL DEVICES AND ROAD SAFETYWORKS

- 8.1 Traffic control devices and road safety works shall be provided in accordance with Section 9 of the Two Lane Manual (IRC: SP 73 -2018). (Polymer rumble strips (min. 1700 RM) on hazardous locations specially on shoulders of valley side curves).
- 8.2 Specifications of the reflecting sheeting: As per the Clause 9.3 of the Two Lane Manual (IRC : SP 73 -2018) of Specification and Standards.

Dec 2020

# The Tentative quantity of Traffic signages and pavement marking are as tabulated below -

	Traffic Signages, Road Marking and other	r appurtenance	es
1	Road Marking: - Lane, Centre Line, Pedestrian crossing		
	Centre line on straight portion	Sqm	448
	Centre line on curve portion	Sqm	170
	Edge Line at Paved Shoulder	Sqm	2261
	Add 15% for Misc. including Pedestrian X-ingsetc	Sqm	432
	Total	Sqm	3311
2	Directional Arrows, letter marking etc.	Nos.	60
3	Advance Direction signs size 1800X1200 mm	Nos.	25
4	Village name boards size 600X900mm	Sqm	8.1
5	Place Identification signs size 1200X900 mm	Sqm	2.88
6	90 cm Triangle	Nos.	30
7	90 cm Octagon	Nos.	30
8	Hazard plate 300X900 mm	Sqm	103.95
9	800 x 600 mm Size	Nos.	35
10	60 Cm circular	Nos.	35
11	Supply and fixing of Micro Prismatic type Retro-Reflective sign plate which is to be fixed on Overhead/ Cantilever structures with the help of G.I. nut bolts	Sqm	51.36
12	Over Head Sign Truss	MT	5.5
13	Boundary Stone (taken 10% of Qty)	Nos.	
14	5th Km Stone -New	Nos.	As per IRC SP :73 2018
15	Ordinary Km Stone	Nos.	31 .73 2018
16	Hectometer Stone	Nos.	]
17	Delineator	Nos.	250
18	Bollards	Nos.	
19	RCC Guard Post	Nos.	As per IRC
20	Enamel Paint	Sqm	SP:73 2018

### 9 ROADSIDEFURNITURE

- 9.1 Roadside furniture shall be provided in accordance with the provisions of Section 9 of the Two Lane Manual (IRC : SP 73-2018).
- 9.2 The Overhead traffic signs: location and size

Full width overhead sign:1no.

Cantilever overhead signs :2nos. (Locations to be finalized in consultation with Authority's Engineer.)

### 10 COMPULSORY AFFORESTATION

The number of trees which are required to be planted by the contractor as compulsory afforestation shall be as per Forest Conservation Act and as per the Two Lane Manual (IRC : SP 73 -2018).

In addition Hydro seeding/plantation or similar on hill slopes as slope protection works for minimum 64500Sqm)

### 11 HAZARDOUSLOCATIONS

The safety barriers, Protective works shall also be provided at the following hazardous locations / lengths:

Sl. No.	Type of Protection works	Minimum Length (m)	Height (range in m)	Remarks
1	Parapet Wall on Valley side	3252		
2	W-Beam Crash Barrier	2814		As per manual and codes
3	Breast Wall	3525	2 – 6 m	
4	RCC Retaining Wall	3797	2 - 4 m	
5	Gabion Wall	1085	2 - 4 m	

### 12 SPECIAL REQUIREMENTS FOR HILLROADS

All special features shall be provided as per Two Lane Manual (IRC: SP 73-2018).

The side slope shall be protected by using suitable slope protection measures all along the highway on Hill side and Valley side. The details of the protection work are listed in "Annex B" and the typical sections for the protection works are given in "Annex A".

No any major land slide location is identified along the Project alignment, however Contractor shall identify other areas if found after excavation and provide the suitable protection measures to stabilize all the landslide zones. A report on the land slide zones shall be furnished along with the design for the review of the Authority Engineer. No change of scope shall be considered for the additional protection measures, if any.

### 13 Utilities

Provision of accommodating utilities shall be made both over as well as underground wherever required.

# 14 Change of Scope

The length of Structures and bridges specified hereinabove shall be treated as an approximate assessment. The actual lengths as required on the basis of detailed investigations shall be determined by the Contractor in accordance with the Specifications and Standards. Any variations in the lengths specified in this Schedule B shall not constitute a Change of Scope, save and except any variations in the length arising out of a change of scope expressly undertaken in accordance with the provisions of Article13.

## 15.0 Slope Protection Measures

**15.1.1** Breast Wall and Retaining Wall

### Following measures shall be adopted:

Slope protection along hill slope side shall be with breast walls with PCC minimum M15 grade concrete. However, at the zones prone to sliding breast walls will be of sausage type (by stonemesh gabions). Retaining wall has been considered at valley sides. The height of breast walls is varying from 1.5 m to 3m as per site requirement and to be finalized by consultation with Authority Engineers. The breast wall of height 3m has been considered if the height of hill cut is more than 9m and in this circumstances 3m berm with catch water drain is required to be provided. The maximum cut slope at hill side is 55° (0.7H to 1V).

- **15.1.2** Embankment less than 3m in height shall be turfed as per MoRTH Specifications.
- **15.1.3** Vetiver Plantation, Hydro Seeding and Hydro Mulching etc or similar works is to be done for slope protection and site mitigation measure upto a height of 12-15 m all along the slopes in each cutting locations except hard rock location which needs to be protected with appropriate applicable technologies, if required.

.

### **SCHEDULE - C**

### (See Clause 2.1)

### **PROJECT FACILITIES**

# 1 Project Facilities

The Contractor shall construct the Project Facilities in accordance with the provisions of this Agreement. Such Project Facilities shall include:

- (a) Toll plaza[s];
- **(b)** Roadside furniture;
- (c) Pedestrian facilities;
- (d) Tree plantation;
- (e) Truck lay-byes;
- (f) bus-bays and bus shelters;
- (g) rest areas; and
- (h) others to be specified

# 2 Description of Project Facilities

(a) Toll Plaza

NIL

### (b) Road side Furniture

Roadside furniture shall be provided in accordance with the provisions of Section 9 of the Two Lane Manual (IRC: SP 73 -2018).

### (c) Pedestrian Facilities

Pedestrians facilities in the form of guard rails, footpath, at grade pedestrian crossing etc. shall be provided wherever required as per section 9 of the Two Lane Manual (IRC : SP 73 -2018).

### (d) Tree Plantation:

NIL

# (e) Truck lay-byes:

The locations of proposed truck lay byes are as under -

Sl. No.	<b>Existing Km</b>	Design Km	Side	Remarks				
NiL								

# (f) Bus-byes and Bus Shelter,

The locations of proposed Bus bays are as under -

Sl. No.	Existing Chainage (Km)	Design Chainage (m)	Side	Remarks
1		7600	Left	Location may change according to approach road to village
2		9300	Left	

(g) Rest areas:

NIL

(h) Others to bespecified:

NIL

Dec 2020

# SCHEDULE -D (See Clause 2.1)

# **SPECIFICATIONS AND STANDARDS**

### 1 Construction

The Contractor shall comply with the Specifications and Standards set forth in Annex-I of this Schedule-D for construction of the Project Highway.

# 2 Design Standards

The Project Highway including Project Facilities shall conform to design requirements set out in the following documents:

Two Lane Manual (IRC : SP 73 -2018) of Specifications and Standards for Two Laning Published by Indian Roads Congress.

# Annex - I (Schedule-D)

# **Specifications and Standards for Construction**

# 1 Specifications and Standards

All Materials, works and construction operations shall conform to the Two Lane Manual (IRC: SP 73 -2018) of Specifications and Standards for Two- Laning (IRC:SP:73-2018), referred to as the Two Lane Manual (IRC: SP 73 - 2018), and MORTH Specifications for Road and Bridge Works. Where the specification for a work is not given, Good Industry Practice shall be adopted to the satisfaction of the Authority's Engineer.

# 2 Deviations from the Specifications and Standards

- 2.1 The terms 'Concessionaire', 'Independent Engineer' and 'Concession Agreement' used in the Two Lane Manual (IRC : SP 73 -2018) shall be deemed to be substituted by the terms 'Contractor', Authority's Engineer' and 'Agreement' respectively.
- 2.2 NIL

### Schedule - E

(See Clauses 2.1 and 14.2)

# **Maintenance Requirements**

## 1. Maintenance Requirements

- (i) The Contractor shall, at all times maintain the Project Highway in accordance with the provisions of this Agreement, Applicable Laws and Applicable Permits.
- (ii) The Contractor shall repair or rectify any Defect or deficiency set forth in Paragraph 2 of this Schedule-E within the time limit specified therein and any failure in this behalf shall constitute non-fulfillment of the Maintenance obligations by the Contractor. Upon occurrence of any breach hereunder, the Authority shall be entitled to effect reduction in monthly lump sum payment as set forth in Clause 14.6 of this Agreement, without prejudice to the rights of the Authority under this Agreement, including Termination thereof.
- (iii) All Materials, works and construction operations shall conform to the MORTH Specifications for Road and Bridge Works, and the relevant IRC publications. Where the specifications for a work are not given, Good Industry Practice shall be adopted.

[Specify all the relevant documents]

# 2. Repair/rectification of Defects and deficiencies

The obligations of the Contractor in respect of Maintenance Requirements shall include repair and rectification of the Defects and deficiencies specified in Annex - I of this Schedule-E within the time limit set forth therein.

### 3. Other Defects and deficiencies

In respect of any Defect or deficiency not specified in Annex - I of this Schedule-E, the Authority's Engineer may, in conformity with Good Industry Practice, specify the permissible limit of deviation or deterioration with reference to the Specifications and Standards, and any deviation or deterioration beyond the permissible limit shall be repaired or rectified by the Contractor within the time limit specified by the Authority's Engineer.

### 4. Extension of time limit

Notwithstanding anything to the contrary specified in this Schedule-E, if the nature and extent of any Defect or deficiency justifies more time for its repair or rectification than the time specified herein, the Contractor shall be entitled to additional time in conformity with Good Industry Practice. Such additional time shall be determined by the Authority's Engineer and conveyed to the Contractor and the Authority with reasons thereof.

### 5. Emergency repairs/restoration

Notwithstanding anything to the contrary contained in this Schedule-E, if any Defect, deficiency or deterioration in the Project Highway poses a hazard to safety or risk of damage to property, the Contractor shall promptly take all reasonable measures for eliminating or minimizing such danger.

## 6. Daily inspection by the Contractor

The Contractor shall, through its engineer, undertake a daily visual inspection of the Project Highway and maintain a record thereof in a register to be kept in such form and manner as the Authority's Engineer may specify. Such record shall be kept in safe custody of the Contractor and shall be open to inspection by the Authority and the Authority's Engineer at any time during office hours.

### 7. Pre-monsoon inspection / Post-monsoon inspection

The Contractor shall carry out a detailed pre-monsoon inspection of all bridges, culverts and drainage system before [1st June] every year in accordance with the guidelines contained in IRC: SP35. Report of this inspection together with details of proposed maintenance works as required on the basis of this inspection shall be sent to the Authority's Engineer before the [10th June] every year. The Contractor shall complete the required repairs before the onset of the monsoon and send to the Authority's Engineer a compliance report. Post monsoon inspection shall be done by the [30th September] and the inspection report together with details of any damages observed and proposed action to remedy the same shall be sent to the Authority's Engineer.

### 8. Repairs on account of natural calamities

All damages occurring to the Project Highway on account of a Force Majeure Event or wilful default or neglect of the Authority shall be undertaken by the Authority at its own cost. The Authority may instruct the Contractor to undertake the repairs at the rates agreed between the Parties.

Dec 2020

Annex – I

(Schedule-E)

# Repair/rectification of Defects and deficiencies

The Contractor shall repair and rectify the Defects and deficiencies specified in this Annex-I of Schedule-E within the time limit set forth in the table below.

Table -1: Maintenance Criteria for Pavements:

			Level of Service (LOS)  From the service of the ser		Tools/Equip	Standards and References for Inspection and Data Analysis	Time limit for Rectification/ Repair	Maintena nce Specificati ons
Asset Type	Paramet er	Desirable	Accepta ble					
Flexible Pavement (Pavement of MCW, Service Road, approache	Potholes	Nil	< 0.1 % of area and subject to limit of 10 mm in depth		Length Measurement Unit like Scale, Tape, odometer etc.	IRC 82: 2015 and Distress Identification Manual for Long Term Pavement Performance Program, FHWA 2003 (http://www.tfhrc.com/pavement/lttp/ reports/03031/)	24-48 hours	MORT&H Specificatio n 3004.2

# Dec 2020

Asset Type	Perform ance Paramet er	Level of Service (LOS)		Freque ncy of Inspect ion	Tools/Equip	Standards and References for Inspection and Data Analysis	Time limit for Rectification/ Repair	Maintena nce Specificati ons
		Desirable	Accepta ble					
s of Grade structure, approache s of connecting roads, slip roads, lay byes etc. as applicable	Cracking	Nil	< 5 % subject to limit of 0.5 sqm for any 50 m length	Daily			7-15 days	MORT&H Specificatio n 3004.3
)	Rutting	Nil	< 5 mm	Daily	Straight Edge		15 -30 days	MORT&H Specificatio n 3004.2
	Corrugatio ns and Shoving	Nil	< 0.1 % of area	Daily	Length Measuremen t Unit like		2-7 days	IRC:82- 2015

Asset Type	Perform ance Paramet er	Level of Service (LOS)		Freque ncy of Inspect ion	Tools/Equip ment	Standards and References for Inspection and Data Analysis	Time limit for Rectification/ Repair	Maintena nce Specificati ons
		Desirable	Accepta ble					
	Bleeding	Nil	< 1 % of area	Daily	Scale, Tape, odometer etc.		3-7 days	MORT&H Specificatio n 3004.4
	Ravelling / Stripping	Nil	< 1 % of area	Daily			7-15 days	IRC:82- 2015 read with IRC SP 81
	Edge Deformati on/ Breaking	Nil	< 1 m for any 100 m section and width < 0.1 m at any location, restricted				7- 15 days	IRC:82- 2015

	Perform ance Paramet er	Level of Service (LOS)		Freque ncy of Inspect ion	Tools/Equip	Standards and References for Inspection and Data Analysis	Time limit for Rectification/ Repair	Maintena nce Specificati ons
Asset Type		Desirable	Accepta ble					
			d to 30 cm from the edge					
	Roughness BI	2000 mm/km	2400 mm/km	Bi- Annuall y	Class I Profilometer	Class I Profilometer : ASTM E950 (98) :2004 —Standard Test Method for	180 days	IRC:82- 2015
	Skid Number	60SN	50SN	Bi- Annuall y	SCRIM (Sideway- force Coefficient	measuring Longitudinal Profile of Travelled Surfaces with Accelerometer Established Inertial Profiling Reference ASTM E1656 -94: 2000- Standard Guide	180 days	BS: 7941-1: 2006
C	Pavement Condition Index	3	2.1	Bi- Annuall y	Routine Investigation Machine or equivalent)	for Classification of Automatic Pavement Condition Survey Equipment	180 days	IRC:82- 2015

	Perform	Level of Service (LOS)		Freque ncy of Inspect ion	Tools/Equip	Standards and References for Inspection and Data Analysis	Time limit for Rectification/ Repair	Maintena nce Specificati ons
Asset Type	ance Paramet er	Desirable	Accepta ble					
	Other Pavement Distresses			Bi- Annuall y			2-7 days	IRC:82- 2015
	Deflection/ Remaining Life			Annual ly	Falling Weight Deflectomete r	IRC 115: 2014	180 days	IRC:115- 2014
(Pavemen	BI	2200m m/km	2400mm /km	Bi- Annuall y	Class I Profilometer	ASTM E950 (98) :2004 and ASTM E1656 - 94: 2000	180 days	IRC:SP:83 - 2008
of MCW, Service Road, Grade structure,	Skid Resistance no. a different speed of vehice			Bi- Annuall y	SCRIM (Sideway- force	IRC:SP:83-2008	180 days	IRC:SP:83 - 2008

	Perform		of Service (LOS)	Freque ncy of Inspect ion		Standards and References for Inspection and Data Analysis	Time limit for Rectification/ Repair	Maintena nce Specificati ons
Asset Type	ance Paramet er	Desirable	Accepta ble					
approach es of connectin g roads, slip roads,		Minimum SN	Traffic Speed (Km/h)		Coefficient Routine Investigation Machine or equivalent)			
lay byes etc. as applicabl		36	50		•			
e)		33	65					
		32	80					
		31	95					
		31	110					

	Perform	Level of Service (LOS)		Freque ncy of Inspect ion	Tools/Equip	Standards and References for Inspection and Data Analysis	Time limit for Rectification/ Repair	Maintena nce Specificati ons
Asset Type	ance Paramet er	Desirable	Accepta ble					
	Edge drop at shoulders	Nil	40m m	Daily			7-15 days	MORT&H Specificatio n 408.4
Embankm ent/ Slope	Slope of camber/c ross fall	Nil	<2% variation in prescrib ed slope of camber /cross fall	Daily	Length Measuremen	IRC	7-15 days	MORT&H Specificatio n 408.4
	Embankme nt Slopes	Nil	<15 % variation in prescribe	Daily	t Unit like Scale, Tape, odometer etc.		7-15 days	MORT&H Specificatio n 408.4

	Perform	Level of Service (LOS)		Freque ncy of Inspect ion	Tools/Equip	Standards and References for Inspection and Data Analysis	Time limit for Rectification/ Repair	Maintena nce Specificati ons
Asset Type	ance Paramet er	Desirable	Accepta ble					
			slope					
	Embankme nt Protection	Nil	Nil	Daily	NA		7-15 days	MORT&H Specification
	Rain Cuts/ Gullies in slope	Nil	Nil	Daily Speciall y During Rainy Season			7-15 days	MORT&H Specification

In addition to the above performance criterion, the contractor shall strictly maintain the rigid pavements as per requirements in the following table Table -2:

## **Maintenance Criteria for Rigid Pavements:**

			Degree of		Repair Action		
S.No.	Type of Distress		Severity	Assessment Rating	For the case d < D/2	For the case d > D/2	
				CRACKING			
			0	Nil, not discernible	No Action	Not applicable	
		w = width of crack L t= length of crack d = depth of crack D = depth of slab		w < 0.2 mm. hair cracks	1 to 7 tellon	Tvot applicable	
1	intersecting with any			w = 0.2 - 0.5 mm, discernible from slow-moving car	Seal without delay	Seal, and stitch if $L > lm$ .	
			3	w = 0.5 - 1.5 mm, discernible from fast-moving car	The will delay	Within 7days	

		Measured	Dogwood of		Repair Action		
S.No.	Type of Distress	Parameter Parameter	Degree of Severity	Assessment Rating	For the case d < D/2	For the case d > D/2	
			4	w = 1.5 - 3.0 mm	Seal, and stitch if $L > 1$ m.	Staple or Dowel Bar Retrofit, FDR for	
			5	w > 3 mm.	Within 7 days	affected portion. Within 15days	
			0	Nil, not discernible	No Action		
		= length of crack d =	1	w < 0.2 mm, hair cracks		Staple or Dowel Bar	
2	intersecting with one		2	w = 0.2 - 0.5 mm, discernible from slow vehicle	1 7	Retrofit. Within 15days	
			4	w = 0.5 - 3.0 mm, discernible from fast vehicle	Route, seal and stitch, if $L > 1$ m. Within 7 days		

			Danie		Repair Action		
S.No.	Type of Distress	Measured Parameter	Degree of Severity	Assessment Rating	For the case d < D/2	For the case d > D/2	
			4	w = 3.0 - 6.0 mm	Dowel Bar Retrofit.  Within 15 days	Full Depth Repair Dismantle and reconstruct affected.  Portion with norms and specifications	
			5	w > 6 mm, usually associated with spalling, and/or slab rocking under traffic	Not Applicable, as it may be full depth	See Para 5.5 & 9.2 Within 15days	
			0	Nil, not discernible	No Action		
3	Crack intersecting	w = width of crack L = length of crack d = depth of crack D = depth of slab	1	w < 0.5 mm, discernable from slow moving vehicle	Seal with epoxy, if $L > 1$ m. Within 7 days	Staple or dowel bar retrofit. Within 15days	

			D 0		Repair Action	
S.No.	Type of Distress	Measured Parameter	Degree of Severity	Assessment Rating	For the case d < D/2	For the case d > D/2
			· · · ·	w = 0.5 - 3.0 mm, discernible from fast vehicle	Route seal and stitch, if L > 1 m.  Within 15 days	-
			3	w = 3.0 - 6.0 mm	Staple, if L > 1  m. Within 15  days	Partial Depth Repair with stapling.
			4	w = 6.0 - 12.0 mm, usually associated with spalling	Not Applicable, as it may	Within 15 days
			5	w > 12 mm, usually associated with spalling, and/or slab rocking under traffic	be full	Full Depth Repair Dismantle and reconstruct affected portion as per norms and specifications -

		Measured Parameter	D 6		Repair Action	
S.No.	Type of Distress		Degree of Severity	Assessment Rating	For the case d < D/2	For the case d > D/2
						See Para 5.6.4 Within 15 days
			0	Nil, not discernible	No Action	
			1	w < 0.2 mm, hair cracks	Seal, and stitch if $L > 1$ m.	-
	Multiple Cracks		)	w = 0.2 - 0.5 mm. discernible from slow vehicle	Within 15 days	
4			1 3	w = 0.5 - 3.0 mm, discernible from fast vehicle		Dismantle, Reinstate subbase, Reconstruct
			4	w = 3.0 - 6.0 mm panel broken into 2 or 3 pieces	Full depth repair within 15 days	whole slab as per specifications within
			5	w > 6 mm and/or panel broken		30 days

					Repair Action			
S.No.	Type of Distress	Measured Parameter	Degree of Severity	Assessment Rating	For the case d < D/2	For the case d > D/2		
				into more than 4 pieces				
			0	Nil, not discernible	No Action	-		
		w = width of crack L = length of crack	1	w < 0.5 mm; only 1 corner broken	secure broken parts	Seal with epoxy seal		
			2	w < 1.5 mm; L < 0.6 m, only one corner broken		with epoxy Within 7days		
5	Corner Break			L = length of crack	3	w < 1.5 mm; L < 0.6 m, two corners broken	Partial Depth (Refer	
			4	w > 1.5 mm; L > 0.6 m or three corners broken	Figure 8.3 of Full IRC:SP: 83-2008)	Full depth repair		
			5	ree or four corners broken	Within 15 days	Reinstate sub-base, and reconstruct the		

			_		Repair Action	
S.No.	S No.   Type of Distress	Measured Parameter	Degree of Severity	Assessment Rating	For the case d < D/2	For the case d > D/2
						slab as per norms and specifications within 30days
			0	Nil, not discernible		No Action
			1	w < 0.5 mm; L < 3 m/m <sup>2</sup>		Seal with low
	Punchout (Applicable	w = width of crack L = length (m/m2)	2	either $w > 0.5$ mm or $L < 3$ m/m <sup>2</sup>	Not Applicable, as it may be full depth	viscosity epoxy to secure broken parts.
6	to Continuous Reinforced Concrete		3	$w > 1.5 \text{ mm}$ and $L < 3 \text{ m/m}^2$		Within 15days
	Pavement (CRCP ) only)		1 1	w > 3 mm, $L < 3$ m/m <sup>2</sup> and deformation		Full depth repair - Cut out and replace damaged area taking
			5	w > 3 mm, $L > 3$ m/m <sup>2</sup> and deformation		care not to damage reinforcement. Within 30days

		Measured Parameter	Degree of Severity		Repair Action					
S.No.	Type of Distress			Assessment Rating	For the case d < D/2	For the case d > D/2				
	Surface Defects									
			0	Nil, not discernible	Short Term	Long Term				
		r = area damaged surface/total surface of slab (%) h = maximum depth of damage  3	0	•	No action.					
			1		Local repair of areas damaged					
7	Honeycomb type surface		r = 2 - 10 %	and liable to be damaged.  Within 15 days	Not Applicable					
			3		Bonded Inlay, 2 or 3 slabs					
			4	r = 25 - 50 %	affecting.					

		Measured I	Dogwoo of		Repair Action	
S.No.	Type of Distress	Parameter Parameter	Degree of Severity	Assessment Rating	For the case d < D/2	For the case d > D/2
					Within 30 days	
			5	r > 50% and $h > 25$ mm	Reconstruct slabs, 4 or more slabs if affecting. Within 30 days	
		r = damaged		Nil, not discernible	Short Term	Long Term
					No action.	
8	Scaling	surface/total surface of slab (%) h = maximum depth of			Local repair of areas damaged	
		damage	2	r = 2 - 10 %	and liable to be damaged. Within 7days	Not Applicable

			Degree of		Repair Action		
S.No.	Type of Distress	Measured Parameter	Degree of Severity	Assessment Rating	For the case d < D/2	For the case d > D/2	
			3	r = 10 - 20%	Bonded Inlay within 15		
			4	r = 20 - 30 %	days		
			5	r > 30 % and $h > 25$ mm	Reconstruct slab within 30 days		
			0		No action	Not Applicable	
			1	t > 1 mm	No action.		
1 0	Polished Surface/Glazing	t = texture depth, sand patch test	2 '	t = 1 - 0.6 mm	Monitor rate of deterioration		
			3	f = 0.6 - 0.3 mm			
			4	t = 0.3 - 0.1 mm			

		Measured	Degree of		Repair Action		
S.No.	Type of Distress	Parameter	Severity	Assessment Rating	For the case d < D/2	For the case d > D/2	
			5	t < 0.1 mm	Diamond Grinding if affecting 50% or more slabs in a continuous stretch of minimum 5 km. Within 30 days		
			0	d < 50 mm; h < 25 mm; n < 1 per 5 m <sup>2</sup>	No action.		
	Popout (Small Hole), Pothole Refer Para 8.4			•	Partial depth repair 65 mm deep.	Not Applicable	
			2	d = 50 - 100  mm; h > 50  mm; n < 1 per 5 m <sup>2</sup>	Within 15 days		

			Dagmas of		Repair Action	
S.No.	Type of Distress	Measured Parameter	Degree of Severity	Assessment Rating	For the case d < D/2	For the case d > D/2
			1 1	d = 100 - 300  mm; $h < 100  mm n < 1$ per 5 m <sup>2</sup>	Partial depth repair 110mm	
					i.e.10 mm more than the depth	
			4	$d = 100 - 300 \text{ mm}; h > 100 \text{ mm}; n < 1$ $per 5 \text{ m}^2$	of the hole.	
					Within 30 days	
			1 7	d > 300 mm; h > 100 mm: n > 1 per 5	Full depth repair.	
			1 7 1	$m^2$	Within 30 days	

				Joint Defects		
			0	Difficult to discern.	Short Term	Long Term
			U		No action.	
Joint Seal Defects	loss or damage L = Length as % total	1	Discernible, L< 25% but of little immediate consequence with regard to ingress of water or trapping incompressible material.			
		joint length	3	insufficient protection against ingress of water and trapping	selected locations.	Not Applicable
			5	negligible protection	Clean, widen and reseal the joint. Within 7 days	

				and trapping incompressible material.		
			0	Nil, not discernible	No action.	
			1	w < 10 mm	Apply low viscosity epoxy resin/mortar in cracked portion.	
		w = width on either side of the joint L = ling of Joints length of spalled portion (as % joint length)	2	w = 10 - 20 mm, L < 25%	Within 7 days	
12	Spalling of Joints		3	w = 20 - 40  mm, L > 25%	Partial Depth Repair. Within 15 days	Not Applicable
			4	w = 40 - 80 mm, L > 25%	30 - 50  mm deep,  h = w + 20%  of w, within 30 days	
		5	w > 80 mm, and L > 25%	50 - 100 mm deep repair. H = w + 20% of w. Within 30 days		
13	Faulting (or Stepping)	f = difference of level	0	not discernible, < 1 mm	No action.	No action.

	in Cracks or Joints		1	f < 3 mm		
			2	1 t - 3 6 mm	Determine cause and observe, take action for diamond grinding	Replace the slab as appropriate.
			3	f = 6 - 12 mm	Diamond Grinding	Within 30days
			4	f= 12 - 18 mm	Raise sunken slab.	Replace the slab as
			5		Strengthen subgrade and sub-base by grouting and raising sunken slab	appropriate.  Within 30days
			0	Nil, not discernible	Short Term	Long Term
14		h = vertical displacement from-	U	ivii, not discerniole	No Action	
17		normal profile	1	h < 6 mm	140 / Action	
			2	h = 6 - 12 mm	Install Signs to Warn Traffic	

			3	h = 12 - 25 mm	within 7 days	
			4	h > 25 mm	Full Depth Repair. Within 30 days	
			5	shattered slabs, ie 4 or more pieces	Replace broken slabs.  Within 30 days	
			0	Not discernible, h < 5 mm	No action.	
		h = negative vertical displacement from normal profile L =length	1	h = 5 - 15 mm	Tvo action.	
15	Depression			h = 15-30 mm, Nos <20% joints	Install Signs to Warn Traffic	Not Applicable
			3	h = 30 - 50 mm	within 7 days	
			4	h > 50 mm or > 20% joints		
					Reinstate pavement at normal level	

			5	h > 100 mm	if L < 20 m. Within 30 days	
				Not discernible. h < 5	Short Term	Long Term
			0	mm	No action.	
			1	h = 5 - 15 mm	Follow up.	
16	h = positive vertical displacement from normal profile.  L = length	displacement from		h = 15 - 30 mm, Nos <20% joints	Install Signs to Warn Traffic within 7 days  Stabilise subgrade. Reinstate pavement at normal level if length	scrabble
		L = length	3	h = 30 - 50 mm		
			4	h > 50 mm or > 20% joints		
		5	h > 100 mm	< 20 m. Within 30 days		
17	Bump	h = vertical	0	h < 4 mm	No action	

		displacement from normal profile	1	h = 4 - 7 mm	Grind, in case of new construction within 7 days	Construction Limit for New Construction.
			3	h = 7 - 15 mm	Grind, in case of ongoing Maintenance within 15 days	Replace in case of new construction. Within 30days
			5	h > 15 mm	Full Depth Repair. Within 30 days	Full Depth Repair. Within 30days
			0	Nil, not discernible	Short Term	Long Term
			0	< 3mm	No action.	
18	Lane to Shoulder Dropoff	f = difference of level	1	f = 3 - 10 mm	Spot repair of shoulder	
	_		2	f = 10 - 25 mm	within 7 days	
			3	f = 25 - 50 mm	Fill up shoulder	

			4	f = 50 - 75 mm	within 7 dayss	For any 100 m stretch Reconstruct
			5	f > 75 mm		shoulder, if affecting 25% or more of stretch.  Within 30days
				Drainage		
			0	not discernible	No Action	
		quantity of fines and water expelled through open joints and cracks	1 to 2	slight/ occasional Nos < 10%	Repair cracks and joints Without delay.	Inspect and repair sub-drainage at
19	Pumping	Nos	3 to 4	appreciable/ Frequent 10 - 25%	Lift or jack slab within 30 days.	distressed sections and upstream.
		Nos/100 m stretch	5	abundant, crack development > 25%	Repair distressed pavement sections. Strengthen subgrade and subbase. Replace slab.  Within 30 days	

Construction of Balance work of Two – Lane with hard shoulders of Existing Hayuliang – Hawai Road (NH-113) from design km 51.825 to km 63.131 (Existing km 45.050 of Hayuliang – Hawai Road to Hawai town)(11.306 km) on EPC basis in the state of Arunachal Pradesh Package of SARDP –NE (Green Field Alignment)

			0-2	No discernible problem	No action.	
20	Ponding	Ponding on slabs due to blockage of drains	3 to 4	drains but water	Clean drains etc within 7 days, Follow up	Action required to stop water damaging foundation within 30
			5	Ponding, accumulation of water observed	-do-	days.

Table -3: Maintenance Criteria for Safety Related Items and Other Furniture Items:

Asset Type	Performance Parameter	L	evel of Service (I	LOS)	Frequency of Measurement	Testing Method	Recommended Remedial measures	Time limit for Rectification	Specification s and Standards
		of safe s	RC SP :84-2014, a topping sight disple throughout.			Manual Measurement s with Odometer along with video/ image	Removal of obstruction within 24 hours, in case of sight line affected by temporary objects such as trees, temporary encroachments.		IRC:SP 84-2014
Highway	Availability of Safe Sight Distance	Design Speed, kmph	Desirable Minimum Sight Distance (m)	Safe Stoppin g Sight Distance (m)	Monthly	backup	In case of perma design deficiency:  Removal obstruction/improvedeficiency at the easure of the case of perma design deficiency.		
		80	360 260	180			1 0		
Pavemen t Marking	Wear	<70% of	marking remainin	ng	Bi- Annually	Visual Assessment as per Annexure-F of IRC:35-2015			IRC:35- 2015

Asset Type	Performance Parameter	Le	Level of Service (LOS)  g expected life Service Time Cement Road - d/m²/lux Bituminous Road - d/m²/lux and Minimum Performance g Retro reflectivity during ime: n (RL) Retro	Frequency of Measuremen t	Testing Method	Recommended Remedial measures	Time limit for Rectification	Specification s and Standards	
	Day time Visibility	Ce 130mcd/n	ement Road n²/lux tuminous F	l -	Monthly	As per Annexure-D of IRC:35-2015	Re - painting	Cat-1 Defect – within 24 hours Cat-2 Defect – within 2 months	IRC:35- 2015
		Initial and	and Minimum Performance ry Retro reflectivity during time: gn (RL) Retro			As per Annexure-E of IRC:35-2015	Re - painting	Cat-1 Defect – within 24 hours Cat-2 Defect – within 2 months	IRC:35-2015
		Speed							
			Initial (7 days)	Minimum Threshold level (TL) & warranty					
	Night Time Visibility			period required up to 2 years	Bi-Annually				
		Up to 65	200	80					
		65 - 100	250	120					
		Above 100							
			ibility unde	Performance for r wet condition					

Asset Type	Performa Paramet		Level of Service (LOS)	Frequency of Measuremen t	Testing Method	Recommended Remedial measures	Time limit for Rectification	Specification s and Standards
	Skid Resistance		Initial 7 days Retro reflectivity: 100 mcd/m²/lux Minimum Threshold Level: 50 mcd/m²/lux Initial and Minimum performance for Skid Resistance:	Bi-Annually	As per Annexure-G of IRC:35-2015		Within 24 hours	IRC:35-2015
Road Signs	Shape Position	and	Shape and Position as per IRC:67-2012. Signboard should be clearly visible for the design speed of the section.	Daily	Visual with video/image backup	shape is damaged.	48 hours in case of Mandatory Signs, Cautionary and Informatory Signs (Single and Dual post signs)  15 Days in case of Gantry/Cantileve	IRC:67-2012
	Retro reflectivity	7	As per specifications in IRC:67-2012	Bi-Annually	Testing of each	hange of ignboard	r Sign boards  48 hours in case of Mandatory	RC:67-2012

Asset Type	Performance Parameter	Level of Service (LOS)	Frequency of Measuremen t		Recommended Remedial measures	Time limit for Rectification	Specification s and Standards
				signboard using Retro Reflectivity Measuring Device. In accordance with ASTM D 4956-09.		Signs, Cautionary and Informatory Signs (Single and Dual post signs)  1 Month in case of Gantry/Cantilev er Sign boards	
	Kerb Height	As per IRC 86:1983 depending upon type of Kerb	Bi-Annually		Raising Kerb Height	Within 1 Month	RC 86:1983
Kerb	Kerb Painting	Functionality: Functioning of Kerb painting as intended	Daily	Visual with video/image backup	Kerb Repainting	Within 7-days	RC 35:2015
	Markers (Road	Numbers and Functionality as per specifications in IRC:SP:84-2014 and IRC:35-2015, unless specified in Schedule-B.	Daily	Counting	New Installation	Within 2 months	IRC:SP:84- 2014, IRC:35- 2015
Road		Functionality: Functioning of guardrail as intended	Daily	Visual with video/image backup	Rectification	Within 15 days	IRC:SP:84 - 2014
Furnitur e	Traffic Safety Barriers	Functionality: Functioning of Safety Barriers as intended	Daily	Visual with video/image backup	Rectification	Within 7 days	IRC:SP:84 - 2014, IRC:119- 2015
		<u>Functionality:</u> Functioning of End Treatment as intended	Daily	Visual with video/image	Rectification	Within 7 days	IRC:SP:84 - 2014,

Asset Type	Performance Parameter	Level of Service (LOS)	Frequency of Measuremen t	Testing Method	Recommended Remedial measures	Time limit for Rectification	Specification s and Standards
	Traffic Safety Barriers			backup			IRC:119- 2015
	Attenuators	<u>Functionality:</u> Functioning of Attenuators as intended	Daily	Visual with video/image backup	Rectification	Within 7 days	IRC:SP- 2014, IRC:119- 2015
	Guard Posts and Delineators	d Posts and Delineators as intended		Visual with video/image backup	Rectificatio n	Within 15 days	IRC: 79 - 1981
	Overhead Sign Structure	Overhead sign structure shall be structurally adequate	Daily	Visual with video/image backup	Rectification	Within 15 days	IRC:67-2012
	Traffic Blinkers	<u>Functionality:</u> Functioning of Traffic Blinkers as intended	Daily	Visual with video/image backup	Rectification	Within 7 days	IRC:SP:84 - 2014
	Highway	Illumination: Minimum 40 Lux illumination on the road surface	Daily	The illumination level shall be measured with luxmeter	<u> </u>	24 hours	IRC:SP:84 - 2014
	Lights	No major failure in the lighting system	Daily	-	Rectification of failure	24 hours	IRC:SP:84 - 2014
Highway Lighting		No minor failure in the lighting system	Monthly	-	Rectification of failure	8 hours	IRC:SP:84 - 2014
System T	Toll Plaza Canopy Lights	Minimum 40 Lux illumination on the road surface	Daily	The illumination level shall be measured with luxmeter	Improvement in Lighting System	24 hours	IRC:SP:84 - 2014
		No major/minor failure in the lighting system	Daily	-	Rectification of failure	8 hours	IRC:SP:84 - 2014

Asset Type	Performance Parameter	Level of Service (LOS)	Frequency of Measuremen t	Testing Method	Recommended Remedial measures	Time limit for Rectification	Specification s and Standards
Trees and Plantatio n including median plantatio n	obstruction in	No obstruction due to trees		Visual with video/image backup	Removal of trees	Immediate	IRC:SP:84 - 2014
	in health of trees and	Health of plantation shall be as per requirement of specifications & instructions issued by Authority from time to time	Daily	Visual with video/image backup	Timely watering and treatment. Or Replacement of Trees and Bushes.	Within 90 days	IRC:SP:84 - 2014
		Sight line shall be free from obstruction by vegetation	D '1	Visual with video/image backup	Removal of Trees	Immediate	IRC:SP 84- 2014
	Cleaning of Toilets	-	Daily	-	-	Every 4 hours	
Rest Areas	Defects in electrical, water and sanitary Installations	-	Daily	-	Rectification	24 hours	

Construction of Balance work of Two – Lane with hard shoulders of Existing Hayuliang – Hawai Road (NH-113) from design km 51.825 to km 63.131 (Existing km 45.050 of Hayuliang – Hawai Road to Hawai town)(11.306 km) on EPC basis in the state of Arunachal Pradesh Package of SARDP –NE (Green Field Alignment)

Asset Type	Performance Parameter	Level of Service (LOS)	Frequency of Measuremen t	Testing Method	Recommended Remedial measures	Time limit for Rectification	Specifica s and Standa	l
Other				-	Rectification	15 days	IRC:SP	84-
Project	Damage or o	deterioration in Approach Roads,					2014	
<b>Facilities</b>	pedestrian facil	ities, truck lay-bys, bus-bays, bus-	Daily					
and		rossings, Traffic Aid Posts, Medical						
Approac	Aid Posts and or	ther works						
h roads								

Construction o AssHayai Road (I – Hawai Road Package of SA	of Balance work Periormanc VH-113) Wolf de <b>c</b> o <b>Parvaineter</b> )( RDP –NE (Gree	of Two – Lane with hard sign km 51.825 to km 63 11.306 k <b>d ) QS</b> PPC basi n Field Alignment)	Firequency Ends Nicksisting Ends s in the state of Ar	ting Hayuliang – 45.0 <b>50-6-6-11-20 Mierk</b> od unachal Prädesh	Recommended Remedial	Time limit for Rectification	Specifications and Standards
		available	2 times in a year (before and after rainy season)	Engineer as per IRC SP: 35-1990 and recording of depth of silting and area of vegetation.	Cleaning silt up soils and debris in culvert barrel after rainy season, removal of bushes and vegetation, U/s of barrel, under barrel and D/s of barrel before rainy season.	before onset of monsoon and within 30	IRC 5-2015, IRC SP:40- 1993 and IRC SP:13- 2004
	expansion joints if	No leakage through expansion joints	Bi-Annually	Physical inspection of expansion joints as per IRC SP: 35- 1990 if any, for leakage strains on walls at joints.	Fixing with sealant suitably	30 days or before onset of rains whichever comes earlier	IRC SP:40- 1993 and IRC SP:69-2011
	Structurall	Spalling of concrete not more than 0.25 sqm  Delamination of concrete not more than 0.25 sq.m.  Cracks wider than 0.3 mm not more than 1m aggregate length	Bi-Annually	SP:35-1990 and	Repairs to spalling, cracking, delamination, rusting shall be followed as per IRC:SP:40-1993.	15 days	IRC SP 40- 1993 and MORTH Specification s clause 2800

	Protection works in good condition	Damaged of rough stone apron or bank revetment not more than 3 sqm, damage to solid apron (concrete apron) not more than 1 sqm	2 times in a year (before and after rainy season)	Condition survey as per IRC SP:35-1990	Repairs to damaged aprons and pitching	30 days after defect observation or 2 weeks before onset of rainy season whichever is earlier.	IRC: SP 40- 1993 and IRC:SP:13- 2004.
Bridges including ROBs Flyover etc. as applicable	Riding quality or user comfort	No pothole in wearing coat on bridge deck	Daily	Visual inspection as per IRC SP:35-1990	Repairs to BC or wearing coat	15 days	MORT&H Specification 2811
Bridge -Super	Bumps	No bump at expansion joint	Daily	Visual inspection as per IRC SP:35- 1990	Repairs to BC on either side of expansion joints, profile correction course on approach slab in case of settlement to approach embankment	15 days	MORT&H Specification 3004.2 & 2811.
Structure	User safety (condition of crash barrier and guard rail)	No damaged or missing stretch of crash barrier or pedestrian hand railing	Daily	Visual inspection and detailed condition survey as per IRC SP: 35-1990.	Repairs and replacement of safety barriers as the case may be	3days	IRC: 5-1998, IRC SP: 84- 2014 and IRC SP: 40- 1993.

r e S	ent Spalling of concrete Delaminatio	Not more than 0.25 sq.m  Not more than 0.50 sq.m  Not more than 0.50 sq.m	Bi- Annually	Detailed condition survey as per IRC SP: 35-1990 using Mobile Bridge Inspection Unit	All the corroded reinforcement shall need to be thoroughly cleaned from rusting and applied with anti-corrosive coating before carrying out the repairs to affected concrete portion with epoxy mortar / concrete.	15 days	IRC SP: 40- 1993 and MORTH Specificatio n 1600.
	wider than	Not more than 1m total length	Bi-Annually	Detailed condition survey as per IRC SP: 35-1990 using Mobile Bridge Inspection Unit	Grouting with epoxy mortar, investigating causes for cracks development and carry out necessary rehabilitation.	48 Hours	IRC SP: 40- 1993 and MORTH Specification 2800.
	Rainwater seepage through deck slab	Leakage - nil	Quarterly	Detailed condition survey as per IRC SP: 35-1990 using Mobile Bridge Inspection Unit	Grouting of deck slab at leakage areas, waterproofing, repairs to drainage spouts	1 months	MORTH specifications 2600 & 2700.
	Deflection due to permanent loads and	Within design limits.	Once in every 10 years for spans more	Load test method	Carry out major rehabilitation works on bridge to retain original design loads capacity	6 months	IRC SP: 51- 1999.

1	live loads		than 40 m						
d n	briage leck due to	Frequency vibrations shall be more than 5 l		Laser displacement sensors or laser vibrometers	Strengthening structure	of	super	4 months	AASHT O LRFD specifications
E	Leakage in Expansion oints	No damage elastomeric seal compound strip s expansion joint, leakage of t water thro expansion joint case of buried asphalt plug a copper strip joint	to ant in eal no ain agh in and and	Detailed condition survey as per IRC SP:35-1990 using Mobile Bridge Inspection Unit	Replace of expansion joint	seal	in	15 days	MORTH specifications 2600 and IRC SP: 40-1993.
	Debris and dust in strip seal	No dust debris expansion jo	or in Monthly	Detailed condition survey as per IRC SP:35-1990 using	Cleaning of joint gaps thorou	expar ughly	nsion	3 days	MORTH specification s 2600 and

	expansion joint	gap.		Mobile Bridge Inspection Unit			IRC SP: 40- 1993.
	Drainage spouts	No down take pipe missing/broken below soffit of the deck slab. No silt, debris, clogging of drainage spout collection chamber.	Monthly	Detailed condition survey as per IRC SP: 35-1990 using Mobile Bridge Inspection Unit	Cleaning of drainage spouts thoroughly.  Replacement of missing/broken down take pipes with a minimum pipe extension of 500mm below soffit of slab. Providing sealant around the drainage spout if any leakages observed.	3 days	MORTH specification 2700.
Bridge- substructure	Cracks/sp alling of concrete/ rusted steel	No cracks, spalling of concrete and rusted steel	Bi-Annually	Detailed condition survey as per IRC SP: 35-1990 using Mobile Bridge Inspection Unit	All the corroded reinforcement shall need to be thoroughly cleaned from rusting and applied with anti-corrosive coating before carrying out repairs to substructure by grouting/guniting and micro concreting depending on type of defect noticed	30 days	IRC SP: 40- 1993 and MORTH specification 2800.

	Bearings	Delamination of bearing reinforcement not more than 5%, cracking or tearing of rubber not more than 2 locations per side, no rupture of reinforcement or rubber	Bi-Annually	Detailed condition survey as per IRC SP: 35-1990 using Mobile Bridge Inspection Unit	In case of failure of even one bearing on any pier/abutment, all the bearings on that pier/abutment shall be replaced, in order to get uniform load transfer on to bearings.	3 months	MORTH specificatio n 2810 and IRC SP: 40- 199.
Bridge Foundations	Scouring around foundations	Scouring shall not be lower than maximum scour level for the bridge	Bi-Annually	Condition survey and visual inspection as per IRC SP:35-1990 using Mobile Bridge Inspection Unit. In case of doubt, use Underwater camera for inspection of deep wells in major Rivers.	Suitable protection works around pier/abutment	1 month	IRC SP: 40- 1993, IRC 83-2014, MORTH specificatio n 2500
	Protectio n works in good condition	Damaged of rough stone apron or bank revetment not more than 3	2 times in a year (before and after rainy season)	Condition survey as per IRC SP:35-1990	Repairs to damaged aprons and pitching.	30 days after defect observatio n or2	IRC: SP 40- 1993 and IRC:SP:13- 2004.

Construction of Balance work of Two – Lane with hard shoulders of Existing Hayuliang – Hawai Road (NH-113) from design km 51.825 to km 63.131 (Existing km 45.050 of Hayuliang – Hawai Road to Hawai town)(11.306 km) on EPC basis in the state of Arunachal Pradesh Package of SARDP –NE (Green Field Alignment)

Dec 2020

sq.m, damage to		weeks	
solid apron		before	
(concrete apron)		onset of	
not		rainy	
more than 1		season	
sq.m		whichever	
		is earlier.	

Note: Any Structure during the entire contract period which is found that does not complies with all requirements of this Table will be prepared, rehabilitated or even reconstructed under the scope of the contractor.

**Table 4: Maintenance Criteria for Structures and Culverts:** 

#### **Table 5: Maintenance Criteria for Hill Roads**

In addition to above, for hill roads the following provisions for maintenance is also to done.

Hill Roads		
(i)	Damage to Retaining wall/ Breast wall	7 (Seven) days
(ii)	Landslides requiring clearance	12 (Twelve) hours
(iii)	Snow requiring clearance	24 (Twenty Four) hours

<u>Note:</u> For all tables 1 to 5 above, latest BIS & IRC standards (even those not indicated herewith) along with MoRTH specifications shall be binding for all maintenance activities.

## A. Flexible Pavement

	Nature of Defect or deficiency	Time limit for repair/ rectification		
<b>(b)</b>	Granular earth shoulders, side slopes, drains and cul	verts		
(i)	Variation by more than 1 % in the prescribed slope of camber/cross fall (shall not be less than the camber on the main carriageway)	7 (seven) days		
(ii)	Edge drop at shoulders exceeding 40 mm	7 (seven) days		
(iii)	Variation by more than 15% in the prescribed side (embankment) slopes	30 (thirty) days		
(iv)	Rain cuts/gullies in slope	7 (seven) days		
(v)	Damage to or silting of culverts and side drains	7 (seven) days		
(vi)	Desilting of drains in urban/semi- urban areas	24 (twenty four) hours		
(vii)	Railing, parapets, crash barriers	7 (seven) days (Restore immediately if causing safety hazard)		
(c)	c) Road side furniture including road sign and pavement marking			
(i)	Damage to shape or position, poor visibility or loss of retro- reflectivity	48 (forty eight) hours		
(ii)	Painting of km stone, railing, parapets, crash barriers	As and when required/ Once every year		
(iii)	Damaged/missing signs road requiring replacement	7 (seven) days		
(iv)	Damage to road mark ups	7 (seven) days		
(d)	Road lighting			
(i)	Any major failure of the system	24 (twenty four) hours		
(ii)	Faults and minor failures	8 (eight) hours		
(e)	Trees and plantation			

	Nature of Defect or deficiency	Time limit for repair/ rectification				
(i)	Obstruction in a minimum head- room of 5 m above carriageway or obstruction in visibility of road signs	24 (twenty four)hours				
(ii)	Removal of fallen trees from carriageway	4 (four) hours				
(iii)	Deterioration in health of trees and bushes	Timely watering and treatment				
(iv)	Trees and bushes requiring replacement	30 (thirty) days				
(v)	Removal of vegetation affecting sight line and road structures	15 (fifteen) days				
<b>(f)</b>	Rest area					
(i)	Cleaning of toilets	Every 4 (four) hours				
(ii)	Defects in electrical, water and sanitary installations	24 (twenty four) hours				
(g)	(g) [Toll Plaza]					
(h)	Other Project Facilities and Approach roads					
(i)	Damage in approach roads, pedestrian facilities, truck lay- byes, bus-bays, bus-shelters, cattle crossings, [Traffic Aid Posts, Medical Aid Posts] and service roads	15 (fifteen) days				
(ii)	Damaged vehicles or debris on the road	4 (four) hours				
(iii)	Malfunctioning of the mobile crane	4 (four) hours				
Brid	ges					
(a)	Superstructure					
(i)	Any damage, cracks, spalling/ scaling	within 48 (forty eight) hours				
	Temporary measures	within 15 (fifteen) days or as				
	Permanent measures	specified by the Authority's Engineer				
(b)	Foundations					

	Nature of Defect or deficiency	Time limit for repair/ rectification
(i)	Scouring and/or cavitation	15 (fifteen) days
(c)	Piers, abutments, return walls and wing walls	
(i)	Cracks and damages including settlement and tilting, spalling, scaling	30 (thirty) days
(d)	Bearings (metallic) of bridges	
(i)	Deformation, damages, tilting or shifting of bearings	15 (fifteen) days Greasing of metallic bearings once in a year
(e)	Joints	
(i)	Malfunctioning of joints	15 (fifteen) days
<b>(f)</b>	Other items	
(i)	Deforming of pads in elastomeric bearings	7 (seven) days
(ii)	Gathering of dirt in bearings and joints; or clogging of spouts, weep holes and vent-holes	3 (three) days
(iii)	Damage or deterioration in kerbs, parapets, handrails and crash barriers	3 (three) days (immediately within 24 hours if posing danger to safety)
(iv)	Rain-cuts or erosion of banks of the side slopes of approaches	7 (seven) days
(v)	Damage to wearing coat	15 (fifteen) days
(vi)	Damage or deterioration in approach slabs, pitching, apron, toes, floor or guide bunds	30 (thirty) days
(vii)	Growth of vegetation affecting the structure or obstructing the waterway	15 (fifteen) days
(g)	Hill Roads	
(i)	Damage to retaining wall/breast wall	7 (seven) days
(ii)	Landslides requiring clearance	12 (twelve) hours

	Nature of Defect or deficiency	Time limit for repair/ rectification
(iii)	Snow requiring clearance	24 (twenty four) hours

[Note: Where necessary, the Authority may modify the time limit for repair/rectification, or add to the nature of Defect or deficiency before issuing the bidding document, with the approval of the competent authority.]

## **Schedule - F** (See Clause 4.1 (vii)(a))

#### **Applicable Permits**

#### 1. Applicable Permits

- (i) The Contractor shall obtain, as required under the Applicable Laws, the following Applicable Permits:
  - (a) Permission of the State Government for extraction of boulders from quarry;
  - (b) Permission of Village Panchayats and Pollution Control Board for installation of crushers;
  - (c) Licence for use of explosives;
  - (d) Permission of the State Government for drawing water from river/reservoir;
  - (e) Licence from inspector of factories or other competent Authority for setting up batching plant;
  - (f) Clearance of Pollution Control Board for setting up batching plant;
  - (g) Clearance of Village Panchayats and Pollution Control Board for setting up asphalt plant;
  - (h) Permission of Village Panchayats and State Government for borrow earth; and
  - (i) Any other permits or clearances required under Applicable Laws.
- (ii) Applicable Permits, as required, relating to environmental protection and conservation shall have been procured by the Authority in accordance with the provisions of this Agreement.

## Schedule - G

(See Clauses 7.1 and 19.2)

#### Annex-I

(See Clause 7.1)

#### Form of Bank Guarantee

#### [Performance Security/Additional Performance Security]

[Managing Director, NHIDCL, PTI Building, New Delhi] WHEREAS:

- [name and address of contractor] (hereinafter called the "Contractor") and [NHIDCL, PTI Building, New Delhi], (hereinafter called the "Authority") have entered into an agreement (hereinafter called the "Agreement") for Construction of Balance work of Two Lane with hard shoulders of Existing Hayuliang Hawai Road (NH-113) from design km 51.825 to km 63.131 (Existing km 45.050 of Hayuliang Hawai Road to Hawai town)(11.306 km) on EPC basis in the state of Arunachal Pradesh Package of SARDP –NE (Green Field Alignment), subject to and in accordance with the provisions of the Agreement

NOW, THEREFORE, the Bank hereby, unconditionally and irrevocably, guarantees and affirms as follows:

- 1. The Bank hereby unconditionally and irrevocably guarantees the due and faithful performance of the Contractor's obligations during the {Construction Period/ Defects Liability Period and Maintenance Period} under and in accordance with the Agreement, and agrees and undertakes to pay to the Authority, upon its mere first written demand, and without any demur, reservation, recourse, contest or protest, and without any reference to the Contractor, such sum or sums up to an aggregate sum of the Guarantee Amount as the Authority shall claim, without the Authority being required to prove or to show grounds or reasons for its demand and/or for the sum specified therein.
- 2. A letter from the Authority, under the hand of an officer not below the rank of

[General Manager in the NHIDCL], that the Contractor has committed default in the due and faithful performance of all or any of its obligations under and in accordance with the Agreement shall be conclusive, final and binding on the Bank. The Bank further agrees that the Authority shall be the sole judge as to whether the Contractor is in default in due and faithful performance of its obligations during and under the Agreement and its decision that the Contractor is in default shall be final and binding on the Bank, notwithstanding any differences between the Authority and the Contractor, or any dispute between them pending before any court, tribunal, arbitrators or any other authority or body, or by the discharge of the Contractor for any reason whatsoever.

- 3. In order to give effect to this Guarantee, the Authority shall be entitled to act as if the Bank were the principal debtor and any change in the constitution of the Contractor and/or the Bank, whether by their absorption with any other body or corporation or otherwise, shall not in any way or manner affect the liability or obligation of the Bank under this Guarantee.
- 4. It shall not be necessary, and the Bank hereby waives any necessity, for the Authority to proceed against the Contractor before presenting to the Bank its demand under this Guarantee.
- 5. The Authority shall have the liberty, without affecting in any manner the liability of the Bank under this Guarantee, to vary at any time, the terms and conditions of the Agreement or to extend the time or period for the compliance with, fulfillment and/ or performance of all or any of the obligations of the Contractor contained in the Agreement or to postpone for any time, and from time to time, any of the rights and powers exercisable by the Authority against the Contractor, and either to enforce or forbear from enforcing any of the terms and conditions contained in the Agreement and/or the securities available to the Authority, and the Bank shall not be released from its liability and obligation under these presents by any exercise by the Authority of the liberty with reference to the matters aforesaid or by reason of time being given to the Contractor or any other forbearance, indulgence, act or omission on the part of the Authority or of any other matter or thing whatsoever which under any law relating to sureties and guarantors would but for this provision have the effect of releasing the Bank from its liability and obligation under this Guarantee and the Bank hereby waives all of its rights under any such law.
- 6. This Guarantee is in addition to and not in substitution of any other guarantee or security now or which may hereafter be held by the Authority in respect of or relating to the Agreement or for the fulfillment, compliance and/or performance of all or any of the obligations of the Contractor under the Agreement.
- 7. Notwithstanding anything contained hereinbefore, the liability of the Bank under this Guarantee is restricted to the Guarantee Amount and this Guarantee will remain in force for the period specified in paragraph 8 below and unless a demand or claim in writing is made by the Authority on the Bank under this Guarantee all rights of the Authority under this Guarantee shall be forfeited and

the Bank shall be relieved from its liabilities hereunder.

- 8. The Guarantee shall cease to be in force and effect on \*\*\*\*\$. Unless a demand or claim under this Guarantee is made in writing before expiry of the Guarantee, the Bank shall be discharged from its liabilities hereunder.
- 9. The Bank undertakes not to revoke this Guarantee during its currency, except with the previous express consent of the Authority in writing, and declares and warrants that it has the power to issue this Guarantee and the undersigned has full powers to do so on behalf of the Bank.
- 10. Any notice by way of request, demand or otherwise hereunder may be sent by post addressed to the Bank at its above referred branch, which shall be deemed to have been duly authorised to receive such notice and to effect payment thereof forthwith, and if sent by post it shall be deemed to have been given at the time when it ought to have been delivered in due course of post and in proving such notice, when given by post, it shall be sufficient to prove that the envelope containing the notice was posted and a certificate signed by an officer of the Authority that the envelope was so posted shall be conclusive.
- 11. This Guarantee shall come into force with immediate effect and shall remain in force and effect for up to the date specified in paragraph 8 above or until it is released earlier by the Authority pursuant to the provisions of the Agreement.
- 12. This guarantee shall also be operable at our Branch at New Delhi, from whom, confirmation regarding the issue of this guarantee or extension / renewal thereof shall be made available on demand. In the contingency of this guarantee being invoked and payment thereunder claimed, the said branch shall accept such invocation letter and make payment of amounts so demanded under the said invocation.

13. Bank Guarantee has been sent to authority's bank through SFMS gateway as per the details below: -

SI. No	Particulars	Details
1	Name of the Beneficiary	National Highways and
		Infrastructure Development
		Corporation Limited
2	Beneficiary Bank Account No.	90621010002659
3	Beneficiary Bank Branch	IFSC SYNB0009062
4	Beneficiary Bank Branch Name	Transport Bhawan, New Delhi
5	Beneficiary Bank Address	Syndicate Bank, Transport
		Bhawan, 1st Parliament street, New Delhi-110001

Signed and sealed this	day of	, 20	at
SIGNED, SEALED AND I	DELIVERED		

Construction of Balance work of Two – Lane with hard shoulders of Existing Hayuliang – Hawai Road (NH-113) from design km 51.825 to km 63.131 (Existing km 45.050 of Hayuliang – Hawai Road to Hawai town)(11.306 km) on EPC basis in the state of Arunachal Pradesh Package of SARDP –NE (Green Field Alignment)

Dec 2020

For and on behalf of the Bank by: (Signature)
(Name)
(Designation)
(Code
Number)
(Address)
NOTES:

- (i) The bank guarantee should contain the name, designation and code number of the officer(s) signing the guarantee.
- (ii) The address, telephone number and other details of the head office of the Bank as well as of issuing branch should be mentioned on the covering letter of issuing branch.

#### Annex – II

(Schedule - G)

(See Clause 19.2)

## Form for Guarantee for Advance Payment

[Managing Director, NHIDCL, PTI Building, New Delhi] WHEREAS:

- (A) [name and address of contractor] (hereinafter called the "Contractor") has executed an agreement (hereinafter called the "Agreement") with the [NHIDCL, PTI Building, New Delhi], (hereinafter called the "Authority") for the construction of the Construction of Balance work of Two Lane with hard shoulders of Existing Hayuliang Hawai Road (NH-113) from design km 51.825 to km 63.131 (Existing km 45.050 of Hayuliang Hawai Road to Hawai town)(11.306 km) on EPC basis in the state of Arunachal Pradesh Package of SARDP –NE (Green Field Alignment), subject to and in accordance with the provisions of the Agreement
- (B) In accordance with Clause 19.2 of the Agreement, the Authority shall make to the Contractor an interest bearing @Bank Rate + 3% advance payment (herein after called "Advance Payment") equal to 10% (ten per cent) of the Contract Price; and that the Advance Payment shall be made in two installments subject to the Contractor furnishing an irrevocable and unconditional guarantee by a scheduled bank for an amount equivalent to 110% (one hundred and ten percent) of such installment to remain effective till the complete and full repayment of the installment of the Advance Payment as security for compliance with its obligations in accordance with the Agreement. The amount of {first/second} installment of the Advance Payment is Rs. ------ cr. (Rupees crore) and the amount of this Guarantee is Rs. ------ cr. (Rupees ----- crore) (the "Guarantee Amount").

NOW, THEREFORE, the Bank hereby, unconditionally and irrevocably, guarantees and affirms as follows:

1. The Bank hereby unconditionally and irrevocably guarantees the due and faithful repayment on time of the aforesaid installment of the Advance Payment under and in accordance with the Agreement, and agrees and undertakes to pay to the

<sup>§</sup> The Guarantee Amount should be equivalent to 110% of the value of the applicable instalment.

Authority, upon its mere first written demand, and without any demur, reservation, recourse, contest or protest, and without any reference to the Contractor, such sum or sums up to an aggregate sum of the Guarantee Amount as the Authority shall claim, without the Authority being required to prove or to show grounds or reasons for its demand and/or for the sum specified therein.

A letter from the Authority, under the hand of an officer not below the rank of [General Manager in the National Highways Authority of India], that the Contractor has committed default in the due and faithful performance of all or any of its obligations for the repayment of the installment of the Advance Payment under and in accordance with the Agreement shall be conclusive, final and binding on the Bank. The Bank further agrees that the Authority shall be the sole judge as to whether the Contractor is in default in due and faithful performance of its obligations during and under the Agreement and its decision that the Contractor is in default shall be final and binding on the Bank, notwithstanding any differences between the Authority and the Contractor, or any dispute between them pending before any court, tribunal, arbitrators or any other authority or body, or by the discharge of the Contractor for any reason whatsoever.

- In order to give effect to this Guarantee, the Authority shall be entitled to act as if the Bank were the principal debtor and any change in the constitution of the Contractor and/or the Bank, whether by their absorption with any other body or corporation or otherwise, shall not in any way or manner affect the liability or obligation of the Bank under this Guarantee.
- 3. It shall not be necessary, and the Bank hereby waives any necessity, for the Authority to proceed against the Contractor before presenting to the Bank its demand under this Guarantee.
- 4. The Authority shall have the liberty, without affecting in any manner the liability of the Bank under this Guarantee, to vary at any time, the terms and conditions of the Advance Payment or to extend the time or period of its repayment or to postpone for any time, and from time to time, any of the rights and powers exercisable by the Authority against the Contractor, and either to enforce or forbear from enforcing any of the terms and conditions contained in the Agreement and/or the securities available to the Authority, and the Bank shall not be released from its liability and obligation under these presents by any exercise by the Authority of the liberty with reference to the matters aforesaid or by reason of time being given to the Contractor or any other forbearance, indulgence, act or omission on the part of the Authority or of any other matter or thing whatsoever which under any law relating to sureties and guarantors would but for this provision have the effect of releasing the Bank from its liability and obligation under this Guarantee and the Bank hereby waives all of its rights under any such law.
- 5. This Guarantee is in addition to and not in substitution of any other guarantee or security now or which may hereafter be held by the Authority in respect of or relating to the Advance Payment.

- Notwithstanding anything contained hereinbefore, the liability of the Bank under this Guarantee is restricted to the Guarantee Amount and this Guarantee will remain in force for the period specified in paragraph 8 below and unless a demand or claim in writing is made by the Authority on the Bank under this Guarantee all rights of the Authority under this Guarantee shall be forfeited and the Bank shall be relieved from its liabilities hereunder.
- 7. The Guarantee shall cease to be in force and effect on \*\*\*\*. Unless a demand or claim under this Guarantee is made in writing on or before the aforesaid date, the Bank shall be discharged from its liabilities hereunder.
- 8 The Bank undertakes not to revoke this Guarantee during its currency, except with the previous express consent of the Authority in writing, and declares and warrants that it has the power to issue this Guarantee and the undersigned has full powers to do so on behalf of the Bank.
- 9. Any notice by way of request, demand or otherwise hereunder may be sent by post addressed to the Bank at its above referred branch, which shall be deemed to have been duly authorised to receive such notice and to effect payment thereof forthwith, and if sent by post it shall be deemed to have been given at the time when it ought to have been delivered in due course of post and in proving such notice, when given by post, it shall be sufficient to prove that the envelope containing the notice was posted and a certificate signed by an officer of the Authority that the envelope was so posted shall be conclusive.
- 10. This Guarantee shall come into force with immediate effect and shall remain in force and effect up to the date specified in paragraph 8 above or until it is released earlier by the Authority pursuant to the provisions of the Agreement.
- 11. This guarantee shall also be operable at our Branch at New Delhi, from whom, confirmation regarding the issue of this guarantee or extension / renewal thereof shall be made available on demand. In the contingency of this guarantee being invoked and payment thereunder claimed, the said branch shall accept such invocation letter and make payment of amounts so demanded under the said invocation.
- 12. Bank Guarantee has been sent to authority's bank through SFMS gateway as per the details below: -

SI. No	Particulars	Details
1	Name of the Beneficiary	National Highways and Infrastructure Development Corporation Limited
2	Beneficiary Bank Account No.	90621010002659
3	Beneficiary Bank Branch	IFSC SYNB0009062
4	Beneficiary Bank Branch Name	Transport Bhawan, New Delhi
5	Beneficiary Bank Address	Syndicate Bank, Transport

Construction of Balance work of Two – Lane with hard shoulders of Existing Hayuliang – Hawai Road (NH-113) from design km 51.825 to km 63.131 (Existing km 45.050 of Hayuliang – Hawai Road to Hawai town)(11.306 km) on EPC basis in the state of Arunachal Pradesh Package of SARDP –NE (Green Field Alignment)

Dec 2020

			Bhawan, 1st Parliament street, New Delhi-110001				
	13.						
	Signed and sealed this day of, 20 at SIGNED, SEALED AND DELIVERED						
	For and on behalf of the Bank by: (Signature)						
(	(Name)						
(	(Designation)						
(	(Code Nu	umber)					
(	(Address)	)					
]	NOTES:						

(i) The bank guarantee should contain the name, designation and code number of the officer(s) signing the guarantee.

The address, telephone number and other details of the head office of the Bank as well as of issuing branch should be mentioned on the covering letter of issuing branch.

<sup>§</sup> Insert a date being 90 (ninety) days after the end of one year from the date of payment of the Advance payment to the Contractor (in accordance with Clause 19.2 of the Agreement).

#### **SCHEDULE - H**

## (See Clauses 10.1.4 and 19.3)

## **Contract Price Weightages**

1.1	The	Contract	Price	for this	Agreement is	Rs/-	-

1.2 Proportions of the Contract Price for different stages of Construction of the Project Highway shall be as specified below:

specified b			1	ı
ITEM	WEIGHTAGE IN PERCENTAGE TO THE CONTRACT PRICE	STAGE FOR PAYMENT	PERCENTAGE WEIGHTAGE	PERCENTAGE WEIGHTAGE vis a vis overall Project
1	2	3	4	5
		A-Widening and		
		Strengthening		
		(1) Earthwork up to top of the sub-grade including excavation in soil, soft rock and hard rock.	0.00%	0.0000%
		(2) Granular work (sub- base, base, shoulders)	0.00%	0.0000%
		(3) Bituminous work	0.00%	0.0000%
		a) DBM	0.00%	0.0000%
		b) BC	0.00%	0.0000%
Road works	72%	(4) Concrete Pavement	0.00%	0.0000%
including culverts,		(5) Site Clearance	0.00%	0.0000%
minor bridges, underpasses,		(6) Widening and repair of culverts	0.00%	0.0000%
overpasses, approaches to		(7) Protection of existing works	0.00%	0.0000%
ROB/RUB/ Major Bridges/ Structures		(8) Widening and repair of minor bridges	0.00%	0.0000%
(but excluding		B- New 2-lane		
service roads/slip roads)		alignment		
Todus		1 (a) Earthwork up to top of the sub-grade including excavation in soil, soft rock and hard rock.	55.22%	39.7500%
		1(b) Rectification Work	2.97%	2.1384%
		(2) Granular work (sub- base, base, shoulders)	8.19%	5.9000%
		(3) Bituminous work		
		a) DBM	5.51%	3.9700%
		b) BC	3.03%	2.1800%
		(4) CC Pavement	0.00%	0.0000%
		(5) Protection Works	0.00%	0.0000%

ITEM	WEIGHTAGE IN PERCENTAGE TO THE CONTRACT PRICE	STAGE FOR PAYMENT	PERCENTAGE WEIGHTAGE	PERCENTAGE WEIGHTAGE vis a vis overall Project
1	2	3	4	5
		(6) RCC / Reinf. Earth ret wall in approaches of RoB	0.00%	0.0000%
		(7) Drainage Works	0.00%	0.0000%
		(8) Clearing & Grubbing	0.01%	0.0100%
		(9) Protection works	0.00%	0.0000%
		C- New culverts, minor bridges, underpasses, overpasses on existing road, realignments,		
		bypasses:		
		(1) Box / Slab Culverts	25.07%	18.0500%
		(2) HP Culverts	0.00%	0.0000%
		(3) Embankment Protection (New Lane)	0.00%	0.0000%
		(4) Grade Separated structures	0.00%	0.0000%
		(5) Overpasses	0.00%	0.0000%
		(6) Elephant underpasss	0.00%	0.0000%
		(7) Approaches to ROB and Viaduct	0.00%	0.0000%
		(8) Minor bridges	0.00%	0.0000%
		(9) Cattles/Pedestrian Underpasses	0.00%	0.0000%
		(10) Vehicular Underpasses	0.00%	0.0000%
		A- Widening and repairs of Major Bridges		
		(1) Foundation	0.00%	0.0000%
		(2) Sub-structure	0.00%	0.0000%
		(3) Super-structure (including wearing coat, crash barriers etc. complete in all respect )	0.00%	0.0000%
Major Bridge works	13.83%	B- Widening and repair of		
and ROB/RUB		(a) ROB	0.00%	0.0000%
		(b) RUB	0.00%	0.0000%
		C- New Major		
		Bridges  (4) Other Missellessesses		
		(1) Other Miscellaneous	0.00%	0.0000%
		(2) Guide Bund	0.00%	0.0000%
		(3) Foundation	45.00%	6.2200%

(5) Super-structure (including wearing coat, crash barriers etc. complete in all respect.) (6) Protection Works  D- New rail-road  bridge including Viaduct (a) ROB (b) RUB  0.00%  0.0000  (1) Foundation  0.00%  0.0000  (2) Sub-structure (including crash barriers etc. complete) (4) Reinforced Earth  Other Works  14.17%  (5) Super-structure (including viaduct) (a) ROB 0.00%  0.00000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.00000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.00000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.00000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.00000 0.00000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.0000 0.000	WEIGHTAGE IN PERCENTAGE TO THE CONTRACT PRICE		STAGE FOR PAYMENT	PERCENTAGE WEIGHTAGE	PERCENTAGE WEIGHTAGE vis a vis overall Project
(5) Super-structure (including wearing coat, crash barriers etc. complete in all respect.) (6) Protection Works  D- New rail-road  bridge including Viaduct (a) ROB (b) RUB  0.00%  0.0006 (b) RUB  0.00%  0.0006 (c) Protection Works  0.00%  0.0006 (d) RUB  0.00%  0.0006 (e) RUB  0.00%  0.0006 (f) Poundation  0.00% 0.0006 (g) Sub-structure (including crash barriers etc. complete) (d) Reinforced Earth 0.00% 0.0006 (f) Road Marking 0.00% 0.0006 Road Marking 0.00% 0.0006 Road Appurtenances 0.00% 0.0006 Road Side plantation 0.00% 0.0006 Protection works 0.00% 0.0006 Road side drains & toe wall 0.00% 0.0006 Road Side drains &	1	2	3	4	5
Wearing coat, crash barriers etc. complete in all respect			(4) Sub-structure	25.00%	3.4600%
D- New rail-road   bridge including Viaduct   (a) ROB   0.00%   0.0000   0.0000   (b) RUB   0.00%   0.0000			wearing coat, crash barriers	30.00%	4.1500%
Dridge including Viaduct   (a) ROB			(6) Protection Works	0.00%	0.0000%
(a) ROB			D- New rail-road		
(b) RUB			bridge including Viaduct		
Color			` '		0.0000%
Color   Colo			(b) RUB	0.00%	0.0000%
Celevated sections, reinforced earth    Country   Coun	Structures		(1) Foundation	0.00%	0.0000%
(3) Super-structure (including crash barriers etc. complete)   (4) Reinforced Earth   0.00%   0.0000		0.00%	(2) Sub-structure	0.00%	0.0000%
Morks   Major Junction   0.00%   0.0000		5.50%	(including crash barriers	0.00%	0.0000%
Major Junction   0.00%   0.0000			(4) Reinforced Earth	0.00%	0.0000%
Major Junction			Other Engineering		
Road Marking			Works		
Road Appurtenances   0.00%   0.0000			Major Junction	0.00%	0.0000%
Road Side plantation			Road Marking	0.00%	0.0000%
Protection works			Road Appurtenances	0.00%	0.0000%
Service roads/slip road   0.00%   0.0000			Road Side plantation	0.00%	0.0000%
Toll Plaza			Protection works	0.00%	0.0000%
Road side drains & toe wall   4.54%   0.6433			Service roads/slip road	0.00%	0.0000%
Other Works         Project facilities         0.09%         0.0129           Safety & traffic mgmt.         0.00%         0.0000           During construction         0.00%         0.0510			Toll Plaza	0.00%	0.0000%
Other Works  14.17%  Safety & traffic mgmt. During construction  Traffic Sign, KM Stone  0.00%  0.0000  0.0000			Road side drains & toe wall	4.54%	0.6433%
During construction  Traffic Sign, KM Stone  0.00%  0.0000  0.0000  0.0000			Project facilities	0.09%	0.0129%
	Other Works	14.17%		0.00%	0.0000%
Pavement marking, Painting 0.99% 0.1403			Traffic Sign, KM Stone	0.36%	0.0510%
			Pavement marking, Painting	0.99%	0.1403%
barrier			barrier	4.13%	0.5852%
Boundary stone, km stone,5th km stone, &hectometre 0.03% 0.0043 stones			km stone, &hectometre	0.03%	0.0043%
Traffic blinker LED Delineator, stud, reflective 0.34% 0.0482 payment marker, tree			Delineator, stud, reflective	0.34%	0.0482%

ITEM	WEIGHTAGE IN PERCENTAGE TO THE CONTRACT PRICE	STAGE FOR PAYMENT	PERCENTAGE WEIGHTAGE	PERCENTAGE WEIGHTAGE vis a vis overall Project
1	2	3	4	5
		reflector		
		Traffic Island	0.00%	0.0000%
		Median Kerbs	0.00%	0.0000%
		Bus Bays & Bus shelter	0.87%	0.1233%
		Road side plantation & medium Plantatio	0.00%	0.0000%
		Protection works of guide bund including construction of flexible aprons, boulder pitching and filter media on slopes	0.00%	0.0000%
		Minor junction	1.58%	0.2239%
		Median filling shrub plantation & maintenance for 1 year	0.00%	0.0000%
		Overhead signboard	0.43%	0.0609%
		painting on kerb	0.00%	0.0000%
		Footpath &Separater	0.00%	0.0000%
		Vetiver Plantation	0.00%	0.0000%
		Interlocking concrete block payment	0.00%	0.0000%
		CC kerb	0.00%	0.0000%
		Painting	0.00%	0.0000%
		Cable duct	0.00%	0.0000%
		Solar stud & solar blinking LED	0.00%	0.0000%
		Rest area with development of site including One no Bus bay and Bus shelter, landscaping and tree plantation	0.00%	0.0000%
		For Plantation (Hydro seeding & plantation on hill slopes as slope protection measures)	6.88%	0.9749%
		Traffic control devices and road safety works (Polymer rumble strips on hazardous locations specially valley side curves)	1.38%	0.1955%

ITEM	WEIGHTAGE IN PERCENTAGE TO THE CONTRACT PRICE	STAGE FOR PAYMENT	PERCENTAGE WEIGHTAGE	PERCENTAGE WEIGHTAGE vis a vis overall Project
1	2	3	4	5
		Road furniture	0.00%	0.0000%
		Roads side drains I/C Chute drain	0.00%	0.0000%
		Repair of protections works	0.00%	0.0000%
		Traffic diversion, Safety and traffic management during construction	0.00%	0.0000%
		Retaining wall	0.00%	0.0000%
		Miscellaneous items	0.00%	0.0000%
		Breast wall and RCC retaining wall	0.00%	0.0000%
		Site Clearance	0.00%	0.0000%
		M-20 kerb with channel	0.00%	0.0000%
		Prefabricated railing over kerb in median	0.00%	0.0000%
		Safety Barrier	0.00%	0.0000%
		(v) Project facilities		
		(a) Truck lay-byes	0.00%	0.0000%
		(b) others	0.00%	0.0000%
		(vi) Repairs to bridges/structures		
		Other items (Junctions	0.00%	0.0000%
		Providing wearing coat	0.00%	0.0000%
		Replacement of bearing joints	0.00%	0.0000%
		Providing crash barriers	0.00%	0.0000%
				0.0000%
		(vii) Protection works		
		Breast wall	29.57%	4.1901%
		RCC Retaining wall	32.97%	4.6718%
		Gabion Wall	4.51%	0.6391%
		Parapet	6.01%	0.8516%
		Slope Protection at Land Slide locations.	5.33%	0.7553%
			300.00%	100.00%

## 1.3 Procedure of estimating the value of work done

1.3.1Road works including approaches to minor bridges, Major Bridges and Structures (excluding service roads). Procedure for estimating the value of road work done shall be as follows:

## **TABLE 1.3.1**

STAGE OF PAYMENT	PERCENTAGE WEIGHTAGE vis a vis overall Project	PAYMENT PROCEDURE	
A-Widening and Strengthening			
(1) Earthwork up to top of the sub-grade including excavation in soil, soft rock and hard rock.	0.00%		
(2) Granular work (sub- base, base, shoulders)	0.00%	Unit of measurement is linear length.  Payment of each stage shall be made on pro	
(3) Bituminous work		rata basis on completion of a stage in a length of not less than 5 (five) percent of the	
a) Prime & Tack Coat	0.00%	total length.	
b) DBM	0.00%	_	
c) BC	0.00%		
(4) Concrete Pavement	0.00%		
(5) Site Clearance	0.00%		
(6) Widening and repair of culverts	0.00%	Cost of ten completed culverts shall be determined pro rata with respect to the total number of culverts. Payment shall be made on the completion of five culverts.	
(7) Protection of existing works	0.00%	Unit of measurement is linear length. Payment of each stage shall be made on pro rata basis on completion of a stage in a length of not less than 5 (five) percent of the total length.	
(8) Widening and repair of minor bridges	0.00%	Cost of each minor bridge shall be determined on pro rata basis with respect to the total linear length of the minor bridges. Payment shall be made on the completion of a minor bridge.	
B- New 2-lane alignment			
1(a) Earthwork up to top of the sub-grade including excavation in soil, soft rock and hard rock.	39.7500%		
1(b) Rectification Work	2.1384%	Unit of measurement is linear length.	
(2) Granular work (sub- base, base, shoulders)	5.9000%	Payment of each stage shall be made on pr rata basis on completion of a stage in a	
(3) Bituminous work	0.00%	length of not less than 05 (five) percent of	
a) Prime & Tack Coat	0.00%	total length.	
b) DBM	3.9700%		
c) BC	2.1800%		
(4) CC Pavement	0.00%		
(5) Protection Works	0.00%		

STAGE OF PAYMENT	PERCENTAGE WEIGHTAGE vis a vis overall Project	PAYMENT PROCEDURE
(6) RCC / Reinf. Earth ret wall in approaches of RoB	0.00%	
(7) Drainage Works	0.00%	
(8) Clearing & Grubbing	0.0100%	
(9) Protection works	0.00%	
C- New culverts, minor bridges, underpasses, overpasses on existing road, realignments, bypasses:		
(1) Box / Slab Culverts	18.0500%	Cost of each culvert shall be determined on pro rata basis with respect to the total number of culverts. Payment shall be made on the completion of five culverts.
(2) HP Culverts	0.00%	on the completion of five curverts.
(3) Embankment Protection (New Lane)	0.00%	Unit of measurement is linear length. Payment of each stage shall be made on pro rata basis on completion of a stage in a length of not less than 10 (ten) percent of the total length.
(4) Grade Separated structures	0.00%	Cost of each structure shall be determined
(5) Overpasses	0.00%	on pro rata basis with respect to the total
(6) Elephant underpasses	0.00%	number of structures. Payment shall be made on the completion of each number of
(7) Approaches to ROB and Viaduct	0.00%	structures specified.
(8) Minor bridges	0.00%	Cost of each minor bridge/Culvert shall be determined on pro rata basis with respect to the total linear length of the minor bridges/culvert. Payment shall be made on the completion of a minor bridge/culvert.
(9) Cattles/Pedestrian Underpasses	0.00%	Cost of each structure shall be determined on pro rata basis with respect to the total
(10) Vehicular Underpasses	0.00%	number of structures. Payment shall be made on the completion of each number of structures specified.

@. For example, if the total length of bituminous work to be done is 100 km, the cost per km of bituminous work shall be determined as follows:

Cost per km = P x weightage for bituminous work x (1/L)

Where P= Contract Price

L = Total length in km

Similarly, the rates per km for stages (1), (2) and (4) above shall be worked out.

- 1.3 Procedure of estimating the value of work done
- 1.3.2 Major Bridge works and ROB/RUB.

Procedure for estimating the value of Major Bridge works and of ROB/RUB shall be as stated in table 1.3.2:

**TABLE 1.3.2** 

STAGE OF PAYMENT	WEIGHTAGE at overall Project	PAYMENT PROCEDURE	
A- Widening and repairs of Major Bridges		Cost of each Major Bridge (widening and repairs) shall be	
(1) Foundation	0.00%	determined on pro rata basis with respect to the total linear	
(2) Sub-structure	0.00%	length (m) of the Major Bridges	
(3) Super-structure (including crash barriers etc. complete)	0.00%	(widening and repairs). Payment shall be made on completion of each stage of a Major Bridge as per the weightage given in this table.	
B- Widening and repair of		Cost of each ROB/RUB	
(a) ROB	0.00%	(widening and repairs) shall be determined on pro rata basis	
(b) RUB	0.00%	with respect to the total linear length (m) of the ROB/RUB (widening and repairs). Payment shall be made on completion of an ROB/RUB	
C- New Major Bridges			
(1) Other Miscellaneous Items	0.00%		
(2) Guide Bund	0.00%		
(3) Foundation	6.2200%	Payment shall be made on pro rata basis on completion of 25	
(4) Sub-structure	3.4600%	(twenty five) percent of each stage of a Major Bridge as per	
(5) Super-structure (including crash barriers etc. complete)	4.1500%	the weightage given in this table	
(6) Protection Works	0.00%		
D- New rail-road bridge		Payment shall be made on pro rata basis on completion of 25	
(a) ROB	0.00%	(twenty five) percent of each stage of a ROB/RUB as per the	
(b) RUB	0.00%	weightage given in this table.	

**TABLE: 1.3.3** 

STAGE OF PAYMENT	PERCENTAGE WEIGHTAGE vis a vis overall Project	PAYMENT PROCEDURE
(1) Foundation: On completion of the foundation works including foundations for wing and return walls	0.00%	Cost of each structure shall be determined on pro rata basis in
(2) Sub-structure: On completion of abutments, piers up to the abutment/pier cap	0.00%	respect to the total linear length (m) of all the structures. Payment shall be made on
(3) Super-structure: On completion of the Structure along with super structure, including hand rails/crash barriers, wing walls, return walls, tests on completion etc., elevated structure complete in all respects and fit for use.	0.00%	completion of each stage of a structure as per the weightage given in this table.
(4) Reinforced earth work	0.00%	Payment shall be made on pro rata basis on completion of 20 (twenty) percent of total area.

#### 1.3.4 Other works.

Procedure for estimating the value of other works done shall be as stated in table 1.3.4:

**TABLE 1.3.4** 

STAGE OF PAYMENT	PERCENTAGE WEIGHTAGE vis a vis overall Project	PAYMENT PROCEDURE
Other Engineering Works		
Major Junction	0.00%	Payment shall be made on pro rata basis for
Road Marking	0.00%	completed facilities.
Road Appurtenances	0.00%	
Road Side plantation	0.00%	Unit of measurement is linear length in km. Cost per km shall be determined on pro rata basis with respect to the total length of the service roads/slip roads. Payment shall be made for completed
Protection works	0.00%	Todas. Layment shall be made for completed

Service roads/slip road	0.00%	service roads/slip roads in a length of not less than 20 (twenty) percent of the total length of service roads/slip roads.
Toll Plaza	0.00%	Unit of measurement is each completed toll plaza. Payment of each toll plaza shall be made on pro rata basis with respect to the total of all toll plazas.
Road side drains & toe wall	0.6433%	Unit of measurement is linear length. Payment shall be made on pro rata basis on completion of a stage in a length of not less than 5 (five) percent of the total length.
Project facilities	0.0129%	
Safety & traffic mgmt. During construction	0.00%	
Traffic Sign	0.0510%	
Pavement marking	0.1403%	
Crash barrier/ W matel crash barrier	0.5852%	Payment shall be made for completed items.
Boundary stone, km stone,5th km stone, &hectometre stones	0.0043%	
Traffic blinker LED Delineator, stud, reflective payment marker,	0.0482%	

STAGE OF PAYMENT	PERCENTAGE WEIGHTAGE vis a vis overall Project	PAYMENT PROCEDURE
tree reflector	•	
Traffic Island	0.00%	
Median Kerbs	0.00%	Unit of measurement is linear length. Payment shall be made on pro rata basis on completion of a stage in a length of not less than 10 (ten) percent of the total length.
Bus Bays & Bus shelter	0.1233%	Payment shall be made for completed items.
Road side plantation & medium Plantation	0.00%	Unit of measurement is linear length. Payment
Protection works of guide bund including construction of flexible aprons, boulder pitching and filter media on slopes	0.00%	shall be made on pro rata basis on completion of a stage in a length of not less than 10 (ten) percent of the total length.
Minor junction	0.2239%	Payment shall be made for completed items.
Median filling shrub plantation & maintenance for 1 year	0.00%	
Overhead signboard	0.0609%	
painting on kerb	0.00%	
Footpath &Separater	0.00%	
Vetiver Plantation	0.00%	
Interlocking concrete block payment	0.00%	
CC kerb	0.00%	
Painting	0.00%	
Cable duct	0.00%	Unit of measurement is linear length. Payment
Solar stud & solar blinking LED	0.00%	shall be made on pro rata basis on completion of a
Rest area with development of site including One no Bus bay and Bus shelter, landscaping and tree plantation	0.00%	stage in a length of not less than 5 (five) percent of the total length.
For Plantation (Hydro seeding & plantation on hill slopes as slope protection measures)	0.9749%	
Traffic control devices and road safety works (Polymer rumble strips on hazardous locations specially valley side curves)	0.1955%	

STAGE OF PAYMENT	PERCENTAGE WEIGHTAGE vis a vis overall Project	PAYMENT PROCEDURE	
Road furniture	0.00%		
Roads side drains I/C Chute drain	0.00%		
Repair of protections works	0.00%		
Traffic diversion, Safety and traffic management during construction	0.00%		
Retaining wall	0.00%		
Miscellaneous items	0.00%		
Breast wall and RCC retaining wall	0.00%		
Site Clearance	0.00%		
M-20 kerb with channel	0.00%		
Prefabricated railing over kerb in median	0.00%		
Safety Barrier	0.00%		
(v) Project facilities			
(a) Truck lay-byes	0.00%	Payment shall be made for completed items.	
(b) others	0.00%	1 ayment shall be made for completed items.	
(vi) Repairs to bridges/structures			
Other items (Junctions)	0.00%		
Providing wearing coat	0.00%	Dayment shall be made for completed items	
Replacement of bearing joints	0.00%	Payment shall be made for completed items.	
Providing crash barriers	0.00%		
(vii) Protection works			
Breast wall	4.1901%	Unit of measurement is linear length. Payment shall be	
Retaining wall	4.6718%	made on pro rata basis on completion of a stage in a	
Gabion Wall	0.6391%	length of not less than 5 (five) percent of the total	
Parapet	0.8516%	length.	
Slope Protection at Land Slide locations.	0.7553%		

- 1 Procedure for payment forMaintenance
- 1.1 The cost for maintenance shall be as stated in Clause 14.1.1.
- 1.2 Payment for Maintenance shall be made in quarterly installments in accordance with the provisions of Clause 19.7.

## Schedule - I

(See Clause 10.2 (iv))

## **Drawings**

## 1. Drawings

In compliance of the obligations set forth in Clause 10.2 of this Agreement, the Contractor shall furnish to the Authority's Engineer, free of cost, all Drawings listed in Annex-I of this Schedule-I.

## 2. Additional Drawings

If the Authority's Engineer determines that for discharging its duties and functions under this Agreement, it requires any drawings other than those listed in Annex-I, it may by notice require the Contractor to prepare and furnish such drawings forthwith. Upon receiving a requisition to this effect, the Contractor shall promptly prepare and furnish such drawings to the Authority's Engineer, as if such drawings formed part of Annex-I of this Schedule-I.

# Annex - I

(Schedule - I)

## **List of Drawings**

[**Note**: The Authority shall describe in this Annex-I, all the Drawings that the Contractor is required to furnish under Clause 10.2.]

#### Schedule - J

(See Clause 10.3 (ii))

# **Project Completion Schedule**

#### 1. Project Completion Schedule

During Construction period, the Contractor shall comply with the requirements set forth in this Schedule-J for each of the Project Milestones and the **Scheduled Completion Date**. Within 15 (fifteen) days of the date of each Project Milestone, the Contractor shall notify the Authority of such compliance along with necessary particulars thereof.

## 2. Project Milestone-I

- (i) Project Milestone-I shall occur on the date falling on the 256th day from the Appointed Date (the "**Project Milestone-I**").
- (ii) Prior to the occurrence of Project Milestone-I, the Contractor shall have commenced construction of the Project Highway and submitted to the Authority duly and validly prepared Stage Payment Statements for an amount not less than 10% (ten per cent) of the Contract Price.

## 3. Project Milestone-II

- (i) Project Milestone-II shall occur on the date falling on the 439<sup>th</sup> day from the Appointed Date (the "**Project Milestone-II**").
- (ii) Prior to the occurrence of Project Milestone-II, the Contractor shall have continued with construction of the Project Highway and submitted to the Authority duly and validly prepared Stage Payment Statements for an amount not less than 35% (thirty five per cent) of the Contract Price and should have started construction of all bridges

## 4. Project Milestone-III

- (i) Project Milestone-III shall occur on the date falling on the 623<sup>th</sup> day from the Appointed Date (the "**Project Milestone-III**").
- (ii) Prior to the occurrence of Project Milestone-III, the Contractor shall have continued with construction of the Project Highway and submitted to the Authority duly and validly prepared Stage Payment Statements for an amount not less than 70% (seventy per cent) of the Contract Price and should have started construction of all project facilities.

## 5. Scheduled Completion Date

Construction of Balance work of Two – Lane with hard shoulders of Existing Hayuliang – Hawai Road (NH-113) from design km 51.825 to km 63.131 (Existing km 45.050 of Hayuliang – Hawai Road to Hawai town)(11.306 km) on EPC basis in the state of Arunachal Pradesh Package of SARDP –NE (Green Field Alignment)

Dec 2020

- (i) The Scheduled Completion Date shall occur on the 730<sup>th</sup> [Scheduled Construction Period] day from the Appointed Date.
- (ii) On or before the Scheduled Completion Date, the Contractor shall have completed construction in accordance with this Agreement.

#### 6. Extension of time

Upon extension of any or all of the aforesaid Project Milestones or the Scheduled Completion Date, as the case may be, under and in accordance with the provisions of this Agreement, the Project Completion Schedule shall be deemed to have been amended accordingly.

#### Schedule - K

(See Clause 12.1 (ii))

## **Tests on Completion**

#### 1. Schedule for Tests

- (i) The Contractor shall, no later than 30 (thirty) days prior to the likely completion of construction, notify the Authority's Engineer and the Authority of its intent to subject the Project Highway to Tests, and no later than 10(ten) days prior to the actual date of Tests, furnish to the Authority's Engineer and the Authority detailed inventory and particulars of all works and equipment forming part of Works.
- (ii) The Contractor shall notify the Authority's Engineer of its readiness to subject the Project Highway to Tests at any time after 10 (ten) days from the date of such notice, and upon receipt of such notice, the Authority's Engineer shall, in consultation with the Contractor, determine the date and time for each Test and notify the same to the Authority who may designate its representative to witness the Tests. The Authority's Engineer shall thereupon conduct the Tests itself or cause any of the Tests to be conducted in accordance with Article 12 and this Schedule-K.

#### 2. Tests

- (i) Visual and physical test: The Authority's Engineer shall conduct a visual and physical check of construction to determine that all works and equipment forming part thereof conform to the provisions of this Agreement. The physical tests shall include [\*\*\*].
- (ii) Riding quality test: Riding quality of each lane of the carriageway shall be checked with the help of a Network Survey Vehicle (NSV) fitted with latest equipments and the maximum permissible roughness for purposes of this Test shall be [2,000 (two thousand)] mm for each kilometre.
- (iii) Tests for bridges: All major and minor bridges shall be subjected to the rebound hammer and ultrasonic pulse velocity tests, to be conducted in accordance with the procedure described in Special Report No. 17: 1996 of the IRC Highway Research Board on Nondestructive Testing Techniques, at two spots in every span, to be chosen at random by the Authority's Engineer. Bridges with a span of 15 (fifteen) metres or more shall also be subjected to load testing.
- (iv) Other tests: The Authority's Engineer may require the Contractor to carry out or cause to be carried additional tests, in accordance with Good Industry Practice, for determining the compliance of the Project Highway with Specifications and Standards, except tests as specified in clause 5,but shall include measuring the reflectivity of road markings and road signs; and measuring the illumination level (lux) of lighting using requisite testing equipment.

- (v) Environmental audit: The Authority's Engineer shall carry out a check to determine conformity of the Project Highway with the environmental requirements set forth in Applicable Laws and Applicable Permits.
- (vi) Safety Audit: The Authority's Engineer shall carry out, or cause to be carried out, a safety audit to determine conformity of the Project Highway with the safety requirements and Good Industry Practice.

#### 3. Agency for conducting Tests

All Tests set forth in this Schedule-K shall be conducted by the Authority's Engineer or such other agency or person as it may specify in consultation with the Authority.

#### 4. Completion Certificate

Upon successful completion of Tests, the Authority's Engineer shall issue the Completion Certificate in accordance with the provisions of Article 12.

**5.** The Authority Engineer will carry out tests with following equipment at his own cost in the presence of contractor's representative.

Sr. No.	Key metrics of Asset	Equipment to be used	Frequency of condition survey
1	Surface defects of pavement	Network Survey Vehicle (NSV)	At least twice a year (As per survey months defined for the state basis rainy season)
2	Roughness of pavement	Network Survey Vehicle (NSV)	At least twice a year (As per survey months defined for the state basis rainy season)
3	Strength of pavement	Falling Weight Deflectometer (FWD)	At least once a year
4	Bridges	Mobile Bridge Inspection Unit (MBU)	At least twice a year (As per survey months defined for the state basis rainy season)
5	Road signs	Retro-reflectometer	At least twice a year (As per survey months defined for the state basis rainy season)

The first testing with the help of NSV shall be conducted at the time of issue of Completion Certificate.

# Schedule - L

(See Clause 12.2)

# **Completion Certificate**

1	I,
2	It is certified that, in terms of the aforesaid Agreement, all works forming part of Project Highway have been completed, and the Project Highway is hereby declared fit for entry into operation on this the day of 20, Scheduled Completed Date for which was the day of
	SIGNED, SEALED AND DELIVERED  For and on behalf of the Authority's Engineer by:
	(Signature) (Name
	) (Designation)
	(Address)

# Schedule - M

(See Clauses 14.6, 15.2 and 19.7)

# **Payment Reduction for Non-Compliance**

# 1. Payment reduction for non-compliance with the Maintenance Requirements

- (i) Monthly lump sum payments for maintenance shall be reduced in the case of non-compliance with the Maintenance Requirements set forth in Schedule-E.
- (ii) Any deduction made on account of non-compliance with the Maintenance Requirements shall not be paid even after compliance subsequently. The deductions shall continue to be made every month until compliance is done.
- (iii) The Authority's Engineer shall calculate the amount of payment reduction on the basis of weightage in percentage assigned to non-conforming items as given in Paragraph 2.

# 2. Percentage reductions in lump sum payments on monthly basis

(i) The following percentages shall govern the payment reduction:

S. No.	Item/Defect/Deficiency	Percentage
(a)	Carriageway/Pavement	
(i)	Potholes, cracks, other surface defects	15%
(ii)	Repairs of Edges, Rutting	5%
(b)	Road, Embankment, Cuttings, Shoulders	
(i)	Edge drop, inadequate cross fall, undulations, settlement, potholes, ponding, obstructions	10%
(ii)	Deficient slopes, raincuts, disturbed pitching, vegetation growth, pruning of trees	5%
(c)	Bridges and Culverts	
(i)	Desilting, cleaning. vegetation growth, damaged pitching, flooring, parapets, wearing course, footpaths, any damage to foundations	20%
(ii)	Any Defects in superstructures, bearings and sub-structures	10%

S. No.	Item/Defect/Deficiency	Percentage
(iii)	Painting, repairs/replacement kerbs, railings, parapets, guideposts/crash barriers	5%
(d)	Roadside Drains	
(i)	Cleaning and repair of drains	5%
(e)	Road Furniture	
(i)	Cleaning, painting, replacement of road signs, delineators, road markings, 200 m/km/5th km stones	5%
<b>(f)</b>	Miscellaneous Items	
(i)	Removal of dead animals, broken down/accidented vehicles, fallen trees, road blockades or malfunctioning of mobile crane	10%
(ii)	Any other Defects in accordance with paragraph 1.	5%
(g)	<b>Defects in Other Project Facilities</b>	5%

(ii) The amount to be deducted from monthly lump-sum payment for non- compliance of particular item shall be calculated as under:

$$R = \frac{P}{100} \times (M1 \text{ or } M2) \times \frac{L1}{L}$$

Where,

P= Percentage of particular item/Defect/deficiency for deduction

M1= Monthly lump-sum payment in accordance para 1.2 above of this Schedule M2= Monthly lump-sum payment in accordance para 1.2 above of this Schedule L1= Non-complying length L = Total length of the road,

R= Reduction (the amount to be deducted for non-compliance for a particular item/Defect/deficiency

The total amount of reduction shall be arrived at by summation of reductions for such items/Defects/deficiency or non-compliance.

For any Defect in a part of one kilometer, the non-conforming length shall be taken as one kilometer.

# Schedule - N

(See Clause 18.1 (i))

# **Selection of Authority's Engineer**

## 1. Selection of Authority's Engineer

- (i) The provisions of the Model Request for Proposal for Selection of Technical Consultants, issued by the Ministry of Finance in May 2009, or any substitute thereof shall apply for selection of an experienced firm to discharge the functions and duties of an Authority's Engineer.
- (ii) In the event of termination of the Technical Consultants appointed in accordance with the provisions of Paragraph 1.1, the Authority shall appoint another firm of Technical Consultants forthwith and may engage a government-owned entity in accordance with the provisions of Paragraph 3 of this Schedule-N.

# 2. Terms of Reference

The Terms of Reference for the Authority's Engineer (the "**TOR**") shall substantially conform with Annex 1 to this Schedule N.

# 3. Appointment of Government entity as Authority's Engineer

Notwithstanding anything to the contrary contained in this Schedule, the Authority may in its discretion appoint a government-owned entity as the Authority's Engineer; provided that such entity shall be a body corporate having as one of its primary functions the provision of consulting, advisory and supervisory services for engineering projects; provided further that a government-owned entity which is owned or controlled by the Authority shall not be eligible for appointment as Authority's Engineer.

#### Annex - I

(Schedule - N)

# Terms of Reference for Authority's Engineer

## 1. Scope

- - # In case the bid of Authority's Engineer's invited simultaneously with the bid of EPC project, then the status of bidding of EPC project only to be indicated
- (ii) The TOR shall apply to construction and maintenance of the Project Highway.

# 2. Definitions and interpretation

- (i) The words and expressions beginning with or in capital letters and not defined herein but defined in the Agreement shall have, unless repugnant to the context, the meaning respectively assigned to them in the Agreement.
- (ii) References to Articles, Clauses and Schedules in this TOR shall, except where the context otherwise requires, be deemed to be references to the Articles, Clauses and Schedules of the Agreement, and references to Paragraphs shall be deemed to be references to Paragraphs of this TOR.
- (iii) The rules of interpretation stated in Article 1 of the Agreement shall apply, mutatis mutandis, to this TOR.

#### 3. General

- (i) The Authority's Engineer shall discharge its duties in a fair, impartial and efficient manner, consistent with the highest standards of professional integrity and Good Industry Practice.
- (ii) The Authority's Engineer shall perform the duties and exercise the authority in accordance with the provisions of this Agreement, but subject to obtaining prior written approval of the Authority before determining:
  - (a) any Time Extension;
  - (b) any additional cost to be paid by the Authority to the Contractor;
  - (c) the Termination Payment; or

- (d) issuance of Completion Certificate or
- (e) any other matter which is not specified in (a), (b), (c) or (d) above and which creates a financial liability on either Party.
- (iii) The Authority's Engineer shall submit regular periodic reports, at least once every month, to the Authority in respect of its duties and functions under this Agreement. Such reports shall be submitted by the Authority's Engineer within 10 (ten) days of the beginning of every month.
- (iv) The Authority's Engineer shall inform the Contractor of any delegation of its duties and responsibilities to its suitably qualified and experienced personnel; provided, however, that it shall not delegate the authority to refer any matter for the Authority's prior approval in accordance with the provisions of Clause 18.2.
- (v) The Authority's Engineer shall aid and advise the Authority on any proposal for Change of Scope under Article 13.
- (vi) In the event of any disagreement between the Parties regarding the meaning, scope and nature of Good Industry Practice, as set forth in any provision of the Agreement, the Authority's Engineer shall specify such meaning, scope and nature by issuing a reasoned written statement relying on good industry practice and authentic literature.

#### 4. Construction Period

- During the Construction Period, the Authority's Engineer shall review and approve the Drawings furnished by the Contractor along with supporting data, including the geotechnical and hydrological investigations, characteristics of materials from borrow areas and quarry sites, topographical surveys, and the recommendations of the Safety Consultant in accordance with the provisions of Clause 10.1 (vi). The Authority's Engineer shall complete such review and approval and send its observations to the Authority and the Contractor within 15 (fifteen) days of receipt of such Drawings; provided, however that in case of a Major Bridge or Structure, the aforesaid period of 15 (fifteen) days may be extended upto 30 (thirty) days. In particular, such comments shall specify the conformity or otherwise of such Drawings with the Scope of the Project and Specifications and Standards.
- (ii) The Authority's Engineer shall review and approve any revised Drawings sent to it by the Contractor and furnish its comments within 10 (ten) days of receiving such Drawings.
- (iii) The Authority's Engineer shall review and approve the Quality Assurance Plan submitted by the Contractor and shall convey its comments to the Contractor within a period of 21 (twenty one) days stating the modifications, if any, required thereto.

- (iv) The Authority's Engineer shall complete the review and approve of the methodology proposed to be adopted by the Contractor for executing the Works, and convey its comments to the Contractor within a period of 10 (ten) days from the date of receipt of the proposed methodology from the Contractor.
- (v) The Authority's Engineer shall grant written approval to the Contractor, where necessary, for interruption and diversion of the flow of traffic in the existing lane(s) of the Project Highway for purposes of maintenance during the Construction Period in accordance with the provisions of Clause 10.4.
- (vi) The Authority's Engineer shall review the monthly progress report furnished by the Contractor and send its comments thereon to the Authority and the Contractor within 7 (seven) days of receipt of such report.
- (vii) The Authority's Engineer shall inspect the Construction Works and the Project Highway and shall submit a monthly Inspection Report bringing out the results of inspections and the remedial action taken by the Contractor in respect of Defects or deficiencies. In particular, the Authority's Engineer shall include in its Inspection Report, the compliance of the recommendations made by the Safety Consultant.
- (viii) The Authority's Engineer shall conduct the pre-construction review of manufacturer's test reports and standard samples of manufactured Materials, and such other Materials as the Authority's Engineer may require.
- (ix) For determining that the Works conform to Specifications and Standards, the Authority's Engineer shall require the Contractor to carry out, or cause to be carried out, tests at such time and frequency and in such manner as specified in the Agreement and in accordance with Good Industry Practice for quality assurance. For purposes of this Paragraph 4 (ix), the tests specified in the IRC Special Publication-11 (Handbook of Quality Control for Construction of Roads and Runways) and the Specifications for Road and Bridge Works issued by MORTH (the "Quality Control Manuals") or any modification/substitution thereof shall be deemed to be tests conforming to Good Industry Practice for quality assurance.
- (x) The Authority's Engineer shall test check at least 50 (fifty) percent of the quantity or number of tests prescribed for each category or type of test for quality control by the Contractor.
- (xi) The timing of tests referred to in Paragraph 4 (ix), and the criteria for acceptance/ rejection of their results shall be determined by the Authority's Engineer in accordance with the Quality Control Manuals. The tests shall be undertaken on a random sample basis and shall be in addition to, and independent of, the tests that may be carried out by the Contractor for its own quality assurance in accordance with Good Industry Practice.
- (xii) In the event that results of any tests conducted under Clause 11.10 establish any Defects or deficiencies in the Works, the Authority's Engineer shall require the Contractor to carry out remedial measures.

- (xiii) The Authority's Engineer may instruct the Contractor to execute any work which is urgently required for the safety of the Project Highway, whether because of an accident, unforeseeable event or otherwise; provided that in case of any work required on account of a Force Majeure Event, the provisions of Clause 21.6 shall apply.
- (xiv) In the event that the Contractor fails to achieve any of the Project Milestones, the Authority's Engineer shall undertake a review of the progress of construction and identify potential delays, if any. If the Authority's Engineer shall determine that completion of the Project Highway is not feasible within the time specified in the Agreement, it shall require the Contractor to indicate within 15 (fifteen) days the steps proposed to be taken to expedite progress, and the period within which the Project Completion Date shall be achieved. Upon receipt of a report from the Contractor, the Authority's Engineer shall review the same and send its comments to the Authority and the Contractor forthwith.
- (xv) The Authority's Engineer shall obtain from the Contractor a copy of all the Contractor's quality control records and documents before the Completion Certificate is issued pursuant to Clause 12.2.
- (xvi) Authority's Engineer may recommend to the Authority suspension of the whole or part of the Works if the work threatens the safety of the Users and pedestrians. After the Contractor has carried out remedial measure, the Authority's Engineer shall inspect such remedial measures forthwith and make a report to the Authority recommending whether or not the suspension hereunder may be revoked.
- (xvii) In the event that the Contractor carries out any remedial measures to secure the safety of suspended works and Users, and requires the Authority's Engineer to inspect such works, the Authority's Engineer shall inspect the suspended works within 3 (three) days of receiving such notice, and make a report to the Authority forthwith, recommending whether or not such suspension may be revoked by the Authority.
- (xviii) The Authority's Engineer shall carry out, or cause to be carried out, all the Tests specified in Schedule-K and issue a Completion Certificate, as the case may be. For carrying out its functions under this Paragraph 4 (xviii) and all matters incidental thereto, the Authority's Engineer shall act under and in accordance with the provisions of Article 12 and Schedule-K.

#### 5. Maintenance Period

- (i) The Authority's Engineer shall aid and advise the Contractor in the preparation of its monthly Maintenance Programme and for this purpose carry out a joint monthly inspection with the Contractor.
- (ii) The Authority's Engineer shall undertake regular inspections, at least once every month, to evaluate compliance with the Maintenance Requirements and submit a Maintenance Inspection Report to the Authority and the Contractor.

- (iii) The Authority's Engineer shall specify the tests, if any, that the Contractor shall carry out, or cause to be carried out, for the purpose of determining that the Project Highway is in conformity with the Maintenance Requirements. It shall monitor and review the results of such tests and the remedial measures, if any, taken by the Contractor in this behalf.
- (iv) In respect of any defect or deficiency referred to in Paragraph 3 of Schedule- E, the Authority's Engineer shall, in conformity with Good Industry Practice, specify the permissible limit of deviation or deterioration with reference to the Specifications and Standards and shall also specify the time limit for repair or rectification of any deviation or deterioration beyond the permissible limit.
- (v) The Authority's Engineer shall examine the request of the Contractor for closure of any lane(s) of the Project Highway for undertaking maintenance/repair thereof, and shall grant permission with such modifications, as it may deem necessary, within 5 (five) days of receiving a request from the Contractor. Upon expiry of the permitted period of closure, the Authority's Engineer shall monitor the reopening of such lane(s), and in case of delay, determine the Damages payable by the Contractor to the Authority under Clause 14.5.

# 6. Determination of costs and time

- (i) The Authority's Engineer shall determine the costs, and/or their reasonableness, that are required to be determined by it under the Agreement.
- (ii) The Authority's Engineer shall determine the period of Time Extension that is required to be determined by it under the Agreement.
- (iii) The Authority's Engineer shall consult each Party in every case of determination in accordance with the provisions of Clause 18.5.

#### 7. Payments

- (i) The Authority's Engineer shall withhold payments for the affected works for which the Contractor fails to revise and resubmit the Drawings to the Authority's Engineer in accordance with the provisions of Clause 10.2 (iv) (d).
- (ii) Authority's Engineer shall -
  - (a) within 10 (ten) days of receipt of the Stage Payment Statement from the Contractor pursuant to Clause 19.4, determine the amount due to the Contractor and recommend the release of 90 (ninety) percent of the amount so determined as part payment, pending issue of the Interim Payment Certificate; and
  - (b) within 15 (fifteen) days of the receipt of the Stage Payment Statement referred to in Clause 19.4, deliver to the Authority and the Contractor an Interim Payment Certificate certifying the amount due and payable to the

Contractor, after adjustments in accordance with the provisions of Clause 19.10.

- (iii) The Authority's Engineer shall, within 15 (fifteen) days of receipt of the Monthly Maintenance Statement from the Contractor pursuant to Clause 19.6, verify the Contractor's monthly statement and certify the amount to be paid to the Contractor in accordance with the provisions of the Agreement.
- (iv) The Authority's Engineer shall certify final payment within 30 (thirty) days of the receipt of the final payment statement of Maintenance in accordance with the provisions of Clause 19.16.

#### 8. Other duties and functions

The Authority's Engineer shall perform all other duties and functions as specified in the Agreement.

#### 9. Miscellaneous

- (i) A copy of all communications, comments, instructions, Drawings or Documents sent by the Authority's Engineer to the Contractor pursuant to this TOR, and a copy of all the test results with comments of the Authority's Engineer thereon, shall be furnished by the Authority's Engineer to the Authority forthwith.
- (ii) The Authority's Engineer shall retain at least one copy each of all Drawings and Documents received by it, including 'as-built' Drawings, and keep them in its safe custody.
- (iii) Within 90 (ninety) days of the Project Completion Date, the Authority's Engineer shall obtain a complete set of as-built Drawings, in 2 (two) hard copies and in micro film form or in such other medium as may be acceptable to the Authority, reflecting the Project Highway as actually designed, engineered and constructed, including an as-built survey illustrating the layout of the Project Highway and setback lines, if any, of the buildings and structures forming part of Project Facilities; and shall hand them over to the Authority against receipt thereof.
- (iv) The Authority's Engineer, if called upon by the Authority or the Contractor or both, shall mediate and assist the Parties in arriving at an amicable settlement of any Dispute between the Parties.
- (v) The Authority's Engineer shall inform the Authority and the Contractor of any event of Contractor's Default within one week of its occurrence.

# Schedule - O

(See Clauses 19.4 (i), 19.6 (i), and 19.8 (i))

# **Forms of Payment Statements**

## 1. Stage Payment Statement for Works

The Stage Payment Statement for Works shall state:

- (a) the estimated amount for the Works executed in accordance with Clause 19.3 (i) subsequent to the last claim;
- (b) amounts reflecting adjustments in price for the aforesaid claim;
- (c) the estimated amount of each Change of Scope Order executed subsequent to the last claim;
- (d) amounts reflecting adjustment in price, if any, for (c) above in accordance with the provisions of Clause 13.2 (iii) (a);
- (e) total of (a), (b), (c) and (d) above;
- (f) Deductions:
  - i. Any amount to be deducted in accordance with the provisions of the Agreement except taxes;
  - ii. Any amount towards deduction of taxes; and
  - iii. Total of (i) and (ii) above.
- (g) Net claim: (e) (f) (iii);
- (h) The amounts received by the Contractor upto the last claim:
  - i. For the Works executed (excluding Change of Scope orders);
  - ii. For Change of Scope Orders, and
  - iii. Taxes deducted

# 2. Monthly Maintenance Payment Statement

The monthly Statement for Maintenance Payment shall state:

- (a) the monthly payment admissible in accordance with the provisions of the Agreement;
- (b) the deductions for maintenance work not done;
- (c) net payment for maintenance due, (a) minus (b);
- (d) amounts reflecting adjustments in price under Clause 19.12; and
- (e) amount towards deduction of taxes

# 3. Contractor's claim for Damages

**Note**: The Contractor shall submit its claims in a form acceptable to the Authority.

#### Schedule - P

(See Clause 20.1)

#### **Insurance**

# 1. Insurance during Construction Period

- (i) The Contractor shall effect and maintain at its own cost, from the Appointed Date till the date of issue of the Completion Certificate, the following insurances for any loss or damage occurring on account of Non Political Event of Force Majeure, malicious act, accidental damage, explosion, fire and terrorism:
  - (a) insurance of Works, Plant and Materials and an additional sum of [15 (fifteen)] per cent of such replacement cost to cover any additional costs of and incidental to the rectification of loss or damage including professional fees and the cost of demolishing and removing any part of the Works and of removing debris of whatsoever nature; and
  - (b) insurance for the Contractor's equipment and Documents brought onto the Site by the Contractor, for a sum sufficient to provide for their replacement at the Site.
- (ii) The insurance under sub para (a) and (b) of paragraph 1(i) above shall cover the Authority and the Contractor against all loss or damage from any cause arising under paragraph 1.1 other than risks which are not insurable at commercial terms.

# 2. Insurance for Contractor's Defects Liability

The Contractor shall effect and maintain insurance cover of not less than 15% of the Contract Price for the Works from the date of issue of the Completion Certificate until the end of the Defects Liability Period for any loss or damage for which the Contractor is liable and which arises from a cause occurring prior to the issue of the Completion Certificate. The Contractor shall also maintain other insurances for maximum sums as may be required under the Applicable Laws and in accordance with Good Industry Practice.

# 3. Insurance against injury to persons and damage to property

(i) The Contractor shall insure against its liability for any loss, damage, death or bodily injury, or damage to any property (except things insured under Paragraphs 1 and 2 of this Schedule or to any person (except persons insured under Clause 20.9), which may arise out of the Contractor's performance of this Agreement. This insurance shall be for a limit per occurrence of not less than the amount stated below with no limit on the number of occurrences.

The insurance cover shall be not less than: Rs. [\*\*\*\*\*]

- (ii) The insurance shall be extended to cover liability for all loss and damage to the Authority's property arising out of the Contractor's performance of this Agreement excluding:
  - (a) the Authority's right to have the construction works executed on, over, under, in or through any land, and to occupy this land for the Works; and
  - (b) damage which is an unavoidable result of the Contractor's obligations to execute the Works.

# 4. Insurance to be in joint names

The insurance under paragraphs 1 to 3 above shall be in the joint names of the Contractor and the Authority.

# **Schedule-Q**

(See Clause 14.10)

# **Tests on Completion of Maintenance Period**

# 1. Riding Quality test:

Riding quality test: Riding quality of each lane of the carriageway shall be checked with the help of a calibrated bump integrator and the maximum permissible roughness for purposes of this Test shall be [2,200 (two thousand and two hundred only)] mm for each kilometre.

# 2. Visual and physical test:

The Authority's Engineer shall conduct a visual and physical check of construction to determine that all works and equipment forming part thereof conform to the provisions of this Agreement. The physical tests shall include measurement of cracking, rutting, stripping and potholes and shall be as per the requirement of maintenance mentioned in Schedule-E.

# Schedule-R

(See Clause 14.10)

Taking Over Certificate			
I,	nent dated (the "Agreement")  Two – Lane with hard shoulders of H-113) from design km 51.825 to km g – Hawai Road to Hawai town)(11.306		
km) on EPC basis in the state of Aruna	_		
	(Name of Contractor), hereby certify		
that the Tests on completion of Maintenance Period in accordance with successfully undertaken to determine com provisions of the Agreement and I hereby the Project highway from the Contractor o	repliance of the Project Highway with the certify that the Authority has taken over		
	SIGNED, SEALED AND DELIVERED		
` `	gnature) ume and designation of Authority's		

Representative)

(Address)