

Technical Schedule



NATIONAL HIGHWAYS & INFRASTRUCTURE DEVELOPMENT CORPORATION LTD. (NHIDCL)

NOVEMBER2020

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

TABLE OF CONTENTS

| | |
|---|-----------|
| SCHEDULES | 5 |
| Schedule-A | 6 |
| Site of the Project..... | 6 |
| 1. The Site | 6 |
| Annex – I | 7 |
| Site | 7 |
| Nil | 12 |
| Annex – II..... | 13 |
| Dates for providing Right of Way of Construction Zone | 13 |
| Annex - III | 14 |
| Alignment Plans..... | 14 |
| Annex – IV..... | 15 |
| Environment Clearances..... | 15 |
| Schedule - B | 16 |
| Development of the Project Highway | 16 |
| 1. Development of the Project Highway | 16 |
| 2. Rehabilitation and augmentation | 16 |
| 3. Specifications and Standards..... | 16 |
| Annex – I | 17 |
| Description of the Project..... | 17 |
| Schedule - C..... | 41 |
| Project Facilities | 41 |
| 1. ProjectFacilities..... | 41 |
| 2. Description of Project Facilities | 41 |
| Schedule - D | 42 |
| Specifications and Standards | 42 |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| | | |
|----|-----------------------|----|
| 1. | Construction | 42 |
| 2. | Design Standards..... | 42 |

| | |
|------------------------|-----------|
| Annex – I | 43 |
|------------------------|-----------|

| | |
|--|-----------|
| Specifications and Standards for Construction | 43 |
|--|-----------|

| | |
|---------------------------|-----------|
| ATTACHMENT-DI..... | 44 |
|---------------------------|-----------|

| | |
|--|-----------|
| TECHNICAL SPECIFICATIONS FOR ROAD & BRIDGE..... | 44 |
|--|-----------|

Schedule - E 67

| | |
|---------------------------------------|-----------|
| Maintenance Requirements | 67 |
|---------------------------------------|-----------|

| | | |
|----|---|----|
| 1. | MaintenanceRequirements | 67 |
| 2. | Repair/rectification of Defects anddeficiencies | 67 |
| 3. | Other Defects anddeficiencies..... | 67 |
| 4. | Extension of timelimit | 67 |
| 5. | Emergencyrepairs/restoration | 67 |
| 6. | Daily inspection by theContractor | 67 |
| 7. | Pre-monsoon inspection / Post-monsooninspection..... | 67 |
| 8. | Repairs on account of naturalcalamities | 68 |

Annex -I 69

| | |
|---|----|
| Repair/rectification of Defects and deficiencies..... | 69 |
|---|----|

| | |
|--|----|
| Table -1: Maintenance Criteria for Pavements:..... | 69 |
|--|----|

| | |
|---|----|
| Table -3: Maintenance Criteria for Safety Related Items and Other Furniture Items:..... | 76 |
|---|----|

Schedule - F 90

| | |
|--------------------------|----|
| Applicable Permits | 90 |
|--------------------------|----|

| | | |
|----|-------------------------|----|
| 1. | Applicable Permits..... | 90 |
|----|-------------------------|----|

| | |
|--------------------------|-----------|
| Schedule – G..... | 91 |
|--------------------------|-----------|

| | |
|---------------------|-----------|
| Annex-I..... | 91 |
|---------------------|-----------|

| | |
|-------------------------------------|-----------|
| Form of Bank Guarantee | 91 |
|-------------------------------------|-----------|

| | |
|--|-----------|
| Form for Guarantee for Advance Payment..... | 93 |
|--|-----------|

Schedule - H 98

| | |
|---------------------------------------|-------------------------------------|
| Contract Price Weightages..... | Error! Bookmark not defined. |
|---------------------------------------|-------------------------------------|

| | |
|--------------------------|------------|
| Schedule - I..... | 105 |
|--------------------------|------------|

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| | |
|---|------------|
| Drawings..... | 105 |
| 1. Drawings | 105 |
| 2. AdditionalDrawings | 105 |
| Annex – I | 106 |
| List of Drawings..... | 106 |
| Schedule - J..... | 107 |
| Project Completion Schedule | 107 |
| 1. Project CompletionSchedule..... | 107 |
| 2. ProjectMilestone-I..... | 107 |
| 3. ProjectMilestone-II..... | 107 |
| 4. ProjectMilestone-III | 107 |
| 5. Scheduled CompletionDate | 107 |
| 6. Extension oftime..... | 107 |
| Schedule - K | 108 |
| Tests on Completion..... | 108 |
| 1. Schedule forTests | 108 |
| 2. Tests | 108 |
| 3. Agency for conductingTests..... | 108 |
| 4. CompletionCertificate..... | 109 |
| Schedule - L..... | 110 |
| Completion Certificate..... | 110 |
| Schedule - M..... | 111 |
| Payment Reduction for Non-Compliance..... | 111 |
| 1. Payment reduction for non-compliance with the Maintenance Requirements | 111 |
| 2. Percentage reductions in lump sum payments on monthlybasis | 111 |
| Schedule - N | 113 |
| Selection of Authority’s Engineer | 113 |
| 1. Selection of Authority’sEngineer | 113 |
| 2. Terms ofReference..... | 113 |
| 3. Appointment of Government entity as Authority’sEngineer | 113 |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode.

(Pkg-VI).”

Terms of Reference for Authority’s Engineer 114

Schedule - O 119

Forms of Payment Statements 119

1. Stage Payment Statement forWorks..... 119
2. Monthly Maintenance PaymentStatement..... 119
3. Contractor’s claim forDamages 119

Schedule - P 120

Insurance 120

1. Insurance during ConstructionPeriod 120
2. Insurance for Contractor's DefectsLiability 120
3. Insurance against injury to persons and damage toproperty..... 120
4. Insurance to be in jointnames..... 120

Schedule-Q 121

Tests on Completion of Maintenance Period 121

1. Riding Qualitytest..... 121
2. Visual and physicaltest..... 121

Schedule-R 122

Taking Over Certificate 122

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

SCHEDULES

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

Schedule-A

(See Clauses 2.1 and 8.1)

Site of the Project

1. The Site

- (i) Site of the Two-Lane Project Highway shall include the land, buildings, structures and road works as described in Annex-I of this Schedule-A.
- (ii) The dates of handing over the Right of Way to the Contractor are specified in **Annex-II** of this Schedule-A.
- (iii) An inventory of the Site including the land, buildings, structures, road works, trees and any other immovable property on, or attached to, the Site shall be prepared jointly by the Authority Representative and the Contractor, and such inventory shall form part of the memorandum referred to in Clause 8.2 (i) of this Agreement.
- (iv) The alignment plans of the Project Highway are specified in Annex-III. The proposed profile of the Project Highways shall be followed by the contractor with minimum FRL as indicated in the alignment plan. The Contractor, however, improve/upgrade the Road Profile as indicated in Annex-III based on site/design requirement.
- (v) The status of the environment clearances obtained or awaited is given in Annex-IV.

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

Annex - I
(Schedule-A)

Site

1. Site

The Site of the Two-Lane Project Highway comprises the section of National Highway 244 commencing from km 235.070 to km 236.107 i.e. the Vailoo - Donipawa section in the UT of Jammu & Kashmir. The land, carriageway and structures comprising the Site are described below.

2. Land

The Site of the Project Highway comprises the land (sum of land already in possession and land to be possessed) as described below:

| Sr.No. | Design Chainage | | Right of Way (m) | Remarks |
|--------|-----------------|---------|------------------|---------|
| | From | To | | |
| 1 | 148+589 | 155+600 | 27 | |
| 2 | 155+600 | 157+800 | 28 | |
| 3 | 157+800 | 159+200 | 29 | |
| 4 | 159+200 | 160+000 | 28 | |
| 5 | 160+000 | 160+400 | 25 | |
| 6 | 160+400 | 161+200 | 27 | |
| 7 | 161+200 | 166+800 | 26 | |
| 8 | 166+800 | 167+600 | 28 | |
| 9 | 167+600 | 169+800 | 26 | |
| 10 | 169+800 | 170+600 | 28 | |
| 11 | 170+600 | 170+750 | 22 | Masjid |
| 12 | 170+750 | 171+600 | 27 | |
| 13 | 171+600 | 173+200 | 28 | |
| 14 | 173+200 | 173+600 | 27 | |
| 15 | 173+600 | 176+589 | 28 | |

3. Carriageway

The present carriageway of the Project Highway is 2-lane (7m)and 14 m in some urban area. The type of pavement is flexible.

4. Major Bridges

The Site includes the following Major Bridges:

| Sr. No. | Ex Chainage (km) | Type of Structure | | | No. of Spans with span length (m) | Width (m) |
|---------|------------------|-------------------|----------------------------|-----------------|-----------------------------------|-----------|
| | | Foundation | Sub-structure | Super-structure | | |
| 1 | 250+550 | Open | Wall Type Circular pier | PSC Box Girder | 3x25=115m | 12.5 |

5. Road over-bridges (ROB)/ Road under-bridges (RUB)

The Site includes the following ROB (road over railway line)/RUB (road under railway line):

| S. No. | Chainage (km) | Type of Structure | | No. of Spans with span length (m) | Width (m) | ROB/ RUB |
|--------|---------------|-------------------|----------------|-----------------------------------|-----------|----------|
| | | Foundation | Superstructure | | | |
| Nil | | | | | | |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI)."

6. Grade separators

The Site includes the following grade separators:

| S. No. | Chainage (km) | Type of Structure | | No. of Spans with span length (m) | Width (m) |
|--------|---------------|-------------------|----------------|-----------------------------------|-----------|
| | | Foundation | Superstructure | | |
| Nil | | | | | |

7. Minor bridges

The Site includes the following minor bridges:

| S. No. | Chainage (km) | Type of Structure | | | No. of Spans with span length (m) | Width (m) |
|--------|---------------|-------------------|--------------------|------------------|-----------------------------------|-----------|
| | | Foundation | Sub- structure | Super- structure | | |
| 1 | 237+525 | Open | Wall Type Abutment | Bailey type | 1 X 18.2 = 18.2 | 5.1 |
| 2 | 239+278 | Open | Wall Type Abutment | RCC Solid Slab | 1 X 7 = 7 | 12.2 |
| 3 | 244+575 | Open | Wall Type Abutment | RCC Solid Slab | 1 X 7.2 = 7.2 | 11.6 |
| 4 | 245+567 | Open | Wall Type Abutment | RCC Solid Slab | 1 X 7 = 7 | 12 |
| 5 | 246+200 | Open | Wall Type Abutment | RCC Solid Slab | 1 X 7 = 7 | 12 |
| 6 | 249+775 | Open | Wall Type Abutment | RCC Solid Slab | 1 X 7.3 = 7.3 | 12 |
| 7 | 250+255 | Open | Wall Type Abutment | RCC Solid Slab | 1 X 7.3 = 7.3 | 14 |
| 8 | 250+610 | Open | Wall Type Abutment | RCC Solid Slab | 1 X 6.6 = 6.6 | 12 |
| 9 | 250+875 | Open | Wall Type Abutment | RCC T Girder | 1 X 24.4 = 24.4 | 12 |
| 10 | 251+225 | Open | Wall Type Abutment | PSC Box Girder | 1 X 40.7 = 40.7 | 12.4 |
| 11 | 251+350 | Open | Wall Type Abutment | RCC Solid Slab | 1 X 6.7 = 6.7 | 12 |
| 12 | 251+400 | Open | Wall Type Abutment | RCC T Girder | 1 X 21.5 = 21.5 | 12 |
| 13 | 251+500 | Open | Wall Type Abutment | RCC T Girder | 1 X 22.2 = 22.2 | 12 |
| 14 | 256+950 | Open | Wall Type Abutment | RCC Solid Slab | 1 X 7 = 7 | 12.7 |

8. Railway level crossings

The Site includes the following railway level crossings:

| S. No. | Location (km) | Remarks |
|--------|---------------|---------|
| Nil | | |

9. Underpasses (vehicular, non-vehicular)

The Site includes the following underpasses:

| S. No. | Chainage (km) | Type of Structure | No. of Spans with span length (m) | Width (m) |
|--------|---------------|-------------------|-----------------------------------|-----------|
|--------|---------------|-------------------|-----------------------------------|-----------|

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI)."

Nil

10. Culverts

The Site has the following culverts:

| S. No. | Chainage (km) | Type of Culvert | Span /Opening with span length (m) | | Width (m) |
|--------|---------------|-----------------|------------------------------------|------------|-----------|
| | | | No | Clear Span | |
| 1 | 235+130 | Slab | 1 | 2 | 16.2 |
| 2 | 235+337 | Slab | 1 | 2 | 10.3 |
| 3 | 235+822 | Slab | 1 | 2 | 12 |
| 4 | 236+105 | Slab | 1 | 2 | 12 |
| 5 | 236+475 | Slab | 1 | 2 | 12 |
| 6 | 236+675 | Slab | 1 | 2 | 12 |
| 7 | 236+776 | Slab | 1 | 2 | 12 |
| 8 | 236+922 | Slab | 1 | 2 | 12 |
| 9 | 237+232 | Slab | 1 | 2 | 12 |
| 10 | 237+345 | Slab | 1 | 4.7 | 12 |
| 11 | 237+773 | Slab | 1 | 1.2 | 12 |
| 12 | 238+015 | Slab | 1 | 3 | 12 |
| 13 | 238+426 | Slab | 1 | 3 | 12 |
| 14 | 238+755 | Slab | 1 | 2 | 12 |
| 15 | 239+376 | Slab | 1 | 2 | 12 |
| 16 | 239+534 | Slab | 1 | 0.8 | 12 |
| 17 | 239+700 | Slab | 1 | 3 | 12 |
| 18 | 239+860 | Slab | 1 | 3.2 | 12 |
| 19 | 240+045 | Slab | 1 | 3 | 12 |
| 20 | 240+295 | Slab | 1 | 3 | 12 |
| 21 | 240+841 | Slab | 1 | 2 | 12 |
| 22 | 240+877 | Slab | 1 | 1 | 12 |
| 23 | 241+779 | Slab | 1 | 0.3 | 12 |
| 24 | 242+090 | Slab | 1 | 0.8 | 12 |
| 25 | 242+332 | Slab | 1 | 2 | 12 |
| 26 | 242+468 | Slab | 1 | 2 | 12 |
| 27 | 242+615 | Slab | 1 | 2 | 12 |
| 28 | 242+696 | Slab | 1 | 2 | 12 |
| 29 | 243+420 | Slab | 1 | 2 | 12 |
| 30 | 243+665 | Slab | 1 | 2 | 12 |
| 31 | 243+993 | Slab | 1 | 2 | 12 |
| 32 | 244+017 | Slab | 1 | 2 | 12 |
| 33 | 244+597 | Pipe | 1 | 1 | 12 |
| 34 | 244+868 | Slab | 1 | 2 | 12 |
| 35 | 245+143 | Slab | 1 | 2 | 12 |
| 36 | 246+217 | Slab | 1 | 2 | 12 |
| 37 | 246+505 | Slab | 1 | 2 | 12 |
| 38 | 246+776 | Slab | 1 | 3.4 | 12 |
| 39 | 246+925 | Slab | 1 | 3.4 | 12 |
| 40 | 247+177 | Slab | 1 | 2 | 12 |
| 41 | 247+373 | Slab | 1 | 2 | 12 |
| 42 | 247+709 | Slab | 1 | 2 | 12 |
| 43 | 247+859 | Slab | 1 | 1.4 | 12 |
| 44 | 248+005 | Slab | 1 | 1.8 | 12 |
| 45 | 248+080 | Slab | 1 | 2 | 12 |
| 46 | 248+268 | Slab | 1 | 3 | 12 |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| S. No. | Chainage (km) | Type of Culvert | Span /Opening with span length (m) | | Width (m) |
|--------|---------------|-----------------|------------------------------------|------------|-----------|
| | | | No | Clear Span | |
| 47 | 248+330 | Slab | 1 | 1.4 | 12 |
| 48 | 248+605 | Slab | 1 | 2 | 12 |
| 49 | 248+882 | Slab | 1 | 2 | 12 |
| 50 | 249+460 | Slab | 1 | 1 | 12 |
| 51 | 249+615 | Slab | 1 | 2 | 12 |
| 52 | 249+813 | Slab | 1 | 2 | 12 |
| 53 | 249+844 | Slab | 1 | 3 | 12 |
| 54 | 249+907 | Slab | 1 | 2 | 12 |
| 55 | 249+960 | Slab | 1 | 2 | 12 |
| 56 | 250+025 | Slab | 1 | 2 | 12 |
| 57 | 250+293 | Slab | 1 | 2 | 12 |
| 58 | 250+614 | Slab | 1 | 2 | 12 |
| 59 | 250+739 | Slab | 1 | 2 | 12 |
| 60 | 250+810 | Slab | 1 | 2 | 12 |
| 61 | 251+001 | Slab | 1 | 2.4 | 12 |
| 62 | 251+096 | Slab | 1 | 2 | 12 |
| 63 | 251+378 | Slab | 1 | 3 | 12 |
| 64 | 251+561 | Slab | 1 | 2 | 12 |
| 65 | 251+713 | Slab | 1 | 2 | 12 |
| 66 | 251+880 | Slab | 1 | 2 | 12 |
| 67 | 252+284 | Slab | 1 | 2 | 12 |
| 68 | 252+718 | Slab | 1 | 2 | 12 |
| 69 | 252+803 | Slab | 1 | 2 | 12 |
| 70 | 253+090 | Slab | 1 | 2 | 12 |
| 71 | 253+219 | Slab | 1 | 2 | 12 |
| 72 | 253+260 | Slab | 1 | 2 | 12 |
| 73 | 253+580 | Slab | 1 | 2 | 12 |
| 74 | 253+788 | Slab | 1 | 2 | 12 |
| 75 | 254+270 | Slab | 1 | 2 | 12 |
| 76 | 254+629 | Slab | 1 | 2 | 12 |
| 77 | 254+780 | Slab | 1 | 2 | 12 |
| 78 | 254+975 | Slab | 1 | 2 | 12 |
| 79 | 255+273 | Slab | 1 | 2 | 12 |
| 80 | 255+745 | Slab | 1 | 2 | 12 |
| 81 | 256+115 | Slab | 1 | 2 | 12 |
| 82 | 257+020 | Slab | 1 | 2 | 12 |
| 83 | 257+076 | Slab | 1 | 2 | 12 |
| 84 | 257+375 | Slab | 1 | 1 | 12 |
| 85 | 257+900 | Slab | 1 | 1.4 | 12 |
| 86 | 258+060 | Slab | 1 | 2 | 12 |
| 87 | 258+445 | Slab | 1 | 2 | 12 |
| 88 | 258+900 | Slab | 1 | 2 | 10 |
| 89 | 259+145 | Slab | 1 | 2 | 15.8 |
| 90 | 259+350 | Slab | 1 | 2 | 12 |
| 91 | 259+585 | Slab | 1 | 2 | 12 |
| 92 | 259+840 | Slab | 1 | 2 | 12 |
| 93 | 259+905 | Slab | 1 | 2 | 12 |
| 94 | 259+980 | Slab | 1 | 2 | 12 |
| 95 | 260+103 | Slab | 1 | 2 | 12 |
| 96 | 260+284 | Slab | 1 | 2 | 12 |
| 97 | 260+395 | Slab | 1 | 2 | 12 |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| S. No. | Chainage (km) | Type of Culvert | Span /Opening with span length (m) | | Width (m) |
|--------|---------------|-----------------|------------------------------------|------------|-----------|
| | | | No | Clear Span | |
| 98 | 260+467 | Slab | 1 | 2 | 12 |
| 99 | 260+872 | Slab | 1 | 2 | 12 |
| 100 | 261+603 | Slab | 1 | 2 | 12 |
| 101 | 261+938 | Slab | 1 | 2 | 12 |
| 102 | 262+023 | Slab | 1 | 2 | 12 |
| 103 | 262+153 | Slab | 1 | 2 | 12 |
| 104 | 262+304 | Slab | 1 | 2 | 12 |
| 105 | 262+590 | Slab | 1 | 2 | 12 |
| 106 | 262+858 | Slab | 1 | 2 | 12 |

11. Bus bays

The details of bus bays on the Site are as follows:

| S. No. | Chainage (km) | Length (m) | Left Hand Side | Right Hand Side |
|--------|---------------|------------|----------------|-----------------|
| Nil | | | | |

12. Truck Lay byes

The details of truck lay byes are as follows:

| S. No. | Chainage (km) | Length (m) | Left Hand Side | Right Hand Side |
|--------|---------------|------------|----------------|-----------------|
| Nil | | | | |

13. Roadside drains

The details of the roadside drains are as follows:

| S. No. | Location | | Type | |
|--------|----------|-------|--------------------|------------------|
| | From km | to km | Masonry/cc (Pucca) | Earthen (Kutcha) |
| Nil | | | | |

14. Major junctions

The details of major junctions are as follows:

| Sr. No. | Chainage | Location | Link | Side |
|---------|----------|----------------|---------------------------|-------|
| 1 | 235+000 | Vailoo village | To proposed Vailoo Tunnel | Left |
| 2 | 257+200 | Achabal | Right – Shangus | + |
| | | | Left - Fatehpura | |
| 3 | 267+825 | Anantnag | Pahalgam | Right |
| 4 | 269+000 | Khanabal | Right – Srinagar | X |
| | | | Left - Jammu | |

(NH: National Highway, SH: State Highway, MDR: Major District Road)

15. Minor junctions

The details of the minor junctions are as follows:

| S. No. | Location | Type | Link | | Remarks |
|--------|----------|------|------------|-------------------|---------|
| | | | LHS | RHS | |
| 1 | 235+060 | Y | Halpora | - | |
| 2 | 237+800 | Y | Maagam | - | |
| 3 | 242+620 | Y | - | Bidder Hayat Pora | |
| 4 | 242+810 | Y | Naroo Pora | - | |
| 5 | 243+490 | Y | Naroo Pora | - | |
| 6 | 243+500 | Y | - | Nagum | |
| 7 | 245+950 | Y | - | Booch | |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| S. No. | Location | Type | Link | | Remarks |
|--------|----------|------|---------------------|--------------------|---------|
| | | | LHS | RHS | |
| 8 | 246+835 | Y | Tangpawa | - | |
| 9 | 248+260 | Y | Lissar Muqam | - | |
| 10 | 248+800 | Y | Lissar Muqam | - | |
| 11 | 249+125 | Y | Ghee Boom | - | |
| 12 | 250+860 | Y | Paragpora | - | |
| 13 | 251+150 | Y | Goripoora | - | |
| 14 | 251+600 | Y | - | Hillar Arhama | |
| 15 | 254+785 | Y | Umar Khar | - | |
| 16 | 256+170 | Y | Achabal Bypass Road | - | |
| 17 | 259+940 | Y | Sandoo | - | |
| 18 | 262+055 | Y | - | Karewa Kangan Haal | |
| 19 | 262+330 | Y | Bul Bul Nowgam | - | |
| 20 | 262+712 | Y | - | Upper Barakpore | |
| 21 | 264+890 | Y | - | | |
| 22 | 265+525 | + | Ashajipora | Sheerpora | |
| 23 | 266+040 | Y | Danter | - | |
| 24 | 266+600 | + | Stadium Road | Court Road | |
| 25 | 267+731 | Y | Naid Khun | - | |

16. Bypasses

The details of the existing road sections proposed to be bypassed are as follows:

| S. No. | Name of bypass (town) | Chainage (km) From km to km | Length (in Km) |
|--------|-----------------------|-----------------------------|----------------|
| Nil | | | |

17. Others

Nil

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

Annex – II

(As per Clause 8.3 (i))

(Schedule-A)

Dates for providing Right of Way of Construction Zone

The dates on which the Authority shall provide Right of Way of Construction Zone to the Contractor on different stretches of the Site are stated below:

| Sl. No. | From (Km) | To (Km) | Length (Km) | Width (m) | Date of providing Right of Way* |
|------------------------------------|-----------|---------|-------------|-----------|---------------------------------|
| 1 | 2 | | 3 | 4 | 5 |
| (i) Full Right of Way (Full Width) | 148+589 | 155+600 | 7.011 | 27 | Appointed Date |
| | 155+600 | 157+800 | 2.200 | 28 | |
| | 157+800 | 159+200 | 1.400 | 29 | |
| | 159+200 | 160+000 | 0.800 | 28 | |
| | 160+000 | 160+400 | 0.400 | 25 | |
| | 160+400 | 161+200 | 0.800 | 27 | |
| | 161+200 | 166+800 | 5.600 | 26 | |
| | 166+800 | 167+600 | 0.800 | 28 | |
| | 167+600 | 169+800 | 2.200 | 26 | |
| | 169+800 | 170+600 | 0.800 | 28 | |
| | 170+600 | 170+750 | 0.150 | 22 | |
| | 170+750 | 171+600 | 0.850 | 27 | |
| | 171+600 | 173+200 | 1.600 | 28 | |
| | 173+200 | 173+600 | 0.400 | 27 | |
| | 173+600 | 176+589 | 2.989 | 28 | |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”


Annex - III

(Schedule-A)

Alignment Plans

The alignment of the Project Highway shall be modified in the following sections as per the alignment plan indicated below:

- (i) The alignment of the Project Highway is enclosed in alignment plan and indicated below. Finished road level indicated in the alignment plan shall be followed by the contractor as minimum FRL. In any case, the finished road level of the project highway shall not be less than those indicated in the alignment plan. The contractor shall, however, improve/upgrade the Road profile as indicated in Annex-III based on site/design requirement.



Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI)."

Annex - IV

(Schedule-A)

Environment Clearances

As per EIA notification 2006 and its amendment S.O.2559 (E) Dt 22nd August 2013, S.O 996(E) Dt 10th April 2015, S.O 382(E) Dt 3rd February 2015 Environmental Clearance Exempted from the purview of the Environmental Impact Assessment

[To be published in the Gazette of India, Extraordinary, Part II, Section 3, Sub-section(iii)]

MINISTRY OF ENVIRONMENT AND FORESTS NOTIFICATION

New Delhi, the 22nd August, 2013

S.O. 2559 (E).- Whereas by notification of the Government of India in the Ministry of Environment and Forests vide number S.O.1533(E), dated the 14th September, 2006 issued under sub-section (1) and clause (v) of sub-section (2) of section (3) of the Environment (Protection) Act, 1986 read with clause (d) of sub-rule (3) of rule 5 of the Environment (Protection) Rules, 1986, the Central Government directed that on and from the date of its publication, the required construction of new projects or activities or the expansion or modernization of existing projects or activities listed in the Schedule to the said notification entailing the capacity addition with change in process or technology and or product mix shall be undertaken in any part of India only after prior environmental clearance from the Central Government or as the case may be, by the State level Environment Impact Assessment Authority, duly constituted by the Central Government under sub-section (3) of section 3 of the said Act, in accordance with the procedure specified therein;

And whereas the Government of India in the Ministry of Environment and Forests had constituted a High Level Committee under the Chairmanship of Member (Environment and Forests and Science and Technology), Planning Commission, vide OM No.21-270/2008-IA.III dated the 11th December, 2012 to review the provisions of Environmental Impact Assessment Notification, 2006 relating to granting Environmental Clearances for Roads, Buildings and Special Economic Zone projects and provisions under the OM dated the 7th February, 2012 issued by the Ministry of Environment and Forests regarding guidelines for High Rise Buildings;

And whereas one of the terms of reference (ToR) of the Committee was to review the requirement of Environmental Clearance for highway expansion projects upto the right of way of 60 meters and length of 200 kms under Environmental Impact Assessment notification;

And whereas the Committee has submitted its report to the Ministry and on this ToR, the Committee has recommended exempting highway expansion projects from the requirement of scoping and that Environmental Impact Assessment or Environment Management Plan for highway expansion projects may be prepared on the basis of model ToRs to be posted on Ministry's website and in respect of requirement of environmental clearance, **the Committee has recommended that expansion of National Highway projects up to 100 kms involving additional right of way or land acquisition upto 40 mts on existing alignments and 60 mts on re-alignments or by-passes may be exempted from the preview of the notification;**

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

Schedule - B

(See Clause 2.1)

Development of the Project Highway

1. Development of the Project Highway

Development of the Project Highway shall include design and construction of the Project Highway as described in this Schedule-B and in Schedule-C.

2. Rehabilitation and augmentation

Rehabilitation and augmentation shall include Two-Laning and Strengthening of the Project Highway as described in Annex-I of this Schedule-B and in Schedule-C.

3. Specifications and Standards

The Project Highway shall be designed and constructed in conformity with the Specifications and Standards specified in Annex-I of Schedule-D.

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

Annex – I
(Schedule-B)

Description of the Project

Construction and Upgradation to 2/4-lane with paved shoulder from km 148+589 (Ex. Km 235+070) to km 176+532 (Ex. Km 263+107) of length 27+943 km on Vailoo – Donipawa section of NH-244 in accordance with IRC-SP:73-2015 for 4-lane section & 2-lane shall be as per IRC:SP:73-2018. If any standards, specification or details are not given in the manual, the minimum design/ construction requirements shall be specified in the schedule.

1. Widening of Existing Highway

- (i) The Project Highway shall follow the existing alignment unless otherwise specified by the Authority and shown in the alignment plans specified in Annex-III of Schedule-A. Geometric deficiencies, if any, in the existing horizontal and vertical profiles shall be corrected as per the prescribed standards for rolling/mountainous terrain to the extent land is available.

| SL. No. | Design Chainage (km) | | Length (km) | Remarks |
|---------|----------------------|---------|-------------|-------------------------------|
| | From | To | | |
| 1 | 148+589 | 176+532 | 27+943 | 2/4- lane with paved shoulder |

- (ii) Width of Carriageway

- (a) 2-Laning with paved shoulders for open country and 4-Laning for built up section shall be undertaken for project road. The paved carriageway shall be 10m/2x7.5m wide in accordance with the typical cross section's drawings attached in schedule B.

Provided that in the built-up areas the width of the carriageway shall be as specified in the following table:

| <i>Design Chainage</i> | | <i>Design Length in m</i> | <i>Width (m)</i> | <i>TCS Detail</i> |
|------------------------|-----------|---------------------------|------------------|-------------------|
| <i>From</i> | <i>To</i> | | | |
| 148+790 | 150+290 | 1500.00 | 2x7.5 | 4-Lane Urban |
| 150+290 | 150+490 | 200.00 | 2x7.5 | 4-Lane Urban(15m) |
| 150+490 | 150+940 | 450.00 | 2x7.5 | 4-Lane Urban |
| 151+240 | 151+690 | 450.00 | 2x7.5 | 4-Lane Urban |
| 152+290 | 152+786 | 496.00 | 2x7.5 | 4-Lane Urban |
| 152+796 | 152+890 | 94.00 | 2x7.5 | 4-Lane Urban |
| 152+890 | 153+090 | 200.00 | 2x7.5 | 4-Lane Urban(15m) |
| 153+090 | 153+490 | 400.00 | 2x7.5 | 4-Lane Urban |
| 154+090 | 156+290 | 2200.00 | 2x7.5 | 4-Lane Urban |
| 156+290 | 156+490 | 200.00 | 2x7.5 | 4-Lane Urban(15m) |
| 156+490 | 157+740 | 1250.00 | 2x7.5 | 4-Lane Urban |
| 158+910 | 159+079 | 169.00 | 2x7.5 | 4-Lane Urban |
| 159+089 | 159+293 | 204.00 | 2x7.5 | 4-Lane Urban |
| 159+303 | 160+440 | 1137.00 | 2x7.5 | 4-Lane Urban |
| 161+140 | 163+285 | 2145.00 | 2x7.5 | 4-Lane Urban |
| 163+295 | 163+740 | 445.00 | 2x7.5 | 4-Lane Urban |
| 164+890 | 164+938 | 47.50 | 2x7.5 | 4-Lane Urban |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| Design Chainage | | Design Length in m | Width (m) | TCS Detail |
|------------------------|-----------|-------------------------------|------------------|-------------------|
| From | To | | | |
| 164+963 | 164+999 | 36.00 | 2x7.5 | 4-Lane Urban |
| 165+024 | 166+990 | 1966.50 | 2x7.5 | 4-Lane Urban |
| 167+590 | 168+690 | 1100.00 | 2x7.5 | 4-Lane Urban |
| 169+790 | 170+260 | 470.00 | 2x7.5 | 4-Lane Urban |
| 170+260 | 170+450 | 190.00 | 2x7.5 | 4-Lane Urban(15m) |
| 170+460 | 170+780 | 320.00 | 2x7.5 | 4-Lane Urban(15m) |
| 170+780 | 171+590 | 810.00 | 2x7.5 | 4-Lane Urban |
| 172+410 | 173+090 | 680.00 | 2x7.5 | 4-Lane Urban |
| 173+090 | 173+590 | 500.00 | 2x7.5 | 4-Lane Urban(15m) |
| 173+590 | 173+890 | 300.00 | 2x7.5 | 4-Lane Urban |
| 175+090 | 175+160 | 70.00 | 2x7.5 | 4-Lane Urban |
| 175+160 | 175+300 | 140.00 | 2x7.5 | 4-Lane Urban(15m) |
| 175+300 | 176+390 | 1090.00 | 2x7.5 | 4-Lane Urban |

- (a) Except as otherwise provided in this agreement, the width of the paved carriageway and cross-sectional features shall confirm to paragraph 1.1 above.

2. Geometric Design and General Features

(i) General

Geometric design and general features of the Project Highway shall be in accordance with Section 2 of the Manual.

(ii) Design speed

The design speed shall be the maximum design speed of 50 Km/hr. and minimum design speed of 40 km/hr. for rolling/mountainous terrain from Km 148+589 to Km 165+589 and the maximum design speed of 100 Km/hr. and minimum design speed of 80 km/hr. for plain/rolling terrain from Km 165+589 to Km 176+532 as per IRC: SP-73:2018 and IRC: SP-48:1998.

(iii) Improvement of the existing road geometrics

In the following sections, improvement of the existing road geometrics to the prescribed standards is proposed as per IRC: SP-73:2018 and IRC: SP-48:1998.

| Sl. No. | Stretch | | Type of deficiency | Remarks |
|----------------|----------------|--------------|--|----------------|
| | From Km | To Km | | |
| 1 | 148+589 | 176+532 | Shall be improved as per Annex-III of Schedule A | |

(iv) Right of Way

Details of the Right of Way are given in Annex II of Schedule-A.

(v) Type of shoulders

- (a) In built-up sections, footpaths/fully paved shoulders shall be provided in the following stretches:

| Sl. No. | Stretch | | Fully paved shoulders/ footpaths | Reference to cross section |
|----------------|----------------|--------------|---|-----------------------------------|
| | From Km | To Km | | |
| 1 | 148+589 | 148+790 | Paved shoulders | TCS-1 |
| 2 | 148+790 | 150+290 | Footpath | TCS-3 |
| 3 | 150+490 | 150+940 | Footpath | TCS-3 |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| Sl. No. | Stretch | | Fully paved shoulders/ footpaths | Reference to cross section |
|---------|---------|---------|----------------------------------|----------------------------|
| | From Km | To Km | | |
| 4 | 150+940 | 151+082 | Paved shoulders | TCS-2 |
| 5 | 151+112 | 151+240 | Paved shoulders | TCS-2 |
| 6 | 151+240 | 151+690 | Footpath | TCS-3 |
| 7 | 151+690 | 152+290 | Paved shoulders | TCS-2 |
| 8 | 152+290 | 152+786 | Footpath | TCS-3 |
| 9 | 152+796 | 152+890 | Footpath | TCS-3 |
| 10 | 153+090 | 153+490 | Footpath | TCS-3 |
| 11 | 153+490 | 154+090 | Paved shoulders | TCS-2 |
| 12 | 154+090 | 156+290 | Footpath | TCS-3 |
| 13 | 156+490 | 157+740 | Footpath | TCS-3 |
| 14 | 157+740 | 158+050 | Paved shoulders | TCS-2 |
| 15 | 158+060 | 158+910 | Paved shoulders | TCS-2 |
| 16 | 158+910 | 159+079 | Footpath | TCS-3 |
| 17 | 159+089 | 159+293 | Footpath | TCS-3 |
| 18 | 159+303 | 160+440 | Footpath | TCS-3 |
| 19 | 160+440 | 161+140 | Paved shoulders | TCS-2 |
| 20 | 161+140 | 163+285 | Footpath | TCS-3 |
| 21 | 163+295 | 163+740 | Footpath | TCS-3 |
| 22 | 163+740 | 163+790 | Paved shoulders | TCS-2 |
| 23 | 163+800 | 163+933 | Paved shoulders | TCS-2 |
| 24 | 164+038 | 164+115 | Paved shoulders | TCS-2 |
| 25 | 164+125 | 164+385 | Paved shoulders | TCS-2 |
| 26 | 164+409 | 164+710 | Paved shoulders | TCS-2 |
| 27 | 164+750 | 164+829 | Paved shoulders | TCS-2 |
| 28 | 164+839 | 164+890 | Paved shoulders | TCS-2 |
| 29 | 164+890 | 164+938 | Footpath | TCS-3 |
| 30 | 164+963 | 164+999 | Footpath | TCS-3 |
| 31 | 165+024 | 166+990 | Footpath | TCS-3 |
| 32 | 166+990 | 167+590 | Paved shoulders | TCS-2 |
| 33 | 167+590 | 168+690 | Footpath | TCS-3 |
| 34 | 168+690 | 169+790 | Paved shoulders | TCS-2 |
| 35 | 169+790 | 170+260 | Footpath | TCS-3 |
| 36 | 170+780 | 171+590 | Footpath | TCS-3 |
| 37 | 171+590 | 172+410 | Paved shoulders | TCS-2 |
| 38 | 172+410 | 173+090 | Footpath | TCS-3 |
| 39 | 173+590 | 173+890 | Footpath | TCS-3 |
| 40 | 173+890 | 175+090 | Paved shoulders | TCS-2 |
| 41 | 175+090 | 175+160 | Footpath | TCS-3 |
| 42 | 175+300 | 176+390 | Footpath | TCS-3 |
| 43 | 176+390 | 176+532 | Paved shoulders | TCS-2 |

(b) In open country/hilly areas, paved shoulders of 1.5m width shall be provided on either side and balance 1.0m width earthen shoulder at valley side only shall be covered with 150 mm thick compacted layer of granular material for project road as per attached typical cross section in schedule B of this manual.

(c) Design and specifications of paved shoulders and granular material shall conform to the requirements specified in the relevant Manual.

(vi) Lateral and vertical clearances at underpasses

(a) Lateral and vertical clearances at underpasses and provision of guardrails/crash barriers shall be as per the provision of relevant Manual.

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

(b) Lateral clearance: The width of the opening at the underpasses shall be as follows:

| Sl.No. | Location (Chainage) (from km to km) | Span/ opening (m) | Remarks |
|--------|-------------------------------------|-------------------|---------|
| Nil | | | |

(vii) Lateral and vertical clearances at overpasses

(a) Lateral and vertical clearances at overpasses shall be as per the provision of relevant Manual.

(b) Lateral clearance: The width of the opening at the overpasses shall be as follows:

| Sl.No. | Location (Chainage) (from km to km) | Span/ opening (m) | Remarks |
|--------|-------------------------------------|-------------------|---------|
| Nil | | | |

(viii) Service roads

Service roads shall be constructed at the locations and for the lengths indicated below:

| Sl.No. | Location of service road (from km to km) | Right hand side (RHS)/Left hand side (LHS)/ or Both sides | Length (m) of service road |
|--------|--|---|----------------------------|
| Nil | | | |

(ix) Grade separated structures

(a) Grade separated structures shall be provided as per provision of the relevant Manual. The requisite particulars are given below:

| Sl. No. | Location of structure | Length (m) | Number and length of spans (m) | Approach gradient | Remarks, if any |
|---------|-----------------------|------------|--------------------------------|-------------------|-----------------|
| Nil | | | | | |

(b) In the case of grade separated structures, the type of structure and the level of the Project Highway and the crossroads shall be as follows:

| Sl. No. | Location | Type of structure Length (m) | Cross road at | | | Remarks, if any |
|---------|----------|---------------------------------|----------------|--------------|---------------|-----------------|
| | | | Existing Level | Raised Level | Lowered Level | |
| Nil | | | | | | |

(x) Cattle and pedestrian underpass/overpass

Cattle and pedestrian underpass/ overpass shall be constructed as follows:

| Sl. No. | Location | Type of crossing |
|---------|----------|------------------|
| Nil | | |

(xi) Typical cross-sections of the Project Highway

Following typical cross sections shall be provided for the Project Highway, designed as per manual.

| Sl. No. | TCS No. | Description | Length in m | Length in km |
|---------------------|---------|----------------------|----------------|----------------|
| 1 | TCS-1 | 2-Lane Left side Cut | 201.5 | 0.202 |
| 2 | TCS-2 | 2-Lane Rural | 8141.935 | 8.142 |
| 3 | TCS-3 | 4-Lane Urban | 17510 | 17.510 |
| 4 | TCS-4 | 4-Lane Urban(15m) | 1750 | 1.750 |
| 5 | | Minor Bridge | 235.1 | 0.235 |
| 6 | | Major Bridge | 105 | 0.105 |
| Total Length | | | 27943.5 | 27.9435 |

3. Intersections and Grade Separators

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

All intersections and grade separators shall be as per the provision of relevant Manual.

Properly designed intersections shall be provided at the locations and of the types and features given in the tablesbelow:

(i) At-gradeintersections

| Sl. No. | Location of intersection | Type of intersection | Other features | Remarks |
|---------|--------------------------|----------------------|----------------|--|
| 1 | 148+589 | T | MAJOR | Road toward Proposed Vailoo Tunnel and Marbal |
| 2 | 151+290 | Y | MINOR | Towards Cheri Tanzi |
| 3 | 152+790 | Y | MINOR | - |
| 4 | 152+990 | T | MINOR | - |
| 5 | 154+630 | T | MINOR | - |
| 6 | 154+690 | T | MINOR | - |
| 7 | 154+990 | T | MINOR | - |
| 8 | 159+280 | T | MINOR | - |
| 9 | 159+420 | T | MINOR | - |
| 10 | 159+505 | T | MINOR | - |
| 11 | 159+600 | T | MINOR | - |
| 12 | 162+290 | Y | MINOR | Towards Tangpawa |
| 13 | 163+770 | Y | MINOR | Towards Booch |
| 14 | 164+370 | T | MINOR | Towards Hardu Dehrana |
| 15 | 164+640 | Y | MINOR | Towards Hardu Dehrana |
| 16 | 164+915 | T | MINOR | - |
| 17 | 166+405 | T | MINOR | Towards Hakura Badas Gam |
| 18 | 167+480 | T | MINOR | - |
| 19 | 168+170 | Y | MINOR | - |
| 20 | 168+280 | T | MINOR | Towards Umar Khar |
| 21 | 168+705 | Y | MINOR | - |
| 22 | 169+640 | Y | MINOR | Towards Shehli Pora |
| 23 | 170+690 | X | MAJOR | Towards Shehli Pora (Left) and Khundru (Right) |
| 24 | 171+360 | T | MINOR | - |
| 25 | 172+880 | T | MINOR | - |
| 26 | 173+660 | T | MINOR | - |
| 27 | 173+730 | T | MINOR | - |
| 28 | 175+190 | Y | MINOR | Towards Krewa Brak Pora |
| 29 | 175+555 | T | MINOR | Towards Kadeh Pora |
| 30 | 175+770 | Y | MINOR | Towards Sandoo and Wanihama |
| 31 | 176+190 | T | MINOR | Towards Nun Wani |

(ii) Grade separated intersection with/withoutramps

| Sl. No. | Location | Salient features | Minimum length of viaduct to be provided | Road to be carried over/under the structures |
|---------|----------|------------------|--|--|
| Nil | | | | |

4. Road Embankment and Cut Section

- (i) Construction of new road embankment/ cuttings shall conform to the Specifications and Standards given in Section 4 of the Manual and the specified cross-sectional

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

details.

- (ii) Raising of the existing road

The existing road shall be raised in the following sections:

| Sl.No. | Section(from km to km) | Length | Extent of raising [Top of finished road level] |
|--------|------------------------|--------|--|
| Nil | | | |

5. Pavement Design

- (i) Pavement design shall be carried out in accordance with the provision of relevant Manual.

- (ii) Type of pavement

Flexible pavement is proposed for the project highway in accordance with IRC: 37-2018.

| Layer | Thickness (mm) |
|------------------------|----------------|
| BC | 40 |
| DBM | 70 |
| WMM (Upper layer) | 125 |
| WMM (Bottom layer) | 125 |
| GSB (Upper layer) | 100 |
| GSB (Bottom Layer) | 100 |
| Total Thickness | 560 |

- (iii) Design requirements

- (a) Design Period and strategy

Flexible pavement for new pavement shall be designed for a period of 20 years and rigid pavement shall be designed for a minimum design period of 30 years. Stage construction shall not be permitted.

- (b) Design Traffic

Notwithstanding anything to the contrary contained in this Agreement or the Manual, the Contractor shall design the pavement for a minimum design traffic of 20(MSA) million standard axles.

6. Roadside Drainage

Drainage system including surface and subsurface drains for the Project Highway shall be provided as per the provision of relevant Manual.

| Roadside PCC Drainage List | | | | |
|----------------------------|---------|-------------------|------|---------------------------|
| Design Chainage in Km | | Design Length (m) | Side | Roadside Drain Length (m) |
| From | To | | | |
| 148+589 | 148+790 | 201.5 | LHS | 201.5 |

| Roadside Earthen Drainage List | | | | |
|--------------------------------|----|-------------------|------|---------------------------|
| Design Chainage in Km | | Design Length (m) | Side | Roadside Drain Length (m) |
| From | To | | | |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| 148+589 | 148+790 | 201.5 | RHS | 201.5 |
|---|-----------|--------------------------|-------------|----------------------------------|
| 150+940 | 151+082 | 142 | LHS+RHS | 284 |
| 151+112 | 151+240 | 128 | LHS+RHS | 256 |
| 151+690 | 152+290 | 600 | LHS+RHS | 1200 |
| 153+490 | 154+090 | 600 | LHS+RHS | 1200 |
| 157+740 | 158+050 | 310 | LHS+RHS | 620 |
| 158+060 | 158+910 | 850 | LHS+RHS | 1700 |
| 160+440 | 161+140 | 700 | LHS+RHS | 1400 |
| 163+740 | 163+790 | 50 | LHS+RHS | 100 |
| 163+800 | 163+933 | 132.5 | LHS+RHS | 265 |
| 164+038 | 164+115 | 77.5 | LHS+RHS | 155 |
| 164+125 | 164+385 | 259.8 | LHS+RHS | 519.6 |
| 164+409 | 164+710 | 300.45 | LHS+RHS | 600.9 |
| 164+750 | 164+829 | 78.65 | LHS+RHS | 157.3 |
| 164+839 | 164+890 | 51 | LHS+RHS | 102 |
| 166+990 | 167+590 | 600 | LHS+RHS | 1200 |
| 168+690 | 169+790 | 1100 | LHS+RHS | 2200 |
| 171+590 | 172+410 | 820 | LHS+RHS | 1640 |
| 173+890 | 175+090 | 1200 | LHS+RHS | 2400 |
| 176+390 | 176+532 | 142 | LHS+RHS | 284 |
| Total Roadside Earthen Drainage Length | | | | 16485 |
| Roadside RCC Covered Drain List | | | | |
| Design Chainage in Km | | Design Length (m) | Side | Roadside Drain Length (m) |
| From | To | | | |
| 148+790 | 150+290 | 1500 | LHS+RHS | 3000 |
| 150+290 | 150+490 | 200 | LHS+RHS | 400 |
| 150+490 | 150+940 | 450 | LHS+RHS | 900 |
| 151+240 | 151+690 | 450 | LHS+RHS | 900 |
| 152+290 | 152+786 | 496 | LHS+RHS | 992 |
| 152+796 | 152+890 | 94 | LHS+RHS | 188 |
| 152+890 | 153+090 | 200 | LHS+RHS | 400 |
| 153+090 | 153+490 | 400 | LHS+RHS | 800 |
| 154+090 | 156+290 | 2200 | LHS+RHS | 4400 |
| 156+290 | 156+490 | 200 | LHS+RHS | 400 |
| 156+490 | 157+740 | 1250 | LHS+RHS | 2500 |
| 158+910 | 159+079 | 169 | LHS+RHS | 338 |
| 159+089 | 159+293 | 204 | LHS+RHS | 408 |
| 159+303 | 160+440 | 1137 | LHS+RHS | 2274 |
| 161+140 | 163+285 | 2145 | LHS+RHS | 4290 |
| 163+295 | 163+740 | 445 | LHS+RHS | 890 |
| 164+890 | 164+938 | 47.5 | LHS+RHS | 95 |
| 164+963 | 164+999 | 36 | LHS+RHS | 72 |
| 165+024 | 166+990 | 1966.5 | LHS+RHS | 3933 |
| 167+590 | 168+690 | 1100 | LHS+RHS | 2200 |
| 169+790 | 170+260 | 470 | LHS+RHS | 940 |
| 170+260 | 170+450 | 190 | LHS+RHS | 380 |
| 170+460 | 170+780 | 320 | LHS+RHS | 640 |
| 170+780 | 171+590 | 810 | LHS+RHS | 1620 |
| 172+410 | 173+090 | 680 | LHS+RHS | 1360 |
| 173+090 | 173+590 | 500 | LHS+RHS | 1000 |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| | | | | |
|---|---------|------|---------|--------------|
| 173+590 | 173+890 | 300 | LHS+RHS | 600 |
| 175+090 | 175+160 | 70 | LHS+RHS | 140 |
| 175+160 | 175+300 | 140 | LHS+RHS | 280 |
| 175+300 | 176+390 | 1090 | LHS+RHS | 2180 |
| Total Roadside RCC Drainage Length | | | | 38520 |


7. Design of Structures

(i) General


(a) All bridges, culverts and structures shall be designed and constructed in accordance with the provision of relevant Manual and shall conform to the cross- sectional features and other details specified therein.

(b) Width of the carriageway of new bridges and structures shall be as follows:

| Sl. No. | Structure/ Bridge at km | Width of carriageway and cross-sectional features* |
|---------|---|---|
| 1 | 151+096, 158+054, 163+794, 163+984, 164+119, 164+833, 170+454 | Width of Carriageway –11 m including Kerb Shyness– 2 x 0.25 m Crash Barrier – 2 x 0.5 m Total Width – 12.5m |
| 2 | 152+790, 159+083, 159+297, 163+289 | Width of Carriageway –2X10 m Crash Barrier – 4 x 0.5 m (both sides) Total Width – 22 m |



Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”



(c) The following structures shall be provided with footpaths:

| Sl. No. | Location at km | Span Arrangement No. x Length (m) | Remarks |
|---------|----------------|-----------------------------------|--------------|
| 1 | 152+790 | 1 x 10 | Minor Bridge |
| 2 | 159+083 | 2 x 10 | Minor Bridge |
| 3 | 159+297 | 3 x 10 | Minor Bridge |
| 4 | 163+289 | 4 x 10 | Minor Bridge |

(d) All bridges shall be high-level bridges.

Refer to the provision of relevant Manual and state if there is any exception

(e) The following structures shall be designed to carry utility services specified in table below:

| Sl. No. | Bridge at km | Utility service to be carried | Remarks |
|---------|--------------|-------------------------------------|------------------------------|
| 1 | 151+096 | Electricity cables, OFC cables etc. | Minor Bridge (Wangon Bridge) |
| 2 | 152+790 | Electricity cables, OFC cables etc. | Minor Bridge |
| 3 | 158+054 | Electricity cables, OFC cables etc. | Minor Bridge |
| 4 | 159+083 | Electricity cables, OFC cables etc. | Minor Bridge |
| 5 | 159+297 | Electricity cables, OFC cables etc. | Minor Bridge |
| 6 | 163+289 | Electricity cables, OFC cables etc. | Minor Bridge |
| 7 | 163+794 | Electricity cables, OFC cables etc. | Minor Bridge |
| 8 | 163+984 | Electricity cables, OFC cables etc. | Major Bridge (HILLAR Bridge) |
| 9 | 164+119 | Electricity cables, OFC cables etc. | Minor Bridge |
| 10 | 164+396 | Electricity cables, OFC cables etc. | Minor Bridge |
| 11 | 164+729 | Electricity cables, OFC cables etc. | Minor Bridge |
| 12 | 164+833 | Electricity cables, OFC cables etc. | Minor Bridge |
| 13 | 164+949 | Electricity cables, OFC cables etc. | Minor Bridge |
| 14 | 165+010 | Electricity cables, OFC cables etc. | Minor Bridge |
| 15 | 170+454 | Electricity cables, OFC cables etc. | Minor Bridge |

(f) Cross-section of the new culverts and bridges at deck level for the Project Highway shall conform to the typical cross-sections given in the provision of relevant Manual.

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

(ii) Culverts

(a) Overall width of all culverts shall be equal to roadway width of the approaches.

(b) Reconstruction of existing culverts:

The existing culverts at the following locations shall be re-constructed as new culverts:

| Sl. No. | Culvert location in Km | Span/Opening (m) (LengthxHt.) | Remarks, if any* |
|----------------|-------------------------------|--------------------------------------|-------------------------|
| 1 | 148+654 | 2x2 | RCC BOX |
| 2 | 148+861 | 3x2 | RCC BOX |
| 3 | 149+354 | 6x4 | RCC BOX |
| 4 | 149+629 | 2x2 | RCC BOX |
| 5 | 149+999 | 2x2 | RCC BOX |
| 6 | 150+219 | 4x3 | RCC BOX |
| 7 | 150+279 | 4x3 | RCC BOX |
| 8 | 150+447 | 2x2 | RCC BOX |
| 9 | 150+757 | 2x2 | RCC BOX |
| 10 | 150+870 | 2x2 | RCC BOX |
| 11 | 151+298 | 2X2 | RCC BOX |
| 12 | 151+540 | 2x2 | RCC BOX |
| 13 | 151+951 | 2x2 | RCC BOX |
| 14 | 152+280 | 2x2 | RCC BOX |
| 15 | 152+901 | 2x2 | RCC BOX |
| 16 | 153+060 | 2x2 | RCC BOX |
| 17 | 153+224 | 3x3 | RCC BOX |
| 18 | 153+384 | 2x2 | RCC BOX |
| 19 | 153+569 | 2x2 | RCC BOX |
| 20 | 153+819 | 2x2 | RCC BOX |
| 21 | 154+344 | 2x2 | RCC BOX |
| 22 | 154+421 | 2x2 | RCC BOX |
| 23 | 155+314 | 2x2 | RCC BOX |
| 24 | 155+614 | 4x3 | RCC BOX |
| 25 | 155+856 | 2x2 | RCC BOX |
| 26 | 155+992 | 2x2 | RCC BOX |
| 27 | 156+139 | 2x2 | RCC BOX |
| 28 | 156+220 | 2x2 | RCC BOX |
| 29 | 156+944 | 2x2 | RCC BOX |
| 30 | 157+189 | 2x2 | RCC BOX |
| 31 | 157+517 | 2x2 | RCC BOX |
| 32 | 157+541 | 2x2 | RCC BOX |
| 33 | 158+121 | 2x2 | RCC BOX |
| 34 | 158+392 | 2x2 | RCC BOX |
| 35 | 158+667 | 2X2 | RCC BOX |
| 36 | 159+741 | 3x3 | RCC BOX |
| 37 | 160+029 | 4x3 | RCC BOX |
| 38 | 160+300 | 2x2 | RCC BOX |
| 39 | 160+449 | 3x2 | RCC BOX |
| 40 | 160+701 | 6x4 | RCC BOX |
| 41 | 160+897 | 4x3 | RCC BOX |
| 42 | 161+233 | 2x2 | RCC BOX |
| 43 | 161+383 | 2x2 | RCC BOX |
| 44 | 161+529 | 2x2 | RCC BOX |
| 45 | 161+604 | 2x2 | RCC BOX |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| Sl. No. | Culvert location in Km | Span/Opening (m) (LengthxHt.) | Remarks, if any* |
|---------|------------------------|-------------------------------|------------------|
| 46 | 161+792 | 2x2 | RCC BOX |
| 47 | 161+854 | 2x2 | RCC BOX |
| 48 | 162+129 | 2x2 | RCC BOX |
| 49 | 162+406 | 2x2 | RCC BOX |
| 50 | 162+984 | 2x2 | RCC BOX |
| 51 | 163+139 | 2X2 | RCC BOX |
| 52 | 163+337 | 4x3 | RCC BOX |
| 53 | 163+368 | 2x2 | RCC BOX |
| 54 | 163+431 | 2x2 | RCC BOX |
| 55 | 163+484 | 2x2 | RCC BOX |
| 56 | 163+549 | 2x2 | RCC BOX |
| 57 | 163+817 | 4x3 | RCC BOX |
| 58 | 164+134 | 4x3 | RCC BOX |
| 59 | 164+259 | 2x2 | RCC BOX |
| 60 | 164+334 | 4x3 | RCC BOX |
| 61 | 164+525 | 2x2 | RCC BOX |
| 62 | 164+620 | 2x2 | RCC BOX |
| 63 | 164+902 | 2x2 | RCC BOX |
| 64 | 165+085 | 3x3 | RCC BOX |
| 65 | 165+237 | 2x2 | RCC BOX |
| 66 | 165+404 | 2x2 | RCC BOX |
| 67 | 165+808 | 2x2 | RCC BOX |
| 68 | 166+242 | 2x2 | RCC BOX |
| 69 | 166+327 | 2x2 | RCC BOX |
| 70 | 166+614 | 2x2 | RCC BOX |
| 71 | 166+743 | 4x3 | RCC BOX |
| 72 | 166+784 | 2x2 | RCC BOX |
| 73 | 167+104 | 2x2 | RCC BOX |
| 74 | 167+312 | 2x2 | RCC BOX |
| 75 | 167+794 | 4x3 | RCC BOX |
| 76 | 168+153 | 2x2 | RCC BOX |
| 77 | 168+304 | 2x2 | RCC BOX |
| 78 | 168+499 | 2x2 | RCC BOX |
| 79 | 168+797 | 4x3 | RCC BOX |
| 80 | 169+269 | 2x2 | RCC BOX |
| 81 | 169+639 | 6x4 | RCC BOX |
| 82 | 170+423 | 4x3 | RCC BOX |
| 83 | 170+545 | 2x2 | RCC BOX |
| 84 | 170+601 | 2x2 | RCC BOX |
| 85 | 170+897 | 4x3 | RCC BOX |
| 86 | 171+422 | 2x2 | RCC BOX |
| 87 | 171+582 | 2x2 | RCC BOX |
| 88 | 171+967 | 2x2 | RCC BOX |
| 89 | 172+422 | 2x2 | RCC BOX |
| 90 | 172+667 | 2x2 | RCC BOX |
| 91 | 172+872 | 6x3 | RCC BOX |
| 92 | 173+107 | 2x2 | RCC BOX |
| 93 | 173+364 | 2x2 | RCC BOX |
| 94 | 173+431 | 2x2 | RCC BOX |
| 95 | 173+504 | 2x2 | RCC BOX |
| 96 | 173+627 | 2x2 | RCC BOX |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| Sl. No. | Culvert location in Km | Span/Opening (m) (LengthxHt.) | Remarks, if any* |
|---------|------------------------|-------------------------------|------------------|
| 97 | 173+808 | 2x2 | RCC BOX |
| 98 | 173+919 | 2x2 | RCC BOX |
| 99 | 173+991 | 2X2 | RCC BOX |
| 100 | 174+396 | 3X2 | RCC BOX |
| 101 | 175+127 | 2x2 | RCC BOX |
| 102 | 175+462 | 2x2 | RCC BOX |
| 103 | 175+547 | 4x3 | RCC BOX |
| 104 | 175+677 | 2x2 | RCC BOX |
| 105 | 175+828 | 2x2 | RCC BOX |
| 106 | 176+114 | 2x2 | RCC BOX |
| 107 | 176+382 | 2x2 | RCC BOX |

*Specify modifications, if any, required in the road level, etc.

(c) Widening of existing culverts:

All existing culverts which are not to be reconstructed shall be widened to the roadway width of the Project Highway as per the typical cross section given in the provision of relevant Manual. Repairs and strengthening of existing structures where required shall be carried out.

| Sl. No. | Culvert location | Type, span, height, and width of existing culvert (m) | Repairs to be carried out [specify] |
|---------|------------------|---|-------------------------------------|
| Nil | | | |

(d) Additional new culverts shall be constructed as per particulars given in the table below:

| S. No. | Proposed Structure | Design Chainage in km | Proposed Span (No. x Length x Ht.) in m |
|--------|--------------------|-----------------------|---|
| 1 | RCC BOX | 150+314 | 1x4x3 |
| 2 | RCC BOX | 165+607 | 1x3X3 |

(e) Repairs/replacements of railing/parapets, flooring and protection works of the existing culverts shall be undertaken as follows:

| Sl. No. | Location at km | Type of repair required |
|---------|----------------|-------------------------|
| Nil | | |

(f) Floor protection works shall be as specified in the relevant IRC Codes and Specifications.

(iii) Bridges

(a) Existing bridges to be re-constructed/widened

(i) The existing bridges at the following locations shall be re-constructed as new Structures

| Sl. No. | Bridge location (km) | Salient details of existing bridge | Adequacy or otherwise of the existing waterway, vertical clearance, etc.* | Remarks |
|---------|----------------------|------------------------------------|---|--|
| 1 | 152+790 | Minor Bridge | Horizontal Clearance: 9 m Vertical Clearance: 3.494 | Reconstruction (due to Masonary Sub-structure) |
| 2 | 158+054 | Minor Bridge | Horizontal Clearance: 9 m Vertical Clearance: 3.069 | Reconstruction (due to Highway Realignment) |
| 3 | 159+083 | Minor Bridge | Horizontal Clearance: 9 m Vertical Clearance: 3.063 | Reconstruction (due to Highway Realignment) |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| Sl. No. | Bridge location (km) | Salient details of existing bridge | Adequacy or otherwise of the existing waterway, vertical clearance, etc.* | Remarks |
|---------|----------------------|------------------------------------|---|---|
| 4 | 159+297 | Minor Bridge | Horizontal Clearance: 9 m Vertical Clearance: 3.448 | Reconstruction (due to Masonary Sub-structre) |
| 5 | 163+289 | Minor Bridge | Horizontal Clearance: 9 m Vertical Clearance: 3.082 | Reconstruction (due to Masonary Sub-structre) |
| 6 | 163+794 | Minor Bridge | Horizontal Clearance: 9 m Vertical Clearance: 3.813 | Reconstruction (due to Masonary Sub-structre) |
| 7 | 164+119 | Minor Bridge | Horizontal Clearance: 9 m Vertical Clearance: 3.847 | Reconstruction (due to Masonary Sub-structre) |
| 8 | 164+833 | Minor Bridge | Horizontal Clearance: 9 m Vertical Clearance: 2.762 | Reconstruction (due to Masonary Sub-structre) |
| 9 | 170+454 | Minor Bridge | Horizontal Clearance: 9 m Vertical Clearance: 2.518 | Reconstruction (due to Masonary Sub-structre) |

(ii) The following narrow bridges shall be widened:

| Sl. No. | Location (km) | Existing width (m) | Extent of widening (m) | Cross-section at deck level for widening @ |
|---------|---------------|--------------------|------------------------|--|
| Nil | | | | |

@ Attach cross-section

(b) Additional new bridges

New bridges at the following locations on the Project Highway shall be constructed. GADs for the new bridges are attached in the drawings folder.

Minor Bridge: -

| S. No. | Design Chainage | Total Length (M) | Span Arrangement No. X length | Type of Superstructure | Deck Width (M) |
|--------|-----------------|------------------|-------------------------------|------------------------------|----------------|
| 1 | 151+096 | 30 | 1 x 30 | Composite Steel Plate Girder | 12.5 |
| 2 | 152+790 | 10 | 1 x 10 | RCC Solid Slab | 2x11 |
| 3 | 158+054 | 10 | 1 x 10 | RCC Solid Slab | 12.5 |
| 4 | 159+083 | 10 | 1 x 10 | RCC Solid Slab | 2x11 |
| 5 | 159+297 | 10 | 1 x 10 | RCC Solid Slab | 2x11 |
| 6 | 163+289 | 10 | 1 x 10 | RCC Solid Slab | 2x11 |
| 7 | 163+794 | 10 | 1 x 10 | RCC Solid Slab | 12.5 |
| 8 | 164+119 | 10 | 1 x 10 | RCC Solid Slab | 12.5 |
| 9 | 164+833 | 10 | 1 x 10 | RCC Solid Slab | 12.5 |
| 10 | 170+454 | 10 | 1 x 10 | RCC Solid Slab | 12.5 |

Viaduct: -

| Sl. No. | Design Chainage | Type of Superstructure | Total Length (m) | Proposed Span Arrangement (no.xlength) | Proposed Overall Deck Width (m) |
|---------|-----------------|------------------------|------------------|--|---------------------------------|
|---------|-----------------|------------------------|------------------|--|---------------------------------|

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| Sl. No. | Design Chainage | Type of Superstructure | Total Length (m) | Proposed Span Arrangement (no.xlength) | Proposed Overall Deck Width (m) |
|---------|-----------------|------------------------|------------------|--|---------------------------------|
| Nil | | | | | |

- (c) The railings of existing bridges shall be replaced by crash barriers at the following locations:

| Sl. No. | Location at km | Remarks |
|---------|----------------|---------|
| Nil | | |

- (d) Repairs/replacements of railing/parapets of the existing bridges shall be undertaken as follows:

| Sl. No. | Location at km | Remarks |
|---------|----------------|---------|
| Nil | | |

- (e) Drainage system for bridge decks

An effective drainage system for bridge decks shall be provided as specified in the provision of relevant Manual

- (f) Structures in marine environment

Refer to the provision of relevant Manual and specify the necessary measures/ treatments for protecting structures in marine environment, where applicable.

- (iv) Rail-road bridges

- (a) Design, construction and detailing of ROB/RUB shall be as specified in the provision of relevant Manual. [Refer to the provision of relevant Manual and specify modification, if any]

- (b) Roadover-bridges

Road over-bridges (road over rail) shall be provided at the following level crossings, as per GAD drawings attached:

| Sl.No. | Location of Level crossing (Chainage km) | Length of bridge (m) |
|--------|--|----------------------|
| Nil | | |

- (c) Road under-bridges

Road under-bridges (road under railway line) shall be provided at the following level crossings, as per GAD drawings attached:

| Sl. No. | Location of Level crossing (Chainage km) | Number and length of span (m) |
|---------|--|-------------------------------|
| Nil | | |

- (v) Grade separated structures

The grade separated structures shall be provided at the locations and of the type and length specified in paragraphs 2 (ix) and 3 of this Annex-I.

- (vi) Repairs and strengthening of bridges and structures

The existing bridges and structures to be repaired /strengthened, and the nature and extent of repairs /strengthening required are given below:

- (a) Bridges

| Sl. No. | Location of bridge (km) | Nature and extent of repairs /strengthening to be carried out |
|---------|-------------------------|---|
|---------|-------------------------|---|

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| | | |
|---|---------|--|
| 1 | 163+984 | Retained with repair, rehabilitation and protection work |
| 2 | 164+396 | Retained without Widening |
| 3 | 164+729 | Retained without Widening |
| 4 | 164+949 | Retained existing bridge with additional 2-lane Bridge |
| 5 | 165+010 | Retained existing bridge with additional 2-lane Bridge |

(b) ROB /RUB

| Sl.No. | Location of ROB/RUB (km) | Nature and extent of repairs /strengthening to be carried out |
|--------|--------------------------|---|
| Nil | | |

(c) Overpasses/Underpasses and other structures

| Sl.No. | Location of Structure (km) | Nature and extent of repairs /strengthening to be carried out |
|--------|----------------------------|---|
| Nil | | |

(vii) List of Bridges and Structures

The following is the list of the Bridges and Structures:

| S. No. | Type of Structure | Design Chainage in km |
|--------|------------------------------|-----------------------|
| 1 | Minor Bridge (Wangon Bridge) | 151+096 |
| 2 | Minor Bridge | 152+790 |
| 3 | Minor Bridge | 158+054 |
| 4 | Minor Bridge | 159+083 |
| 5 | Minor Bridge | 159+297 |
| 6 | Minor Bridge | 163+289 |
| 7 | Minor Bridge | 163+794 |
| 8 | Major Bridge (HILLAR Bridge) | 163+984 |
| 9 | Minor Bridge | 164+119 |
| 10 | Minor Bridge | 164+396 |
| 11 | Minor Bridge | 164+729 |
| 12 | Minor Bridge | 164+833 |
| 13 | Minor Bridge | 164+949 |
| 14 | Minor Bridge | 165+010 |
| 15 | Minor Bridge | 170+454 |

8. Design of Tunnel

Nil

9. Traffic Control Devices and Road Safety Works

- (i) Traffic control devices and road safety works shall be provided in accordance with the section 9 of the manual referred to in Schedule D.
- (ii) Specifications of the reflective sheeting as per IRC :67-2012 has been provided.

9.1 Crash Barrier

- (a) Thie Beam crash barrier with reflective stickers shall be provided along the project highway as per section 9 of the manual. It shall be provided at Culvert/ bridge approaches on both sides and at location of embankment with height greater than or equal to 3m.
- (b) The concrete crash barrier/ railing of bridge and culvert shall be painted in black and white

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

stripes in general.

9.2 Transverse Rumble strip

Transverse rumble strips in the form of thermoplastic bar marking shall be provided to warn the drivers to reduce the speed for safety. Stripes shall be in full width of pavement. The stripes shall be provided at sharp curves, village approaches, location approaching access road, intersections and any other hazardous locations on the project highway. Guidelines of IRC-35 shall be followed.

9.3 Road Marking and Signage

- (iii) The following road marking, signage and safety devise shall be used on the project which is minimum. Further if any shall be in accordance with the section 9 of the manual referred to in Schedule D.

The minimum quantity of Traffic signages and pavement marking as per IRC: 35-2015 are tabulated here:

| Item No. | Description | Unit | Estimated Quantity |
|----------|---|------|--------------------|
| 1 | Providing and fixing of retro- reflectorised cautionary, mandatory and informatory sign | | |
| | A 90 cm equilateral triangle | Nos. | 226 |
| | B 60 cm x 50 cm rectangular | Nos. | 338 |
| | C 90 cm x 30 cm rectangular | Nos. | 42 |
| | D 80 cm x 60 cm rectangular | Nos. | 8 |
| | E 60 cm circular | Nos. | 106 |
| 2 | Over Head Gantry | | |
| A | Gantry Mounted Advance Direction | T | 14 |
| B | Over Head Gantry Mounted Sign | Sqm | 115.2 |
| 3 | Providing and laying of hot applied thermoplastic compound and reflectorising glass beads | Sqm | 17560.84 |
| 4 | Reinforced cement concrete M15grade Kilometre Stone | | |
| | A 5th kilometre stone (precast) | Nos. | 9 |
| | B Ordinary kilometre stone (precast) | Nos. | 40 |
| | C Hectometre stone (precast) | Nos. | 187 |

10. Roadside Furniture

Roadside furniture shall be provided in accordance with the provision of relevant Manual for **Project Road**.

- (i) Delineators = 1507 Nos.
- (ii) Road Stud = 28633.32 Nos.
- (iii) Boundary Pillars = 222 Nos.
- (iv) Steel railing = 38520 Rm
- (v) Jersey barrier = 19260 Rm
- (vi) M20 Kerb = 35020 Rm
- (vii) Anti - Glare Screen = 19260 Rm
- (viii) Utility Duct : 27943 km.

11. Compulsory Afforestation

Refer to the provision of relevant Manual and specify the number of trees which are required to be planted by the Contractor as compensatory afforestation.

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

12. Hazardous Locations

The safety barriers shall also be provided at the following hazardous locations:

| Sl. No. | Location stretch from (km) to (km) | LHS/RHS |
|---------|------------------------------------|---------|
| | Nil | |

13. Special Requirement for Hill Road

This shall be provided accordance with section 13 of the Manual.

The side slope shall be protected by using suitable slope protection measures all along the highway on Hill side and valley side. The retaining wall/Toe wall, gabion wall and Soil nailing or Rock Bolting shall be constructed as per requirement of site condition in accordance with manual requirement. However, minimum length of protection works shall be construction as per details given below and the typical section of protection work are given in **Schedule B-1**.

- a) Retaining wall/Toe wall shall be constructed with minimum length is 280m on Project Road with 2 m ht. as per site condition of stone masonry in cement mortar 1:4 or any other better material acceptable to the Authority Engineer. Contractor need to access the same and bid accordingly.

| Toe Wall | | | | | |
|--------------------|---------|-------------|---------------------|------|-------------|
| Design Chainage Km | | Length in m | Height Adopted in m | Side | Length in m |
| From | To | | | | |
| 151+015 | 151+080 | 65 | 2 | Both | 130 |
| 151+115 | 151+190 | 75 | 2 | Both | 150 |
| Total Length | | | | | 280 |

- b) Gabion wall shall be in wire crates in accordance with applicable clause of section 2500 of MoRTH specification for road and bridge works (fifth revision) and accordance with IRC: SP: 48-1998 and IRC: 56-2011.

| Design Chainage in km | | Length in m | Height Adopted in m |
|-----------------------|----|-------------|---------------------|
| From | To | | |
| Nil | | | |

14. Change of Scope

The length of Structures and bridges specified hereinabove shall be treated as an approximate assessment. The actual lengths as required on the basis of detailed investigations shall be determined by the Contractor in accordance with the Specifications and Standards. Any variations in the lengths specified in this Schedule- B shall not constitute a Change of Scope, save and except any variations in the length arising out of a Change of Scope expressly undertaken in accordance with the provisions of Article 13.

15. Chainages wise indicative widening scheme with applicable typical Cross section

| Sr. No. | Design Chainage in km | | Design Length in m | TCS No |
|---------|-----------------------|---------|--------------------|--------------|
| | From | To | | |
| 1 | 148+589 | 148+790 | 201.5 | TCS-1 |
| 2 | 148+790 | 150+290 | 1500 | TCS-3 |
| 3 | 150+290 | 150+490 | 200 | TCS-4 |
| 4 | 150+490 | 150+940 | 450 | TCS-3 |
| 5 | 150+940 | 151+082 | 142 | TCS-2 |
| 6 | 151+082 | 151+112 | 30 | Minor Bridge |
| 7 | 151+112 | 151+240 | 128 | TCS-2 |
| 8 | 151+240 | 151+690 | 450 | TCS-3 |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”


| Sr. No. | Design Chainage in km | | Design Length in m | TCS No |
|----------------|------------------------------|-----------|---------------------------|---------------|
| | From | To | | |
| 9 | 151+690 | 152+290 | 600 | TCS-2 |
| 10 | 152+290 | 152+786 | 496 | TCS-3 |
| 11 | 152+786 | 152+796 | 10 | Minor Bridge |
| 12 | 152+796 | 152+890 | 94 | TCS-3 |
| 13 | 152+890 | 153+090 | 200 | TCS-4 |
| 14 | 153+090 | 153+490 | 400 | TCS-3 |
| 15 | 153+490 | 154+090 | 600 | TCS-2 |
| 16 | 154+090 | 156+290 | 2200 | TCS-3 |
| 17 | 156+290 | 156+490 | 200 | TCS-4 |
| 18 | 156+490 | 157+740 | 1250 | TCS-3 |
| 19 | 157+740 | 158+050 | 310 | TCS-2 |
| 20 | 158+050 | 158+060 | 10 | Minor Bridge |
| 21 | 158+060 | 158+910 | 850 | TCS-2 |
| 22 | 158+910 | 159+079 | 169 | TCS-3 |
| 23 | 159+079 | 159+089 | 10 | Minor Bridge |
| 24 | 159+089 | 159+293 | 204 | TCS-3 |
| 25 | 159+293 | 159+303 | 10 | Minor Bridge |
| 26 | 159+303 | 160+440 | 1137 | TCS-3 |
| 27 | 160+440 | 161+140 | 700 | TCS-2 |
| 28 | 161+140 | 163+285 | 2145 | TCS-3 |
| 29 | 163+285 | 163+295 | 10 | Minor Bridge |
| 30 | 163+295 | 163+740 | 445 | TCS-3 |
| 31 | 163+740 | 163+790 | 50 | TCS-2 |
| 32 | 163+790 | 163+800 | 10 | Minor Bridge |
| 33 | 163+800 | 163+933 | 132.5 | TCS-2 |
| 34 | 163+933 | 164+038 | 105 | Major Bridge |
| 35 | 164+038 | 164+115 | 77.5 | TCS-2 |
| 36 | 164+115 | 164+125 | 10 | Minor Bridge |
| 37 | 164+125 | 164+385 | 259.8 | TCS-2 |
| 38 | 164+385 | 164+409 | 24.4 | Minor Bridge |
| 39 | 164+409 | 164+710 | 300.45 | TCS-2 |
| 40 | 164+710 | 164+750 | 40.7 | Minor Bridge |
| 41 | 164+750 | 164+829 | 78.65 | TCS-2 |
| 42 | 164+829 | 164+839 | 10 | Minor Bridge |
| 43 | 164+839 | 164+890 | 51 | TCS-2 |
| 44 | 164+890 | 164+938 | 47.5 | TCS-3 |
| 45 | 164+938 | 164+963 | 25 | Minor Bridge |
| 46 | 164+963 | 164+999 | 36 | TCS-3 |
| 47 | 164+999 | 165+024 | 25 | Minor Bridge |
| 48 | 165+024 | 166+990 | 1966.5 | TCS-3 |
| 49 | 166+990 | 167+590 | 600 | TCS-2 |
| 50 | 167+590 | 168+690 | 1100 | TCS-3 |
| 51 | 168+690 | 169+790 | 1100 | TCS-2 |
| 52 | 169+790 | 170+260 | 470 | TCS-3 |
| 53 | 170+260 | 170+450 | 190 | TCS-4 |
| 54 | 170+450 | 170+460 | 10 | Minor Bridge |
| 55 | 170+460 | 170+780 | 320 | TCS-4 |
| 56 | 170+780 | 171+590 | 810 | TCS-3 |
| 57 | 171+590 | 172+410 | 820 | TCS-2 |
| 58 | 172+410 | 173+090 | 680 | TCS-3 |
| 59 | 173+090 | 173+590 | 500 | TCS-4 |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| Sr. No. | Design Chainage in km | | Design Length in m | TCS No |
|----------------|------------------------------|-----------|-------------------------------|---------------|
| | From | To | | |
| 60 | 173+590 | 173+890 | 300 | TCS-3 |
| 61 | 173+890 | 175+090 | 1200 | TCS-2 |
| 62 | 175+090 | 175+160 | 70 | TCS-3 |
| 63 | 175+160 | 175+300 | 140 | TCS-4 |
| 64 | 175+300 | 176+390 | 1090 | TCS-3 |
| 65 | 176+390 | 176+532 | 142.04 | TCS-2 |
| Total | | | 27943.5 | |


Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI)."

TCS




TCS-I TYPICAL CROSS SECTION FOR 2 LANE CARRIAGEWAY WITH
PAVED SHOULDER IN ROLLING/MOUNTAINOUS TERRAIN WITH LEFT SIDE CUT (RURAL SECTION)

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI)."



Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”



[illegible]

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

Schedule B-1

The shifting of utilities and felling of trees shall be carried out by the contractor. The cost of the same shall be borne by the Authority. The details of utilities are as follows:

| Sl. No. | Type of Utility | Unit | Quantity | Location/stretch (LHS/RHS) |
|----------------|------------------------------|-------------|-----------------|-----------------------------------|
| A | Electrical Utilities | | | |
| A1 | Electrical poles single arm | Nos. | 239 | 112 LHS/127 RHS |
| | Double arm | Nos. | 49 | 20 LHS/29 RHS |
| A2 | Electrical cables | Meters | 600 | |
| A3 | Transformers | Nos. | 16 | RHS |
| B | Water/Sewage pipeline | | | |
| B1 | Water pipeline | m | 200 | |
| C | Felling of Trees | Nos. | 46 | |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

Schedule - C

(See Clause 2.1)

Project Facilities

1. ProjectFacilities

The Contractor shall construct the Project Facilities in accordance with the provisions of this Agreement. Such Project Facilities shall include:

- (a) tollplaza[s]
- (b) roadside furniture
- (c) pedestrian facilities
- (d) tree plantation
- (e) truck lay-byes
- (f) bus-bays and bus shelters
- (g) rest areas
- (h) rainwater harvesting and
- (i) others to be specified

2. Description of Project Facilities

Each of the Project Facilities is described below:

- (a) Rainwater Harvesting: As per Ministry of Environment and Forest notification, dated 8 October 2019 and 23 April 2010, construction of rainwater harvesting structure has been adopted accordingly.54 nos. of recharge shaft of 0.5 m dia. for 10 to 15 m depth one on each side of the carriageway are proposed.
- (b) Bus Stop: To promote and facilitate the use of public transport bus stops have been proposed along the length of the project. A total of 38 nos. (2x19nos) of bus stops with bus shelter have been proposed. The location may be decided during the execution with concern of Authority Engineer. The tentative locations are presented in table below:

| SL No | Chainage | Side |
|--------------|-----------------|-------------|
| 1 | 148+840 | Both |
| 2 | 151+260 | Both |
| 3 | 152+740 | Both |
| 4 | 154+590 | Both |
| 5 | 156+160 | Both |
| 6 | 156+940 | Both |
| 7 | 157+690 | Both |
| 8 | 159+590 | Both |
| 9 | 161+740 | Both |
| 10 | 162+690 | Both |
| 11 | 164+340 | Both |
| 12 | 165+390 | Both |
| 13 | 166+790 | Both |
| 14 | 168+240 | Both |
| 15 | 170+540 | Both |
| 16 | 172+490 | Both |
| 17 | 173+790 | Both |
| 18 | 175+570 | Both |
| 19 | 176+430 | Both |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

Schedule - D

(See Clause 2.1)

Specifications and Standards

1. Construction

The Contractor shall comply with the Specifications and Standards set forth in Annex- I of this Schedule-D for construction of the Project Highway.

2. Design Standards

The Project Highway including Project Facilities shall conform to design requirements set out in the following documents:

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

Annex – I

(Schedule-D)

Specifications and Standards for Construction

1. Specifications and Standards

All Materials works and construction operations shall conform to the Manual of Specifications and Standards for Two-Laning of Highways IRC:SP:73-2018, Hill Road Manual (IRC:SP: 48-1998), and MORTH Specifications for Road and Bridge Works. Where the specification for a work is not given, Good Industry Practice shall be adopted to the satisfaction of the Authority’s Engineer.

2. Deviations from the Specifications and Standards

- (i) The terms “Concessionaire”, “Independent Engineer” and “Concession Agreement” used in the Manual shall be deemed to be substituted by the terms “Contractor”, “Authority’s Engineer” and “Agreement” respectively.
- (ii) Notwithstanding anything to the contrary contained in Paragraph 1 above, the following Specifications and Standards shall apply to the Project Highway, and for purposes of this Agreement, the aforesaid Specifications and Standards shall be deemed to be amended to the extent set forth below:

| Sr. No. | Item | Clause referred in Manual | Provision as per Manual | Modified Provision |
|----------------|----------------------------|----------------------------------|--|--|
| 1 | Design Speed | 2.2.1 | Mountainous and steep terrain (cross slope of the ground more than 25%) Minimum design speed 40 kmph. | The design speed shall be the minimum design speed of 40 kmph except the locations given in alignment drawing (Annex-III, Schedule A). |
| 2 | Width of Shoulders | 2.6.1 | | These clauses are deemed to be amended as shown in the typical cross section (refer Schedule B). |
| 3 | Roadway Width | 2.7 | | |
| 4 | Typical Cross section | 2.16 | | |
| 5 | Typical Cross Section | 2.6.1, 2.7 and 2.16 | | |
| 6 | Radii of Horizontal Curve | 2.9.4 | | |
| 7 | Radii of Horizontal Curves | 2.9.4 | Mountainous and steep terrain, desirable minimum radii and absolute minimum shall be 150 m and 75 m, respectively. | Mountainous and steep terrain, desirable minimum radii and absolute minimum shall be 150 m and 75 m, respectively except at the location given in alignment drawing (Annex-III, schedule A). |
| 8 | Width of New Bridge | 7.3 | | To be amended as shown in the typical Cross section. |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

ATTACHMENT-DI

TECHNICAL SPECIFICATIONS FOR ROAD & BRIDGE

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

Table of Contents

1.1 Site Information General

1.1.4 Seismic Zone

2 GENERAL REQUIREMENTS

2.1 Part-I: General Technical Specifications

2.2 Part-II: Supplementary Technical Specifications

2.3 PART-III Specifications for Miscellaneous Works

CLAUSE 102 DEFINITIONS

CLAUSE 106 CONSTRUCTION EQUIPMENT

CLAUSE 108 SITE INFORMATION

CLAUSE 109 SETTING OUT

CLAUSE 111 PRECAUTIONS FOR SAFEGUARDING THE ENVIRONMENT

Sub-Clause 111.1 General

Sub-Clause 111.2 Borrow Pits for Embankment Construction

Sub-Clause 111.3 Quarry Operations

Sub-Clause 111.5 Pollution from Hot-Mix Plant and Batching Plants

Sub-Clause 111.8.2 Air Quality

Sub-Clause 111.8.3 Water Sources and Water Quality

Sub-Clause 111.20 Control and Disposal of Wastes

Sub-Clause 111.14 Equipment and Vehicles used for the Works

Sub-Clause 111.15 Noise Control

Sub-Clause 111.16 Vibration Control

Sub-Clause 111.17 Measurement

CLAUSE 112 ARRANGEMENT FOR TRAFFIC DURING CONSTRUCTION

Sub-Clause 112.6 Measurement for Payment and Rates

CLAUSE 114 SCOPE OF RATES FOR DIFFERENT ITEMS OF WORK

CLAUSE 115 METHODOLOGY AND SEQUENCE OF WORK

Sub-Clause 115.1 Submission of Method Statement

Sub-Clause 115.2 Approval of Proprietary Product/Process/System

CLAUSE 120 FIELD LABORATORY

Sub-Clause 120.3 Ownership

Sub-Clause 120.4 Maintenance

Sub-Clause 120.5 Rate

SECTION 200 Site Clearance

CLAUSE 201 CLEARING AND GRUBBING

CLAUSE 202 DISMANTLING CULVERTS, BRIDGES AND OTHER STRUCTURES/ PAVEMENTS

SECTION 300 Earthwork, Erosion Control and Drainage

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

CLAUSE 301 EXCAVATION FOR ROADWAY AND DRAINS

CLAUSE 304 EXCAVATION FOR STRUCTURES

CLAUSE 305 EMBANKMENT CONSTRUCTION

Sub-Clause 305.2.2.2 Borrow Materials

Sub-Clause 305.2.2.4 Compaction Requirements

Sub-Clause 305.3 Construction Operations

Sub-Clause 305.8 Measurement for Payment

CLAUSE 306 SOIL EROSION AND SEDIMENTATION CONTROL

SECTION 400 Sub-Bases, Bases (Non-Bituminous) and Shoulders

CLAUSE 401 GRANULAR SUB -BASE

Sub-Clause 401.2.2 Physical Requirements

CLAUSE 406 WET MIX MACADAM SUB -BASE/BASE

Sub-Clause 406.4 Opening to Traffic

SECTION 500 Base and Surface Courses (Bituminous)

Sub-Clause 501.2 Materials

Sub clause 501.2.1 Binder

Binder of VG-30 grade shall be used or if available viscosity grade of bitumen shall be used in accordance with IS: 73

CLAUSE 505 DENSE BITUMINOUS MACADAM

CLAUSE 507 BITUMINOUS CONCRETE

Binder of CRMB-60 grade shall be used.

SECTION 800 Traffic Signs, Markings and Other Road Appurtenances

CLAUSE 803 ROAD MARKINGS

CLAUSE 806 ROAD DELINATORS

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

TECHNICAL SPECIFICATIONS

- 1** The Technical Specifications contained herein shall be read in conjunction with the other Bidding Documents as specified in Volume-IX.

1.1 Site Information General

- 1.1.1 The information given hereunder and provided elsewhere in these documents is given in good faith by the Employer, but the Contractor shall satisfy himself regarding all aspects of site conditions and no claim will be entertained on the plea that the information supplied by the Employer is erroneous or insufficient.

- 1.1.2 The area in which the works are located is in partly hilly terrain and partly in plain/rolling terrain, Snow Bound Area the project road starts from 33.5640° N, 75.3602° E and ends at 33.7184° N, 75.1677° E in the UT of Jammu & Kashmir.

1.1.3 Climatic Conditions

- 1.1.3.1 The temperature in this region is as under:

- i) During summer months, the temperature varies from 14°C to 30°C.
- ii) During winter months, the temperature varies from -2°C to 10°C.
- iii) The location receives about 300 mm of rain, with January the wettest month.

1.1.4 Seismic Zone

The stretch lies in Seismic Zone-IV as defined in Fig. 18 of IRC: 6-2017.

2 GENERAL REQUIREMENTS

The Technical Specifications in accordance with which the entire work described hereinafter shall be constructed and completed by the Contractor shall comprise of the following:

2.1 Part-I: General Technical Specifications

The General Technical Specifications shall be the "SPECIFICATIONS FOR ROAD AND BRIDGE WORKS" (Fifth Revision, April 2013), issued by the Ministry of Road Transport and Highways, Government of India and published by the Indian Roads Congress, henceforth called MORT&H Specifications and deemed to be bound into this document.

2.2 Part-II: Supplementary Technical Specifications

The Supplementary Technical Specifications shall comprise of various Amendments/Modifications/ Additions to the "SPECIFICATIONS FOR ROAD AND BRIDGE WORKS" referred to in Part-I above and Additional Specifications for item of works which are not covered in Part-I.

- 2.3** A clause or a part thereof in "SPECIFICATIONS FOR ROAD AND BRIDGE WORKS (Fifth Revision April 2013)", referred in Part-I above, where Amended/Modified/Added upon, and incorporated in Part-II, referred to above, such Amendment/Modification/ Addition supersedes the relevant Clause or part of the Clause.

- 2.3.1 The Additional Specifications shall comprise of specifications for item of works which not covered in Part-I.

- 2.3.2 When an Amended/Modified/Added Clause supersedes a Clause or part thereof in the said Specifications, then any reference to the superseded Clause shall be deemed to refer to the Amended/Modified/Added Clause or partthereof.

- 2.3.3 In so far as Amended/Modified/Added Clause may come in conflict or be inconsistent with any of the provisions of the said MORT&H Specifications under reference; the Amended/Modified/Added Clause shall alwaysprevail.

- 2.3.4 The following Clauses in the "SPECIFICATIONS FOR ROAD AND BRIDGE WORKS (Fifth Revision

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

April 2013”), have been Amended/Modified/Added upon

| Sr. No. | Section No. | Section Title | Clause No. |
|----------------|--------------------|--|--|
| 1. | 100 | General | 102,106,108,109, 111,112,114,115 and 120 |
| 2. | 200 | Site Clearance | 201 and 202 |
| 3. | 300 | Earthwork, Erosion Control and Drainage | 301,304,305 and 306 |
| 4. | 400 | Sub-base, Bases (Non-Bituminous) and Shoulder | 401and 406 |
| 4. | 500 | Bases and Surface Courses (Bituminous) | 501,505 and 507 |
| 5. | 800 | Traffic signs, Markings and other Road Appurtenances | 803 and 806 |
| 6. | 2100 | Open Foundations | 2104 |

2.4 PART-III Specifications for Miscellaneous Works

Technical Specifications for Miscellaneous works shall be the latest “Specifications volume I to VI, 1996 for Civil Works and General Specifications for Electrical Works PART I – INTERNAL, PART – II, EXTERNAL for electric work 1994 as published by the Central Public Works Department (CPWD), Government of India” and deemed to be bound into this document.

- 2.5** The latest edition till 60 days before the final date of submission of the bid of all specifications / standard shall be applicable.

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

SCOPE OF WORKS

Road Works

Site clearance; setting-out and layout; widening of existing carriageway and strengthening including camber corrections; construction of new road/ parallel service road; bituminous pavements remodelling/construction of junctions, intersections, bus bays, lay byes; supplying and placing of drainage channels, flumes, guard posts, guard rails and other related items; construction/extension of cross drainage works, bridges, approaches and other related works; road markings, road signs and kilometer/ hectometre stones; protective works for roads/ bridges; all aspects of quality assurance of various components of works; rectification of the defects in the completed works during the Defect Liability Period; submission of “As built” drawings and any other related documents; and other items of work as may be required to be carried out for completing the works in accordance with the drawings and provisions of the Contract to insure safety.

Other Items

Execution of any other items of work for the construction and completion of the Works in accordance with the provisions of the Contract including all incidental items as well as preparation and submittal of reports, plans as may be required.

During the period of the Contract the right of way and all existing roads shall be kept open for traffic and maintained in a safe and usable condition. Residents along and adjacent to the works are always to be provided with safe and convenient access to their properties. Traffic control and traffic diversions shall be used as necessary to protect the works and maintenance will be carried out as directed by the Engineer and provided in the Contract.

Any other items as required to fulfil all contractual obligations as per the Bid Documents.

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI)."

PART II

SUPPLEMENTARY TECHNICAL SPECIFICATION

AMENDMENTS/MODIFICATIONS/ADDITIONS TO EXISTING CLAUSES OF GENERAL TECHNICAL SPECIFICATIONS

SECTION 100 General

CLAUSE 102

DEFINITIONS

The following abbreviations shall be added in this Clause: "MORT&H" :
Ministry of Road Transport & Highways

(Previously known as 'MOST', Ministry of Surface Transport)

"NHAI" : National Highways Authority of India

CLAUSE 106

CONSTRUCTION EQUIPMENT

Add the following sub para (g) and (h) after sub para (f)

- Adequate standby equipment including spare parts shall be available.
- All measuring devices and gauges shall be in good working condition. Measuring devices that can affect product quality shall be calibrated prior to use and at prescribed intervals against certified equipment. Calibration procedures shall be established, maintained and documented and corrective actions taken when results are unsatisfactory. Accuracy and fitness of measuring devices shall be ensured by proper maintenance.

CLAUSE 108

SITE INFORMATION

Sub-Clause 108.4

This clause shall be as follows:

"Identification of quarry sites and borrow areas shall be the responsibility of the Contractor. Materials procured from quarry sites and borrow areas identified by Contractor and to be used in Works must comply with the requirements of quality as stipulated in the Technical Specification for particular items of work."

CLAUSE 109

SETTING OUT

Sub-Clause 109.8

Delete the 2nd and 3rd sentences in Clause 109.8 and substitute the following:
"Setting out of the road alignment and measurement of angles shall be done by using Total Station."

CLAUSE 111

PRECAUTIONS FOR SAFEGUARDING THE ENVIRONMENT

Sub-Clause 111.1

General

Delete the text of Clause 111.1 in its entirety and substitute the following:

"The Contractor shall take all necessary measures and precautions and otherwise ensure that the execution of the Works and all associated operations on site or off-site are carried out in conformity with statutory and regulatory requirements including those prescribed elsewhere in this document.

The Contractor shall take all measures and precautions to avoid any nuisance or disturbance arising for the execution of the Works. This shall wherever possible be achieved by suppression of the nuisance at source rather than abatement of the nuisance once generated. All vehicles deployed for material haulage shall be spillage proof.

Haul roads shall be inspected at least once daily to clear any accidental spillage. In the event of any spoil, debris, wastes or any deleterious substance

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI)."

from the Site being deposited on any adjacent land, the Contractor shall immediately remove all such material at no cost to the Contract and restore the affected area to its original state to the satisfaction of the Engineer."

Sub-Clause 111.2 Borrow Pits for Embankment Construction

Delete the text of Clause 111.2 and substitute the following:

"Prior approval shall be sought from the concerned State Authorities, and the Contractor shall comply with all local environmental regulations. For all borrow areas, the actual extent of area/zones to be excavated shall be demarcated with the signboards and the operational areas shall be access controlled.

In the case of borrow from tank beds, a regrade/improvement of the inlet channels (at least up to 100m stretch) shall be undertaken in consultation with the concerned state government departments (the Minor Irrigation department of the State PWD) and local bodies. The Contractor shall ensure that excavation of tank beds is uniform over the entire area and that the finished profile of the bed is smooth.

In the case of borrow from the dry highlands, all borrow areas shall be reinstated by the formation gentle side slopes, re-vegetated and connected to the nearest drainage channel to avoid the formation of pools during/after the rainy seasons.

Plant and machinery used in the borrow areas shall conform to State noise emission regulations. All operation areas shall be water sprinkled to contain dust levels to the National Ambient Air Quality Standards."

Sub-Clause 111.3 Quarry Operations

Delete the text of Clause 111.3 and substitute the following:

"Aggregates shall be sourced only from quarry sites that comply with the local/state environmental and other applicable regulations. Occupational safety procedures/practices for the work force in all quarries shall be in accordance with applicable laws. Quarry and crushing units shall have adequate dust suppression measures, such as sprinklers, in work areas and along all approach roads to the quarry sites. These shall preferably be located on the upwind side."

Sub-Clause 111.5 Pollution from Hot-Mix Plant and Batching Plants

Delete the 1st sentence of Clause 111.5 and substitute the following:

"Bituminous hot mix plant and concrete batching plants shall be located at least one (1) km away from the sensitive receptors (schools, hospitals, etc.) and at least 500m from urban settlements, unless otherwise required by the statutory requirements."

Sub-Clause 111.8.1 Environmental Protection:

Add the following sentences in the first paragraph of Sub Clause 111.8.1:

Water tankers with suitable sprinkling system shall be deployed along the haulage roads and in the work sites. Water shall be sprinkled regularly all along the routes to suppress airborne dusts from truck/dumper movements particularly on unpaved roads. Actual frequency will be agreed with the Engineer to suit site conditions."

Sub-Clause 111.8.2 Air Quality

The Contractor shall devise and implement methods of working to minimize

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

dust, gaseous and other air-borne emissions and carry out the Works in such a manner as to minimize adverse impacts on the air quality. Construction camps shall have facilities for LPG fuel. The use of firewood shall not be permitted.

The Contractor shall utilize effective water sprays during delivery, manufacture, processing and handling of materials when dust is likely to be created, and to dampen stored materials during dry and windy weather. Stockpiles of friable materials shall be covered with clean tarpaulins, with applications of sprayed water during dry and windy weather. Stockpiles of materials or debris shall be dampened prior to their movement, except where this is contrary to the Specification.

Any vehicle with an open load-carrying area used for transporting potentially dust-producing material shall have properly fitting side and tail boards. Materials having the potential to produce dust shall not be loaded to a level higher than the side and tail boards and shall be covered with clean tarpaulins in good condition. The tarpaulin shall be properly secured and extend at least 300mm over the edges of the side of the side and tailboards.

The Contractor shall monitor air-quality once weekly in all operational areas under the project and take the necessary steps to comply with the specified requirements. Air quality parameters will include SPM, RPM, SO₂, NO_x, HC and CO. operational areas include work sites, haulage roads, hot mix plants, quarries, crushing plants, stockpiles, borrow sites and spoil disposal sites.

Sub-Clause 111.8.3

Water Sources and Water Quality

The Contractor shall provide independent sources of water supply, such as bore wells, for use in the Works and for associated storage, workshop and work force compounds. Prior approval shall be obtained from the relevant State Authorities and all installations shall follow local regulations. Bore wells installed and used for the project shall be left in good operating condition for the use of NHAI and local communities. The Contractor shall prevent any interference with the supply to or abstraction from and prevent any pollution of water resources (including underground percolating water) as a result of the execution of the Works.

Areas where water is regularly or repetitively used for dust suppression purposes shall be laid to fall to specially constructed settlement tanks to permit sedimentation of particulate matter. After settlement, the water may be re-used for dust suppression and rinsing. The Contractor shall protect all watercourses, waterways, ditches, canals, drains, lakes and the likes from pollution as a result of the execution of the Works.

All water and other liquid waste products arising on the Site shall be collected and disposed of at a location on or off the Site and in a manner that shall not cause either nuisance or pollution.

The Contractor shall at all times ensure that all existing stream courses and drains within, and adjacent to, the Site are kept safe and free from any debris and any materials arising from the Works. The Contractor shall not discharge or deposit any matter arising from the execution of the Works into any water except with the permission of the Engineer and the regulatory authority concerned.

Work force camps shall have septic tank and soak away pits. Operational areas like POL storage areas/hot mix plant areas shall comply with local/state environmental regulations and safety procedures. Storage and handling areas shall be impervious and surrounded by an impervious lined drain to catch any

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

accidental spills. Storm water shall be stored in lined holding tanks with oil, grease-tapping facility prior to disposal in to nearby watercourses. The trappings and sludge of holding tanks shall be disposed off in accordance with the procedures approved by the local regulatory authority.

Sub-Clause 111.20 Control and Disposal of Wastes

The Contractor shall control the disposal of all forms of waste generated by the construction operations and in all associated activities. No uncontrolled deposition or dumping shall be permitted. Wastes to be so controlled shall include, but shall not be limited to, all forms of fuels and engine oils, all types of bitumen, cement, and surplus aggregates, gravels, bituminous mixtures etc. The Contractor shall make specific provision for the proper disposal of these and any other waste products, conforming to local regulations and acceptable to the Engineer.

Spilling of oil and bituminous products during construction and transport shall be avoided to reduce the chances of contamination of surface as well as ground water.

Degraded materials shall be disposed of in a manner as approved by the Engineer and wastewater shall be disposed into septic tanks and soak pits etc. The Contractor shall make arrangements to clean-up spoil as soon as the work finishes in a stretch. If such sites are located outside the ROW, restoration of the site to a level acceptable to the land owner(s) will be carried out within a time period agreed between landowner(s) and the Contractor. Separators shall be used to separate POL materials from wastewater prior to discharging to the watercourses or as approved by the Engineer in conformance with directives and guidelines.

Disposal of solid waste materials shall be outlined in a plan for which environmental clearances shall be obtained from State environmental regulatory authorities. Potential locations for solid waste disposal are the natural depressions and borrow areas. The areas used for dumping of uncontaminated debris shall be covered with 300mm soil and shall be planted. Contaminated debris shall be dumped in depressions whose bed must be impervious e.g., stone quarry sites or depressions made impervious with 450mm thick impervious floor apron as per MORT&H Technical Specifications. Each successive 1.0m layers shall be covered with 500mm thick soil layer, and the area will be covered with 300mm thick layer and planted.

After Clause 111.12 add the following new Clauses 111.13 to 111.17

Sub-Clause 111.13 Haulage Roads

Existing roads used for hauling shall be strengthened and/ or widened by the Contractor in accordance with the requirements for normal and construction traffic.

Where such roads are not existing, the Contractor shall construct project specific single lane paved roads in settlement areas and gravel roads in open areas conforming to the Ministry of Road Transport and Highways (MORT&H) specifications.

The alignment of the haulage roads shall be fixed to avoid agricultural land to the extent possible. In unavoidable circumstances, suitable compensation shall be paid to the people whose land will be temporarily acquired for the duration of the operations. The compensation shall cover for loss of income for the

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

duration of temporary acquisition and land restoration. Prior to the construction of the haul roads, topsoil shall be stripped and stockpiled for re-use.

Material dumping sites shall be access controlled to prevent the unauthorized entry of the people, grazing cattle and stray animals.

Haulage roads shall be reinstated upon completion of hauling for the use of local communities.”

Sub-Clause 111.14 Equipment and Vehicles used for the Works

Equipments and vehicles deployed for the construction activities shall not be older than 5 years. Equipments used for road and bridge works shall be based on new technology and shall generate noise and pollutants not exceeding the limits specified by the relevant State Authorities. Vehicles and machineries used for road and bridge works are to be regularly maintained to conform to the National Air Quality Standards. Blasting, if any, will be carried out using smallcharges.

Sub-Clause 111.15 Noise Control

The Contractor shall consider noise as an environmental constrain in the planning and execution of the Works.

The Contractor shall take all necessary measures so that the operation of all mechanical equipment and construction processes on and off the site shall not cause any unnecessary or excessive noise, taking in to account applicable environmental requirements. The Contractor shall use all necessary measures and shall maintains all plant and silencing equipment in good conditions so as to minimize the noise emission during constructionworks.

Any member of the work force likely to be exposed to beyond their thresholdnoise levels shall be provided with protective equipment, such as earplugs, and shall be rotated every fourhours.

Construction operations shall be limited to daytime hours only, particularly in the settlement areas.

Sub-Clause 111.16 Vibration Control

The Contractor shall take measures during construction activities to control the movement of the work force and construction machinery/equipment, and to avoid/ minimize activities, which produce vibrations.

Sub-Clause 111.17 Measurement

Monitoring of Air/Water/Noise and Soil quality shall be paid as per numbers of samples tested. For Compliance of all other provisions made in this Clause 111, it shall be deemedtobeincidentaltotheworkandnoseparatemeasurementsshallbemade. The Contractor shall be deemed to have made allowance for such compliance with these provisions in the preparations of his prices for items of work included in the Bills of Quantities and full compensation for such compliance shall be deemed to be covered bythem.”

CLAUSE 112 ARRANGEMENT FOR TRAFFIC DURING CONSTRUCTION

Sub-Clause 112.4 Traffic Safety and Control

Last line of Para 5 shall be read as under:

“The signs shall be of approved design and of reflector type.” **Add the following paragraph at the end of the clause:**

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

“Before commencement of any construction, the Contractor shall prepare and submit details of the arrangements for passing traffic during construction, design of barricades, signs, markings, lights, flags etc. conforming and satisfying the requirements of the “Guidelines on Safety in Road Construction Zones” of IRC: SP 55-2001 and get the same approved by the Engineer.

Sub-Clause 112.6 Measurement for Payment and Rates

- a) The provision of treated shoulder including construction of temporary cross drainage structures, if required, as described in Clause 112.2 including their maintenance, dismantling and clearing debris, where necessary, shall be considered as incidental to the works and shall be Contractor’s responsibility.
- b) The Construction of temporary diversion including temporary cross drainage structures as described in subclause 112.3, shall be measured in linear meter and the unit contract rate shall be inclusive of full compensation for construction (including supply of material, labor, tools, etc.), maintenance as per sub clause 112.5, final dismantling, and disposal.
- c) All Traffic safety and control devices during construction as per sub clause 112.4 including providing, erecting and maintaining barrier, signs, markings, flags, lights and providing flag men etc. is included in item rate.

CLAUSE 114 SCOPE OF RATES FOR DIFFERENT ITEMS OF WORK

Sub-Clause 114.2 Item (ii) of Clause 114.2 shall read as follows:

A detailed resource-based construction programme including resources planning using computerized critical path network method/PERT in a form, which facilitates control of the progress of the works and consequences of any changes in terms of time. The programme shall also include detailed network, activities for the submission and approval of materials, procurement of critical materials and equipment, fabrication of special products/ equipment and their installation and testing and for all activities of the Contractor that are likely to affect the progress of work etc. including updating all such activities on the basis of decisions taken at the periodic site review meetings or as directed by the Engineer. The Contractor shall submit data via electronic media to the Engineer in a form readily compatible with Engineer’s planning system.

The first issue of the detailed construction programme including the detailed description of the system and the procedures shall be submitted to the Engineer for acceptance not later than 28 days after the date of receipt of the letter of acceptance.

The contractor shall submit to the Engineer for approval & consent, the updated & revised programme at every three months interval or as such as directed by the Engineer. The updated & revised programme shall be submitted showing the actual progress achieved (physical & financial) and the effects of the progress achieved on the timing of the remaining work including any change to the sequence of the activities

CLAUSE 115 METHODOLOGY AND SEQUENCE OF WORK

The Clause shall be substituted as follows:

Sub-Clause 115.1 Submission of Method Statement

The Contractor shall submit methods statement within 28 days after the date of letter of acceptance. The methods statement shall be submitted in two parts.

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

The General part of the methods statement shall describe the Contractor’s proposals regarding preliminary works, common facilities, and items that require consideration at the early stage of the Contract. The General part shall be furnished along with the first issue of the construction programme (refer clause 114.2) and shall include information on:

- a) Sources of materials like coarse aggregate and fine aggregate, quantity and quality of materials available in different sources;
- b) Sources of manufactured materials like cement, steel, bitumen reinforcement, prestressing strands and bearings. Wherever possible the Contractor shall identify at least two sources for each of the items; he shall also submit test certificates of recently manufactured materials for the consideration of the Engineer.
- c) Locations of site facilities like batching plant, hot mix plant, aggregate processing plant, crushing plant etc.
- d) Details of facilities/approaches for transportation of men, equipment and materials for construction of pavements, foundations and substructure in riverbed, and plan for free traffic flow and safe drainage.
- e) Information on procedures to be adopted by the Contractor for prevention and mitigation of negative environmental impact due to construction activities.
- f) Any other information required by the Engineer subsequent to the scrutiny of method statement

The General part of the Q.A. Programme shall accompany the methods statement under sub-clause 105.3.

The Special part of the methods statement shall be submitted to the Engineer by the Contractor for each important item of work like construction of embankments and subgrade, pavements, pile/well foundations, concreting, prestressing, repair and rehabilitation of existing structures, concrete superstructure, dismantling of structures and pavement and for any other item as directed by the Engineer.

These statements shall give information on

- i) Details of personnel both for execution and quality control of the work.
- ii) Equipment deployment with details of number of units, capacity, standby arrangements
- iii) Sequence of construction, details of temporary or enabling works like, diversions, cofferdams, formwork including specialized formwork for superstructure, details of borrow areas, method of construction of embankment and subgrade, pavements, piles, wells, concreting procedures, details of proprietary process and products (e.g. details of prestressing systems, proprietary piling systems, bearings, expansion joints etc.) and details of equipment to be deployed. Wherever necessary, technical literature, design calculations and drawings shall be included in the methods statement.
- iv) Testing and acceptance procedures including documentation.
- v) Special part of the Q.A. Programme referred in clause 105.3 for the particular item of work shall be submitted along with the methods statement for the concerned activity.
- vi) Engineer shall examine and approve the methods statement or direct

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

the Contractor to resubmit the statement with required modifications. The modified statement shall be submitted within 14 days of receipt of Engineer's comments.

The sole responsibility for the safety and adequacy of the methods adopted by the Contractor shall rest on the Contractor irrespective of any approval given by the Engineer.

Sub-Clause115.2

Approval of Proprietary Product/Process/System

Only proprietary products proven by International usage in comparable projects shall be permitted to be used. Fully authenticated details of licensing and collaboration arrangement shall be submitted by the manufacturer, where relevant.

Within 90 days of award of work the Contractor shall submit the following information for all proprietary products for approval by the Engineer.

i) Name of manufacturer and name of product/ process/system.

Complete details of the manufacturer of the product/ process/ system shall be furnished. Details of projects where similar product/process/system has been successfully used shall be furnished. Authenticated copies of license/collaboration agreement shall be furnished.

ii) General features of the product/product process/system.

Detailed write up with methods statements shall be furnished for each product/ process/ system. This shall include complete working drawings & installation drawings, technical specifications covering fabrication, materials, system of corrosion protection etc.

i) Details of product development and developmenttesting.

ii) Acceptance test andcriteria.

Manufacturer shall submit a quality assurance system document. Details of acceptance test and criteria of acceptance shall be furnished in this document.

i) Installationprocedure.

ii) Maintenance procedure andschedule.

iii) Warranty proposal.

The Engineer may instruct any additional tests for the purpose of accepting the product. The charges of these additional tests shall be borne by the Employeronly in case the product satisfies thespecifications.

CLAUSE 120

FIELD LABORATORY

Sub-Clause 120.2

Description

Replace the words “indicated in the drawings” in the first sentence of second paragraph of this Clause with the words “per provisions indicated in this Clause and at a location approved by the Engineer.”

Replace “electric supply etc.” to the second sentence of first paragraph by “including uninterrupted power supply etc.”

Delete the first sentence of second paragraph “The floor space in the drawing”and substitute the following:

“The floor space required for the field laboratory shall be not less than 200 sq.m.

“The fourth sentenceofsecond paragraphs “Thefurnishing In Table100-2”shall

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

read as under.

“A good semi furnished office accommodation shall be provided to the Material Engineers of the Supervision Team as per the direction of the Engineer.”

Add the following at the end of this Clause:

“There shall also be provided a concrete paved area, for storing samples adjacent to the laboratory, of about 100 sq.m and another 75 sq.m shall be suitably roofed with open sides giving protection against sun and rain.

Within 14 (fourteen) days of the commencement date, the Contractor shall prepare and submit a layout plan and details of the laboratory building and make/supplier of the equipment to the Engineer for his approval.

The field laboratory to be provided under the Contract shall be handed over to the Engineer in finished and fully equipped condition not later than 2 months after the receipt of Notice to Commence Work, and the field laboratory with all equipment/instrument shall be to the entire satisfaction of the Engineer. During the 2-month period starting from the Notice to Commence work, the laboratory tests shall be performed in another laboratory proposed by the Contractor and approved by the Engineer.

Laboratory Equipment

General

The items of laboratory equipment shall be provided in the field laboratory depending upon the items to be executed as per Table mentioned below instead of Table 100-2 shown in MORTH:

The following items of laboratory equipment shall be provided in the field laboratory:

The equipment and instruments shall be new and shall be quality certified by Bureau of Indian Standards (BIS).

| Sr. No. | Sub No. | Item, Specifications | Nos. required |
|-------------------|---|---|----------------------|
| A: General | | | |
| (i) | Balance | | |
| | (a) | 7 kg to 10 kg capacity semi -self indicating Electronic Type –Accuracy 1 gm | 2 |
| | (b) | 500 gm capacity semi-self-indicating Electronic Type – Accuracy 0.01 gm | 2 |
| | (c) | Chemical balance 100gm capacity - Accuracy 0.0001gm | 1 |
| | (d) | Pan balance 5 kg capacity - Accuracy 0.5 gm | 2 |
| | (e) | Platform Scale – 300 kg capacity | 1 |
| | (f) | Triple Beam balance-25kg capacity Accuracy 1gm | 2 |
| (ii) | Ovens – Electrically operated, thermostatically controlled | | |
| | (a) | From 100°C to 220°C – Sensitivity | 2 |
| (iii) | Sieves, as per IS 460-1962 | | |
| | (a) | IS Sieves 450 mm internal dia. of sieve sets as per BIS of required sieve sizes complete with lid and pan | 2 set |
| | (b) | IS sieve 200 mm internal dia. (brass frame and steel or brass wire cloth mesh) consisting of sieve sets of required sieve sizes complete with lid and pan | 2 set |
| (iv) | Sieve shaker capable of taking 200 mm and 450 mm dia. Sieves electrically | | 1 |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| | | |
|--------|--|--------------|
| | operated with time switch assembly (As per BIS) | |
| (v) | 200 tones compression testing machine | 1 |
| (vi) | Stop watches 1/5 sec. Accuracy | 2 |
| (vii) | Glassware comprising of Beakers, Pipettes, dishes, measuring cylinders (100 to 1000 cc capacity) glass rods and funnels, glass thermometers range 0°C to 100°C and metallic thermometers range 300°C | 1 Dozen each |
| (viii) | Hot plates 200 mm dia (1500 watt) | 6 |
| (ix) | Enamel trays | |
| | (a) 600 mm x 450 mm x 50 mm | 10 |
| | (b) 450 mm x 300 mm x 40 mm | 10 |
| | (c) 300 mm x 250 mm x 40 mm | 6 |
| | (d) Circular plates of 250 mm dia. | 6 |
| (x) | Water Testing Kit | 1 |
| (xi) | First Aid Box | 1 |
| (xii) | Spatula Set of 100 and 200 long | 3 |
| (xiii) | Digging Tools (pixels, shovel, fork etc.) | As reqd. |
| (xiv) | Miscellaneous tools (sledge hammer, lump hammer, wooden pegs etc.) | As reqd. |
| (xv) | Maximum and Minimum Thermometer | 2 Set |
| (xvi) | Rain Gauge | 1 Set |
| (xvii) | Timer 0-60 minutes with alarm & 1/5 sec accuracy. | 3 Sets |

| B: For Soils and Aggregates | | |
|------------------------------------|--|--------------|
| (i) | Water still, 3 litre/hr with fittings and accessories | 1 |
| (ii) | Liquid limit device with Casagrande and ASTM grooving tools as per IS: 2720 | 1 |
| (iii) | Sampling pipettes fitted with pressure and suction inlets, 10 mlCapacity | 2 set |
| (iv) | Compaction apparatus (Proctor) as per IS: 2720 (Part 8) complete with collar, base plate and hammer | 1 set |
| (v) | Modified AASHTO compaction apparatus as per IS. 2720 (Part 7) 1980 or Heavy Compaction Apparatus as per IS complete with collar, base plate and hammer | 1 set |
| (vi) | Sand pouring cylinder with conical funnel and tap and complete as per IS 2720 (Part 28) 1980 including modified equipment | 4 |
| (vii) | Sampling tins with lids 100 mm dia x 75 mm ht ½ kg capacity and miscellaneous items like moisture,tins with lid (50 grams) etc. | 12 |
| (viii) | Lab CBR testing equipment for conducting CBR testing, load frame with 5 Ton capacity, electrically operated with speed control as per IS: 2720 (Part 16), and consisting of following: | 1 set |
| | (a) CBR moulds 150-mm dia – 175-mm ht complete with collar, base plateetc. | 24 |
| | (b) Tripod stands for holding dial gauge holder | 24 |
| | (c) CBR plunger with settlement dial gauge holder | 1 |
| | (d) Surcharge weight 147-mm dia 2.5 kg weight with centralhole | 48 |
| | (e) Spacer disc 148-mm dia, 47.7-mm ht. With handle | 3 |
| | (f) Perforated plate (Brass) | 24 |
| | (g) Soaking tank for accommodating 24 CBR moulds | 1 each |
| | (h) Provingringsof1000kg,2500kgand5000kgcapacity | |
| | (i) Dial gauges, 25 mm travel- 0.01 mm/division | |
| | (j) Aluminium Tis | 10 |
| | 50x30m | 36 nos |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| | | |
|--------|---|--------|
| | 55x35m | 36 nos |
| | 70x45m | 36 nos |
| | 70x50m | 36 nos |
| | 80x50m | 36 nos |
| (ix) | Standard Penetration test equipment | 1 |
| (x) | Nuclear Moisture Density Meter or equivalent | 2 |
| (xi) | Speedy moisture meter complete with chemicals | 2 |
| (xii) | Unconfined compression test apparatus | 1 set |
| (xiii) | Aggregate Impact Test Apparatus | 1 |
| (xiv) | Aggregate Impact Test Apparatus as per IS 2386 (Part 4)1963 | 1 |
| (xv) | Los Angeles abrasion Test Apparatus as per IS 2386 (Part 4)1963 | 1 |
| (xvi) | Riffle Box of Slot size of 50mm as per ASTM C-136 | 1 |

| C: For Bitumen and Bituminous Mixes | | |
|--|--|-------------|
| (i) | Constant temperature bath for accommodating bitumen | 2 |
| | Test specimen electrically operated and thermostatically controlled, 50-liter capacity temp. range ambient 80o C | |
| (ii) | Penetrometer automatic type, adjustable weight arrangement and needles as per IS. 1203 – 1978 | 2 |
| (iii) | Solvent extraction or centrifuge type apparatus complete (AASHTO, T-164) with extraction thimbles with stocks of solvent and filter paper | 1 |
| (iv) | Laboratory mixer including required accessories about .02 cum capacity electrically operated fitted with heating jacket | 1 |
| (v) | Marshall compaction apparatus automatically operated as per ASTM 1559-62 T and complete with electrically operated loading unit, compaction pedestal heating head assembly, dial micrometre and bracket for flow measurement, load transfer bar, specimen mould 100 mm dia. (4 in) with base plate, collars, specimen extractor, compaction hammer 4.53 kg (10 lb.) x457 mm (18 in) fall | 1 set |
| (vi) | Distant Reading Digital Thermometer for Measuring Temperatures in Asphaltic Mixes | As required |
| (vii) | Riffle Box | 1 |
| (viii) | Automatic Asphalt Content Gauge [Nuclear are equivalent] | 1 |
| (ix) | Thin film Oven test apparatus to the requirement of AASHTO T 179, including accessories | 1 |
| (x) | Ring Ball Apparatus as per IS 1205- 1978 | 1 |
| (xi) | Asphalt Institute Vacuum Viscometer as per IS 1206(part II) – 1978 | 1 |
| (xii) | BS U- Tube Modified Reverse Floro Viscometer IS 1206(Part III) – 1978 | 1 |
| (xiii) | Apparatus for Determination of Ductility Test as per IS 1208 – 1978 | 1 |
| (xiv) | Pen Sky – Martars closed Tester for testing flashandfire point as per IS 1209 – 1978. | 1 |
| (xv) | Apparatus for Float Test – IS – 1210 – 1978 | 1 |
| (xvi) | Apparatus for Determination of water content (Deanand Shark Method) IS – 1211 – 1978 | 1 |
| (xvii) | Apparatus for Determination of Loss on Heading IS- 1212-1978. | 1 |
| (xviii) | Apparatus of Determination of specified Gravity IS- 1202-1978 | 1 |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| | | |
|--------|---|---|
| (xix) | Core cutting machine with 100mm dia. Diamond cutting Edge | 1 |
| (xx) | Apparatus for Elastic Recovery test for Modified Bitumen | 1 |
| (xxi) | Apparatus for Storage Stability test for Modified Bitumen | 1 |
| (xxii) | Apparatus for Separation test for modified bitumen | 1 |

| D: For Cement, Cement Concrete and Materials | | | |
|--|---|--|-------------|
| (i) | Water still | | 1 |
| (ii) | Vicat needle apparatus for setting time with plungers, as per IS. 269-1967 | | 1 |
| (iii) | Moulds | | |
| | (a) | 150 mm x 300 mm ht cylinder with capping component | As required |
| | (b) | 150mmx150 mm x150mm cubical for compressive strength | As required |
| | (c) | 150mmx100 mm x600mm beam for flexural strength | As required |
| (iv) | Concrete permeability apparatus | | 1 |
| (v) | High frequency mortar cube vibrator for cement testing | | 1 |
| (vi) | Concrete mixer power driven, 1 cu ft. capacity | | 1 |
| (vii) | Variable frequency and amplitude vibrating table size 1 metre x 1 metre, as per the relevant British Standard | | 1 |
| (viii) | Flakiness & Elongation test apparatus | | 2each |
| (ix) | Aggregate impact test apparatus as per IS 2386 (Part 4) 1963 | | 2 |
| (x) | Los Angeles abrasion apparatus as per IS. 2386 (Part 4) 1963 | | 1 |
| (xi) | Flow table as per IS 712-1973 | | 1 |
| (xii) | (a) | Equipment for slump test | 2 |
| | (b) | Compaction factor test equipment | 1 |
| (xiii) | Equipment for determination of specific gravity for fine and coarse aggregate as per IS 2386 (Part 3) 1963 | | 2 |
| (xiv) | Flexural attachment to compression testing machine | | 1 |
| (xv) | Core cutting machine with 150 mm dia. Diamond cutting edge | | 1 |
| (xvi) | Needle vibrator | | 1 |
| (xvii) | Vibrating hammer as per BS specification | | 1 |
| (xviii) | Air entrainment meter ASTM C - 231 | | 1 |
| (xix) | 0.5 Cft, 1 Cft cylinder for checking bulk density of aggregate with tamping rod | | 1 |
| (xx) | Soundness testing apparatus for cement | | 1 |
| (xxi) | Flexural Beam testing machine with accessories | | 1 |
| (xxii) | Chemicals solutions and consumable | | As reqd. |
| (xxiii) | Chloride Testing kit for chemical analysis of chloride content. | | 1 |
| (xxiv) | ION Exchange kit for rapid determination of sulphate content. | | 1 |

| E: For Control of Profile and Surface Evenness | | |
|---|--|--------|
| (i) | Digital Level complete with all accessories | 2 sets |
| (ii) | Distomat or equivalent | 2 Nos. |
| (iii) | Theodolite – Electronically operated with computerized output attachment | 2 sets |
| (iv) | Total Station with all accessories | 2 sets |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| | | |
|--------|--|---------|
| (v) | Towed Fifth Wheel Bump Indicator | 1 set |
| (vi) | 3meter straight edge and measuring wedge | 2 sets |
| | Camber templates 2 lane | |
| (vii) | String line Arrangement with paver and sensor powers | 1 |
| | (a) Crown type cross-section | 2 sets |
| | (b) Straight run cross-section | 2 sets |
| (viii) | Steel tape | |
| | (a) 5 m long | as reqd |
| | (b) 10 m long | as reqd |
| | (c) 20 m long | as reqd |
| | (d) 30 m long | as reqd |
| | (e) 50 m long | As reqd |
| | (e) 50 m long | As reqd |
| (ix) | Precision Staff | 3 Sets |

Note: The laboratory set-up must be complete including a set of reference standards, adequately staffed and operational to the satisfaction of the Engineer not later than 2 months from the date of receipt of Notice to commence the works.

Sub-Clause 120.3 Ownership

This Clause shall read as under:

“Land for the laboratory shall be provided by the Contractor.”

Sub-Clause 120.4 Maintenance

This Clause shall read as under:

“The Contractor shall arrange to maintain the field laboratory including sample store yards in a satisfactory manner until the issue of Taking over Certificate for the whole work. Maintenance includes all activities described in Clause 120.4 and maintenance of equipment and running of the same including chemicals and consumables.”

Sub-Clause 120.5 Rate

The construction, supply, installation, maintenance, and operation including all consumables like chemicals & reagents etc., and all other expenses involved in connection thereto for the field laboratory shall be incidental to the work, and shall not be paid for separately.

SECTION 200 Site Clearance

CLAUSE 201 CLEARING AND GRUBBING

Sub-Clause 201.1 Scope

Replace with following Para:

This work shall consist of cutting, excavating, removing, and disposing of all materials such as trees of girth up to 300 mm, bushes, shrubs, stumps, roots, grass weeds, rubbish etc. and top soil up to 150 mm, which in the opinion of Engineer is unsuitable for incorporation in the work including draining out stagnant water if any from the area of road land, drain, cross drainage structure and other area as specified in the drawing or instructed by Engineer. It shall include necessary excavation by harrow discs or any other suitable equipment, backfilling of the pits by suitable soil, resulting from uprooting of trees & stumps and making the surface in proper grade by suitable equipment and compacted by power roller to required compaction as per Clause 305.3.4.

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI)."

The work also includes handling, salvaging and disposal of cleared material. Clearing and grubbing shall be performed less than one month in advance of earthwork operation and in accordance with requirement of thesespecifications.

CLAUSE 202 DISMANTLING CULVERTS, BRIDGES AND OTHER STRUCTURES/ PAVEMENTS

Sub-Clause 202.5 Disposal of Materials

The first paragraph of the sub clause shall read as below:

All materials obtained of dismantling/milling shall be the property of the Contractor for which he shall quote a rate for rebate in BOQ Bill No. 1, and the Contractor shall be free to use this material in work, or he may sell/dispose the material to as desired / deemed fit by him.

The existing pavement crust shall be reused as indicated below:

Contractor shall be free to use dismantled / milled material, as is where basis is, or by suitably modifying the material, or by crushing the material, or by breaking the material, and screening the same, provided it meets the specifications and is approved by the Engineer.

SECTION 300 Earthwork, Erosion Control and Drainage

CLAUSE 301 EXCAVATION FOR ROADWAY AND DRAINS

Sub-Clause 301.1 Scope

Add the following as second paragraph under this clause:

"The work shall also include excavation for channel training at culverts/bridges, excavation of existing shoulders and medians for purposes of widening the pavement and excavation of existing embankment for reconstruction to specification."

CLAUSE 304 EXCAVATION FOR STRUCTURES

Sub-Clause 304.3.2 Excavation

At the end of 1stparagraph of Clause 304.3.2 inserts the following additional sentences:

"TheContractor shall ensure the stability and structural integrity of adjacent existing foundations and structures and if necessary shall, at his own expense,install temporary or permanent sheet piles, coffer dams, shoring or similar as support or protection to the satisfaction of theEngineer."

CLAUSE 305 EMBANKMENT CONSTRUCTION

Sub-Clause 305.2 Material and General Requirements

Sub-Clause 305.2.1 Physical Requirements:

Sub-Clause 305.2.1.2 Add the following after second paragraph:

"Soils having medium and high swelling potential shall be defined based onLiquid Limit, Plastic Limit, Shrinkage Limit, Gradation, Free swelling Index, Field dry Density and Field Moisture Content and types of Clay minerals present in the soil and as directed by the Engineer. The location and the extent of these soils with medium to high swelling potential should be defined as directed by the Engineer."

Sub-Clause 305.2.2.2 Borrow Materials

Para 1 of this Clause shall read as under:

" No borrow area shall be made available by the Employer for this work. The

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI)."

arrangement for the source of supply of the material for embankment and sub-grade as well as compliance to the different environmental requirements in respect of excavation and borrow areas as stipulated, from time to time, by the Ministry of Environmental and Forest, Government of India and the local bodies, as applicable, shall be the sole responsibility of the Contractor."

Sub-Clause 305.2.2.4 Compaction Requirements

In Clause 305.2.2.4 delete Table 300-2 and substitute the following:

Table 300-2

Compaction Requirements of Embankment and Subgrade

| Sr. No. | Type of Work/Material | Relative Compaction as %age of maximum laboratory dry density as per IS 2720 (Part 8) |
|----------------|---|--|
| 1 | Subgrade and earthen shoulders | Not less than 97% |
| 2 | Embankment | Not less than 95% |
| 3 | Expansive clays | Not allowed |
| 4 | Design CBR of Subgrade & Shoulder has been taken 8. The borrow earth used for subgrade material must satisfied the requirement of the design CBR of 8 % | |

Para 2 of this Clause given below Table 300-2 shall read as under:

The contractor shall at least 21 working days before commencement of construction of embankment and the subgrade; submit the following to the Engineer for approval:

- (i) The values of maximum dry density and optimum moisture content obtained in accordance with IS: 2720 (Part 8) for each fill material proposed to be used in the construction of embankment and subgrade.
- (ii) The graphs of Density plotted against moisture content from which each of the values in (i) above of maximum dry density and optimum moisture content were determined.
- (iii) The dry density-moisture content-CBR relationships, heavy comp active efforts conforming to the IS 2770 (part 8) for each of the fill material proposed to be used in the subgrade.

The above information shall form the basis for compaction only upon its approval by the Engineer."

Sub-Clause 305.3 Construction Operations

Sub-Clause 305.3.4 Compacting Ground Supporting Embankment/Subgrade

Para 1 of this clause shall be read as

"Where necessary the original ground shall be levelled, scarified, mixed with water and then compacted by rolling to facilitate placement of first layer of embankment so as to achieve minimum dry density as given in Table 300-2.

Sub-Clause 305.8 Measurement for Payment

Substitute Clause 305.8.1 shall be read as

"Earth embankment/sub-grade construction shall be measured separately by taking cross sections at intervals after clearing and grubbing and if necessary compaction of original ground before the embankment work starts and after its completion and computing the volumes of earthwork in cubic metres by the method of average and areas."

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI)."

CLAUSE 306 SOIL EROSION AND SEDIMENTATION CONTROL

Sub-Clause 306.4 Measurements for Payment

Substitute Clause 306.4 as follows:

"All temporary sedimentation and pollution control works shall be deemed as incidental to the earthwork and other items of work and as such no separate payment shall be made for the same."

SECTION 400 Sub-Bases, Bases (Non-Bituminous) and Shoulders

CLAUSE 401 GRANULAR SUB BASE

Sub-Clause 401.1 Scope

Add the following at the end of this Clause:

"A site trial shall be performed in accordance with Clause 901.16."

Sub-Clause 401.2.2 Physical Requirements

Add at the end of this clause as under:

The Contractor shall, at least 21 working days before the commencement of the construction of the sub-base course, submit to the Engineer, the results for approval of the laboratory testing on the physical properties defined above. The construction of the sub-base course shall be taken up only upon the Engineer's approval of the material.

Grading-I of table 400-1 shall be adopted at site.

CLAUSE 406 WET MIX MACADAM SUB BASE/BASE

Sub-Clause 406.4 Opening to Traffic

The Clause shall be read as follows:

No vehicular traffic of any kind shall be allowed on the finished wet mix macadam surface.

SECTION 500 Base and Surface Courses (Bituminous)

Sub-Clause 501.2 Materials

Sub clause 501.2.1 Binder

Binder of VG-30 grade shall be used or if available viscosity grade of bitumen shall be used in accordance with IS: 73

Sub-Clause 501.2.2 Delete "Crushed gravel or other hard material" from first Line of Para 1."

Para 3 is deleted.

CLAUSE 505 DENSE BITUMINOUS MACADAM

Sub-Clause 505.2.1 Bitumen

Binder of VG-30 grade shall be used or if available viscosity grade of bitumen shall be used in accordance with IS: 73.

CLAUSE 507 BITUMINOUS CONCRETE

Sub-Clause 507.2.1 Bitumen

Binder of CRMB-60 grade shall be used.

SECTION 800 Traffic Signs, Markings and Other Road Appurtenances

CLAUSE 803 ROAD MARKINGS

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI)."

Sub-Clause 803.2

Materials

This clause shall read as under:

"Road markings shall be hot applied thermoplastic compound and the materials shall meet the requirements as specified in Clause 803.4.

The road markings shall be laid in one layer with appropriate road marking machine approved by the Engineer. Before the road-marking machine is used on the permanent works, the satisfactory working of the machine shall be demonstrated on a suitable site, which is not part of the permanent works. The rate of application shall be checked and adjusted as necessary before application on a large scale is commenced, and thereafter daily."

CLAUSE 806

ROAD DELINATORS

Sub-Clause 806.2

This clause shall read as follows:

- a) Triangular Object Marker shall be 300mm side with four red reflectors, made out of 2mm thick aluminium sheet, face to be fully covered by high intensity grade white retro reflective sheeting of encapsulated lens type as per clause 801. The background/border/symbols shall be made by screen-printing of desired colours as per sign details. The sign plate shall be fixed with 6mm dia. aluminium rivets on MS angle iron frame. The angle iron frame shall be made with angle of size 40mmx40mmx5mm. The sign shall be fixed with nut-bolts & welding on MS pipe 50mm dia (NB-MW) and 500mm high.
- b) Rectangular hazard marker 600mm x 300mm made out of 2mm thick aluminium sheet, face to be fully covered by high intensity grade white retro reflective sheeting of encapsulated lens type. The background/ border/ symbols shall be made by screen-printing of desired colour as per sign details. The sign plate shall be fixed with 6mm dia aluminium rivets on MS angle iron frame. The angle iron frame shall be made with angle of size 40mmx40mmx5mm. The sign shall be fixed to 80mm dia (NB-MW) MS pipe.
- c) Roadway Indicators shall be 1000mm high made with 100 mm dia. NB medium weight MS pipe. One reflector of high intensity grade retro reflective sheeting with encapsulated lens shall be provided on top of the reflector. The white & red reflector shall be provided alternatively of 40mm width, so that total width of reflector shall be 120mm. A wire mesh cover of 150mm height shall be provided on top.
- d) All components of signs & supports shall be thoroughly descaled, cleaned, primed and painted with two coats of epoxy paint. The sign backside shall be with grey colour and post shall be white colour/ alternate white & black bands. The post below ground shall be painted with three coats of red lead.

Clause 2100

Open Foundation

Sub-Clause 2104.1

Preparation of Foundation

Please add the following as a last para-

Considering the soil SBC as per Geotechnical report, 1 m of depth below the founding level of bridges shall be removed and replaced with granular sand. The cost of the excavation and sand shall be made from respective items.

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

Schedule - E

(See Clauses 2.1 and 14.2)

Maintenance Requirements

1. Maintenance Requirements

- (i) The Contractor shall, at all times maintain the Project Highway in accordance with the provisions of this Agreement, Applicable Laws and Applicable Permits.
- (ii) The Contractor shall repair or rectify any Defect or deficiency set forth in Paragraph 2 of this Schedule-E within the time limit specified therein and any failure in this behalf shall constitute non-fulfilment of the Maintenance obligations by the Contractor. Upon occurrence of any breach hereunder, the Authority shall be entitled to effect reduction in monthly lump sum payment as set forth in Clause 14.6 of this Agreement, without prejudice to the rights of the Authority under this Agreement, including Termination thereof.
- (iii) All Materials works and construction operations shall conform to the MORTH Specifications for Road and Bridge Works, and the relevant IRC publications. Where the specifications for a work are not given, Good Industry Practice shall be adopted.

[Specify all the relevant documents]

2. Repair/rectification of Defects and deficiencies

The obligations of the Contractor in respect of Maintenance Requirements shall include repair and rectification of the Defects and deficiencies specified in Annex - I of this Schedule-E within the time limit set forth therein.

3. Other Defects and deficiencies

In respect of any Defect or deficiency not specified in Annex - I of this Schedule-E, the Authority's Engineer may, in conformity with Good Industry Practice, specify the permissible limit of deviation or deterioration with reference to the Specifications and Standards, and any deviation or deterioration beyond the permissible limit shall be repaired or rectified by the Contractor within the time limit specified by the Authority's Engineer.

4. Extension of time limit

Notwithstanding anything to the contrary specified in this Schedule-E, if the nature and extent of any Defect or deficiency justifies more time for its repair or rectification than the time specified herein, the Contractor shall be entitled to additional time in conformity with Good Industry Practice. Such additional time shall be determined by the Authority's Engineer and conveyed to the Contractor and the Authority with reasons thereof.

5. Emergency repairs/restoration

Notwithstanding anything to the contrary contained in this Schedule-E, if any Defect, deficiency or deterioration in the Project Highway poses a hazard to safety or risk of damage to property, the Contractor shall promptly take all reasonable measures for eliminating or minimizing such danger.

6. Daily inspection by the Contractor

The Contractor shall, through its engineer, undertake a daily visual inspection of the Project Highway and maintain a record thereof in a register to be kept in such form and manner as the Authority's Engineer may specify. Such record shall be kept in safe custody of the Contractor and shall be open to inspection by the Authority and the Authority's Engineer at any time during office hours.

7. Pre-monsoon inspection / Post-monsoon inspection

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

The Contractor shall carry out a detailed pre-monsoon inspection of all bridges, culverts and drainage system before [1st June] every year in accordance with the guidelines contained in IRC: SP35. Report of this inspection together with details of proposed maintenance works as required on the basis of this inspection shall be sent to the Authority's Engineer before the [10th June] every year. The Contractor shall complete the required repairs before the onset of the monsoon and send to the Authority's Engineer a compliance report. Post monsoon inspection shall be done by the [30th September] and the inspection report together with details of any damages observed and proposed action to remedy the same shall be sent to the Authority's Engineer.

8. Repairs on account of natural calamities

- (a) All damages occurring to the Project Highway on account of a Force Majeure Event or wilful default or neglect of the Authority shall be undertaken by the Authority at its own cost. The Authority may instruct the Contractor to undertake the repairs at the rates agreed between the Parties

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

Annex -I

(Schedule-E)

Repair/rectification of Defects and deficiencies

The Contractor shall repair and rectify the Defects and deficiencies specified in this Annex-I of Schedule-E within the time limit set forth in the table below.

Table -1: Maintenance Criteria for Pavements:

| Asset Type | Performance Parameter | Level of Service (LOS) | | Frequency of Inspection | Tools/Equipment | Standards and References for Inspection and Data Analysis | Time limit for Rectification/Repair | Maintenance Specifications |
|---|----------------------------|------------------------|--|-------------------------|---|---|-------------------------------------|----------------------------------|
| | | Desirable | Acceptable | | | | | |
| Flexible Pavement (Pavement of MCW, Service Road, Approaches of Grade structure, approaches of connecting roads, slip roads, lay byes etc. as applicable) | Potholes | Nil | < 0.1 %of area and subject to limit of 10 mm in depth | Daily | Length Measurement Unit like Scale, Tape, odometer etc. | IRC 82: 2015 and Distress Identification Manual for Long Term Pavement Performance Program, FHWA2003(http://www.tfhr.com/pavement/ltpp/reports/03031/) | 24-48 hours | MORT&H Specification 3004.2 |
| | Cracking | Nil | < 5 %subject to limitof0.5 sq.m for any 50 m length | Daily | | | 7-15 days | MORT&H Specification 3004.3 |
| | Rutting | Nil | < 5 mm | Daily | Straight Edge | | 15 -30 days | MORT&H Specification 3004.2 |
| | Corrugations and Shoving | Nil | < 0.1% ofarea | Daily | Length Measurement Unit like | | 2-7 days | IRC:82- 2015 |
| | Bleeding | Nil | < 1 % of area | Daily | | | 3-7 days | MORT&H Specification 3004.4 |
| | Ravelling/Stripping | Nil | < 1 % of area | Daily | | | 7-15 days | IRC:82- 2015 read with IRC SP 81 |
| | Edge Deformation/ Breaking | Nil | < 1 m for any 100 m section and width <0.1 matanylocation, restricted to 30 cm from the edge | Daily | Scale, Tape, odometer etc. | | 7- 15 days | IRC:82- 2015 |
| | Roughness BI | 2000mm/km | 2400mm/km | Bi- Annually | Class I Profilometer SCRIM(Sideway- force) | Class I Profilometer: ASTM E950 (98) 2004 –Standard Test Method for measuring | 180 days | IRC:82- 2015 |
| | Skid Number | 60SN | 50SN | Bi- Annually | CoefficientRoutine Investigation Machine or equivalent) | Longitudinal Profile of Travelled Surfaces with Accelerometer Established Inertial Profiling Reference ASTM E1656 -94: 2000- Standard | 180 days | BS: 7941-1: 2006 |
| | Pavement | 3 | 2.1 | Bi- Annually | | | 180 days | IRC:82- 2015 |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| Asset Type | Performance Parameter | Level of Service (LOS) | | Frequency of Inspection | Tools/Equipment | Standards and References for Inspection and Data Analysis | Time limit for Rectification/Repair | Maintenance Specifications |
|--|-----------------------------|--|---|--|--|---|-------------------------------------|----------------------------|
| | | Desirable | Acceptable | | | | | |
| | Condition Index | | | | | Guide for Classification of Automatic Pavement Condition Survey Equipment | | |
| | Other Pavement Distresses | | | Bi- Annually | | | 2-7 days | IRC:82- 2015 |
| | Deflection/ Remaining Life | | | Annually | Falling Weight Deflectometer | IRC 115: 2014 | 180 days | IRC:115- 2014 |
| | Roughness BI | 2200m m/km | 2400mm /km | Bi- Annually | Class I Profilometer | ASTM E950 (98) :2004 and ASTM E1656 - 94: 2000 | 180 days | IRC:SP:83- 2008 |
| Rigid Pavement (Pavement of MCW, Service Road, Grade structure, approaches of connecting road, slip roads, lay byes etc. as applicable) | Skid | Skid Resistance no. at different speed of vehicles | | Bi- Annually | SCRIM (Sideway- force | IRC:SP:83-2008 | 180 days | IRC:SP:83- 2008 |
| | | Minimum SN 36 33 32 31 31 | | traffic Speed (Km/h) 50 65 80 95 110 | Coefficient Routine Investigation Machine or equivalent) | | | |
| Embankment/ Slope | Edge drop at shoulders | Nil | 40m m | Daily | | IRC | 7-15 days | MORT&H Specification 408.4 |
| | Slope of camber/cross fall | Nil | <2%variation inprescribedslope of camber/cross fall | Daily | Length Measurement Unit like Scale, Tape, odometer etc. | | 7-15 days | MORT&H Specification 408.4 |
| | Embankment Slopes | Nil | <15 %variation inprescribe side slope | Daily | | | 7-15 days | MORT&H Specification 408.4 |
| | Embankment Protection | Nil | Nil | Daily | NA | | 7-15 days | MORT&H Specification |
| | Rain Cuts/ Gullies in slope | Nil | Nil | DailySpeciall y During Rainy Season | NA | | 7-15 days | MORT&H Specification |

In addition to the above performance criterion, the contractor shall strictly maintain the rigid pavements as per requirements in the following table

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

Table -2:Maintenance Criteria for Rigid Pavements:

| Sr.No. | Type of Distress | Measured Parameter | Degree of Severity | Assessment Rating | Repair Action | |
|----------|--|--|--------------------|--|---|--|
| | | | | | For the case $d < D/2$ | For the case $d > D/2$ |
| CRACKING | | | | | | |
| 1 | Single Discrete Cracks Not intersecting with any joint | w = width of crack L = length of crack d = depth of crack D = depth of slab | 0 | Nil, not discernible | No Action | Not applicable |
| | | | 1 | w < 0.2 mm. hair cracks | | |
| | | | 2 | w = 0.2 - 0.5 mm, discernible from slow-moving car | Seal without delay | Seal, and stitch if L > 1m. Within 7 days |
| | | | 3 | w = 0.5 - 1.5 mm, discernible from fast-moving car | | |
| | | | 4 | w = 1.5 - 3.0 mm | Seal, and stitch if L > 1 m. Within 7 days | Staple or Dowel Bar Retrofit, FDR for affected portion. Within 15 days |
| | | | 5 | w > 3 mm. | | |
| 2 | Single Transverse (or Diagonal) Crack intersecting with one or more joints | w = width of crack L = length of crack d = depth of crack D = depth of slab | 0 | Nil, not discernible | No Action | |
| | | | 1 | w < 0.2 mm, hair cracks | Route and seal with epoxy. Within 7 days | Staple or Dowel Bar Retrofit. Within 15 days |
| | | | 2 | w = 0.2 - 0.5 mm, discernible from slow vehicle | | |
| | | | 3 | w = 0.5 - 3.0 mm, discernible from fast vehicle | Route, seal and stitch, if L > 1m. Within 7 days | |
| | | | 4 | w = 3.0 - 6.0 mm | Dowel Bar Retrofit. Within 15 days | Full Depth Repair Dismantle and reconstruct affected. |
| | | | 5 | w > 6 mm, usually associated with spalling, and/or slab rocking under traffic | Not Applicable, as it may be full depth | Portion with norms and specifications - See Para 5.5 & 9.2 Within 15 days |
| 3 | Single Longitudinal Crack intersecting with one or more joints | w = width of crack L = length of crack d = depth of crack D = depth of slab | 0 | Nil, not discernible | No Action | |
| | | | 1 | w < 0.5 mm, discernible from slow moving vehicle | Seal with epoxy, if L > 1 m. Within 7 days | Staple or dowel bar retrofit. Within 15 days |
| | | | 2 | w = 0.5 - 3.0 mm, discernible from fast vehicle | Route seal and stitch, if L > 1 m. Within 15 days | - |
| | | | 3 | w = 3.0 - 6.0 mm | Staple, if L > 1 m. Within 15 days | Partial Depth Repair with stapling. Within 15 days |
| | | | 4 | w = 6.0 - 12.0 mm, usually associated with spalling | Not Applicable, as it may be full depth | |
| | | | 5 | w > 12 mm, usually associated with spalling, and/or slab rocking under traffic | | Full Depth Repair Dismantle and reconstruct affected portion as per norms And specifications - See Para 5.6.4 Within 15 days |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| Sr.No. | Type of Distress | Measured Parameter | Degree of Severity | Assessment Rating | Repair Action | |
|--------|---|--|--------------------|---|--|---|
| | | | | | For the case d < D/2 | For the case d > D/2 |
| 4 | MultipleCracks intersecting with one or morejoints | w = width of crack | 0 | Nil, not discernible | No Action | Dismantle, Reinstatement subbase, Reconstruct whole slab as per specifications within 30 days |
| | | | 1 | w < 0.2 mm, hair cracks | Seal, and stitch if L > 1 m. Within 15 days | |
| | | | 2 | w = 0.2 - 0.5 mm. discernible from slow vehicle | | |
| | | | 3 | w = 0.5 - 3.0 mm, discernible from fast vehicle | Full depth repair within 15 days | |
| | | | 4 | w = 3.0 - 6.0 mm panel broken into 2 or 3pieces | | |
| | | | 5 | w > 6 mm and/or panelbroken into more than 4 pieces | | |
| 5 | Corner Break | w = width of crack L = length of crack | 0 | Nil, not discernible | No Action | - |
| | | | 1 | w < 0.5 mm; only 1 corner broken | Seal with low viscosity epoxy to secure broken parts Within 7 days | Seal with epoxy seal withepoxy Within 7days |
| | | | 2 | w < 1.5 mm; L < 0.6 m, only one cornerbroken | Partial Depth (Refer Figure 8.3 of IRC: SP: 83-2008) Within 15 days | Full depth repair Reinstatement sub-base, and reconstructthe slab as per norms and specifications within 30days |
| | | | 3 | w < 1.5 mm; L < 0.6 m, two corners broken | | |
| | | | 4 | w > 1.5 mm; L > 0.6 m or three corners broken | | |
| | | | 5 | three or four corners broken | | |
| 6 | Punch out (Applicable to Continuous Reinforced Concrete Pavement (CRCP) only) | w = width of crack L = length(m/m2) | 0 | Nil, not discernible | | No Action |
| | | | 1 | w < 0.5 mm; L < 3 m/m ² | Applicable, as it may be fulldepth | Seal with low viscosity epoxy to secure broken parts. Within 15days |
| | | | 2 | either w > 0.5 mm or L < 3 m/m ² | | |
| | | | 3 | w > 1.5 mm and L < 3 m/m ² | | Full depth repair - Cut out and replace damaged area taking care not to damage reinforcement. Within30days |
| | | | 4 | w > 3 mm, L < 3 m/m ² and deformation | | |
| | | | 5 | w > 3 mm, L > 3 m/m ² and deformation | | |
| 7 | RavellingorHoneycombttype surface | r = area damaged surface/total surface of slab (%) h = maximum depth of damage | 0 | Nil, not discernible | Short Term No action. | Long Term Not Applicable |
| | | | 1 | r < 2 % | Local repair of areas damaged and liable to be damaged. Within 15 days | |
| | | | 2 | r = 2 - 10 % | | |
| | | | 3 | r = 10-25% | Bonded Inlay, 2 or 3 slabs if affecting. Within 30 days Reconstruct slabs, 4 or more | |
| | | | 4 | r = 25 - 50 % | | |
| | | | 5 | | | |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| Sr.No. | Type of Distress | Measured Parameter | Degree of Severity | Assessment Rating | Repair Action | |
|--------|--|---|--------------------|---|---|------------------------|
| | | | | | For the case $d < D/2$ | For the case $d > D/2$ |
| 8 | Scaling | r = damaged surface/total surface of slab (%) h = maximum depth of damage | 0 | Nil, not discernible | slabs if affecting. Within 30 days | |
| | | | 1 | $r < 2\%$ | Short Term No action. | Long Term |
| | | | 2 | $r = 2 - 10\%$ | Local repair of areas damaged and liable to be damaged. Within 7 days | Not Applicable |
| | | | 3 | $r = 10 - 20\%$ | Bonded Inlay within 15 days | |
| | | | 4 | $r = 20 - 30\%$ | Reconstruct slab within 30 days | |
| 9 | Polished Surface/Glazing | t = texture depth, sand patch test | 0 | | No action. | |
| | | | 1 | $t > 1\text{ mm}$ | | |
| | | | 2 | $t = 1 - 0.6\text{ mm}$ | | |
| | | | 3 | $t = 0.6 - 0.3\text{ mm}$ | Monitor rate of deterioration | Not Applicable |
| | | | 4 | $t = 0.3 - 0.1\text{ mm}$ | | |
| 10 | Pop out (Small Hole), Pothole Refer Para 8.4 | n = number/m ² d = diameter h = maximum depth | 0 | $d < 50\text{ mm}; h < 25\text{ mm}; n < 1\text{ per } 5\text{ m}^2$ | No action. | |
| | | | 1 | $d = 50 - 100\text{ mm}; h < 50\text{ mm}; n < 1\text{ per } 5\text{ m}^2$ | Partial depth repair 65 mm deep. Within 15 days | |
| | | | 2 | $d = 50 - 100\text{ mm}; h > 50\text{ mm}; n < 1\text{ per } 5\text{ m}^2$ | | Not Applicable |
| | | | 3 | $d = 100 - 300\text{ mm}; h < 100\text{ mm}; n < 1\text{ per } 5\text{ m}^2$ | | |
| | | | 4 | $d = 100 - 300\text{ mm}; h > 100\text{ mm}; n < 1\text{ per } 5\text{ m}^2$ | | |
| 11 | Joint Seal Defects | loss or damage L = Length as % total joint length | 0 | Difficult to discern. | Short Term No action. | Long Term |
| | | | 1 | Discernible, $L < 25\%$ but of little immediate consequence with regard to ingress of water or trapping | Clean joint, inspect later. | Not Applicable |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| Sr.No. | Type of Distress | Measured Parameter | Degree of Severity | Assessment Rating | Repair Action | |
|--------|--|---|--------------------|---|---|----------------------------------|
| | | | | | For the case d < D/2 | For the case d > D/2 |
| | | | | incompressible material. | | |
| | | | 3 | Notable. L > 25% insufficient protection against ingress of water and trapping incompressible material. | Clean and reapply sealant in selected locations. Within 7 days | |
| | | | 5 | Severe; w > 3 mm negligible protection against ingress of water and trapping incompressible material. | Clean, widen and reseal the joint. Within 7 days | |
| 12 | Spalling of Joints | w = width on either side of the joint L = length of spalled portion (as % joint length) | 0 | Nil, not discernible | No action. | |
| | | | 1 | w < 10 mm | Apply low viscosity epoxy resin/ mortar in cracked portion. Within 7 days | |
| | | | 2 | w = 10 - 20 mm, L < 25% | Partial Depth Repair. Within 15 days | |
| | | | 3 | w = 20 - 40 mm, L > 25% | 30 - 50 mm deep, h = w + 20% of w, within 30 days | |
| | | | 4 | w = 40 - 80 mm, L > 25% | 50 - 100 mm deep repair. H = w + 20% of w. Within 30 days | |
| | | | 5 | w > 80 mm, and L > 25% | | Not Applicable |
| | | | | | | |
| 13 | Faulting (or Stepping) in Cracks or Joints | f = difference of level | 0 | not discernible, < 1 mm | No action. | No action. |
| | | | 1 | f < 3 mm | | |
| | | | 2 | f = 3 - 6 mm | Determine cause and observe, take action for diamond grinding | Replace the slab as appropriate. |
| | | | 3 | f = 6 - 12 mm | Diamond Grinding | Within 30 days |
| | | | 4 | f = 12 - 18 mm | Raise sunken slab. | Replace the slab as appropriate. |
| | | | 5 | f > 18 mm | Strengthen subgrade and sub-base by grouting and raising sunken slab | Within 30 days |
| | | | | | | |
| 14 | Blow-up or Buckling | H = vertical displacement from normal profile | 0 | Nil, not discernible | Short Term | Long Term |
| | | | 1 | h < 6 mm | No Action | |
| | | | 2 | h = 6 - 12 mm | Install Signs to Warn Traffic | |
| | | | 3 | h = 12 - 25 mm | within 7 days | |
| | | | 4 | h > 25 mm | Full Depth Repair. Within 30 days | |
| | | | 5 | shattered slabs, i.e. 4 or more pieces | Replace broken slabs. Within 30 days | |
| | | | | | | |
| 15 | Depression | H = negative vertical displacement from | 0 | Not discernible, h < 5 mm | | |
| | | | 1 | h = 5 - 15 mm | No action. | Not Applicable |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| Fig 1.5: | | | | | | |
|----------|---------------------------|---|--------------------|---------------------------------|---|---|
| Sr.No. | Type of Distress | Measured Parameter | Degree of Severity | Assessment Rating | Repair Action | |
| | | | | | For the case d < D/2 | For the case d > D/2 |
| | | normal profile L=length | 2 | h = 15-30 mm, Nos<20% joints | Install Signs to Warn Traffic within 7 days | |
| | | | 3 | h = 30 - 50 mm | | |
| | | | 4 | h > 50 mm or > 20% joints | Strengthen subgrade. Reinstate pavement at normal level | |
| | | | 5 | h > 100 mm | If L < 20 m. Within 30 days | |
| | | | | | | |
| 16 | Heave | h = positive vertical displacement from normal profile. L = length | 0 | Not discernible. h < 5 mm | Short Term No action. | Long Term |
| | | | 1 | h = 5 - 15 mm | Follow up. | |
| | | | 2 | h = 15 - 30 mm, Nos <20% joints | Install Signs to Warn Traffic within 7 days | |
| | | | 3 | h = 30 - 50 mm | | |
| | | | 4 | h > 50 mm or > 20% joints | Stabilise subgrade. Reinstate pavement at normal level if length < 20 m. Within 30 days | |
| | | | 5 | h > 100 mm | scrabble | |
| 17 | Bump | H =vertical displacement from normal profile | 0 | h < 4 mm | No action | Construction Limit for New Construction. Replace in case of new construction. Within 30days Full Depth Repair. Within 30days |
| | | | 1 | h = 4 - 7 mm | Grind, in case of new construction within 7 days | |
| | | | 3 | h = 7 - 15 mm | Grind, in case of ongoing Maintenance within 15 days | |
| | | | 5 | h > 15 mm | Full Depth Repair. Within 30 days | |
| | | | | | | |
| 18 | Lane to Shoulder Drop-off | f = difference of level | 0 | Nil, not discernible < 3mm | Short Term No action. | Long Term |
| | | | 1 | f = 3 - 10 mm | Spot repair of shoulder | |
| | | | 2 | f = 10 - 25 mm | within 7 days | |
| | | | 3 | f = 25 - 50 mm | | |
| | | | 4 | f = 50 - 75 mm | | |
| | | | 5 | f > 75 mm | Fill up shoulder within 7 days | |
| Drainage | | | | | | |
| 19 | Pumping | quantity of fines and water expelled through open joints and cracks | 0 | not discernible | No Action | Inspect and repair sub-drainage at distressed |
| | | | 1 to 2 | slight/ occasional Nos < 10% | Repair cracks and joints Without delay. | |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| Sr.No. | Type of Distress | Measured Parameter | Degree of Severity | Assessment Rating | Repair Action | |
|--------|------------------|--|--------------------|---|--|---|
| | | | | | For the case d < D/2 | For the case d > D/2 |
| | | Nos Nos/100 m stretch | 3 to 4 | appreciable/ Frequent 10 -25% | Lift or jack slab within 30 days. | sections and upstream. |
| | | | 5 | abundant,crack development >25% | Repair distressed pavement sections. Strengthen subgrade and subbase. Replace slab. Within 30 days | |
| 20 | Ponding | Ponding on slabs due to blockage of drains | 0-2 | Nodiscernible problem | No action. | |
| | | | 3 to 4 | Blockages observed in drains, but water flowing | Clean drains etc. within 7 days, Follow up | Action required to stop water damaging foundation within 30 days. |
| | | | 5 | Ponding, accumulation of water observed | -do- | |

Table -3: Maintenance Criteria for Safety Related Items and Other Furniture Items:

| Asset Type | Performance Parameter | Level of Service (LOS) | | | Frequency of Measurement | Testing Method | Recommended Remedial measures | Time limit for Rectification | Specifications and Standards |
|------------------|-------------------------------------|--|--------------------------------------|----------------------------------|--------------------------|---|---|--|------------------------------|
| Highway | Availability of Safe Sight Distance | As per IRC SP: 84-2014, a minimum of safe stopping sight distance shall be available throughout. | | | Monthly | ManualMeasurementswithOdometeralongwithvideo/image backup | Removal of obstruction within 24 hours, in case of sight line affected by temporary objects such as trees, temporary encroachments. In case of permanent structure or design deficiency: Removalofobstruction/improvementof efficiency at theearliestSpeed Restriction boards and suitable traffic calming measures such as transverse bar marking, blinkers, etc. shall be applied during the period of rectification. | | IRC: SP 84-2014 |
| | | Design Speed, kmph | Desirable Minimum Sight Distance (m) | Safe Stopping Sight Distance (m) | | | | | |
| | | 100 | 360 | 180 | | | | | |
| | | 80 | 260 | 130 | | | | | |
| Pavement Marking | Wear | <70% of marking remaining | | | Bi- Annually | Visual Assessment as per Annexure-F of IRC:35-2015 | Re - painting | Cat-1 Defect – within 24 hours Cat-2 Defect within 2months- | IRC:35-2015 |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| Asset Type | Performance Parameter | Level of Service (LOS) | Frequency of Measurement | Testing Method | Recommended Remedial measures | Time limit for Rectification | Specifications and Standards |
|------------|-----------------------|--|---|---------------------------------|-------------------------------|--|------------------------------|
| | Day time Visibility | During expected life Service Time Cement Road -130mcd/m ² /lux BituminousRoad-100mcd/m ² /lux | Monthly | As perAnnexure-D of IRC:35-2015 | Re - painting | Cat-1 Defect – within 24 hours Cat-2 Defect – within 2 months | IRC:35-2015 |
| | Night Time Visibility | <u>Initial and Minimum Performancefor Dry Retro reflectivity during nighttime:</u> | | As perAnnexure-E of IRC:35-2015 | Re - painting | Cat-1 Defect – within 24 hours Cat-2 Defect – within 2 months | IRC:35-2015 |
| | | Design Speed (km/h) | (RL) Retro Reflectivity (mcd/m ² /lux) | | | | |
| | | | Minimum Threshold level (TL) & warranty period required up to 2 years | | | | |
| | | Up to 65 | 200 80 | | | | |
| | | 65 - 100 | 250 120 | | | | |
| | | Above 100 | 350 150 | | | | |
| | | | | | | | |
| | | <u>Initial and Minimum Performance for Night Visibility under wet condition(Retro</u> | | | | | |
| | | | | | | | |
| | | | | | | | |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| Asset Type | Performance Parameter | Level of Service (LOS) | Frequency of Measurement | Testing Method | Recommended Remedial measures | Time limit for Rectification | Specifications and Standards |
|------------|-----------------------|--|--------------------------|--|--|--|------------------------------|
| | | reflectivity): | | | | | |
| | | Initial 7 days Retro reflectivity: 100 mcd/m ² /lux Minimum Threshold Level: 50 mcd/m ² /lux | | | | | |
| | Skid Resistance | Initial and Minimum performance for SkidResistance: Initial (7days): 55BPN Min. Threshold: 44BPN *Note: shall be considered under urban/city traffic condition encompassing the locations like pedestrian crossings, bus bay, bus stop, cycle track intersection delineation, transverse bar markingsetc. | Bi-Annually | As per Annexure-G of IRC:35-2015 | | Within 24 hours | IRC:35-2015 |
| Road Signs | Shape Position and | Shape and Position as per IRC: 67- 2012. Signboard should be clearly visible for the design speed of the section. | Daily | Visual with video/image backup | Improvement of shape, in case if shapeisDamaged. | 48 hours in case of Mandatory Signs, Cautionary and Informatory Signs (Single and Dual post signs) | IRC:67-2012 |
| | Retro reflectivity | As per specifications in IRC:67-2012 | Bi-Annually | Testingof each Signboard usingRetroReflectivityMeasuring Device.In accordance with ASTM D 4956-09. | Relocation asper requirement change of signboard | 15 Days in case of Gantry/Cantilever Sign boards 48 hours in case of | RC:67-2012 |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| Asset Type | Performance Parameter | Level of Service (LOS) | Frequency of Measurement | Testing Method | Recommended Remedial measures | Time limit for Rectification | Specifications and Standards |
|----------------------|--|---|--------------------------|--------------------------------|-------------------------------|---|------------------------------|
| | | | | | | Mandatory Signs, Cautionary and Informatory Signs (Single and Dual postsigns) 1 Month in case of Gantry/Cantilever Sign boards | |
| Kerb | Kerb Height | As per IRC 86:1983 depending upon type of Kerb | Bi-Annually | Use of distance measuring tape | Raising Kerb Height | Within 1 Month | RC 86:1983 |
| | Kerb Painting | <u>Functionality:</u> Functioning of Kerb painting as intended | Daily | Visual with video/image backup | Kerb Repainting | Within 7-days | RC 35:2015 |
| Other Road Furniture | Reflective Pavement Markers (Road Studs) | Numbers and Functionality as per specifications in IRC:SP:84-2014 and IRC: 35-2015, unless specified in Schedule-B. | Daily | Counting | New Installation | Within 2 months | IRC:SP:84-2014,IRC:35-2015 |
| | Pedestrian Guardrail | <u>Functionality:</u> Functioning of guardrail as intended | Daily | Visual with video/image backup | Rectification | Within 15 days | IRC:SP:84-2014 |
| | Traffic Safety | <u>Functionality:</u> Functioning of Safety Barriers as intended | Daily | Visual with video/image backup | Rectification | Within 7 days | IRC:SP:84-2014, IRC:119-2015 |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| Asset Type | Performance Parameter | Level of Service (LOS) | Frequency of Measurement | Testing Method | Recommended Remedial measures | Time limit for Rectification | Specifications and Standards |
|-------------------------|-----------------------------|---|--------------------------|--|--------------------------------|------------------------------|------------------------------|
| | Barriers | | | | | | |
| | End Treatment | <u>Functionality:</u> Functioning of End Treatment as intended | Daily | Visual with video/image | Rectification | Within 7 days | IRC:SP:84-2014, |
| | Traffic Safety Barriers | | | backup | | | IRC:119-2015 |
| | Attenuators | <u>Functionality:</u> Functioning of Attenuators as intended | Daily | Visual with video/image backup | Rectification | Within 7 days | IRC:SP-2014, IRC:119-2015 |
| | Guard Posts and Delineators | <u>Functionality:</u> Functioning of Guard Posts and Delineators as intended | Daily | Visual with video/image backup | Rectification | Within 15 days | IRC: 79 1981 |
| | Overhead Sign Structure | Overhead sign structure shall be structurally adequate | Daily | Visual with video/image backup | Rectification | Within 15 days | IRC:67-2012 |
| | Traffic Blinkers | <u>Functionality:</u> Functioning of Traffic Blinkers as intended | Daily | Visual with video/image backup | Rectification | Within 7 days | IRC:SP:84-2014 |
| Highway Lighting System | Highway Lights | Illumination: Minimum 40 Lux illumination on the road surface | Daily | The illumination level shall be measured with luxmeter | Improvement in Lighting System | 24 hours | IRC:SP:84-2014 |
| | | No major failure in the lighting system | Daily | - | Rectification of failure | 24 hours | IRC:SP:84-2014 |
| | | No minor failure in the lighting system | Monthly | - | Rectification of failure | 8 hours | IRC:SP:84-2014 |
| | Toll Pl | Minimum 40 Lux illumination on the road surface | Daily | The illumination level shall be measured with luxmeter | Improvement in Lighting System | 24 hours | IRC:SP:84-2014 |
| | | No major/minor failure | Daily | - | Rectification of | 8 hours | IRC:SP:84- |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| Asset Type | Performance Parameter | Level of Service (LOS) | Frequency of Measurement | Testing Method | Recommended Remedial measures | Time limit for Rectification | Specifications and Standards |
|--|---|---|--------------------------|--------------------------------|--|------------------------------|------------------------------|
| | Canopy Lights | in the lighting system | | | failure | | 2014 |
| Trees and Plantation including median plantation | Obstruction in a minimum head-room of 5.5 m above carriageway or obstruction in visibility road signs | No obstruction due to trees | Monthly | Visual with video/image backup | Removal of trees | Immediate | IRC:SP:84-2014 |
| | Deterioration in health of trees and bushes | Health of plantation shall be as per requirement of specifications & instructions issued by Authority from time to time | Daily | Visual with video/image backup | Timely watering and treatment. Or Replacement of Trees and Bushes. | Within 90 days | IRC:SP:84-2014 |
| | Vegetation affecting sight line and road structures | Sight line shall be free from obstruction by vegetation | Daily | Visual with video/image backup | Removal of Trees | Immediate | IRC:SP 84-2014 |
| Rest Areas | Cleaning toilets | - | Daily | - | - | Every 4 hours | |
| | Defects installation s | - | Daily | - | Rectification | 24 hours | |
| Other Project | Damage or deterioration in | | | - | Rectification | 15 days | IRC:SP 84-2014 |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| Asset Type | Performance Parameter | Level of Service (LOS) | Frequency of Measurement | Testing Method | Recommended Remedial measures | Time limit for Rectification | Specifications and Standards |
|--------------------------------------|--|--|---|--|--|---|--|
| Facilities and Approach roads | Approach Roads, pedestrian facilities, truck lay-bys, bus-bays, bus-shelters, cattle crossings, Traffic Aid Posts, Medical Aid Posts and other works | | Daily | | | | |
| Pipe/box/slab culverts | Free waterway/unobstructed flow section | 85% of culvert normal flow area to available. | 2 times in a year (before and after rainy season) | Inspection by Bridge Engineer as per IRC SP: 35-1990 and recording of depth of silting and area of vegetation. | Cleaning silt up soils and debris in culvert barrel after rainy season, removal of bushes and vegetation, U/s of barrel, under barrel and D/s of barrel before rainy season. | 15 days before onset of monsoon and within 30 days after end of rainy season. | IRC 5-2015, IRC SP: 40-1993 and IRC SP: 13-2004 |
| | Leak-proof expansion joints if any | No leakage through expansion joints | Bi-Annually | Physical inspection of expansion joints as per IRC SP: 35-1990 if any, for leakage strains on walls at joints. | Fixing with sealant suitably | 30 days or before onset of rains whichever comes earlier | IRC SP: 40-1993 and IRC SP: 69-2011 |
| | Structurally sound | Spalling of concrete not more than 0.25 sqm | Bi-Annually | Detailed inspection of all components of culvert as per IRC SP: 35-1990 and recording the defects | Repairs to spalling, cracking, delamination, rusting shall be followed as per IRC: SP: 40-1993. | 15 days | IRC SP 40-1993 and MORTH Specification clause 2800 |
| | | Delamination of concrete not more than 0.25 sq.m. | | | | | |
| | | Cracks wider than 0.3 mm not more than 1m aggregate length | | | | | |
| | | Damaged of rough stone | 2 times in a | Condition survey as per IRC SP: 35-1990 | Repairs to | 30 days | |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| Asset Type | Performance Parameter | Level of Service (LOS) | Frequency of Measurement | Testing Method | Recommended Remedial measures | Time limit for Rectification | Specifications and Standards |
|---|--|---|--------------------------------------|--|--|--|---|
| | Protection works in good condition | apron or bank revetment not more than 3 sqm, damage to solid apron (concrete apron) not more than 1 sqm | year (before and after rainy season) | | damaged aprons and pitching | after defect observation or 2 weeks before onset of rainy season whichever is earlier. | IRC: SP 40-1993 and IRC:SP:13-2004. |
| Bridges including ROB's Flyover etc. as applicable | Riding quality or user comfort | No pothole in wearing coat on bridge deck | Daily | Visual inspection as per IRC SP:35-1990 | Repairs to BC or wearing coat | 15 days | MORT&H Specification 2811 |
| Bridge Super Structure | Bumps | No bump at expansion joint | Daily | Visual inspection as per IRC SP:35- 1990 | Repairs to BC on either side of expansion joints, profile correction course on approach slab in case of settlement to approach embankment | 15 days | MORT&H Specification 3004 & 2811. |
| | User safety (condition of crash barrier and guardrail) | No damaged or missing stretch of crash barrier or pedestrian hand railing | Daily | Visual inspection and detailed condition survey as per IRC SP: 35- 1990. | Repairs and replacement of safety barriers as the case may be | 3 days | IRC: 5-1998, IRC SP: 84-2014 and IRC SP: 40-1993. |
| | Rusted reinforcement Spalling of concrete Delamination | Not more than 0.25 sq.m Not more than 0.50 sq.m Not more than 0.50 sq.m | Bi- Annually | Detailed condition survey as per IRC SP: 35-1990 using Mobile Bridge Inspection Unit | All the corroded reinforcement shall need to be thoroughly cleaned from rusting and applied with anti-corrosive coating before carrying out the repairs to | 15 days | IRC SP: 40-1993 and MORTH Specification 1600. |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| Asset Type | Performance Parameter | Level of Service (LOS) | Frequency of Measurement | Testing Method | Recommended Remedial measures | Time limit for Rectification | Specifications and Standards |
|------------|--|---|---|--|---|------------------------------|---|
| | | | | | affected concrete portion with epoxy mortar / concrete. | | |
| | Cracks wider than 0.30 mm | Not more than 1m total length | Bi-Annually | Detailed condition survey as per IRC SP: 35-1990 using Mobile Bridge Inspection Unit | Grouting with epoxy mortar, investigating causes for cracks development and carry out necessary rehabilitation. | 48 Hours | IRC SP: 40-1993 and MORTH Specification 2800. |
| | Rainwater seepage through deck slab | Leakage - nil | Quarterly | Detailed condition survey as per IRC SP: 35-1990 using Mobile Bridge Inspection Unit | Grouting of deck slab at leakage areas, waterproofing, repairs to drainage spouts | 1 months | MORTH specifications 2600 & 2700. |
| | Deflection due to permanent loads and live loads | Within design limits. | Once every years for spans more than 40 m | Load test method | Carry out major rehabilitation works on bridge to retain original design load capacity | 6 months | IRC SP: 51-1999. |
| | Vibrations in bridge deck due | Frequency of vibrations shall not be more than 5 Hz | Once more than 30m a | Laser displacement sensors or laser vibro-meters | Strengthening structure of super | 4 months | AASHTO LRFD specification |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| Asset Type | Performance Parameter | Level of Service (LOS) | Frequency of Measurement | Testing Method | Recommended Remedial measures | Time limit for Rectification | Specifications and Standards |
|------------|---|---|---|---|--|------------------------------|--|
| | to moving trucks | | and every 10 years for spans between 15 to 30 m | | | | ns |
| | Leakage in Expansion joints | No damage to elastomeric sealant compound in strip seal expansion joint, no leakage of rain water through expansion joint in case of buried and asphalt plug and copper stripjoint. | Bi-Annually | Detailed condition survey as per IRC SP:35-1990 using Mobile Bridge InspectionUnit | Replace of expansionjoint seal in | 15 days | MORTH specifications 2600 and IRC SP: 40-1993. |
| | Debris and dust in strip seal expansion joint | No dust debris expansion or in joint gap. | Monthly | Detailed condition survey as per IRC SP:35-1990 using Mobile Bridge InspectionUnit | Cleaning of expansion joint gapthoroughly | 3 days | MORTH specifications 2600 and IRC SP: 40-1993. |
| | Drainage spouts | No down take pipe missing/broken below soffit of the deck slab. No silt, debris, clogging of drainage spout | Monthly | Detailed condition survey as per IRC SP: 35-1990 using Mobile Bridge InspectionUnit | Cleaning of drainage spouts thoroughly. Replacement of missing/broken down take pipes with a | 3 days | MORTH specifications |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| Asset Type | Performance Parameter | Level of Service (LOS) | Frequency of Measurement | Testing Method | Recommended Remedial measures | Time limit for Rectification | Specifications and Standards |
|----------------------------|--|---|--------------------------|--|---|------------------------------|---|
| | | collection chamber. | | | minimum pipe extension of 500mm below soffit of slab. Providing sealant around the drainagespout if any leakages observed. | | n 2700. |
| Bridge-substructure | Cracks/spalling of concrete/rusted steel | No cracks, spalling of concrete and rusted steel | Bi-Annually | Detailed condition survey as per IRC SP: 35-1990 using Mobile Bridge InspectionUnit | All the corroded reinforcement shall need to be thoroughly cleaned from rusting and applied with defect noticed | 30 days | IRC SP: 40-1993 and MORTH specification n 2800. |
| | Bearings | Delamination of bearing reinforcement not more than 5%, cracking or tearing of rubber not more than 2 locations per side, no rupture of reinforcement or rubber | Bi-Annually | Detailed condition survey as per IRC SP: 35-1990 using Mobile Bridge InspectionUnit | In case of failure of even one bearing on any pier/abutment, all the bearings on that pier/abutment shall be replaced, in order to get uniform load transfer on tobearings. | 3 months | MORTH specification n 2810andIRC SP: 40-199. |
| Bridge Foundations | Scouring around foundations | Scouring shall not be lower than maximum scour level for the bridge | Bi-Annually | Condition survey and visualinspection as per IRC SP:35-1990 UsingMobile Bridge Inspection Unit. In case of doubt, use Underwater camera for inspection of deep wells inmajor Rivers. | Suitable protection works around pier/abutment | 1 month | IRC SP: 40-1993,IRC 83-2014, MORTH specification n 2500 |
| | Protection works | Damaged of rough stone apron or bank | 2 times in a year | Condition survey as per IRC SP:35- 1990 | Repairs todamage | 30 days after defect | IRC: SP 40-1993 and |

Construction & Upgradation to 2-lane /4lane with paved shoulder from Design Km 148+589 (Existing km 235+070) (Vailoo)to Design Km 176+532 (Existing km 263+070) Donipawa of 27.943 km length on Khellani-Khanabal section of NH-244 in the Union Territory of Jammu & Kashmir on EPC mode. (Pkg-VI).”

| Asset Type | Performance Parameter | Level of Service (LOS) | Frequency of Measurement | Testing Method | Recommended Remedial measures | Time limit for Rectification | Specifications and Standards |
|---|-----------------------|---|---------------------------------|----------------|-------------------------------|--|------------------------------|
| | in good condition | revetment not more than 3 | (before and after rainy season) | | d aprons and pitching. | observation or 2 | IRC: SP: 13-2004. |
| | | sq.m, damage to solid apron (concrete apron) not more than 1 sq.m | | | | weeks before onset of rainy season whichever is earlier. | |
| Note: Any Structure during the entire contract period which is found that does not complies with all requirements of this Table will be prepared, rehabilitated or even reconstructed under the scope of the contractor. | | | | | | | |

Table 4: Maintenance Criteria for Hill Roads

In addition to above, for hill roads the following provisions for maintenance is also to done.

| Hill Roads | | |
|------------|---------------------------------------|------------------------|
| (i) | Damage to Retaining wall/ Breast wall | 7 (Seven) days |
| (ii) | Landslides requiring clearance | 12 (Twelve) hours |
| (iii) | Snow requiring clearance | 24 (Twenty-Four) hours |

Note: For all tables 1 to 5 above, latest BIS & IRC standards (even those not indicated herewith) along with MoRT&H specifications shall be binding for all maintenance activities.

A. Flexible Pavement

| Nature of Defect or deficiency | | Time limit for repair/ rectification |
|--|---|---|
| (b) Granular earth shoulders, side slopes, drains and culverts | | |
| (i) | Variation by more than 1 % in the prescribed slope of camber/cross fall (shall not be less than the camber on the main carriageway) | 7 (seven) days |
| (ii) | Edge drop at shoulders exceeding 40 mm | 7 (seven) days |
| (iii) | Variation by more than 15% in the prescribed side (embankment) slopes | 30 (thirty) days |
| (iv) | Rain cuts/gullies in slope | 7 (seven) days |
| (v) | Damage to or silting of culverts and side drains | 7 (seven) days |
| (vi) | Desilting of drains in urban/semi- urban areas | 24 (twenty-four) hours |
| (vii) | Railing, parapets, crash barriers | 7 (seven) days (Restore immediately if causing safety hazard) |
| (c) Roadside furniture including road sign and pavement marking | | |
| (i) | Damage to shape or position, poor visibility or loss of retro-reflectivity | 48 (forty-eight) hours |
| (ii) | Painting of km stone, railing, parapets, crash barriers | As and when required/ Once every year |
| (iii) | Damaged/missing signs road requiring replacement | 7 (seven) days |
| (iv) | Damage to road mark ups | 7 (seven) days |
| (d) Roadlighting | | |
| (i) | Any major failure of the system | 24 (twenty-four) hours |
| (ii) | Faults and minor failures | 8 (eight) hours |
| (e) Trees and plantation | | |
| (i) | Obstruction in a minimum head- room of 5 m above carriageway or obstruction in visibility of road signs | 24 (twenty-four) hours |
| (ii) | Removal of fallen trees from carriageway | 4 (four) hours |
| (iii) | Deterioration in health of trees and bushes | Timely watering and treatment |
| (iv) | Trees and bushes requiring replacement | 30 (thirty) days |
| (v) | Removal of vegetation affecting sight line and road structures | 15 (fifteen) days |
| (f) Rest area | | |
| (i) | Cleaning of toilets | Every 4 (four) hours |
| (ii) | Defects in electrical, water and sanitary installations | 24 (twenty-four) hours |
| (g) [Toll Plaza] | | |
| (h) Other Project Facilities and Approach roads | | |

| | | |
|---|--|---|
| (i) | Damage in approach roads, pedestrian facilities, truck lay- byes, bus-bays, bus-shelters, cattle crossings, [Traffic Aid Posts, Medical Aid Posts] and service roads | 15 (fifteen) days |
| (ii) | Damaged vehicles or debris on the road | 4 (four) hours |
| (iii) | Malfunctioning of the mobilecrane | 4 (four) hours |
| Bridges | | |
| (a) Superstructure | | |
| (i) | Any damage, cracks, spalling/ scaling Temporarymeasures Permanentmeasures | within 48 (forty-eight) hours within 15 (fifteen) days or as specified by the Authority's Engineer |
| (b) Foundations | | |
| (i) | Scouring and/or cavitation | 15 (fifteen) days |
| (c) Piers, abutments, return walls and wingwalls | | |
| (i) | Cracks and damages including settlement and tilting, spalling, scaling | 30 (thirty) days |
| (d) Bearings (metallic) ofbridges | | |
| (i) | Deformation, damages, tilting or shifting of bearings | 15 (fifteen) days Greasing of metallic bearings once in a year |
| (e) Joints | | |
| (i) | Malfunctioning of joints | 15 (fifteen) days |
| (f) Otheritems | | |
| (i) | Deforming of pads in elastomeric bearings | 7 (seven) days |
| (ii) | Gathering of dirt in bearings and joints; or clogging of spouts, weep holes and vent-holes | 3 (three) days |
| (iii) | Damage or deterioration in kerbs, parapets, handrails and crash barriers | 3 (three) days (immediately within 24 hours if posing danger to safety) |
| (iv) | Rain-cuts or erosion of banks of the side slopes of approaches | 7 (seven) days |
| (v) | Damage to wearing coat | 15 (fifteen) days |
| (vi) | Damage or deterioration in approach slabs, pitching, apron, toes, floor or guidebunds | 30 (thirty) days |
| (vii) | Growth of vegetation affecting the structure or obstructing the waterway | 15 (fifteen) days |
| (g) HillRoads | | |
| (i) | Damage to retaining wall/breast wall | 7 (seven) days |
| (ii) | Landslides requiring clearance | 12 (twelve) hours |
| (iii) | Snow requiring clearance | 24 (twenty-four) hours |

[Note: Where necessary, the Authority may modify the time limit for repair/rectification, or add to the nature of Defect or deficiency beforeissuing the bidding document, with the approval of the competent authority.]

Schedule - F

(See Clause 4.1 (vii) (a))

Applicable Permits

1. Applicable Permits

- (i) The Contractor shall obtain, as required under the Applicable Laws, the following ApplicablePermits:
 - (a) Permission of the State Government for extraction of boulders fromquarry;
 - (b) Permission of Village Panchayats and Pollution Control Board for installation ofcrushers;
 - (c) Licence for use ofexplosives;
 - (d) Permission of the State Government for drawing water fromriver/reservoir;
 - (e) Licence from inspector of factories or other competent Authority for setting up batchingplant;
 - (f) Clearance of Pollution Control Board for setting up batchingplant;
 - (g) Clearance of Village Panchayats and Pollution Control Board for setting up asphaltplant;
 - (h) Permission of Village Panchayats and State Government for borrow earth;and
 - (i) Any other permits or clearances required under ApplicableLaws.
- (ii) Applicable Permits, as required, relating to environmental protection and conservation shall have been procured by the Authority in accordance with the provisions of thisAgreement.

Schedule – G

(See Clauses 7.1 and 19.2)

Annex-I

(See Clause 7.1)

Form of Bank Guarantee

[Performance Security/Additional Performance Security]

[MD,

National Highways & Infrastructure Development Corporation Limited, New Delhi] WHEREAS:

- (A) ____ [name and address of contractor] (Hereinafter called the “**Contractor**”) and [name and address of the authority], (hereinafter called the “**Authority**”) have entered into an agreement (hereinafter called the “**Agreement**”) for the upgradation to 2/4-lane with paved shoulder from km 148+589 to km 176+532 of length 27+943 km on Vailoo – Donipawa section of National Highway No.244 in Union Territory of Jammu & Kashmir on Engineering, Procurement and Construction (the “**EPC**”) basis, subject to and in accordance with the provisions of the Agreement
- (B) The Agreement requires the Contractor to furnish a Performance Security for due and faithful performance of its obligations, under and in accordance with the Agreement, during the {Construction Period/ Defects Liability Period and Maintenance Period} (as defined in the Agreement) in a sum of Rs. cr. (Rupees crore) (the “**Guarantee Amount**”).
- (C) We, through our branch at (the “**Bank**”) have agreed to furnish this bank guarantee (hereinafter called the “**Guarantee**”) by way of Performance Security.

NOW, THEREFORE, the Bank hereby, unconditionally and irrevocably, guarantees and affirms as follows:

1. The Bank hereby unconditionally and irrevocably guarantees the due and faithful performance of the Contractor’s obligations during the {Construction Period/ Defects Liability Period and Maintenance Period} under and in accordance with the Agreement, and agrees and undertakes to pay to the Authority, upon its mere first written demand, and without any demur, reservation, recourse, contest or protest, and without any reference to the Contractor, such sum or sums up to an aggregate sum of the Guarantee Amount as the Authority shall claim, without the Authority being required to prove or to show grounds or reasons for its demand and/or for the sum specified therein.
2. A letter from the Authority, under the hand of an officer not below the rank of [General Manager in the National Highways Authority of India], that the Contractor has committed default in the due and faithful performance of all or any of its obligations under and in accordance with the Agreement shall be conclusive, final and binding on the Bank. The Bank further agrees that the Authority shall be the sole judge as to whether the Contractor is in default in due and faithful performance of its obligations during and under the Agreement and its decision that the Contractor is in default shall be final and binding on the Bank, notwithstanding any differences between the Authority and the Contractor, or any dispute between them pending before any court, tribunal, arbitrators or any other authority or body, or by the discharge of the Contractor for any reason whatsoever.
3. In order to give effect to this Guarantee, the Authority shall be entitled to act as if the Bank were the principal debtor and any change in the constitution of the Contractor and/or the Bank, whether by their absorption with any other body or corporation or otherwise, shall not in any way or manner affect the liability or obligation of the Bank under this Guarantee.
4. It shall not be necessary, and the Bank hereby waives any necessity, for the Authority to proceed against the Contractor before presenting to the Bank its demand under this Guarantee.
5. The Authority shall have the liberty, without affecting in any manner the liability of the Bank

under this Guarantee, to vary at any time, the terms and conditions of the Agreement or to extend the time or period for the compliance with, fulfilment and/ or performance of all or any of the obligations of the Contractor contained in the Agreement or to postpone for any time, and from time to time, any of the rights and powers exercisable by the Authority against the Contractor, and either to enforce or forbear from enforcing any of the terms and conditions contained in the Agreement and/or the securities available to the Authority, and the Bank shall not be released from its liability and obligation under these presents by any exercise by the Authority of the liberty with reference to the matters aforesaid or by reason of time being given to the Contractor or any other forbearance, indulgence, act or omission on the part of the Authority or of any other matter or thing whatsoever which under any law relating to sureties and guarantors would but for this provision have the effect of releasing the Bank from its liability and obligation under this Guarantee and the Bank hereby waives all of its rights under any such law.

6. This Guarantee is in addition to and not in substitution of any other guarantee or security now or which may hereafter be held by the Authority in respect of or relating to the Agreement or for the fulfilment, compliance and/or performance of all or any of the obligations of the Contractor under the Agreement.
7. Notwithstanding anything contained hereinbefore, the liability of the Bank under this Guarantee is restricted to the Guarantee Amount and this Guarantee will remain in force for the period specified in paragraph 8 below and unless a demand or claim in writing is made by the Authority on the Bank under this Guarantee all rights of the Authority under this Guarantee shall be forfeited and the Bank shall be relieved from its liabilities hereunder.
8. The Guarantee shall cease to be in force and effect on ****\$. Unless a demand or claim under this Guarantee is made in writing before expiry of the Guarantee, the Bank shall be discharged from its liabilities hereunder.
9. The Bank undertakes not to revoke this Guarantee during its currency, except with the previous express consent of the Authority in writing and declares and warrants that it has the power to issue this Guarantee and the undersigned has full powers to do so on behalf of the Bank.
10. Any notice by way of request, demand or otherwise hereunder may be sent by post addressed to the Bank at its above referred branch, which shall be deemed to have been duly authorised to receive such notice and to effect payment thereof forthwith, and if sent by post it shall be deemed to have been given at the time when it ought to have been delivered in due course of post and in proving such notice, when given by post, it shall be sufficient to prove that the envelope containing the notice was posted and a certificate signed by an officer of the Authority that the envelope was so posted shall be conclusive.
11. This Guarantee shall come into force with immediate effect and shall remain in force and effect for up to the date specified in paragraph 8 above or until it is released earlier by the Authority pursuant to the provisions of the Agreement.

Signed and sealed this day of, 20..... at

SIGNED, SEALED AND DELIVERED

For and on behalf of the Bank by:

(Signature) (Name) (Designation) (Code Number) (Address)

NOTES:

- (i) The bank guarantee should contain the name, designation and code number of the officer(s) signing the guarantee.

The address, telephone number and other details of the head office of the Bank as well as of issuing branch should be mentioned on the covering letter of issuing branch.

Annex – II
(Schedule - G)
(See Clause 19.2)

Form for Guarantee for Advance Payment

[MD,

National Highways & Infrastructure Development Corporation Limited, New Delhi] WHEREAS:

- (A) [name and address of contractor] (hereinafter called the “**Contractor**”) has executed an agreement (hereinafter called the “**Agreement**”) with the [name and address of the authority], (hereinafter called the “**Authority**”) for upgradation to 2/4-lane with paved shoulder from km 148+589 to km 176+532 of length 27+943 km on Vailoo – Donipawa section of National Highway No. 244 in Union Territory of Jammu & Kashmir on Engineering, Procurement and Construction (the “**EPC**”) basis, subject to and in accordance with the provisions of the Agreement
- (B) In accordance with Clause 19.2 of the Agreement, the Authority shall make to the Contractor an interest bearing @Bank Rate + 3% advance payment (herein after called “**Advance Payment**”) equal to 10% (ten percent) of the Contract Price; and that the Advance Payment shall be made in two instalments subject to the Contractor furnishing an irrevocable and unconditional guarantee by a scheduled bank for an amount equivalent to 110% (one hundred and ten percent) of such instalment to remain effective till the complete and full repayment of the instalment of the Advance Payment as security for compliance with its obligations in accordance with the Agreement. The amount of {first/second} instalment of the Advance Payment is Rs. ----- cr. (Rupees crore) and the amount of this Guarantee is Rs. ----- cr. (Rupees ----- crore) (the “**Guarantee Amount**”) ^{\$}.
- (C) We, through our branch at (the “**Bank**”) have agreed to furnish this bank guarantee (hereinafter called the “**Guarantee**”) for the Guarantee Amount.

NOW, THEREFORE, the Bank hereby, unconditionally and irrevocably, guarantees and affirms as follows:

The Bank hereby unconditionally and irrevocably guarantees the due and faithful repayment on time of the aforesaid instalment of the Advance Payment under and in accordance with the Agreement, and agrees and undertakes to pay to the Authority, upon its mere first written demand, and without any demur, reservation, recourse, contest or protest, and without any reference to the Contractor, such sum or sums up to an aggregate sum of the Guarantee Amount as the Authority shall claim, without the Authority being required to prove or to show grounds or reasons for its demand and/or for the sum specified therein.

1. A letter from the Authority, under the hand of an officer not below the rank of [General Manager in the National Highways Authority of India], that the Contractor has committed default in the due and faithful performance of all or any of its obligations for the repayment of the instalment of the Advance Payment under and in accordance with the Agreement shall be conclusive, final and binding on the Bank. The Bank further agrees that the Authority shall be the sole judge as to whether the Contractor is in default in due and faithful performance of its obligations during and under the Agreement and its decision that the Contractor is in default shall be final and binding on the Bank, notwithstanding any differences between the Authority and the Contractor, or any dispute between them pending before any court, tribunal, arbitrators or any other authority or body, or by the discharge of the Contractor for any reason whatsoever.
2. In order to give effect to this Guarantee, the Authority shall be entitled to act as if the Bank were the principal debtor and any change in the constitution of the Contractor and/or the Bank, whether by their absorption with any other body or corporation or otherwise, shall not in any way or manner affect the liability or obligation of the Bank under this Guarantee.
3. It shall not be necessary, and the Bank hereby waives any necessity, for the Authority to proceed against the Contractor before presenting to the Bank its demand under this Guarantee.

^{\$} The Guarantee Amount should be equivalent to 110% of the value of the applicable instalment.

4. The Authority shall have the liberty, without affecting in any manner the liability of the Bank under this Guarantee, to vary at any time, the terms and conditions of the Advance Payment or to extend the time or period of its repayment or to postpone for any time, and from time to time, any of the rights and powers exercisable by the Authority against the Contractor, and either to enforce or forbear from enforcing any of the terms and conditions contained in the Agreement and/or the securities available to the Authority, and the Bank shall not be released from its liability and obligation under these presents by any exercise by the Authority of the liberty with reference to the matters aforesaid or by reason of time being given to the Contractor or any other forbearance, indulgence, act or omission on the part of the Authority or of any other matter or thing whatsoever which under any law relating to sureties and guarantors would but for this provision have the effect of releasing the Bank from its liability and obligation under this Guarantee and the Bank hereby waives all of its rights under any such law.
5. This Guarantee is in addition to and not in substitution of any other guarantee or security now or which may hereafter be held by the Authority in respect of or relating to the Advance Payment.
6. Notwithstanding anything contained hereinbefore, the liability of the Bank under this Guarantee is restricted to the Guarantee Amount and this Guarantee will remain in force for the period specified in paragraph 8 below and unless a demand or claim in writing is made by the Authority on the Bank under this Guarantee all rights of the Authority under this Guarantee shall be forfeited and the Bank shall be relieved from its liabilities hereunder.
7. The Guarantee shall cease to be in force and effect on ****\$unless a demand or claim under this Guarantee is made in writing on or before the aforesaid date, the Bank shall be discharged from its liabilities hereunder.
8. The Bank undertakes not to revoke this Guarantee during its currency, except with the previous express consent of the Authority in writing and declares and warrants that it has the power to issue this Guarantee and the undersigned has full powers to do so on behalf of the Bank.
9. Any notice by way of request, demand or otherwise hereunder may be sent by post addressed to the Bank at its above referred branch, which shall be deemed to have been duly authorised to receive such notice and to effect payment thereof forthwith, and if sent by post it shall be deemed to have been given at the time when it ought to have been delivered in due course of post and in proving such notice, when given by post, it shall be sufficient to prove that the envelope containing the notice was posted and a certificate signed by an officer of the Authority that the envelope was so posted shall be conclusive.
10. This Guarantee shall come into force with immediate effect and shall remain in force and effect up to the date specified in paragraph 8 above or until it is released earlier by the Authority pursuant to the provisions of the Agreement.

Signed and sealed this day of, 20..... at

SIGNED, SEALED AND DELIVERED

For and on behalf of the Bank by:

(Signature) (Name) (Designation) (Code Number) (Address)

NOTES:

(i) The bank guarantee should contain the name, designation and code number of the officer(s) signing the guarantee.

\$ Insert a date being 90 (ninety) days after the end of one year from the date of payment of the Advance payment to the Contractor (in accordance with Clause 19.2 of the Agreement).

(ii) The address, telephone number and other details of the head office of the Bank as well as of issuing branch should be mentioned on the covering letter of issuing branch.

Annex – III

(Schedule - G)

(See Clause 7.5.v)

Form for Guarantee for Withdrawal of Retention Money

The Managing Director,
National Highways & Infrastructure Development Corporation Limited
New Delhi

WHEREAS:

- (A) [name and address of contractor] (hereinafter called the “**Contractor**”) has executed an agreement (hereinafter called the “**Agreement**”) with the [name and address of the authority], (hereinafter called the “**Authority**”) for the construction of the ***** section of [National Highway No. **] on Engineering, Procurement and Construction (the “**EPC**”) basis, subject to and in accordance with the provisions of the Agreement.
- (B) In accordance with Clause 7.5.3 of the Agreement, the Contractor may withdraw the retention money (hereinafter called the “**Retention Money**”) after furnishing to the Authority a bank guarantee for an amount equal to the proposed withdrawal.
- (C) We, through our branch at (the “**Bank**”) have agreed to furnish this bank guarantee (hereinafter called the “**Guarantee**”) for the amount of Rs. - ----- cr. (Rs.-----crore) (the “**Guarantee Amount**”).

NOW, THEREFORE, the Bank hereby unconditionally and irrevocably guarantees and affirms as follows:

1. The Bank hereby unconditionally and irrevocably undertakes to pay to the Authority, upon its mere first written demand, and without any demur, reservation, recourse, contest or protest, and without any reference to the Contractor, such sum or sums up to an aggregate sum of the Guarantee Amount as the Authority shall claim, without the Authority being required to prove or to show grounds or reasons for its demand and/or for the sum specified therein.
2. A letter from the Authority, under the hand of an officer not below the rank of General Manager in the National Highways & Infrastructure Development Corporation Limited (NHIDCL) , that the Contractor has committed default in the due and faithful performance of all or any of its obligations for under and in accordance with the Agreement shall be conclusive, final and binding on the Bank. The Bank further agrees that the Authority shall be the sole judge as to whether the Contractor is in default in due and faithful performance of its obligations during and under the Agreement and its decision that the Contractor is in default shall be final, and binding on the Bank, notwithstanding any differences between the Authority and the Contractor, or any dispute between them pending before any court,

- tribunal, arbitrators or any other authority or body, or by the discharge of the Contractor for any reason whatsoever.
3. In order to give effect to this Guarantee, the Authority shall be entitled to act as if the Bank were the principal debtor and any change in the constitution of the Contractor and/or the Bank, whether by their absorption with any other body or corporation or otherwise, shall not in any way or manner affect the liability or obligation of the Bank under this Guarantee.
 4. It shall not be necessary, and the Bank hereby waives any necessity, for the Authority to proceed against the Contractor before presenting to the Bank its demand under this Guarantee.
 5. The Authority shall have the liberty, without affecting in any manner the liability of the Bank under this Guarantee, to vary at any time, the terms and conditions of the Retention Money and any of the rights and powers exercisable by the Authority against the Contractor, and either to enforce or forbear from enforcing any of the terms and conditions contained in the Agreement and/or the securities available to the Authority, and the Bank shall not be released from its liability and obligation under these presents by any exercise by the Authority of the liberty with reference to the matters aforesaid or by reason of time being given to the Contractor or any other forbearance, indulgence, act or omission on the part of the Authority or of any other matter or thing whatsoever which under any law relating to sureties and guarantors would but for this provision have the effect of releasing the Bank from its liability and obligation under this Guarantee and the Bank hereby waives all of its rights under any such law.
 6. This Guarantee is in addition to and not in substitution of any other guarantee or security now or which may hereafter be held by the Authority in respect of or relating to the Retention Money.
 7. Notwithstanding anything contained hereinbefore, the liability of the Bank under this Guarantee is restricted to the Guarantee Amount and this Guarantee will remain in force for the period specified in paragraph 8 below and unless a demand or claim in writing is made by the Authority on the Bank under this Guarantee all rights of the Authority under this Guarantee shall be forfeited and the Bank shall be relieved from its liabilities hereunder.
 8. The Guarantee shall cease to be in force and effect 90 (ninety) days after the date of the Completion Certificate specified in Clause 12.4 of the Agreement.
 9. The Bank undertakes not to revoke this Guarantee during its currency, except with the previous express consent of the Authority in writing, and declares and warrants that it has the power to issue this Guarantee and the undersigned has full powers to do so on behalf of the Bank.
 10. Any notice by way of request, demand or otherwise hereunder may be sent by post addressed to the Bank at its above referred branch, which shall be deemed to have been duly authorized to receive such notice and to effect payment thereof forthwith, and if sent

by post it shall be deemed to have been given at the time when it ought to have been delivered in due course of post and in proving such notice, when given by post, it shall be sufficient to prove that the envelope containing the notice was posted and a certificate signed by an officer of the Authority that the envelope was so posted shall be conclusive.

11. This Guarantee shall come into force with immediate effect and shall remain in force and effect up to the date specified in paragraph 8 above or until it is released earlier by the Authority pursuant to the provisions of the Agreement.
12. This guarantee shall also be operatable at ourBranch at New Delhi, from whom, confirmation regarding the issue of this guarantee or extension / renewal thereof shall be made available on demand. In the contingency of this guarantee being invoked and payment thereunder claimed, the said branch shall accept such invocation letter and make payment of amounts so demanded under the said invocation.
13. The guarantor/bank hereby confirms that it is on the SFMS (Structural Finance Messaging System) platform & shall invariably send an advice of this Bank Guarantee to the designated bank of NHIDCL, details of which is as under:

| S.No | Particulars | Details |
|------|------------------------------|--|
| 1 | Name of Beneficiary | National Highways & Infrastructure Development Corporation Limited |
| 2 | Beneficiary Bank Account No. | 90621010002610 |
| 3 | Beneficiary Bank Branch | IFSC SYNB0009062 |
| 4 | Beneficiary Bank Branch Name | Transport Bhawan, New Delhi |
| 5 | Beneficiary Bank Address | Canara Bank (erstwhile Syndicate Bank) transport Bhawan, 1st Parliament Street, New Delhi-110001 |

Signed and sealed this day of, 20..... at

SIGNED, SEALED AND DELIVERED For and on
behalf of the Bank by:

(Signature)

(Name)

(Designation) (Code

Number) (Address) NOTES:

- (i) The bank guarantee should contain the name, designation and code number of the officer(s) signing the guarantee.
- (ii) The address, telephone number and other details of the head office of the Bank as well as of issuing branch should be mentioned on the covering letter of issuing branch.

Schedule – H

See Clauses 10.1 (iv) and 19.3

Contract Price Weightages

- 1.1 The Contract Price for this Agreement is **Rs. 203.043 Crores**
- 1.2 Proportions of the Contract Price for different stages of Construction of the Project Highway shall be as specified below:

| Item | Weightage in percentage to the Contract Price | Stage of Payment | Percentage Weightage |
|--|---|--|----------------------|
| 1 | 2 | 3 | 4 |
| Road works including culverts, widening and repair of culverts. | 48.960% | B.1 - Reconstruction/New 2-lane realignment/bypass (Flexible pavement) | |
| | | (1) Earthwork up to top of sub-grade | 5.980% |
| | | (2) Sub-Base Course | 12.970% |
| | | (3) Non-Bituminous Base Course | 14.749% |
| | | (4) Bituminous Base Course | 21.834% |
| | | (5) Wearing Coat | 13.392% |
| | | C.1 - Reconstruction/New service road/Link Road (Flexible pavement) | |
| | | 1) Earthwork up to top of Sub-grade | 0.000% |
| | | 2) Sub-Base Course | 0.000% |
| | | 3) Non -Bituminous Base Course | 0.000% |
| | | 4) Bituminous Base Course | 0.000% |
| | | 5) Wearing Coat | 0.000% |
| | | D - Re-Construction and New culverts on existing road, realignments, bypasses: | |
| | | (1) Culverts (length < 6m) | 31.075% |
| Minor Bridges/ Underpasses/Overpasses/Viaduct | 9.964% | A.1-Widening and repair of minor bridges (length > 6m and < 60m) | |
| | | Minor Bridges | 0.617% |
| | | A.2- New minor bridges/ Viaduct | |
| | | (i) Foundation +Sub- Structure: On completion of the foundation work including foundations for wing and return walls, abutments, piers up to the abutment/pier cap. | 66.562% |
| | | (ii) Super-structure: On completion of the superstructure in all respects including wearing coat, bearings, expansion joints, handrails, crash barriers, road signs & markings, tests on completion etc. complete in all respect. | 31.853% |
| | | (iii) Approaches: On completion of approaches including Retaining walls, | 0.968% |

| Item | Weightage in percentage to the Contract Price | Stage of Payment | Percentage Weightage |
|---|---|---|----------------------|
| 1 | 2 | 3 | 4 |
| | | stone pitching, protection works complete in all respect and fit for use. | |
| Major Bridge (length >60 m) works and ROB/ RUB/ elevated sections/flyovers including viaducts, if any | 2.069% | A.1- Widening and repairs of Major Bridges | |
| | | 1) Dismantling of old existing bridge | 1.785% |
| | | 2) Foundation | 17.057% |
| | | 3) Sub-structure | 0.000% |
| | | 4) Super-structure (including bearings) | 1.785% |
| | | 5) Wearing Coat including expansion joints | 2.211% |
| | | 6) Miscellaneous Items like handrails, crash barriers, road markings etc.) | 2.639% |
| | | 7) Wing walls/return walls | 0.000% |
| | | 8) Guide Bunds, River Training works etc. | 50.143% |
| | | 9) Approaches (including Retaining walls, stone pitching and protection works) | 24.380% |
| Other Works | 39.007% | 1) Toll Plaza | 0.000% |
| | | 2) Roadside drains | 57.067% |
| | | 3) Road signs, markings, km stones safety devices, crash barrier..... | 29.588% |
| | | 4) Project Facilities | 0.000% |
| | | a) Bus bye /Bus Stop & Rainwater Harvesting | 1.129% |
| | | b) Truck lay-byes | 0.000% |
| | | c) Others | 0.000% |
| | | d) Junctions | 3.420% |
| | | e) High Mast Lighting & Electric Pole | 4.129% |
| | | 5) Roadside plantation & Miscellaneous | 0.704% |
| | | 6) Protection works including structures location i.e. Retaining/Toe wall/Gabion Wall | 0.748% |
| | | 7) Slope Protection (Hill Side) (Breast Wall & Wire Mesh) | 0.000% |
| | | 8) Safety and traffic management during construction | 3.215% |

1.3 Procedure of estimating the value of work done

1.3.1 Road works

Procedure for estimating the value of road work done shall be as follows:

Table 1.3.1

| Stage of Payment | Percentage - Weightage | Payment Procedure |
|---|------------------------|--|
| B.1 - Reconstruction/New 2-lane realignment/bypass (Flexible pavement) | | Unit of measurement is linear length. Payment of each stage shall be made on pro rata basis on completion of a stage in full length or 10% of total length, whichever is less. |
| (1) Earthwork up to top of the sub-grade | 5.980% | |
| (2) Sub-base Course | 12.970% | |
| (3) Non-Bituminous Course | 14.749% | |
| (4) Bituminous Base Course | 21.834% | |
| (5) Wearing Coat | 13.392% | |
| 6) Widening and repair of culverts | 0.000% | |
| B.2 - Reconstruction/New 2-lane realignment/bypass (Rigid pavement) | | Unit of measurement is linear length. Payment of each stage shall be made on pro rata basis on completion of a stage in full length or 5(five) km. length, whichever is less. |
| (1) Earthwork up to top of the sub-grade | 0.000% | |
| (2) Sub-Base Course | 0.000% | |
| (3) Dry Lean Concrete (DLC) Course | 0.000% | |
| (4) Pavement Quality Control (PQC) Course | 0.000% | |
| C.1 - Reconstruction/New service road (Flexible pavement) | | Unit of measurement is linear length. Payment of each stage shall be made on pro rata basis on completion of a stage in full length or 10% of total length, whichever is less. |
| (1) Earthwork up to top of the sub-grade | 0.000% | |
| (2) Sub-Base Course | 0.000% | |
| (3) Non-Bituminous Course | 0.000% | |
| (4) Bituminous Base Course | 0.000% | |
| (5) Wearing Coat | 0.000% | |
| D - Re-Construction and New culverts on existing road, realignments, bypasses: | | |
| (1) Culverts (length < 6m) | 31.075% | Cost of each culvert shall be determined on pro rata basis with respect to the total number of culverts. Payment shall be made on the completion of at each culverts. |

For example, if the total length of bituminous work to be done is 100 km, the cost per km of bituminous work shall be determined as follows:

Cost per km = P x weightage for road work x weightage for bituminous work x (1/L)

Where P= Contract Price

L = Total length in km

Similarly, the rates per km for other stages shall be worked out accordingly.

Note: The length affected due to law and order problems or litigation during execution due to which the Contractor is unable to execute the work, may be deducted from the total project length for payment purposes. The total length calculated here is only for payment purposes and will not affect and referred in other clauses of the Contract Agreement.

1.3.2 Minor Bridges and Underpasses/Overpasses.

Procedure for estimating the value of Minor bridge and Underpasses/Overpasses shall be as stated in table 1.3.2:

Table 1.3.2

| <u>Stage of Payment</u> | <u>Weightage</u> | <u>Payment Procedure</u> |
|--|------------------|---|
| 1 | 2 | 3 |
| A.1-Widening and repair of minor bridges | 0.617% | Cost of each minor bridge shall be determined on pro rata basis with respect to the total linear length of the minor bridges. Payment shall be made on the completion of widening & repair works of a minor bridge. |
| (length > 6m and < 60m) | | |
| A.2- New minor bridges | | |
| (i) Foundation +Sub- Structure: On completion of the foundation work including foundations for wing and return walls, abutments, piers up to the abutment/pier cap. | 66.562% | (i) Foundation +Sub- Structure: Cost of each minor bridge shall be determined on pro rata basis with respect to the total linear length (m) of the minor bridges. Payment against foundation + sub-structure shall be made on pro-rata basis on completion of a stage i.e. not less than 25% of the scope of foundation +substructure of each bridge subject to completion of at least two foundations along with sub-structure up to abutment/pier cap level of each bridge. In case where load testing is required for foundation, the trigger of first payment shall include load testing also where specified. |
| (ii) Super-structure: On completion of the superstructure in all respects including wearing coat, bearings, expansion joints, handrails, crash barriers, road signs & markings, tests on completion etc. complete in all respect. | 31.853% | (ii) Super-structure: Payment shall be made on pro-rata basis on completion of a stage i.e. completion of super-structure of at least one span in all respects as specified in the column of "Stage of Payment" in this sub-clause. |
| (iii) Approaches: On completion of approaches including Retaining walls, stone pitching, protection works complete in all respect and fit for use. | 0.968% | (iii) Approaches: Payment shall be made on pro-rata basis on completion of a stage i.e. completion of approaches in all respect as specified in the column of "Stage of Payment" in this sub-clause. |
| B.2- New Vehicular Underpass/Overpass | | |
| 1) Foundation +Sub-Structure: On completion of the foundation work including foundations for wing and return walls, abutments, piers upto the abutment/pier cap. | 0.000% | (i) Foundation +Sub- Structure: Cost of each minor bridge shall be determined on pro rata basis with respect to the total linear length (m) of the minor bridges. Payment against foundation + sub-structure shall be made on pro-rata basis on completion of a stage i.e. not less than 25% of the scope of foundation +substructure of each bridge subject to completion of at least two foundations along with sub-structure up to abutment/pier cap level of each bridge. In case where load testing is required for foundation, the trigger of first payment shall include load testing also where specified. |

| Stage of Payment | Weightage | Payment Procedure |
|---|------------------|---|
| 1 | 2 | 3 |
| 2) Super-structure: On completion of the super-structure in all respects including wearing coat, bearings, expansion joints, handrails, crash barriers, road signs & markings tests on completion etc. complete in all respect. | 0.000% | (ii) Super-structure: Payment shall be made on pro-rata basis on completion of a stage i.e. completion of super-structure of at least one span in all respects as specified in the column of “Stage of Payment” in this sub-clause. |
| 3) Approaches: On completion of approaches including Retaining walls, stone pitching, protection works complete in all respect and fit for use. | 0.000% | (iii) Approaches: Payment shall be made on pro-rata basis on completion of a stage i.e. completion of approaches in all respect as specified in the column of “Stage of Payment” in this sub-clause. |

1.3.3 Major Bridge works, ROB/RUB and Structures.

Procedure for estimating the value of Major Bridge works, ROB/RUB and Structures shall be as stated in table 1.3.3:

Table 1.3.3

| Stage of Payment | Weightage | Payment Procedure |
|---|------------------|--|
| 1 | 2 | 3 |
| A.1- Widening and repairs of Major Bridges | | |
| (i) Dismantling & removal of debris from riverbed | 1.785% | (i) Payments shall be made on completion of all dismantling & removal of debris complete in all respects as specified. |
| (ii) Foundation | 17.057% | (ii) Foundation: Cost of each Major Bridge shall be determined on pro rata basis with respect to the total linear length (m) of the Major Bridge. Payment against foundation shall be made on prorata basis on completion of a stage i.e. not less than 25% of the scope of foundation of the major Bridge subject to completion of at least two foundations of the major Bridge. |
| (iii) Sub-structure | 0.000% | (iii) Sub-Structure: Payment against Substructure shall be made on pro-rata basis on completion of a stage i.e. not less than 25% of the scope of substructure of the major bridge subject to completion of at least two sub-structures of abutments/piers up to abutment/pier cap level of the major bridge. |
| (iv) Wing walls/return walls | 0.000% | (iv) Wing walls/return walls: Payments shall be made on completion of all wing walls/return walls complete in all respects as specified. |
| (v) Super-structure: (including bearings) | 1.785% | (v) Super-structure: Payment shall be made on pro-rata basis on completion of a stage i.e. completion of |

| Stage of Payment | Weightage | Payment Procedure |
|---|------------------|--|
| 1 | 2 | 3 |
| | | super-structure including bearings of at least one span in all respects as specified. |
| (vi) Wearing Coat including expansion joints | 2.211% | (vi) Wearing Coat: Payment shall be made on completion of wearing coat including expansion joints complete in all respects as specified. |
| (vii) Miscellaneous Items like handrails, crash barriers, road markings etc. | 2.639% | (vii) Miscellaneous: Payments shall be made on completion of all miscellaneous works like handrails, crash barriers, road markings etc. complete in all respects as specified. |
| (viii) Guide Bunds, River Training works etc. | 50.143% | (viii) Guide Bunds, River Training works: Payments shall be made on completion of all guide bunds/river training works etc. complete in all respects as specified. |
| (ix) Approaches (including Retaining walls, stone pitching and protection works) | 24.380% | (ix) Approaches: Payments shall be made on completion of both approaches including stone pitching, protection works, etc. complete in all respects as specified. |

Note:

- (1) In case of innovate Major Bridge projects like cable suspension/cable stayed/ Extra Dozed and exceptionally long span bridges, the schedule may be modified as per site requirements before bidding with due approval of Competent Authority.
- (2) The Schedule for exclusive tunnel projects may be prepared as per site requirements before bidding with due approval of Competent Authority.

1.3.4 Other works.

Procedure for estimating the value of other works done shall be as stated in table 1.3.4.

Table 1.3.4

| Stage of Payment | Weightage | Payment Procedure |
|--|------------------|---|
| (i) Toll plaza | 0.000% | Unit of measurement is each completed toll plaza. Payment of each toll plaza shall be made on pro rata basis with respect to the total of all toll plazas. |
| (ii) Road-side drains | 57.067% | Unit of measurement is linear length in km./Nos./sqm Payment shall be made on prorate basis on completion of a stage in a length of not less than 5 % (Five per cent) of the scope of work. |
| (iii) Road signs, markings, km stones, safety devices, ... | 29.588% | |
| (iv) Project Facilities | | |
| a) Bus bays including shelter | 1.129% | Payment shall be made on pro rata basis for completed facilities. |
| b) Truck lay-byes | 0.000% | |
| c) Rest areas | 0.000% | |
| d) other Junctions | 3.420% | |

| Stage of Payment | Weightage | Payment Procedure |
|--|-----------|---|
| (v) High Mast Lighting and Lighting in built-up area | 4.129% | Unit of measurement is linear length. |
| (vi) Roadside plantation & Mis. | 0.704% | |
| (vii) protection works i.e. Retaining wall/Toe wall) | 0.748% | Payment shall be made on pro rata basis on completion of a stage in a length of not less than 5% (Five per cent) of the total length. |
| (viii) Slope Protection (Hill Side) i.e. Breast wall | 0.000% | |
| (ix) Safety and traffic management during construction | 3.215% | Every three monthly |

2. Procedure for payment for Maintenance

- 2.1 The cost for maintenance shall be as stated in Clause 14.1.1.
- 2.2 Payment for Maintenance shall be made in quarterly instalments in accordance with the provisions of Clause 19.7.

Schedule - I

(See Clause 10.2 (iv))

Drawings

1. Drawings

In compliance of the obligations set forth in Clause 10.2 of this Agreement, the Contractor shall furnish to the Authority's Engineer, free of cost, all Drawings listed in Annex-I of this Schedule-I.

2. Additional Drawings

If the Authority's Engineer determines that for discharging its duties and functions under this Agreement, it requires any drawings other than those listed in Annex-I, it may by notice require the Contractor to prepare and furnish such drawings forthwith. Upon receiving a requisition to this effect, the Contractor shall promptly prepare and furnish such drawings to the Authority's Engineer, as if such drawings formed part of Annex-I of this Schedule-I.

Annex - I

(Schedule - I)

List of Drawings

1. The Project drawings, as defined in Clause 1.1, Definitions, Article 1, Definitions and Interpretation, Part-I: Preliminary, of the Contract Agreement shall consist:
 - (a) Working Drawings of all the components/elements of the Project as determined by Authority Engineer/Authority, and
 - (b) As-built drawings for the Project components/elements as determined by AE/Authority. As-built drawings shall be duly certified by Authority Engineer.
2. A minimum list of the drawings of the various components/elements of the Project and project facilities required to be submitted by the Contractor is given below:

A. BRIDGE

General Arrangement Drawing
Detailed Drawings of Structures/Bridges

B. ROAD (PLAN & PROFILE)

Plan & Profile
Cross Sections
Drawings of horizontal alignment, vertical profile and cross sections
Drawings of cross drainage works
Drawings of traffic diversion plans and traffic control measures
Drawings of road drainage measures
Drawings of typical details slope protection measures
Drawings of landscaping and horticulture
Drawings of street lighting

C. STANDARD DRAWINGS

Detail of Mandatory Regulatory Signs
Detail of Mandatory Regulatory Signs & Compulsory Direction Control and Other Signs
Detail of Informatroy Signs
Detail of Cautionary Signs-TS
Detail of cautionary warning signs
Detail of cautionary warning signs
Details of route marking (chevron marking)
Details of road marking
Details of directional signs
Details Toe drain
Details of pitching, filtermaterial, chute drain and energy dissipation basin-std
Details of double head metal beam crash barrier
Details for 200meter 1 km & km post
Detail for boundary stone & guard post
Drain retaining wall & kerb
Gabion wall

Schedule - J

(See Clause 10.3 (ii))

Project Completion Schedule

1. Project CompletionSchedule

During Construction period, the Contractor shall comply with the requirements set forth in this Schedule-J for each of the Project Milestones and the **Scheduled Completion Date**. Within 15 (fifteen) days of the date of each Project Milestone, the Contractor shall notify the Authority of such compliance along with necessary particulars thereof.

2. ProjectMilestone-I

- (i) Project Milestone-I shall occur on the date falling on the **192th**(One Hundred and Ninety Two) day from the Appointed Date (the “**Project Milestone-I**”).
- (ii) Prior to the occurrence of Project Milestone-I, the Contractor shall have commenced construction of the Project Highway and submitted to the Authority duly and validly prepared Stage Payment Statements for an amount not less than 10% (ten per cent) of the ContractPrice.

3. ProjectMilestone-II

- (i) Project Milestone-II shall occur on the date falling on the **329th**(Three Hundred and Twenty Nine) day from the Appointed Date (the “Project Milestone- II”).
- (ii) Prior to the occurrence of Project Milestone-II, the Contractor shall have continued with construction of the Project Highway and submitted to the Authority duly and validly prepared Stage Payment Statements for an amount not less than 35% (thirty-five per cent) of the Contract Price and should have started construction of all bridges.

4. ProjectMilestone-III

- (i) Project Milestone-III shall occur on the date falling on the **466st**(Four Hundred &Sixty Six) day from the Appointed Date (the “Project Milestone- III”).
- (ii) Prior to the occurrence of Project Milestone-III, the Contractor shall have continued with construction of the Project Highway and submitted to the Authority duly and validly prepared Stage Payment Statements for an amount not less than 70% (seventy per cent) of the Contract Price and should have started construction of all project facilities.

5. Scheduled CompletionDate

- (i) The Scheduled Completion Date shall occur on the **548th**(Five Hundred and Forty Eight) day from the Appointed Date.
- (ii) On or before the Scheduled Completion Date, the Contractor shall have completed construction in accordance with this Agreement.

6. Extension of time

Upon extension of any or all of the aforesaid Project Milestones or the Scheduled Completion Date, as the case may be, under and in accordance with the provisions of this Agreement, the Project Completion Schedule shall be deemed to have been amended accordingly.

Schedule - K

(See Clause 12.1 (ii))

Tests on Completion

1. Schedule for Tests

- (i) The Contractor shall, no later than 30 (thirty) days prior to the likely completion of construction, notify the Authority's Engineer and the Authority of its intent to subject the Project Highway to Tests, and no later than 10(ten) days prior to the actual date of Tests, furnish to the Authority's Engineer and the Authority detailed inventory and particulars of all works and equipment forming part of Works.
- (ii) The Contractor shall notify the Authority's Engineer of its readiness to subject the Project Highway to Tests at any time after 10 (ten) days from the date of such notice, and upon receipt of such notice, the Authority's Engineer shall, in consultation with the Contractor, determine the date and time for each Test and notify the same to the Authority who may designate its representative to witness the Tests. The Authority's Engineer shall thereupon conduct the Tests itself or cause any of the Tests to be conducted in accordance with Article 12 and this Schedule-K.

2. Tests

A. Road and Bridge

- (i) Visual and physical test: The Authority's Engineer shall conduct a visual and physical check of construction to determine that all works and equipment forming part thereof conform to the provisions of this Agreement. The physical tests shall include [***].
- (ii) Riding quality test: Riding quality of each lane of the carriageway shall be checked with the help of a Network Survey Vehicle (NSV) fitted with latest equipments and the maximum permissible roughness for purposes of this Test shall be [2,000 (two thousand)] mm for each kilometre.
- (iii) Tests for bridges: All major and minor bridges shall be subjected to the rebound hammer and ultrasonic pulse velocity tests, to be conducted in accordance with the procedure described in Special Report No. 17: 1996 of the IRC Highway Research Board on Nondestructive Testing Techniques, at two spots in every span, to be chosen at random by the Authority's Engineer. Bridges with a span of 15 (fifteen) metres or more shall also be subjected to load testing.
- (iv) Other tests: The Authority's Engineer may require the Contractor to carry out or cause to be carried additional tests, in accordance with Good Industry Practice, for determining the compliance of the Project Highway with Specifications and Standards, except tests as specified in clause 5, but shall include measuring the reflectivity of road markings and road signs; and measuring the illumination level (lux) of lighting using requisite testing equipment.

B. Other Tests

- (i) Environmental audit: The Authority's Engineer shall carry out a check to determine conformity of the Project Highway with the environmental requirements set forth in Applicable Laws and Applicable Permits.
- (ii) Safety Audit: The Authority's Engineer shall carry out, or cause to be carried out, a safety audit to determine conformity of the Project Highway with the safety requirements and Good Industry Practice.

3. Agency for conducting Tests

All Tests set forth in this Schedule-K shall be conducted by the Authority's Engineer or such other agency or person as it may specify in consultation with the Authority.

4. Completion Certificate

Upon successful completion of Tests, the Authority's Engineer shall issue the Completion Certificate in accordance with the provisions of Article 12.

5. The Authority Engineer will carry out tests with following equipment at his own cost in the presence of contractor's representative.

| Sr.No. | Key metrics of Asset | Equipment to be used | Frequency of condition survey |
|--------|-----------------------------|-------------------------------------|---|
| 1 | Surface of defects pavement | Network Survey Vehicle (NSV) | At least twice a year (As per survey months defined for the state basis rainy season) |
| 2 | Roughness of pavement | Network Survey Vehicle (NSV) | At least twice a year (As per survey months defined for the state basis rainy season) |
| 3 | Strength of pavement | Falling Weight Deflectometer (FWD) | At least once a year |
| 4 | Bridges | Mobile Bridge Inspection Unit (MBU) | At least twice a year (As per survey months defined for the state basis rainy season) |
| 5 | Road signs | Retro-reflectometer | At least twice a year (As per survey months defined for the state basis rainy season) |

The first testing with the help of NSV shall be conducted at the time of issue of Completion Certificate.

Schedule - L

(See Clause 12.2)

Completion Certificate

1 I, (Name of the Authority's Engineer), acting as the Authority's Engineer, under and in accordance with the Agreement dated (the "**Agreement**"), for upgradation to 2/4-lane with paved shoulder from form Km 148+589 (Ex. Km 235+070) to Km 176+532 (Ex. Km 263+107) of length 27.944 Km on Vailoo-Donipawa section of NH-244 in Union Territory of Jammu & Kashmir (the "**Project Highway**") on Engineering, Procurement and Construction (EPC) basis through (Name of Contractor), hereby certify that the Tests in accordance with Article 12 of the Agreement have been successfully undertaken to determine compliance of the Project Highway with the provisions of the Agreement, and I am satisfied that the Project Highway can be safely and reliably placed in service of the Users thereof.

2 It is certified that, in terms of the aforesaid Agreement, all works forming part of Project Highway have been completed, and the Project Highway is hereby declared fit for entry into operation on this the day of 20..., Scheduled Completed

Date for which was the day of 20....

SIGNED, SEALED AND DELIVERED

For and on behalf of the Authority's Engineer by:

(Signature)

(Name) (Designation) (Address)

Schedule - M

(See Clauses 14.6, 15.2 and 19.7)

Payment Reduction for Non-Compliance

1. Payment reduction for non-compliance with the Maintenance Requirements

- (i) Monthly lump sum payments for maintenance shall be reduced in the case of non-compliance with the Maintenance Requirements set forth in Schedule-E.
- (ii) Any deduction made on account of non-compliance with the Maintenance Requirements shall not be paid even after compliance subsequently. The deductions shall continue to be made every month until compliance is done.
- (iii) The Authority's Engineer shall calculate the amount of payment reduction on the basis of weightage in percentage assigned to non-conforming items as given in Paragraph 2.

2. Percentage reductions in lump sum payments on monthly basis

- (i) The following percentages shall govern the payment reduction:

| S. No. | Item/Defect/Deficiency | Percentage |
|--|--|------------|
| (a) Carriageway/Pavement | | |
| (i) | Potholes, cracks, other surface defects | 15% |
| (ii) | Repairs of Edges, Rutting | 5% |
| (b) Road, Embankment, Cuttings, Shoulders | | |
| (i) | Edge drop, inadequate cross fall, undulations, settlement, potholes, ponding, obstructions | 10% |
| (ii) | Deficient slopes, rain cuts, disturbed pitching, vegetation growth, pruning of trees | 5% |
| (c) Bridges and Culverts | | |
| (i) | Desilting, cleaning, vegetation growth, damaged pitching, flooring, parapets, wearing course, footpaths, any damage to foundations | 20% |
| (ii) | Any Defects in superstructures, bearings and sub-structures | 10% |
| (iii) | Painting, repairs/replacement kerb, railings, parapets, guideposts/crash barriers | 5% |
| (d) Roadside Drains | | |
| (i) | Cleaning and repair of drains | 5% |
| (e) Road Furniture | | |
| (i) | Cleaning, painting, replacement of road signs, delineators, road markings, 200 m/km/5 th km stones | 5% |
| (f) Miscellaneous Items | | |
| (i) | Removal of dead animals, broken down/accidental vehicles, fallen trees, road blockades or malfunctioning of mobile crane | 10% |
| (ii) | Any other Defects in accordance with paragraph 1. | 5% |
| (g) Defects in Other Project Facilities | | 5% |

- (ii) The amount to be deducted from monthly lump-sum payment for non-compliance of particular item shall be calculated as under:

$$R = \frac{P}{100} \times (M1 \text{ or } M2) \times \frac{L1}{L}$$

Where,

P = Percentage of particular item/Defect/deficiency for deduction

M1= Monthly lump-sum payment in accordance para 1.2 above of this Schedule M2= Monthly lump-sum payment in accordance para 1.2 above of this Schedule L1= Non-complying length L = Total length of the road,

R= Reduction (the amount to be deducted for non-compliance for a particular item/Defect/deficiency

The total amount of reduction shall be arrived at by summation of reductions for such items/Defects/deficiency or non-compliance.

For any Defect in a part of one kilometer, the non-conforming length shall be taken as one kilometer.

Schedule - N

(See Clause 18.1 (i))

Selection of Authority's Engineer

1. Selection of Authority's Engineer

- (i) The provisions of the Model Request for Proposal for Selection of Technical Consultants, issued by the Ministry of Finance in May 2009, or any substitute thereof shall apply for selection of an experienced firm to discharge the functions and duties of an Authority's Engineer.
- (ii) In the event of termination of the Technical Consultants appointed in accordance with the provisions of Paragraph 1.1, the Authority shall appoint another firm of Technical Consultants forthwith and may engage a government-owned entity in accordance with the provisions of Paragraph 3 of this Schedule-N.

2. Terms of Reference

The Terms of Reference for the Authority's Engineer (the "**TOR**") shall substantially conform with Annex 1 to this Schedule N.

3. Appointment of Government entity as Authority's Engineer

Notwithstanding anything to the contrary contained in this Schedule, the Authority may in its discretion appoint a government-owned entity as the Authority's Engineer; provided that such entity shall be a body corporate having as one of its primary functions the provision of consulting, advisory and supervisory services for engineering projects; provided further that a government-owned entity which is owned or controlled by the Authority shall not be eligible for appointment as Authority's Engineer.

Annex - I

(Schedule - N)

Terms of Reference for Authority's Engineer

1. Scope

- (i) These Terms of Reference (the "**TOR**") for the Authority's Engineer are being specified pursuant to the EPC Agreement dated (the "**Agreement**"), which has been entered into between the [name and address of the Authority] (the "**Authority**") and (the "**Contractor**")[#] for upgradation to 2/4-lane with paved shoulder from form Km 148+589 (Ex. Km 235+070) to Km 176+532 (Ex. Km 263+107) of length 27.944 Km on Vailoo-Donipawa section of NH-244 in Union Territory of Jammu & Kashmiron Engineering, Procurement, Construction (EPC) basis, and a copy of which is annexed hereto and marked as Annex-A to form part of this TOR.

- In case the bid of Authority's Engineer is invited simultaneously with the bid of EPC project, then the status of bidding of EPC project only to be indicated

- (ii) The TOR shall apply to construction and maintenance of the Project Highway.

2. Definitions and interpretation

- (i) The words and expressions beginning with or in capital letters and not defined herein but defined in the Agreement shall have, unless repugnant to the context, the meaning respectively assigned to them in the Agreement.
- (ii) References to Articles, Clauses and Schedules in this TOR shall, except where the context otherwise requires, be deemed to be references to the Articles, Clauses and Schedules of the Agreement, and references to Paragraphs shall be deemed to be references to Paragraphs of this TOR.
- (iii) The rules of interpretation stated in Article 1 of the Agreement shall apply, mutatis mutandis, to this TOR.

3. General

- (i) The Authority's Engineer shall discharge its duties in a fair, impartial and efficient manner, consistent with the highest standards of professional integrity and Good Industry Practice.
- (ii) The Authority's Engineer shall perform the duties and exercise the authority in accordance with the provisions of this Agreement, but subject to obtaining prior written approval of the Authority before determining:
- (a) any Time Extension;
 - (b) any additional cost to be paid by the Authority to the Contractor;
 - (c) the Termination Payment; or
 - (d) issuance of Completion Certificate or
 - (e) any other matter which is not specified in (a), (b), (c) or (d) above and which creates a financial liability on either Party.
- (iii) The Authority's Engineer shall submit regular periodic reports, at least once every month, to the Authority in respect of its duties and functions under this Agreement. Such reports shall be submitted by the Authority's Engineer within 10 (ten) days of the beginning of every month.
- (iv) The Authority's Engineer shall inform the Contractor of any delegation of its duties and responsibilities to its suitably qualified and experienced personnel; provided, however, that it shall not delegate the authority to refer any matter for the Authority's prior approval in accordance with the provisions of Clause 18.2.

- (v) The Authority's Engineer shall aid and advise the Authority on any proposal for Change of Scope under Article 13.
- (vi) In the event of any disagreement between the Parties regarding the meaning, scope and nature of Good Industry Practice, as set forth in any provision of the Agreement, the Authority's Engineer shall specify such meaning, scope and nature by issuing a reasoned written statement relying on good industry practice and authentic literature.

4. Construction Period

- (i) During the Construction Period, the Authority's Engineer shall review and approve the Drawings furnished by the Contractor along with supporting data, including the geo-technical and hydrological investigations, characteristics of materials from borrow areas and quarry sites, topographical surveys, and the recommendations of the Safety Consultant in accordance with the provisions of Clause 10.1 (vi). The Authority's Engineer shall complete such review and approval and send its observations to the Authority and the Contractor within 15 (fifteen) days of receipt of such Drawings; provided, however that in case of a Major Bridge or Structure, the aforesaid period of 15 (fifteen) days may be extended upto 30 (thirty) days. In particular, such comments shall specify the conformity or otherwise of such Drawings with the Scope of the Project and Specifications and Standards.
- (ii) The Authority's Engineer shall review and approve any revised Drawings sent to it by the Contractor and furnish its comments within 10 (ten) days of receiving such Drawings.
- (iii) The Authority's Engineer shall review and approve the Quality Assurance Plan submitted by the Contractor and shall convey its comments to the Contractor within a period of 21 (twenty one) days stating the modifications, if any, required thereto.
- (iv) The Authority's Engineer shall complete the review and approve of the methodology proposed to be adopted by the Contractor for executing the Works, and convey its comments to the Contractor within a period of 10 (ten) days from the date of receipt of the proposed methodology from the Contractor.
- (v) The Authority's Engineer shall grant written approval to the Contractor, where necessary, for interruption and diversion of the flow of traffic in the existing lane(s) of the Project Highway for purposes of maintenance during the Construction Period in accordance with the provisions of Clause 10.4.
- (vi) The Authority's Engineer shall review the monthly progress report furnished by the Contractor and send its comments thereon to the Authority and the Contractor within 7 (seven) days of receipt of such report.
- (vii) The Authority's Engineer shall inspect the Construction Works and the Project Highway and shall submit a monthly Inspection Report bringing out the results of inspections and the remedial action taken by the Contractor in respect of Defects or deficiencies. In particular, the Authority's Engineer shall include in its Inspection Report, the compliance of the recommendations made by the Safety Consultant.
- (viii) The Authority's Engineer shall conduct the pre-construction review of manufacturer's test reports and standard samples of manufactured Materials, and such other Materials as the Authority's Engineer may require.
- (ix) For determining that the Works conform to Specifications and Standards, the Authority's Engineer shall require the Contractor to carry out, or cause to be carried out, tests at such time and frequency and in such manner as specified in the Agreement and in accordance with Good Industry Practice for quality assurance. For purposes of this Paragraph 4 (ix), the tests specified in the IRC Special Publication-11 (Handbook of Quality Control for Construction of Roads and Runways) and the Specifications for Road and Bridge Works issued by MORTH (the "Quality Control Manuals") or any

modification/substitution thereof shall be deemed to be tests conforming to Good Industry Practice for quality assurance.

- (x) The Authority's Engineer shall test check at least 50 (fifty) percent of the quantity or number of tests prescribed for each category or type of test for quality control by the Contractor.
- (xi) The timing of tests referred to in Paragraph 4 (ix), and the criteria for acceptance/rejection of their results shall be determined by the Authority's Engineer in accordance with the Quality Control Manuals. The tests shall be undertaken on a random sample basis and shall be in addition to, and independent of, the tests that may be carried out by the Contractor for its own quality assurance in accordance with Good Industry Practice.
- (xii) In the event that results of any tests conducted under Clause 11.10 establish any Defects or deficiencies in the Works, the Authority's Engineer shall require the Contractor to carry out remedial measures.
- (xiii) The Authority's Engineer may instruct the Contractor to execute any work which is urgently required for the safety of the Project Highway, whether because of an accident, unforeseeable event or otherwise; provided that in case of any work required on account of a Force Majeure Event, the provisions of Clause 21.6 shall apply.
- (xiv) In the event that the Contractor fails to achieve any of the Project Milestones, the Authority's Engineer shall undertake a review of the progress of construction and identify potential delays, if any. If the Authority's Engineer shall determine that completion of the Project Highway is not feasible within the time specified in the Agreement, it shall require the Contractor to indicate within 15 (fifteen) days the steps proposed to be taken to expedite progress, and the period within which the Project Completion Date shall be achieved. Upon receipt of a report from the Contractor, the Authority's Engineer shall review the same and send its comments to the Authority and the Contractor forthwith.
- (xv) The Authority's Engineer shall obtain from the Contractor a copy of all the Contractor's quality control records and documents before the Completion Certificate is issued pursuant to Clause 12.2.
- (xvi) Authority's Engineer may recommend to the Authority suspension of the whole or part of the Works if the work threatens the safety of the Users and pedestrians. After the Contractor has carried out remedial measure, the Authority's Engineer shall inspect such remedial measures forthwith and make a report to the Authority recommending whether or not the suspension hereunder may be revoked.
- (xvii) In the event that the Contractor carries out any remedial measures to secure the safety of suspended works and Users, and requires the Authority's Engineer to inspect such works, the Authority's Engineer shall inspect the suspended works within 3 (three) days of receiving such notice, and make a report to the Authority forthwith, recommending whether or not such suspension may be revoked by the Authority.
- (xviii) The Authority's Engineer shall carry out, or cause to be carried out, all the Tests specified in Schedule-K and issue a Completion Certificate, as the case may be. For carrying out its functions under this Paragraph 4 (xviii) and all matters incidental thereto, the Authority's Engineer shall act under and in accordance with the provisions of Article 12 and Schedule-K.

5. Maintenance Period

- (i) The Authority's Engineer shall aid and advise the Contractor in the preparation of its monthly Maintenance Programme and for this purpose carry out a joint monthly inspection with the Contractor.
- (ii) The Authority's Engineer shall undertake regular inspections, at least once every month, to evaluate compliance with the Maintenance Requirements and submit a Maintenance

Inspection Report to the Authority and the Contractor.

- (iii) The Authority's Engineer shall specify the tests, if any, that the Contractor shall carry out, or cause to be carried out, for the purpose of determining that the Project Highway is in conformity with the Maintenance Requirements. It shall monitor and review the results of such tests and the remedial measures, if any, taken by the Contractor in this behalf.
- (iv) In respect of any defect or deficiency referred to in Paragraph 3 of Schedule- E, the Authority's Engineer shall, in conformity with Good Industry Practice, specify the permissible limit of deviation or deterioration with reference to the Specifications and Standards and shall also specify the time limit for repair or rectification of any deviation or deterioration beyond the permissible limit.
- (v) The Authority's Engineer shall examine the request of the Contractor for closure of any lane(s) of the Project Highway for undertaking maintenance/repair thereof, and shall grant permission with such modifications, as it may deem necessary, within 5 (five) days of receiving a request from the Contractor. Upon expiry of the permitted period of closure, the Authority's Engineer shall monitor the reopening of such lane(s), and in case of delay, determine the Damages payable by the Contractor to the Authority under Clause 14.5.

6. Determination of costs and time

- (i) The Authority's Engineer shall determine the costs, and/or their reasonableness, that are required to be determined by it under the Agreement.
- (ii) The Authority's Engineer shall determine the period of Time Extension that is required to be determined by it under the Agreement.
- (iii) The Authority's Engineer shall consult each Party in every case of determination in accordance with the provisions of Clause 18.5.

7. Payments

- (i) The Authority's Engineer shall withhold payments for the affected works for which the Contractor fails to revise and resubmit the Drawings to the Authority's Engineer in accordance with the provisions of Clause 10.2 (iv)(d).
- (ii) Authority's Engineer shall-
 - (a) within 10 (ten) days of receipt of the Stage Payment Statement from the Contractor pursuant to Clause 19.4, determine the amount due to the Contractor and recommend the release of 90 (ninety) percent of the amount so determined as part payment, pending issue of the Interim Payment Certificate; and
 - (b) within 15 (fifteen) days of the receipt of the Stage Payment Statement referred to in Clause 19.4, deliver to the Authority and the Contractor an Interim Payment Certificate certifying the amount due and payable to the Contractor, after adjustments in accordance with the provisions of Clause 19.10.
- (iii) The Authority's Engineer shall, within 15 (fifteen) days of receipt of the Monthly Maintenance Statement from the Contractor pursuant to Clause 19.6, verify the Contractor's monthly statement and certify the amount to be paid to the Contractor in accordance with the provisions of the Agreement.
- (iv) The Authority's Engineer shall certify final payment within 30 (thirty) days of the receipt of the final payment statement of Maintenance in accordance with the provisions of Clause 19.16.

8. Other duties and functions

The Authority's Engineer shall perform all other duties and functions as specified in the Agreement.

9. Miscellaneous

- (i) A copy of all communications, comments, instructions, Drawings or Documents sent by the Authority's Engineer to the Contractor pursuant to this TOR, and a copy of all the test results with comments of the Authority's Engineer thereon, shall be furnished by the Authority's Engineer to the Authority forthwith.
- (ii) The Authority's Engineer shall retain at least one copy each of all Drawings and Documents received by it, including 'as-built' Drawings, and keep them in its safe custody.
- (iii) Within 90 (ninety) days of the Project Completion Date, the Authority's Engineer shall obtain a complete set of as-built Drawings, in 2 (two) hard copies and in micro film form or in such other medium as may be acceptable to the Authority, reflecting the Project Highway as actually designed, engineered and constructed, including an as-built survey illustrating the layout of the Project Highway and setback lines, if any, of the buildings and structures forming part of Project Facilities; and shall hand them over to the Authority against receipt thereof.
- (iv) The Authority's Engineer, if called upon by the Authority or the Contractor or both, shall mediate and assist the Parties in arriving at an amicable settlement of any Dispute between the Parties.
- (v) The Authority's Engineers shall inform the Authority and the Contractor of any event of Contractor's Default within one week of its occurrence.

Schedule - O

(See Clauses 19.4 (i), 19.6 (i), and 19.8 (i))

Forms of Payment Statements

1. Stage Payment Statement for Works

The Stage Payment Statement for Works shall state:

- (a) the estimated amount for the Works executed in accordance with Clause 19.3
- (i) subsequent to the last claim;
- (b) amounts reflecting adjustments in price for the aforesaid claim;
- (c) the estimated amount of each Change of Scope Order executed subsequent to the last claim;
- (d) amounts reflecting adjustment in price, if any, for (c) above in accordance with the provisions of Clause 13.2 (iii)(a);
- (e) total of (a), (b), (c) and (d) above;
- (f) Deductions:
 - i. Any amount to be deducted in accordance with the provisions of the Agreement except taxes;
 - ii. Any amount towards deduction of taxes; and
 - iii. Total of (i) and (ii) above.
- (g) Net claim: (e) – (f)(iii);
- (h) The amounts received by the Contractor upto the last claim:
 - i. For the Works executed (excluding Change of Scope orders);
 - ii. For Change of Scope Orders; and
 - iii. Taxes deducted

2. Monthly Maintenance Payment Statement

The monthly Statement for Maintenance Payment shall state:

- (a) the monthly payment admissible in accordance with the provisions of the Agreement;
- (b) the deductions for maintenance work not done;
- (c) net payment for maintenance due, (a) minus (b);
- (d) amounts reflecting adjustments in price under Clause 19.12; and
- (e) amount towards deduction of taxes

3. Contractor's claim for Damages

Note: The Contractor shall submit its claims in a form acceptable to the Authority.

Schedule - P

(See Clause 20.1)

Insurance

1. Insurance during ConstructionPeriod

- (i) The Contractor shall effect and maintain at its own cost, from the Appointed Date till the date of issue of the Completion Certificate, the following insurances for any loss or damage occurring on account of Non Political Event of Force Majeure, malicious act, accidental damage, explosion, fire andterrorism:
 - (a) insurance of Works, Plant and Materials and an additional sum of [15 (fifteen)] per cent of such replacement cost to cover any additional costs of and incidental to the rectification of loss or damage including professional fees and the cost of demolishing and removing any part of the Works and of removing debris of whatsoever nature;and
 - (b) insurance for the Contractor's equipment and Documents brought onto the Site by the Contractor, for a sum sufficient to provide for their replacement at theSite.
- (ii) The insurance under sub para (a) and (b) of paragraph 1(i) above shall cover the Authority and the Contractor against all loss or damage from any cause arising under paragraph 1.1 other than risks which are not insurable at commercialterms.

2. Insurance for Contractor's DefectsLiability

The Contractor shall effect and maintain insurance cover of not less than 15% of the Contract Price for the Works from the date of issue of the Completion Certificate until the end of the Defects Liability Period for any loss or damage for which the Contractor is liable and which arises from a cause occurring prior to the issue of the Completion Certificate. The Contractor shall also maintain other insurances for maximum sums as may be required under the Applicable Laws and in accordance with Good Industry Practice.

3. Insurance against injury to persons and damage toproperty

- (i) The Contractor shall insure against its liability for any loss, damage, death or bodily injury, or damage to any property (except things insured under Paragraphs 1 and 2 of this Schedule or to any person (except persons insured under Clause 20.9), which may arise out of the Contractor's performance of this Agreement. This insurance shall be for a limit per occurrence of not less than the amount stated below with no limit on the number ofoccurrences.

The insurance cover shall be not less than: Rs. 2,00,00,000/- (Two Crore only)

- (ii) The insurance shall be extended to cover liability for all loss and damage to the Authority's property arising out of the Contractor's performance of this Agreement excluding:
 - (a) the Authority's right to have the construction works executed on, over, under, in or through any land, and to occupy this land for the Works;and
 - (b) damage which is an unavoidable result of the Contractor's obligations to execute theWorks.

4. Insurance to be in jointnames

The insurance under paragraphs 1 to 3 above shall be in the joint names of the Contractor and the Authority.

Schedule-Q

(See Clause 14.10)

Tests on Completion of Maintenance Period

1. Riding Qualitytest

Riding quality test: Riding quality of each lane of the carriageway shall be checked with the help of a calibrated bump integrator and the maximum permissible roughness for purposes of this Test shall be [2,200 (two thousand and two hundred only)] mm for each kilometer.

2. Visual and physicaltest

The Authority's Engineer shall conduct a visual and physical check of construction to determine that all works and equipment forming part thereof conform to the provisions of this Agreement. The physical tests shall include measurement of cracking, rutting, stripping and potholes and shall be as per the requirement of maintenance mentioned in Schedule-E.

Schedule-R

(See Clause 14.10)

Taking Over Certificate

I, (Name and designation of the Authority's Representative) under and in accordance with the Agreement dated (the "**Agreement**"), for upgradation to 2/4-lane with paved shoulder from form Km 148+589 (Ex. Km 235+070) to Km 176+532 (Ex. Km 263+107) of length 27.944 Km on Vailoo-Donipawa section of NH-244 in Union Territory of Jammu & Kashmir (the "Project Highway") on Engineering, Procurement and Construction (EPC) basis through (Name of Contractor), hereby certify that the Tests on completion of Maintenance Period in accordance with Article 14 of the Agreement have been successfully undertaken to determine compliance of the Project Highway with the provisions of the Agreement and I hereby certify that the Authority has taken over the Project highway from the Contractor on this day.....

SIGNED, SEALED AND DELIVERED

(Signature)

(Name and designation of Authority's Representative)

(Address)

******* End of the Document *******