Schedule A

(See Clause 2.1 and 8.1)

SITE OF THE PROJECT

1 The Site

1.1 Site of the Two-Lane Project Highway shall include the land, buildings, Structures and road works as described in Annex-I of this Schedule-A.

- 1.2 The dates of handing over the Right of Way to the Contractor are specified in Annex-II of this Schedule-A.
- 1.3 An inventory of the Site including the land, buildings, Structures, road works, trees and any other immovable property on, or attached to, the Site shall be prepared jointly by the Authority Representative and the Contractor, and such inventory shall form part of the memorandum referred to in Clause 8.2.1 of this Agreement.
- 1.4 The alignment plans of the Project Highway are specified in Annex-III. In the case of sections where no modification in the existing alignment of the Project Highway is contemplated, the alignment plan has not been provided. Alignment plans have only been given for sections where the existing alignment is proposed to be modified.
- 1.5 The status of the environment clearances obtained or awaited is given in Annex-IV.

Annex – I

(Schedule-A)

Site

1. Site

The site of the Two Lane project highway comprises the section of State Highway No 4 commencing from Km 31+700 to Km 59+270 i.e. the Ranikor-Nonghyllam-Maheshkhola-Baghmara road in the state of Meghalaya. The Land, carriageway and structures comprising the site are described below.

2. Land

The Site of the Project Highway comprises the land described below:

| C No | Chaina | Eviction Day (m) | |
|--------|--------|------------------|------------------|
| S. No. | From | То | Existing Row (m) |
| 1 | 31+000 | 32+000 | 9.65 |
| 2 | 32+000 | 32+470 | 9.4 |
| 3 | 32+470 | 33+000 | 9.6 |
| 4 | 33+000 | 34+000 | 9.7 |
| 5 | 34+000 | 34+960 | 9.4 |
| 6 | 34+960 | 35+000 | 9.75 |
| 7 | 35+000 | 36+000 | 9.65 |
| 8 | 36+000 | 37+000 | 9.5 |
| 9 | 37+000 | 37+860 | 9.3 |
| 10 | 37+860 | 38+460 | 9.45 |
| 11 | 38+460 | 39+000 | 9.6 |
| 12 | 39+000 | 40+000 | 9.4 |
| 13 | 40+000 | 41+000 | 9.8 |
| 14 | 41+000 | 41+320 | 9.55 |
| 15 | 41+320 | 41+420 | 9.55 |
| 16 | 41+420 | 41+830 | 9.4 |
| 17 | 41+830 | 43+000 | 9.6 |
| 18 | 43+000 | 43+250 | 9.4 |
| 19 | 43+250 | 44+000 | 9.5 |
| 20 | 44+000 | 44+180 | 9.45 |
| 21 | 44+180 | 45+000 | 9.3 |
| 22 | 45+000 | 45+675 | 9.2 |

Chainage (km) S. No. Existing Row (m) **From** To 23 45+675 46+000 9.3 24 46+000 47+000 9.45 25 47+000 9.55 48+000 26 48+000 49+000 9.45 49+000 27 9.3 50+000 28 50+000 9.55 51+000 29 51+000 52+000 9.75 30 52+000 53+000 9.7 31 53+000 53+770 9.1 32 53+770 54+000 9.6 33 9.6 54+000 55+000 34 55+000 55+600 10.35 35 55+600 56+000 9.7 36 9.7 56+000 57+000 37 57+000 58+400 9.55 38 58+400 58+500 9.4 39 58+500 59+000 9.5 40 7.6 59+000 59+195 41 7.95 59+195 59+270

3. Carriageway

The present carriageway of the Project Road is Single lane with average formation width of 6 m and carriageway width of 3.5 - 4.0 m with earthen shoulders of width 1.5 m on either side for the entire stretch. The type of the existing pavement is flexible.

4. Major Bridge

The Site includes the following Major Bridges:

| Location | | Ту | pe of Structure | Length of Bridge/ | Total width | |
|----------|--------|-----------------------|------------------|-------------------|----------------------------|------|
| S/no | in km | Super Structure | Sub Structure | Foundati on | Span Arrangement (m) | (m) |
| 1 | 59+195 | Prestressed Bridge | Cement concrete | Open | 72.98m (2 x 38.00)m | 4.20 |

5. Road over-bridges (ROB)/ Road under-bridges (RUB)

The Site includes the following ROB (road over railway line)/ RUB (road under railway line):

| SI No | Chainage(km) | Type of | structure | No of Span | pan ROB/RUB | |
|-------|---------------|------------|----------------|------------|-------------|---------|
| O. NO | Onamage(Kill) | Foundation | Superstructure | length(m) | (m) | KOD/KOD |
| | | | NIL | | | |

6. Grade separators

The Site includes the following grade separators:

| SI No | Chainage(km) | Type o | f structure | No of Span | width |
|-------|--------------|------------|----------------|------------|-------|
| OI NO | Onamage(km) | Foundation | Superstructure | length(m) | (m) |
| | | NI | L | | |

7. Railway level crossings

The Site includes the following railway level crossings:

| SI No | Location(km) | Remarks | | |
|-------|--------------|---------|--|--|
| NIL | | | | |

8. Underpasses (vehicular, non vehicular)

The Site includes the following underpasses:

| SI No | Chainage(km) | Type of structure | No of Span with Span length(m) | width (m) |
|-------|--------------|-------------------|-----------------------------------|-----------|
| | | NIL | | |

9. Truck Lay bays

The details of truck bays on the Site are as follows:

| SI No | Chainage(km) | Length(m) | Left Hand side | Right Hand side |
|-------|--------------|-----------|----------------|-----------------|
| | | NIL | - | |

10. Road side drains

The details of the roadside drains are as follows:

| S/NO | LOCATION IN KM | TYPE | REMARKS |
|------|----------------|------|---------|
| | | NIL | |

11. Minor Bridges

The Site includes the following Minor Bridges:

| | Location | Тур | e of Structures | 3 | Length of Bridge/ | Total |
|-------|----------|--------------------|------------------|------------|----------------------|-----------|
| S. no | in km | Super Structure | Sub Structure | Foundation | Span Arrangement (m) | width (m) |

| | Location | Тур | e of Structures | Length of Bridge/ | Total | |
|-------|----------|----------------------------|--------------------------------|-------------------|----------------------|-----------|
| S. no | in km | Super Structure | Sub Structure | Foundation | Span Arrangement (m) | width (m) |
| 1 | 32+140 | Timber decking | PCC 1:3:6 | Open | 1x10.00 | 3.80 |
| 2 | 40+690 | BUG with Timber decking | PCC 1:3:6 | Open | 1x19.50 | 3.80 |
| 3 | 44+043 | Timber decking | PCC 1:3:6 | Open | 1x9.40 | 3.80 |
| 4 | 45+480 | Timber decking | PCC 1:3:6 | Open | 1x9.50 | 3.80 |
| 5 | 45+670 | BUG with Timber decking | Stone masonry in CM | Open | 1x13.50 | 3.80 |
| 6 | 49+820 | BUG with Timber decking | RCC 1:3:6 | Open | 1x25.90 | 3.80 |
| 7 | 52+085 | Timber decking | Stone masonry in cm 1: 6 | Open | 1x9.50m | 3.80 |
| 8 | 52+585 | Timber decking | Stone masonry in cm 1: 6 | Open | 1x7.60m | 3.80 |
| 9 | 54+280 | Timber decking | RCC 1:3:6 | Open | 1x9.80m | 3.80 |
| 10 | 54+455 | Timber decking | Stone masonry in cm 1: 6 | Open | 1x7.70m | 3.80 |
| 11 | 57+915 | Timber decking | RCC 1:3:6 | Open | 1x8.10m | 3.80 |
| 12 | 58+175 | Timber decking | RCC 1:3:6 | Open | 1x10.10m | 3.80 |

12. Culvert

| S/No. | Existing Chainage | CD Width | Type of | Span arrangement |
|-------|-------------------|----------|---------|------------------|
| | (km) | | Culvert | (No x Span/dia) |
| 1 | 32+460 | 5.9 | Slab | 1 x 1.00 |
| 2 | 33+250 | 5.6 | Slab | 1 x 0.60 |
| 3 | 34+610 | 6.2 | Slab | 1 x 1.00 |
| 4 | 34+740 | 6.3 | Slab | 1 x 1.00 |
| 5 | 35+070 | 7.4 | Slab | 1 x 2.00 |
| 6 | 35+305 | 7.5 | Slab | 1 x 1.00 |
| 7 | 35+410 | 8.1 | Slab | 1 x 1.00 |
| 8 | 35+480 | 8.1 | Slab | 1 x 1.00 |
| 9 | 35+620 | 7.2 | Slab | 1 x 2.00 |
| 10 | 36+215 | 6.9 | Slab | 1 x 1.00 |

| S/No. | Existing Chainage | CD Width | Type of | Span arrangement |
|-------|-------------------|----------|------------|------------------|
| | (km) | | Culvert | (No x Span/dia) |
| 11 | 36+430 | 7.1 | Slab | 1 x 1.00 |
| 12 | 36+470 | 8.2 | Slab | 1 x 1.00 |
| 13 | 36+610 | 7.2 | Slab | 1 x 1.00 |
| 14 | 37+130 | 6.5 | HP | 1 x 0.90 dia |
| 15 | 37+420 | 6.5 | HP | 1 x 0.90 dia |
| 16 | 37+490 | 7.5 | HP | 1 x 0.90 dia |
| 17 | 37+860 | 6 | Slab | 1 x 1.00 |
| 18 | 38+010 | 6 | Slab | 1 x 1.00 |
| 19 | 38+050 | 7.5 | HP | 1 x 0.90 dia |
| 20 | 38+150 | 7.5 | Slab | 1 x 1.00 |
| 21 | 38+240 | 7.5 | HP | 1 x 0.90 dia |
| 22 | 38+410 | 7 | HP | 1 x 0.90 dia |
| 23 | 38+730 | 6 | HP | 1 x 0.90 dia |
| 24 | 38+780 | 7 | HP | 1 x 0.90 dia |
| 25 | 38+880 | 6.5 | HP | 1 x 0.90 dia |
| 26 | 38+930 | 7.5 | HP | 1 x 0.90 dia |
| 27 | 39+020 | 5.9 | HP | 1 x 0.90 dia |
| 28 | 39+110 | 7.5 | HP | 1 x 0.90 dia |
| 29 | 39+350 | 7.6 | Slab | 1 x 1.00 |
| 30 | 39+390 | 7.5 | Slab | 1 x 1.00 |
| 31 | 39+470 | 6.7 | HP | 1 x 0.90 dia |
| 32 | 39+560 | 7.3 | Slab | 1 x 1.00 |
| 33 | 39+680 | 6.2 | Slab | 1 x 1.00 |
| 34 | 40+050 | 6.25 | Slab | 1 x 1.00 |
| 35 | 40+120 | 7.5 | HP | 1 x 0.90 dia |
| 36 | 40+170 | 6 | HP | 1 x 0.90 dia |
| 37 | 40+470 | 4.5 | HP | 1 x 0.90 dia |
| 38 | 40+520 | 4.5 | HP | 1 x 0.90 dia |
| 39 | 40+570 | 4.3 | Slab | 1 x 2.50 |
| 40 | 40+740 | 7.2 | HP | 1 x 0.90 dia |
| 41 | 40+785 | 7 | HP | 1 x 0.90 dia |
| 42 | 40+795 | 10 | Slab+HP | 1 x 0.90 dia |
| 43 | 40+800 | 7.5 | Slab | 1 x 0.60 |
| 44 | 40+810 | 7 | HP | 1 x 0.90 dia |
| 45 | 40+900 | 4.5 | Slab | 1 x 1.00 |
| 46 | 40+970 | 6.7 | -do- | 1 x 1.00 |
| 47 | 41+320 | 7.20 | -do- | 1 x 1.00 |
| 48 | 41+830 | 4.20 | -do- | 1 x 1.00 |
| 49 | 41+950 | 5.80 | -do- | 1 x 1.00 |
| 50 | 41+985 | 5.90 | -do- | 1 x 1.00 |
| 51 | 42+045 | 4.90 | Wooden Cul | 1 x 5.70 |
| 52 | 42+140 | 7.90 | Slab | 1 x 1.00 |
| 53 | 42+200 | 7.50 | -do- | 1 x 1.00 |

| S/No. | Existing Chainage | CD Width | Type of | Span arrangement | |
|-------|-------------------|----------|------------|------------------|--|
| | (km) | | Culvert | (No x Span/dia) | |
| 54 | 42+260 | 7.00 | -do- | 1 x 1.00 | |
| 55 | 42+280 | 6.50 | -do- | 1 x 1.00 | |
| 56 | 42+340 | 6.30 | Slab | 1 x 0.60 | |
| 57 | 42+475 | 5.40 | -do- | 1 x 1.00 | |
| 58 | 42+650 | 5.20 | -do- | 1 x 1.00 | |
| 59 | 42+835 | 4.90 | -do- | 1 x 1.00 | |
| 60 | 43+435 | 5.10 | -do- | 1 x 1.00 | |
| 61 | 43+550 | 5.80 | -do- | 1 x 1.00 | |
| 62 | 43+640 | 4.30 | -do- | 1 x 1.00 | |
| 63 | 43+740 | 4.80 | -do- | 1 x 1.00 | |
| 64 | 43+800 | 4.70 | -do- | 1 x 0.60 | |
| 65 | 43+970 | 5.20 | -do- | 1 x 1.00 | |
| 66 | 44+010 | 6.90 | -do- | 1 x 1.00 | |
| 67 | 44+050 | 3.60 | Wooden cul | 1 x 5.80 | |
| 68 | 44+210 | 6.70 | Slab | 1 x 1.00 | |
| 69 | 44+375 | 6.80 | -do- | 1 x 1.00 | |
| 70 | 44+465 | 6.20 | -do- | 1 x 1.00 | |
| 71 | 44+670 | 7.30 | -do- | 1 x 1.00 | |
| 72 | 44+825 | 6.80 | -do- | 1 x 1.00 | |
| 73 | 44+875 | 7.00 | HP | 1 x 0.90 dia | |
| 74 | 44+990 | 6.40 | Slab | 1 x 1.00 | |
| 75 | 45+075 | 6.10 | -do- | 1 x 1.00 | |
| 76 | 45+185 | 6.50 | -do- | 1 x 1.00 | |
| 77 | 45+310 | 3.60 | Wooden cul | 1 x 5.50 | |
| 78 | 45+385 | 5.80 | Slab | 1 x 1.00 | |
| 79 | 45+420 | 4.40 | Wooden cul | 1 x 3.00 | |
| 80 | 45+820 | 6.40 | Slab | 1 x 1.00 | |
| 81 | 45+900 | 5.70 | -do- | 1 x 1.00 | |
| 82 | 45+965 | 4.10 | Wooden cul | 1 x 2.90 | |
| 83 | 46+145 | 4.50 | Slab | 1 x 1.00 | |
| 84 | 46+240 | 5.50 | Slab | 1 x 1.00 | |
| 85 | 46+450 | 5.45 | Slab | 1 x 1.00 | |
| 86 | 46+530 | 6.80 | Slab | 1 x 1.00 | |
| 87 | 46+580 | 7.50 | HP | 1 x 0.90 dia | |
| 88 | 46+790 | 6.50 | Slab | 1 x 1.00 | |
| 89 | 46+860 | 7.50 | HP | 1 x 0.90 dia | |
| 90 | 46+990 | 6.40 | Slab | 1 x 1.00 | |
| 91 | 47+090 | 6.50 | Slab | 1 x 1.00 | |
| 92 | 47+820 | 6.50 | Slab | 1 x 1.00 | |
| 93 | 48+075 | 5.80 | Slab | 1 x 1.00 | |

Type of **Existing Chainage** Span arrangement S/No. **CD Width** (km) Culvert (No x Span/dia) 48+355 HP 94 7.50 1 x 0.90 dia 95 48+420 8.00 HP 1 x 0.90 dia 96 48+440 4.50 Slab 1 x 1.00 97 48+645 6.60 Slab 1 x 1.00 98 48+855 6.10 Slab 1 x 1.00 99 48+925 4.20 wooden 1 x 6.00 100 48+970 5.50 Slab 1 x 1.00 101 49+025 7.50 HP 1 x 0.90 dia 6.20 Slab 102 49+070 1 x 1.00 103 50+120 7.50 HP 1 x 0.90 dia 104 50+220 4.70 Slab 1 x 1.00 105 50+260 6.20 Slab 1 x 1.00 6.20 1 x 1.00 106 50+275 Slab 107 50+315 7.10 Slab 1 x 1.00 108 50+400 6.70 1 x 1.00 Slab 109 50+580 Slab 1 x 1.00 6.50 50+695 4.80 Slab 1 x 1.00 110 111 50+940 6.10 Slab 1 x 1.00 112 51+380 7.10 Slab 1 x 1.00 113 51+490 6.20 Slab 1 x 1.00 51+855 HP 114 7.50 1 x 0.90 dia 115 51+980 4.80 Slab 1 x 1.00 1 x 1.00 116 52+015 6.90 Slab 117 52+040 5.50 Slab 1 x 1.00 118 52+180 6.80 Slab 1 x 1.00 119 1 x 1.00 52+315 6.50 Slab 120 52+360 7.50 HP 1 x 0.90 dia 121 52+505 5.50 Slab 1 x 1.00 122 52+570 6.10 Slab 1 x 1.00 123 52+730 6.70 Slab 1 x 1.00 124 6.00 Slab 52+900 1 x 1.00 125 53+000 4.20 Wooden Cul 1 x 5.60 126 53+030 8.00 Slab 1 x 1.00 127 53+075 5.70 Slab 1 x 1.00 128 53+230 8.30 Slab 1 x 2.50 129 53+295 7.50 HP 1 x 0.90 dia HP 53+400 7.50 1 x 0.90 dia 130 131 53+480 10.00 HP 1 x 0.90 dia 132 53+540 Slab 9.20 1 x 1.00 133 53+630 8.50 Slab 1 x 1.00 53+860 134 6.80 Slab 1 x 1.00 1 x 1.00 135 54+000 6.40 Slab 136 54+035 10.60 Slab 1 x 1.00

Existing Chainage Type of Span arrangement S/No. **CD Width** (km) Culvert (No x Span/dia) 54+160 Wooden Cul 137 4.20 1 x 5.90 5.00 Slab 138 54+560 1 x 1.00 139 54+630 7.80 Slab 1 x 1.00 140 54+770 Slab 1 x 1.00 5.90 141 54+785 10.00 HP 1 x 0.90 dia 142 54+880 Slab 6.00 1 x 1.00 143 54+900 7.40 Slab 1 x 1.00 144 55+175 6.00 Slab 1 x 0.60 145 55+225 6.50 Slab 1 x 0.60 146 55+390 7.00 Slab 1 x 0.60 147 55+410 6.50 Slab 1 x 0.60 148 55+590 6.30 Slab 1 x 0.60 149 55+618 2.20 Slab 1 x 0.60 150 55+720 6.80 Slab 1 x 0.60 55+765 151 8.80 Slab 1 x 0.60 152 55+788 7.00 Slab 1 x 0.50 153 55+820 8.00 Slab 1 x 0.50 154 55+900 7.50 Slab 1 x 0.50 155 55+990 8.00 Slab 1 x 0.50 56+060 9.00 Slab 156 1 x 0.50 157 56+105 6.50 Slab 1 x 1.00 158 56+135 7.00 Slab 1 x 1.00 Wooden Cul 159 56+275 4.28 1 x 4.30 Slab 160 56+330 7.00 1 x 1.00 1 x 1.00 161 56+365 10.00 Slab 162 56+530 7.00 Slab 1 x 1.00 163 4.20 Wooden Cul 56+570 1 x 4.00 10.00 164 56+660 Slab 1 x 1.00 165 56+810 8.00 Slab 1 x 1.00 1 x 1.00 166 56+870 7.50 Slab 1 x 1.00 167 56+975 7.50 Slab 168 57+060 7.50 Slab 1 x 1.00 169 57+095 7.50 Slab 1 x 1.00 170 7.50 1 x 1.00 57+160 Slab 171 57+335 6.50 1 x 1.00 Slab 172 57+474 7.50 wooden 1 x 6.00 173 57+527 7.00 Slab 1 x 1.00 174 57+640 6.00 Slab 1 x 1.00 175 57+765 5.50 Slab 1 x 1.00 176 57+960 7.50 Slab 1 x 1.00 177 57+995 6.00 Slab 1 x 1.00

| S/No. | Existing Chainage (km) | CD Width | Type of Culvert | Span arrangement |
|-------|------------------------|----------|---|------------------|
| | () | | • | (No x Span/dia) |
| 178 | 58+060 | 5.10 | Slab | 1 x 1.00 |
| 179 | 58+445 | 5.50 | Slab | 1 x 1.00 |
| 180 | 58+545 | 6.00 | Slab | 1 x 1.00 |
| 181 | 58+555 | 7.00 | Slab | 1 x 1.00 |
| 182 | 58+570 | 7.50 | Slab | 1 x 1.00 |
| 183 | 58+765 | 7.50 | Slab | 1 x 1.00 |
| 184 | 58+860 | 6.00 | Slab | 1 x 1.00 |

13. Bus bays

The details of bus bays on the Site are as follows:

| SI No | Chainage(km) | Length(m) | Left Hand side | Right Hand side | | |
|-------|--------------|-----------|----------------|-----------------|--|--|
| NIL | | | | | | |

14. Major Intersections along project:

The details of the minor junctions are as follows:

| Sn | Location | Name of Road | Type of Junction | | |
|-----|----------|--------------|---------------------|--|--|
| NIL | | | | | |

15. Minor Intersections along project:

The details of the minor intersections are as follows:

| S/no | Location in km | Type of Crossing | Link | Remarks |
|------|----------------|---------------------|--------------------|----------------------------|
| 1 | 40+13 0 | R | For Khonjoy Bazaar | 4.50m wide Earthen road |
| 2 | 40+13 0 | L | For Village | 4.50m wide Earthen road |

| 3 | 40+53 | L | For Rangawal | 4.50m wide | |
|---|-------|---|--------------|--------------|---|
| | 0 | | Quarry | Earthen road | İ |

| S/no | Location in km | Type of Crossing | Link | Remarks |
|------|----------------|------------------|---------------------------------|--------------------------|
| 4 | 40+670 | L | To River | 4.50m wide Earthen road |
| 5 | 40+800 | R | Chibak | BT road 6.00m wide |
| 6 | 41+175 | L | To River for collection of Sand | 3.00m Earthen road |
| 7 | 41+332 | L | For Stone Quarry | 4.50m wide Earthen road |
| 8 | 41+880 | L | Junction of Bagli | 6.00m wide WBM road |
| 9 | 45+440 | R | Boikut Village | 4.50 m wide Earthen road |
| 10 | 57+040 | R | To Chima sura Village | 5.50m Wide Earthen road |
| 11 | 58+165 | L | Ganga nagar Village | 6.00m wide Earthen road |
| 12 | 59+080 | L | IBB Road | 3.60m wide BT road |
| 13 | 59+105 | R | To Sohyleng Village | 6.00m wide Earthen road |

16. Bypass

The details of Bypasses are as follows:

| | Chainage(km) | | | Carriageway | | | |
|-----------------------------|--------------|---------|---------------|-------------|------|--|--|
| Name of bypass (town) | Fom(km) | To (km) | Length(in km) | width(m) | Туре | | |
| NIL | | | | | | | |

17. Other structures

Nil

Annex II

(Schedule-A)

Dates for providing Right of Way

The dates on which the Authority shall provide Right of Way to the Contractor on different parts of the Site are stated below:

| SI.No. | Location stretch | | Length(Km) | Width(m) | Date of providing ROW |
|-------------------|------------------|--------|------------|----------|---|
| | From(km) | To(km) | | | |
| 1) Full ROW | 31+700 | 59+270 | Nil | 24 | 000% of the land will be |
| 2) Part ROW | 31+700 | 59+270 | 30 | 8 | 90% of the land will be made available on the appointed date and remaining 10% in 90 days from appointed date |
| 3) Balance ROW | 31+700 | 59+270 | 30 | 16 | nom appointed date |


Annex - IIII

(Schedule-A)

Alignment Plans

The existing alignment of the Project Highway shall be modified in the following sections as per the alignment plan indicated below:

- i) The alignment of the Project Highway is enclosed in alignment plan. Finished road level indicated in the alignment plan shall be followed by the contractor as minimum FRL. In any case, the finished road level of the project highway shall not be less than those indicated in the alignment plan. The contractor shall, however, improve/upgrade the Road profile as indicated in Annex-III based on site/design requirement.
- ii) Traffic Signage plan of the Project Highway showing numbers & location of traffic signs is enclosed. The contractor shall, however, improve/upgrade upon the traffic signage plan as indicated in Annex-III based on site/design requirement as per IRC: SP: 99 & IRC: 67.



Annex - IV

(Schedule-A)

Environment Clearances

The following environment clearances have been obtained:

- Environmental clearance is not required as per new notification of MoEF dated 22/08/2013.
- The muck dumping sites shall be identified by the EPC contractor in consultation with the Authority Engineer and forest department for dumping of muck, in addition to the applicable permissions and clearances as stated in Schedule F.

Schedule B

Development of the Project Highway

1 Development of the Project Highway

Development of the Project Highway shall include design and construction of the Project Highway as described in this Schedule-B and in Schedule-C.

2 Rehabilitation and augmentation

Rehabilitation and augmentation shall include Two-Laning and strengthening of the Project Road as described in Annex-I of this Schedule-B and in Schedule-C.

3 Specifications and Standards

The Project Road shall be designed and constructed in conformity with the Specifications and Standards specified in Annex-I of Schedule-D.

Annex – I

(Schedule-B)

Description of Two-Laning with earthen shoulder

1. Development of Nongjri- Maheshkhola–Baghmara road from Km 30.00 to Km 55.525 in Meghalaya to 2-Lane Standards.

The Project Highway shall follow the existing alignment unless otherwise specified by the Authority and shown in the alignment plans specified in Annex III of Schedule-A. Geometric deficiencies, if any, in the existing horizontal and vertical profiles shall be corrected as per the prescribed standards for Hills/rolling terrain to the extent land is available.

1.1 Width of carriageway

Two-Laning with earthen shoulder shall be undertaken. The paved carriageway shall be 7 (Seven) m wide in accordance with the typical cross sections drawings in the Manual.

Provided that in the built-up areas, the width of the carriageway shall be as specified in the following table:

| S. No | Location (I | Km to km) | Width (m) | Typical cross section | |
|-------|-------------|-----------|-------------|--------------------------|--|
| 3. NO | From (Km) | To (Km) | width (III) | | |
| 1 | 37+600 | 38+000 | | | |
| 2 | 55+100 | 55+200 | 7+1.5*2 | TCS-4 | |
| 3 | 55+200 | 55+525 | | | |

1.2 Except as otherwise provided in this Agreement, the width of the paved carriageway and cross-sectional features shall conform to paragraph 1.1 above.

2. Geometric design and general features

2.1 General

Geometric design and general features of the Project Highway shall be in accordance with Section 2 of the Manual.

2.2 Design speed

In general, the Project Highway has been designed for a speed 50 kmph for mountainous terrain but at few locations, 30kmph speed has been provided due to unavoidable circumstances such as steep terrain & sharp curves in accordance with table 6.1 of Hill Road Manual (IRC SP:48-1998)

2.3 Improvement of the existing road geometrics

In the following stretches, where improvement of the existing road geometrics to the prescribed standards is not possible, the existing road geometrics shall be improved to the extent possible within the given right of way and proper road signs and safety measures shall be provided. The locations where the minimum design speed could not be proposed due to site constraints are as per the table below:

| SI. No. | SI. No. HIP CH: Type of Def | | ency Remarks | | | |
|---------|-----------------------------|--|--------------|--|--|--|
| | NIL | | | | | |

2.4 Right of Way

Details of the Right of Way are given in Annex II of Schedule-A.

2.5 Type of shoulders

(a) In built-up section, footpath/fully paved shoulders shall be provided in the following stretches:

| | Stretch | | Fully paved | Reference to cross |
|--------|-----------|---------|----------------------|--------------------|
| S. No. | From (Km) | To (Km) | shoulders/ footpaths | section |
| 1 | 37+600 | 38+000 | Drain aum faatnath | TCS-4 |
| 2 | 55+100 | 55+200 | Drain cum footpath | 105-4 |

| | Stretch | | Fully paved | Reference to cross |
|--------|-----------|---------|----------------------|--------------------|
| S. No. | From (Km) | To (Km) | shoulders/ footpaths | section |
| 3 | 55+200 | 55+525 | | |

The varied width between paved carriageway and drain in built-up area will be covered with paver block as per TCS-IV.

- (b) In open country section the earthen shoulders shall be covered with 150 mm thick compacted layer of granular material. The width of shoulder is 1.5m on both sides.
 - Earthen Shoulder on Valley side includes crash barrier, parapet wall, etc.
 - Earthen Shoulder on hill side includes road side drain.
- (c) Design and specification of paved shoulders and granular material shall confirm to the requirements specified in paragraphs 5.11 of the Manual.

2.6 Lateral and vertical clearances at underpasses

- 2.6.1 Lateral and vertical clearances at underpasses and provision of guardrails/crash barriers shall be as per the paragraph 2.10 of the Manual.
- 2.6.2 Lateral clearance: The size of the opening at the underpasses shall be as follows:

| S. No. | Description | Design Chainage (km) | Span length | Remarks | | | |
|-----------|-------------|-------------------------|-------------|---------|--|--|--|
| | NIL | | | | | | |

2.7 Lateral and vertical clearance at overpasses

2.7.1 Lateral and vertical clearances at overpasses shall be as per paragraph 2.11 of the Manual.

2.7.2 Lateral clearance: The size of the opening at the overpasses shall be as follows:

| S. No. | Location (Chainage) From km to km | Number and length of spans | Remarks | |
|--------|-----------------------------------|----------------------------|---------|--|
| NIL | | | | |

2.8 Service roads/Slip Road

Service roads shall be constructed at the locations and of the lengths indicated below:

| S. No. | Length of | Service road To | Right hand side (RHS)/ Left hand side (LHS)/ or Both sides | Length (km) of service road |
|-----------|-----------|--------------------|--|-----------------------------|
| | | | NIL | |

2.9 Grade separated structures

2.9.1 Grade separated structures shall be provided as per paragraph 2.14.1 of the Manual. The requisite particulars are given below:

| S. No. | Location of structure | Length (m) | Number and length of spans | Approach gradient | | | |
|--------|-----------------------|------------|----------------------------|-------------------|--|--|--|
| | NIL | | | | | | |

2.9.2 In the case of grade separated structures, the type of structure and the level of the Project Highway and the cross roads shall be as follows:

| S. No. | Location | Type of structure Length (m) | | Cross road a | t | |
|--------|----------|------------------------------|----------------|--------------|---------------|--|
| | | Lengui (III) | Existing level | Raised Level | Lowered Level | |
| | NIL | | | | | |


2.10 Cattle and Pedestrian under pass / over pass

Cattle and pedestrian underpass/Overpass shall be constructed as follows:


| S. No. | S. No. Design Chainage (km) | | Type of crossing |
|--------|-----------------------------|--|------------------|
| | NIL | | |

2.11 Typical cross-sections of the Project Highway


| S.No. | Design Length(Km) | TCS Type | Remarks |
|-------|-------------------|----------|------------------|
| 1 | 7.10 | 1 | Widening |
| 2 | 6.22 | 2 | New Construction |
| 3 | 11.382 | 3 | Box-Cut |
| 4 | 0.825 | 4 | Built-up |




TCS-1:- 2 LANE WITH EARTHEN SHOULDER FOR WIDENING



TCS-2 :- 2 LANE WITH EARTHEN SHOULDER FOR NEW CONSTRUCTION



TCS-3:- 2 _ANE WITH EARTHEN SHOULDER FOR BOX CUT SECTION



TCS 4: 2 LANE WITH EARTHEN SHOULDER FOR BUILT-UP SECTION

3. Intersections and grade separators

All intersections and grade separators shall be as per Section 3 of the Manual. Existing intersections which are deficient shall be improved to the prescribed standards.

Properly designed intersections shall be provided at the locations and of types and features given in the tables below:

(a) At-grade intersections

Major Intersection

| S. No. | Location of intersection (km) | Type of intersection | Other features | | | |
|--------|-------------------------------|----------------------|----------------|--|--|--|
| | NIL | | | | | |

Minor Intersection

| S. No | Location of Intersections | Type of Intersection | Other Features |
|-------|---------------------------|----------------------|----------------|
| 1 | 37+996 | Υ | market road |
| 2 | 38+395 | Т | ODR. |
| 3 | 38+545 | Т | To River |
| 4 | 38+700 | Y | Chibak Village |
| 5 | 39+010 | Y | To River |
| 6 | 39+158 | Y | ODR. |
| 7 | 39+705 | Y | Baghi Road |
| 8 | 43+117 | Т | Bolkut Village |
| 9 | 54+490 | Υ | Ganganagar |
| 10 | 55+265 | Т | Soling Village |

| S. No | Location of Intersections | Type of Intersection | Other Features |
|-------|---------------------------|-------------------------|----------------|
| 11 | 55+337 | Y | IBB Road |

Note: All other junctions, if any, identified during the execution of the work shall be developed as per the extant guidelines and shall not be treated as change in scope of work.

At the locations of geometric improvements, the connectivity of built-up area, along existing road, with the proposed highway shall be provided. All such locations shall be finalized as per site requirement in consultation with Authority Engineer and it will not be treated as change in scope of work.

(b) Grade separated intersection with/without ramps

| S. No. | Location | Salient features | Minimum length of viaduct to be provided | Road to be carried over / under the structures | | | |
|--------|----------|---------------------|--|--|--|--|--|
| | NIL | | | | | | |

4. Road embankment and cut section

4.1 Widening and improvement of the existing road embankment/cuttings and construction of new road embankment / cuttings shall conform to the standards and specifications given in Section 4 of the Manual and the specified cross sectional details. Deficiencies in the plan and profile of the existing road shall be corrected.

4.2 Box cut section

The existing road shall be box cutting in the following sections.

| Sr. No. | Chai | nage | Total Length Soil & Soft Rock | | Hard Rock |
|---------|--------|--------|-------------------------------|------|-----------|
| | From | То | | ROCK | |
| 1 | 30+170 | 30+190 | 20 | | 20 |
| 2 | 30+220 | 30+360 | 140 | 140 | |
| 3 | 30+980 | 31+060 | 80 | 80 | |
| 4 | 31+290 | 31+310 | 20 | 20 | |

Chainage Soil & Soft Sr. No. **Total Length Hard Rock Rock** To **From** 200 5 31+360 31+560 200 6 31+630 31+650 20 20 7 32+300 32+620 320 320 8 32+820 32+840 20 20 9 33+040 33+120 80 80 10 33+180 720 33+900 720 11 33+940 33+960 20 20 12 34+240 34+300 60 60 13 34+360 34+400 40 40 14 34+460 34+920 460 460 15 35+420 35+500 80 80 16 35+540 20 20 35+560 17 35+720 35+880 160 160 18 35+920 35+940 20 20 19 36+260 37+520 1260 280 980 20 38+140 38+520 380 380 21 38+640 38+660 20 20 22 38+780 38+900 120 120 23 39+060 39+140 80 80 24 39+210 39+230 20 10 10 25 39+400 39+560 160 160 26 39+580 39+600 20 20 27 39+700 39+760 60 60 39+870 28 39+850 20 20 29 39+930 39+950 20 20 30 40+010 40+030 20 20 31 40+300 40+320 20 20 32 40+490 20 40+510 20 40 33 40+780 40+820 40 40+940 40 34 40+980 40 35 41+780 42+120 340 120 220 42+220 420 420 36 42+640 37 42+710 42+730 20 20 120 38 42+880 43+000 120 39 43+360 43+440 80 80 120 120 40 43+660 43+780 41 44+040 44+060 20 20 42 44+150 44+170 20 20 43 44+200 44+220 20 20 44 44+400 44+460 60 60

Chainage Soil & Soft Sr. No. **Total Length Hard Rock Rock** To **From** 45 44+520 44+600 80 80 46 44+840 45+180 340 340 47 45+280 45+500 220 220 48 45+720 46+160 440 440 46+210 20 49 46+190 20 50 46+320 46+420 100 100 47+140 51 47+060 80 80 52 47+220 47+340 120 120 53 47+480 47+620 140 140 54 47+740 48+860 1120 1120 55 48+970 48+990 20 20 56 49+050 20 20 49+030 57 49+130 49+150 20 20 58 49+240 49+260 20 20 59 49+290 49+310 20 20 60 49+395 49+415 20 20 61 49+440 49+480 40 40 62 49+520 49+720 200 200 63 49+860 50+260 400 400 64 50+450 50+470 20 20 65 50+560 50+660 100 100 66 50+720 50+740 20 20 67 50+880 50+920 40 40 68 51+140 51+380 240 240 69 51+420 51+460 40 40 70 51+600 51+640 40 40 71 51+700 51+740 40 40 72 40 40 51+840 51+880 73 51+940 51+980 40 40 74 52+060 52+120 60 60 75 52+180 52+220 40 40 40 40 76 52+260 52+300 77 52+380 52+420 40 40 78 52+500 52+560 60 60 79 52+640 52+720 80 80 80 52+800 52+820 20 20 81 53+080 53+220 140 140 82 53+260 53+400 140 140 83 53+540 53+660 120 120 84 53+720 53+760 40 40

| Sr. No. | Chainage | | Total Length | Soil & Soft | Hard Rock |
|---------|----------|--------|--------------|-------------|-----------|
| | From | То | 3. | Rock | |
| 85 | 53+800 | 53+840 | 40 | 40 | |
| 86 | 53+940 | 54+000 | 60 | 60 | |
| 87 | 54+040 | 54+200 | 160 | 160 | |
| 88 | 54+280 | 54+360 | 80 | 80 | |
| 89 | 54+420 | 54+480 | 60 | 60 | |
| 90 | 54+520 | 54+560 | 40 | 40 | |
| 91 | 54+860 | 54+880 | 20 | 20 | |
| 92 | 54+960 | 55+060 | 100 | 100 | |

Note: i)Type of soil of existing cutting section shall be verified as per actual site conditions. Any variations in the type of soil specified in the table shall not constitute a Change of Scope or any deviation thereof.

ii) Contractor shall identify the locations and construct a boundary for proper disposal of cut material in consultation with Authority Engineer.

5. Pavement design

5.1 Pavement design shall be carried out in accordance with Section 5 of the Manual.

5.2 Type of pavement

Type of pavement shall be flexible.

5.3 Design requirements

Pavement design shall be as per Section 5 of IRC: SP 73-2018. Design of flexible pavement applies to the new carriageway and widening of existing carriageway. The methodologies recommended in IRC: 37-2018 shall be adopted.

5.3.1 Design Period and strategy

Flexible pavement for new pavement or for widening and strengthening of the existing pavement shall be designed for minimum design period of 15 years. Stage construction shall not be permitted.

5.3.2 Design Traffic

Notwithstanding anything to the contrary contained in this Agreement or the Manual, the Contractor shall design the pavement for design traffic of 10 million standard axles or as per actual traffic survey, whichever is higher.

5.4 Reconstruction of stretches

The following stretches of the existing road shall be reconstructed. These shall be designed as new pavement.

| CI No. | Chai | nage | Louisth |
|--------|--------|--------|---------|
| SI No. | From | То | Length |
| 1 | 30+000 | 30+350 | 350 |
| 2 | 30+500 | 31+400 | 900 |
| 3 | 31+670 | 32+400 | 730 |
| 4 | 32+500 | 32+550 | 50 |
| 5 | 32+600 | 32+800 | 200 |
| 6 | 32+880 | 33+000 | 120 |
| 7 | 33+100 | 33+180 | 80 |
| 8 | 33+520 | 33+820 | 300 |
| 9 | 33+910 | 34+260 | 350 |
| 10 | 34+700 | 34+850 | 150 |
| 11 | 35+100 | 35+450 | 350 |
| 12 | 35+600 | 35+730 | 130 |
| 13 | 35+900 | 37+200 | 1300 |
| 14 | 37+350 | 37+610 | 260 |
| 15 | 37+900 | 38+400 | 500 |
| 16 | 39+250 | 39+600 | 350 |
| 17 | 39+800 | 39+920 | 120 |
| 18 | 40+130 | 41+700 | 1570 |
| 19 | 43+750 | 44+110 | 360 |
| 20 | 44+200 | 44+390 | 190 |
| 21 | 44+610 | 45+500 | 890 |
| 22 | 45+520 | 46+110 | 590 |
| 23 | 46+450 | 46+590 | 140 |
| 24 | 46+680 | 46+960 | 280 |
| 25 | 47+600 | 47+700 | 100 |
| 26 | 48+110 | 48+250 | 140 |
| 27 | 49+650 | 49+800 | 150 |

| SI No. | Cha | Longth | |
|--------|--------|--------|--------|
| | From | То | Length |
| 28 | 50+500 | 50+610 | 110 |
| 29 | 52+820 | 53+050 | 230 |
| 30 | 53+410 | 53+510 | 100 |
| 31 | 53+900 | 54+190 | 290 |
| 32 | 55+100 | 55+525 | 425 |
| | | | 11805 |

6. Roadside drainage

Drainage system including surface and subsurface drains for the Project Highway shall be provided as per stipulations of IRC SP: 42-2014.

Drain shall be provided in following stretches but not limited to:

| S. No | Type of Drain | Length (Km | Remarks |
|----------|-------------------------------|------------|--|
| 1 | Rectangular RCC Covered Drain | 0.725 | Provided in Built-up town areas |
| 2 | V-Shaped Lined Drain | 30.600 | Provided in soils & soft rock portions |
| 3 | V-Shaped Unlined drain | 16.835 | Provided in Hard rock Stretches |

Lined Drain shall be provided in Soil & Soft Rock Areas and in hard rock stretches Unlined Drain shall be provided.

The EPC Contractor shall ensure proper functioning of the roadside drains by designing them as per site conditions and considering the outfall locations.

7. Design of structures

7.1 General

- 7.1.1 All bridges, culverts and structures shall be designed and constructed in accordance with section 7 of the Manual and shall conform to the cross-sectional features and other details specified therein.
- **7.1.2** Width of the carriage way of new/Reconstruction bridge and structures shall be follows:

| S No | Bridge at Km | Deck Width | Carriageway Width | Span Arrangement |
|------|--------------|------------|-------------------|------------------|
| 1 | 30+425 | 12.9 | 10.5 | 1x12 |
| 2 | 38+562 | 12.9 | 10.5 | 1x24 |
| 3 | 41+825 | 12.9 | 10.5 | 1x12 |
| 4 | 43+155 | 12.9 | 10.5 | 1x10 |
| 5 | 43+325 | 12.9 | 10.5 | 1x16 |
| 6 | 47+185 | 12.9 | 10.5 | 1x30 |
| 7 | 49+080 | 12.9 | 10.5 | 1x10 |

| S No | Bridge at Km | Deck Width | Carriageway Width | Span Arrangement |
|------|--------------|------------|-------------------|------------------|
| 8 | 49+496 | 12.9 | 10.5 | 1x10 |
| 9 | 51+085 | 12.9 | 10.5 | 1x12 |
| 10 | 51+250 | 12.9 | 10.5 | 1x10 |
| 11 | 54+236 | 12.9 | 10.5 | 1x10 |
| 12 | 54+500 | 12.9 | 10.5 | 1x12 |
| 13 | 55+485 | 12.9 | 10.5 | 2x38.5 |

7.1.2 The following structures shall be provided with footpaths:

| S. No. | Location at km | Remarks |
|--------|----------------|---------|
| | NIL | |

7.1.3 All bridges shall be high-level bridges

This shall be as per site condition

7.1.4 The following structures shall be designed to carry utility services specified in the table below:

| S. No. | Bridge at km | Utility service to be carried | Remarks | | |
|---|--------------|-------------------------------|---------|--|--|
| All Bridges shall have provisions for utility services to be carried over | | | | | |

7.1.5 Cross-section of the new culverts and bridges at deck level for the Project Highway shall conform to the typical cross-sections given in section 7 of the Manual.

7.2 Culverts

7.2.1 Overall width of all culverts shall be equal to the roadway width of the approaches.

7.2.2 Reconstruction of existing culverts:

The existing culverts at the following locations shall be re-constructed as new culverts:

| S.No | Existing Chainage | Proposed Chainage | No of Span/Row | Length of Span/Dia | Proposed Type of Culvert |
|------|----------------------|----------------------|-------------------|-----------------------|--------------------------------|
| 1 | 32+460 | 30+760 | 1 | 1 | HPC |
| 2 | 33+250 | 31+545 | 1 | 1 | HPC |
| 3 | 34+740 | 32+920 | 1 | 1 | HPC |
| 4 | 35+305 | 33+340 | 1 | 1 | HPC |
| 5 | 35+410 | 33+445 | 1 | 1 | HPC |
| 6 | 35+480 | 33+525 | 1 | 1 | HPC |
| 7 | 36+215 | 34+220 | 1 | 1 | HPC |
| 8 | 36+430 | 34+420 | 1 | 1 | HPC |
| 9 | 36+470 | 34+470 | 1 | 1 | HPC |
| 10 | 36+610 | 34+580 | 1 | 1 | HPC |
| 11 | 37+130 | 35+100 | 1 | 1 | HPC |
| 12 | 37+420 | 35+380 | 1 | 1 | HPC |
| 13 | 37+490 | 35+450 | 1 | 1 | HPC |
| 14 | 37+860 | 35+830 | 1 | 1 | HPC |
| 15 | 38+010 | 35+970 | 1 | 1 | HPC |
| 16 | 38+050 | 36+010 | 1 | 1 | HPC |
| 17 | 38+150 | 36+100 | 1 | 1 | HPC |
| 18 | 38+240 | 36+195 | 1 | 1 | HPC |
| 19 | 38+410 | 36+365 | 1 | 1 | HPC |
| 20 | 38+730 | 36+675 | 1 | 1 | HPC |
| 21 | 38+780 | 36+730 | 1 | 1 | HPC |
| 22 | 38+880 | 36+825 | 1 | 1 | HPC |
| 23 | 38+930 | 36+882 | 1 | 1 | HPC |
| 24 | 39+020 | 36+965 | 1 | 1 | HPC |
| 25 | 39+110 | 37+050 | 1 | 1 | HPC |
| 26 | 39+350 | 37+250 | 1 | 1 | HPC |
| 27 | 39+470 | 37+340 | 1 | 1 | HPC |
| 28 | 39+560 | 37+425 | 1 | 1 | HPC |
| 29 | 39+680 | 37+540 | 1 | 1 | HPC |

Proposed Length of **Existing Proposed** No of S.No Type of Chainage Chainage Span/Row Span/Dia Culvert 30 40+050 37+920 1 1 **HPC** 31 40+120 37+985 1 1 **HPC HPC** 32 40+170 38+035 1 1 33 40+470 38+332 1 1 **HPC** 34 40+520 38+375 1 1 **HPC** 35 40+795 1 1 **HPC** 38+688 1 1 **HPC** 36 40+810 38+700 37 40+970 38+855 1 1 **HPC** 1 1 **HPC** 38 41+320 39+150 39 41+830 1 1 **HPC** 39+662 1 1 **HPC** 40 41+985 39+815 41 42+045 39+880 1 6 Box **HPC** 42 42+140 39+970 1 1 43 1 1 **HPC** 42+260 40+065 44 42+280 40+080 1 1 **HPC HPC** 45 42+340 40+135 1 1 46 42+475 40+265 1 1.2 **HPC** 1 47 1.2 **HPC** 42+650 40+440 48 42+835 40+625 1 1.2 **HPC** 1 49 43+435 41+210 1.2 **HPC** 50 43+550 41+330 1 1.2 **HPC** 1 51 43+640 41+415 1.2 **HPC** 52 43+740 1 1.2 **HPC** 41+520 1 1.2 **HPC** 53 43+800 41+580 1 54 43+970 41+755 1.2 **HPC** 55 44+210 42+000 1 1.2 **HPC** 44+375 1 1.2 **HPC** 56 42+130 57 44+670 42+370 1 1.2 **HPC** 1.2 **HPC** 58 45+075 42+745 1 45+185 42+855 1 1.2 **HPC** 59 1 60 45+310 42+970 6 Box 1 1 **HPC** 61 45+820 43+500 1 1 **HPC** 62 45+900 43+585 63 45+965 43+645 1 3 Box 64 46+145 43+820 1 1.2 **HPC**

| S.No | Existing Chainage | Proposed Chainage | No of Span/Row | Length of Span/Dia | Proposed Type of Culvert |
|------|----------------------|----------------------|-------------------|-----------------------|--------------------------------|
| 65 | 46+240 | 43+910 | 1 | 1.2 | HPC |
| 66 | 46+450 | 44+120 | 1 | 1.2 | HPC |
| 67 | 46+530 | 44+185 | 1 | 1.2 | HPC |
| 68 | 46+580 | 44+230 | 1 | 1 | HPC |
| 69 | 46+860 | 44+485 | 1 | 1 | HPC |
| 70 | 46+990 | 44+630 | 1 | 1.2 | HPC |
| 71 | 47+090 | 44+720 | 1 | 1.2 | HPC |
| 72 | 47+820 | 45+280 | 1 | 1.2 | HPC |
| 73 | 48+075 | 45+510 | 1 | 1.2 | HPC |
| 74 | 48+440 | 45+882 | 1 | 1.2 | HPC |
| 75 | 48+645 | 46+115 | 1 | 1.2 | HPC |
| 76 | 48+855 | 46+220 | 1 | 1.2 | HPC |
| 77 | 48+925 | 46+295 | 1 | 6 | Box |
| 78 | 49+070 | 46+475 | 1 | 1.2 | HPC |
| 79 | 50+120 | 47+450 | 1 | 1 | HPC |
| 80 | 50+260 | 47+580 | 1 | 1.2 | HPC |
| 81 | 50+275 | 47+595 | 1 | 1.2 | HPC |
| 82 | 50+315 | 47+645 | 1 | 1.2 | HPC |
| 83 | 50+580 | 47+798 | 1 | 1.2 | HPC |
| 84 | 50+695 | 47+915 | 1 | 1.2 | HPC |
| 85 | 50+940 | 48+125 | 1 | 1.2 | HPC |
| 86 | 51+380 | 48+450 | 1 | 1.2 | HPC |
| 87 | 51+490 | 48+535 | 1 | 1.2 | HPC |
| 88 | 51+855 | 48+830 | 1 | 1 | HPC |
| 89 | 52+360 | 49+280 | 1 | 1 | HPC |
| 90 | 52+730 | 49+670 | 1 | 1.2 | HPC |
| 91 | 52+900 | 49+830 | 1 | 1.2 | HPC |
| 92 | 53+000 | 49+935 | 1 | 6 | Box |
| 93 | 53+230 | 50+150 | 1 | 3 | Box |
| 94 | 53+295 | 50+218 | 1 | 1 | HPC |
| 95 | 53+400 | 50+290 | 1 | 1 | HPC |
| 96 | 53+540 | 50+418 | 1 | 1.2 | HPC |
| 97 | 53+630 | 50+475 | 1 | 1.2 | HPC |
| 98 | 53+860 | 50+695 | 1 | 1.2 | HPC |
| 99 | 54+000 | 50+830 | 1 | 1.2 | HPC |

| S.No | Existing Chainage | Proposed Chainage | No of Span/Row | Length of Span/Dia | Proposed Type of Culvert |
|------|----------------------|----------------------|-------------------|-----------------------|--------------------------------|
| 100 | 54+160 | 50+950 | 1 | 6 | Box |
| 101 | 54+770 | 51+545 | 1 | 1.2 | HPC |
| 102 | 54+880 | 51+660 | 1 | 1.2 | HPC |
| 103 | 54+900 | 51+677 | 1 | 1.2 | HPC |
| 104 | 55+175 | 51+805 | 1 | 1 | HPC |
| 105 | 55+390 | 52+005 | 1 | 1 | HPC |
| 106 | 55+410 | 52+020 | 1 | 1 | HPC |
| 107 | 55+590 | 52+135 | 1 | 1 | HPC |
| 108 | 55+618 | 52+160 | 1 | 1 | HPC |
| 109 | 55+720 | 52+252 | 1 | 1 | HPC |
| 110 | 55+788 | 52+320 | 1 | 1 | HPC |
| 111 | 55+820 | 52+355 | 1 | 1 | HPC |
| 112 | 55+990 | 52+518 | 1 | 1 | HPC |
| 113 | 56+105 | 52+618 | 1 | 1.2 | HPC |
| 114 | 56+135 | 52+655 | 1 | 1.2 | HPC |
| 115 | 56+275 | 52+760 | 1 | 6 | Box |
| 116 | 56+330 | 52+830 | 1 | 1.2 | HPC |
| 117 | 56+365 | 52+855 | 1 | 1.2 | HPC |
| 118 | 56+530 | 53+020 | 1 | 1.2 | HPC |
| 119 | 56+570 | 53+060 | 1 | 4 | Box |
| 120 | 56+810 | 53+238 | 1 | 1.2 | HPC |
| 121 | 56+870 | 53+290 | 1 | 1.2 | HPC |
| 122 | 57+060 | 53+420 | 1 | 1.2 | HPC |
| 123 | 57+095 | 53+460 | 1 | 1.2 | HPC |
| 124 | 57+160 | 53+515 | 1 | 1.2 | HPC |
| 125 | 57+335 | 53+685 | 1 | 1.2 | HPC |
| 126 | 57+640 | 53+980 | 1 | 1.2 | HPC |
| 127 | 57+765 | 54+108 | 1 | 1.2 | HPC |
| 128 | 58+060 | 54+395 | 1 | 1.2 | HPC |
| 129 | 58+445 | 54+745 | 1 | 1.2 | HPC |
| 130 | 58+555 | 54+830 | 1 | 1.2 | HPC |
| 131 | 58+570 | 54+850 | 1 | 1.2 | HPC |
| 132 | 58+765 | 55+020 | 1 | 1.2 | HPC |
| 133 | 58+860 | 55+125 | 1 | 1.2 | HPC |

Note: The culvert shall be measured in square direction only. The locations, orientation of the above mentioned structures are tentative and shall vary as per the actual site condition. For skew nallah locations the structure shall be provided in skew only. The height of the culvert is minimum clear height only above the invert level. The length and height proposed above is tentative and shall be reconfirmed based on the actual hydrologic calculation. Increase of total length & formation level based on hydrological calculation shall NOT be considered as CHANGE OF SCOPE.

7.2.3 Widening of existing culverts

All existing culverts which are not to be reconstructed shall be widened to the roadway width of the Project Highway as per the typical cross section given in section 7 of the Manual. Repairs and strengthening of existing structures where required shall be carried out.

| S. No | Existing Chainage | Proposed Chainage | No of Span/ Row | Span Length/Dia | Type of Culvert |
|-------|----------------------|----------------------|-----------------------|--------------------|-----------------------|
| | | Nil | | | |

7.2.4 Additional new culverts shall be constructed as per particulars given in the table below:

| S.No | Proposed Chainage | No of Span/Row | Length of Span/Dia | Proposed Type of Culvert |
|------|----------------------|----------------|-----------------------|-----------------------------|
| 1 | 32+810 | 1 | 1 | HPC |
| 2 | 33+175 | 2 | 1 | HPC |
| 3 | 33+655 | 2 | 1 | HPC |
| 4 | 37+290 | 1 | 1 | HPC |
| 5 | 38+415 | 1 | 3 | Box |
| 6 | 38+640 | 1 | 1 | HPC |
| 7 | 38+795 | 1 | 1 | HPC |
| 8 | 39+790 | 1 | 1 | HPC |
| 9 | 40+020 | 1 | 1 | HPC |
| 10 | 41+790 | 1 | 1.2 | HPC |
| 11 | 42+225 | 1 | 1.2 | HPC |
| 12 | 42+560 | 1 | 1.2 | HPC |
| 13 | 42+595 | 1 | 1 | HPC |

| S.No | Proposed Chainage | No of Span/Row | Length of Span/Dia | Proposed Type of Culvert |
|------|----------------------|----------------|-----------------------|-----------------------------|
| 14 | 42+690 | 1 | 1.2 | HPC |
| 15 | 43+045 | 1 | 1 | HPC |
| 16 | 43+070 | 1 | 3 | Box |
| 17 | 44+430 | 1 | 1.2 | HPC |
| 18 | 45+800 | 1 | 1 | HPC |
| 19 | 45+855 | 1 | 1 | HPC |
| 20 | 46+380 | 1 | 1.2 | HPC |
| 21 | 46+435 | 1 | 1 | HPC |
| 22 | 47+550 | 1 | 1.2 | HPC |
| 23 | 47+750 | 1 | 1.2 | HPC |
| 24 | 48+920 | 1 | 1.2 | HPC |
| 25 | 48+990 | 1 | 1.2 | HPC |
| 26 | 49+052 | 1 | 1.2 | HPC |
| 27 | 49+165 | 1 | 1.2 | HPC |
| 28 | 49+225 | 1 | 1.2 | HPC |
| 29 | 49+390 | 1 | 1.2 | HPC |
| 30 | 49+480 | 1 | 1.2 | HPC |
| 31 | 49+965 | 1 | 1.2 | HPC |
| 32 | 50+020 | 1 | 1.2 | HPC |
| 33 | 50+355 | 1 | 1 | HPC |
| 34 | 50+870 | 1 | 1.2 | HPC |
| 35 | 51+360 | 1 | 1.2 | HPC |
| 36 | 51+445 | 1 | 1.2 | HPC |
| 37 | 51+573 | 1 | 1 | HPC |
| 38 | 51+860 | 1 | 1 | HPC |
| 39 | 52+290 | 1 | 1 | HPC |
| 40 | 52+430 | 1 | 1 | HPC |
| 41 | 52+575 | 1 | 1 | HPC |
| 42 | 53+145 | 1 | 1.2 | HPC |
| 43 | 53+340 | 1 | 1.2 | HPC |
| 44 | 53+820 | 1 | 6 | Box |
| 45 | 53+875 | 1 | 1.2 | HPC |
| 46 | 54+265 | 1 | 1.2 | HPC |
| 47 | 54+330 | 1 | 1.2 | HPC |
| 48 | 54+815 | 1 | 1.2 | HPC |

Note: The culvert shall be measured in square direction only. The locations, orientation of the above mentioned structures are tentative and shall vary as per the actual site condition. For skew nallah locations the structure shall be provided in skew only. The height of the culvert is minimum clear height only above the invert level. The length and height proposed above is tentative and shall be reconfirmed based on the actual hydrologic calculation. Increase of total length & formation level based on hydrological calculation shall NOT be considered as CHANGE OF SCOPE.

- 7.2.5 Repairs/replacements of railing/parapets, flooring and protection works of the existing culverts shall be undertaken as per site condition.
- 7.2.6 Floor protection works shall be as specified in the relevant IRC Codes and Specifications

7.3 Bridges

- 7.3.1 Existing bridges to be re-constructed/widened
 - (i) The existing bridges at the following locations shall be re-constructed as new structures:

| S. No | Location | Proposed | Span |
|-------|----------|------------|-------------|
| | (km) | Deck Width | Arrangement |
| 1 | 55+485 | 12.90 | 2x38.5 |

Note: The span mentioned above is centre to centre of expansion joints measured in square direction only. The locations, orientation of the above mentioned structures are tentative and shall vary as per the actual site condition. The span proposed above is tentative and shall be reconfirmed based on the actual hydrologic calculation. Increase of total length & formation level of the bridge based on hydrological calculation shall NOT be considered as CHANGE OF SCOPE.

(ii) The following narrow bridges shall be widened:

| S. No | Location (km) | Proposed Deck Width | Span Arrangement | | |
|-------|---------------|------------------------|---------------------|--|--|
| NII | | | | | |

7.3.2 Additional new bridges

New bridges at the following locations on the Project Highway shall be constructed.

| S No | Proposed Chainages | Span arrangement |
|------|-----------------------|---------------------|
| 1 | 30+425 | 1x12 |
| 2 | 38+562 | 1x24 |
| 3 | 41+825 | 1x12 |
| 4 | 43+155 | 1x10 |
| 5 | 43+325 | 1x16 |
| 6 | 47+185 | 1x30 |
| 7 | 49+080 | 1x10 |
| 8 | 49+496 | 1x10 |
| 9 | 51+085 | 1x12 |
| 10 | 51+250 | 1x10 |
| 11 | 54+236 | 1x10 |
| 12 | 54+500 | 1x12 |

Note: The span mentioned above is centre to centre of expansion joints measured in square direction only. The locations, orientation of the above mentioned structures are tentative and shall vary as per the actual site condition. The span proposed above is tentative and shall be reconfirmed based on the actual hydrologic calculation. Increase of total length & formation level of the bridge based on hydrological calculation shall NOT be considered as CHANGE OF SCOPE.

7.3.2 The railings of existing bridges shall be replaced by crash barriers at the following locations:

| SI No | Location at Km | Type of bridge | | |
|-------|----------------|----------------|--|--|
| NIL | | | | |

7.3.4 Repairs/replacements of railing/parapets of the existing bridges shall be undertaken as follows:

| SI No | Location at Km | Remarks |
|-------|----------------|---------|
| | NIL | |

7.3.5 Drainage system for bridge decks

An effective drainage system for bridge decks shall be provided as specified in paragraph 7.20 of the Manual

7.3.6 Structures in marine environment

Nil

7.4 Rail-road bridges

- **7.4.1** Design, construction and detailing of ROB/RUB shall be as specified in section 7 of the Manual.
- 7.4.2 Road over bridges (road over rail) shall be provided at the following level crossing

| SI No | Location at Km | Length of Bridge |
|-------|----------------|------------------|
| | | Nil |

7.4.3 Road under bridges (road under railway line) shall be provided at the following level crossings:

| S. No. | Location of level crossing | Number and length of span |
|--------|----------------------------|---------------------------|
| | NIL | <u> </u> |

7.5 Grade separated structures

The grade separated structures shall be provided at the locations and of the type and length specified in paragraphs 2.9 & 3 of this Annex-I

7.6 Repairs and strengthening of structures

The existing structures to be repaired/ strengthened, and the nature and extent of repairs / strengthening required are given below:

A - Bridges

| S. No. | Location of bridge (km) | Design Chainage (km) | Nature and extent of repairs / strengthening to be carried out | | |
|--------|-------------------------|-------------------------|--|--|--|
| | NIL | | | | |

B-ROB/RUB

| S. No. | Location of structure (km) | Nature and extent of repairs/strengthening to be carried out | |
|--------|----------------------------|--|--|
| NIL | | | |

C – Overpasses/Underpasses and other structures

| S. No. | Location of structure (km) | Nature and extent of repairs/strengthening to be carried out | |
|--------|----------------------------|--|--|
| NIL | | | |

7.7 List of Major Bridges and Structures

The following is the list of the Major Bridges and structures.

| SI No | Location at Km | Remarks |
|----------|----------------|------------------|
| 1 55+485 | | New Construction |

8. Traffic control devices and road safety works

- 8.1 Traffic control devices and road safety works shall be provided in accordance with Section 9 of the Manual.
- 8.2 Specifications of the reflecting sheeting shall be provided as per Manual.

9. Roadside furniture

Roadside furniture shall be provided in accordance with the provisions of section 12 of the Manual.

9.1 Overhead traffic signs: location and size

| S.No. Design Chainage (km) | | Remarks | | |
|----------------------------|--|---------|--|--|
| NIL | | | | |

10. Compulsory afforestation

Total of 977 trees are identified to be affected in the proposed ROW. As per guideline, new trees to be planted by the concessionaire

11. Hazardous locations

The safety barriers shall also be provided at the following hazardous locations:

| S. No. | Location stretch from (km) to (km) | LHS/RHS | | |
|--|------------------------------------|---------|--|--|
| This shall be Provided as per manual. | | | | |
| Minimum Length of Crash Barrier and parapet wall is 2670m and 11316m respectively. | | | | |

12. Special requirements for hill roads

The Breast wall shall be constructed as per table given below but not limited to.

| Height (m) | Length (m) | |
|------------|------------|--|
| 3 | 200 | |
| 4 | 400 | |
| 5 | 500 | |
| 6 | 600 | |
| Total | 1700 | |

The retaining wall shall be constructed as per table given below but not limited to

| Height (m) | Length (m) | |
|------------|------------|--|
| 1.5 | 740 | |
| 2.5 | 340 | |
| 3 | 140 | |
| 4 | 300 | |
| 6 | 720 | |
| Total | 2240 | |

13. Change of Scope

The length of structures and bridges specified hereinabove shall be treated as an approximate assessment. The actual lengths as required on the basis of detailed investigations shall be determined by the Contractor in accordance with the Specifications and Standards. Any variations in the lengths specified in this Schedule-B shall not constitute a Change of Scope or any deviation thereof.

(Schedule B-1)

Improvement/Widening to 2-lane with Earthen Shoulders from Nongjri to Maheshkhola Package-2 (Design Chainage from km 30+000 to km 55+525)

| Sr. No | Type of Utility | Unit | Quantity | Location/Stretch LHS/RHS | |
|--------|---|--------|----------|---|--|
| A | Electrical Utilities | | | | |
| A1 | Shifting of 11KV lines from Nongjri to Maheshkhola | | | | |
| (i) | GI Pole 14.5 m (HD) long | Nos. | 17.00 | | |
| (ii) | GI Pole 9.5 m long | Nos. | 25.00 | | |
| (iii) | ACSR Weasel Conductor | kms | 5.52 | The details of items/quantities/works to be | |
| (iv) | GI Wire 8 SWG (for cradle guard) | kg | 765.00 | executed for shifting of | |
| (v) | GI Stay wire 7/14 SWG | Nos. | 120.00 | utilities is tentative. All works/quantities/all | |
| A2 | Shifting of LT lines from Nongjri to Maheshkhola | | | miscellaneous items including necessary accessories, fittings, | |
| (i) | GI Pole 9.5 m long | Nos. | 8.00 | lead & lifts & manpower etc to | |
| (ii) | GI Pole 8.0 m long | Nos. | 15.00 | be executed at site as per detailed estimate of utility | |
| (iii) | ACSR Squirel Conductor | kms | 2.76 | owning department, without | |
| (iv) | GI Wire 8 SWG (for cradle guard) | kg | 770.00 | any additional claim/CoS. | |
| (v) | GI Stay wire 7/10 SWG | kg | 360.00 | | |
| В | Water/Sewage pipeline | | | | |
| B1 | Water supply pipeline (Public Health Engineering Dept., PHED) | | | | |
| a | Labour charge for taking out GI pipe including fitting fixing GI specials complete as per specificaiton and as per directed | | | The details of items/quantities/works to be | |
| (i) | Khonjoy-A WSS: 40 mm Dia | meters | 245.00 | executed for shifting of | |
| (ii) | Rangdongai WSS; 40 mm Dia | meters | 180.00 | utilities is tentative. All works/quantities/all | |
| (iii) | Rangdongai WSS; 15 mm Dia | meters | 200.00 | miscellaneous items including necessary accessories, fittings, | |
| (iv) | Chimasora-Maheshkhola comb. WSS: 25 mm Dia | meters | 215.00 | lead & lifts & manpower etc to be executed at site as per | |
| (v) | Chimasora-Maheshkhola comb. WSS: 25 mm Dia | meters | 190.00 | detailed estimate of utility owning department, without any additional claim/CoS. | |
| b | Demolishing RCC works incuding stacking of steel bars and disposing of non- serviceable materials within 50m lead | m3 | 98.81 | | |

| (i) Khonjoy-A WSS: 40 mm Dia | | | |
|--|--------|------------------|--|
| | meters | 245.00 | |
| (ii) Rangdongai WSS; 40 mm Dia | meters | 180.00 | |
| (iii) Rangdongai WSS; 15 mm Dia | meters | 200.00 | |
| (iv) Chimasora-Maheshkhola comb. WSS: 25 mm Dia | | 215.00 | |
| (v) Chimasora-Maheshkhola comb. WSS: 25 mm Dia | | 190.00 | |
| d Re-construction of sedimentation tank | L*B*H | 2.6 x 1.6 x 1.5 | |
| e Re-construction of slow sand filter | L*B*H | 3.8 x 3.8 x 1.5 | |
| f Re-construction of clear water reservoir | L*D | 1.40 x 2.40 | |
| g Re-construction of Intake structures (02 Nos) | L*B*D | 1.8 x 1.6 x 0.80 | |

Schedule - C

(See Clause 2.1)

PROJECT FACILITIES

1 Project Facilities

The Contractor shall construct the Project Facilities in accordance with the provisions of this Agreement. Such Project Facilities shall include:

- a) toll plazas;
- b) roadside furniture;
- c) pedestrian facilities;
- d) tree plantation;
- e) truck lay-bys;
- f) bus-bays and bus shelters;
- g) rest areas;

2 Description of Project Facilities

Each of the Project Facilities is described below:

a) Toll Plaza:

Toll Plaza shall be designed as per the guidelines prescribed on following locations:-

| Sr No | Project Facility | Toll Location (Design Ch.) | Design Requirements | Other Essential Details |
|-------|------------------|----------------------------|---------------------|----------------------------|
| | | | | |
| NIL | | | | |
| | | | | |

b) Roadside Furniture

The roadside furniture shall include the provision of the;

i. Traffic Signs

Traffic signs include roadside signs, overhead signs and curb mounted signs along the entire Project

Highway as per Section 9.2 of the Manual.

ii. Pavement Markings

Pavement markings shall cover road marking for the entire Project Highway as per Section 9.3 of the Manual.

iii. LED Traffic Blinkers

LED traffic blinker signal shall be provided on entire project length.

iv. Crash barrier

W-beam crash barrier shall be provided along the project highway at the locations as suggested in Manual.

v. Delineators

Delineators for the entire Project Highway at the locations as suggested in relevant IRC Manual shall be provided

vi. Boundary stones

For the entire Project Highway as suggested in Manual.

vii. Hectometer / Kilometer stones

For the entire Project Highway as suggested in Manual.

c) Pedestrian Facilities

The pedestrian facilities shall be provided as per Manual.

d) Tree Plantation

The landscaping and tree plantation shall be provided as per IRC:SP:21-2009.

e) Truck Lay byes:

Truck lay byes shall be provided at the following locations:-

| S. No. | Design Chainage | Location |
|--------|-----------------|----------|
| | NIL | - |

f) Bus Stops

2 nos bus bays/stops shall be provided. The location of bus bays shall be finalized in consultation with Authority Engineer.

g) Rest Areas :NIL

Schedule – D

(See Clause 2.1)

SPECIFICATIONS AND STANDARDS

1. Construction

The Contractor shall comply with the Specifications and Standards set forth in Annex-I of this Schedule-D for construction of the Project Highway:

2. Design Standards

The Project Highway including Project Facilities shall conform to design requirements set out in the following documents:

Manual of Standards and Specifications for Two Laning of State Highways published by the Indian Roads Congress – IRC: SP: 73-2018.

Annex - I

(Schedule-D)

Specifications and Standards for Construction

1 Specifications and Standards

All Materials, works and construction operations shall conform to the Manual of Specifications and Standards for Two-Lane Highways published by IRC (referred to as "Manual" in this Schedule) and MORTH Specifications for Road and Bridge Works. Where the specification for a work is not given, Good Industry Practice shall be adopted to the satisfaction of the Authority's Engineer.

2 Deviations from the Specifications and Standards

The terms "Concessionaire", "Independent Engineer" and "Concession Agreement" used in the Manual shall be deemed to be substituted by the terms "Contractor", "Authority's Engineer" and "Agreement" respectively.

Notwithstanding anything to the contrary contained in the Paragraph 1 above, the following Specifications and Standards shall apply to the Project Highway, and for purposes of this Agreement, aforesaid Specifications and Standards shall be deemed to be amended to the extent set forth below:

| S. No | Item | Description of deviation | Clause reference of IRC SP 73:2018 |
|----------|-----------------------------|---|---|
| 1 | Minimum Desirable Radius | Details of curves with radius less than 150 are given in Appendix 1 | Clause 2.9.4 Minimum desirable radius of horizontal curves is 150 m in mountaneous and steep terrain. |
| 2 | Width of carriageway | Roadway(Carriageway + Earthen Shoulders) width is 10m (7+1.5*2) | Fig. 2.8, 2.9 and 2.10. Roadway width shall be 11m,11m and 10.5m respectively. |

| S. No | Item | Description of deviation | Clause reference of IRC SP 73:2018 |
|----------|-----------------------|------------------------------|--|
| 3 | Deck width of bridges | Deck width of bridges is 12m | Fig. 7.6, deck width of bridges shall be 18m |

Appendix 1

| SI. No. | HIPCH: (m) | Easting (m) | Northing (m) | Radius |
|---------|---------------|-------------|-----------------|--------|
| 1 | 30+118.291 | 49676.814 | 45330.516 | 70 |
| 2 | 30+198.648 | 49625.723 | 45268.797 | 70 |
| 3 | 30+452.188 | 49561.168 | 45025.531 | 150 |
| 4 | 30+871.825 | 49427.051 | 44631.72 | 60 |
| 5 | 31+017.017 | 49284.141 | 44707.258 | 50 |
| 6 | 31+128.972 | 49176.166 | 44691.029 | 35 |
| 7 | 31+246.133 | 49301.624 | 44602.205 | 40 |
| 8 | 31+357.914 | 49245.263 | 44498.434 | 70 |
| 9 | 31+451.574 | 49266.074 | 44406.601 | 100 |
| 10 | 31+535.155 | 49277.495 | 44324.507 | 40 |
| 11 | 31+635.878 | 49384.376 | 44337.37 | 40 |
| 12 | 31+763.959 | 49455.013 | 44229.795 | 50 |
| 13 | 31+845.291 | 49527.518 | 44193.254 | 50 |
| 14 | 31+918.529 | 49523.138 | 44115.591 | 50 |
| 15 | 31+999.699 | 49567.313 | 44047.63 | 80 |
| 16 | 32+137.619 | 49667.926 | 43955.251 | 40 |
| 17 | 32+244.041 | 49543.674 | 43909.114 | 40 |
| 18 | 32+332.123 | 49564.905 | 43819.026 | 100 |
| 19 | 32+453.227 | 49633.003 | 43719.366 | 50 |
| 20 | 32+527.380 | 49581.257 | 43658.449 | 70 |
| 21 | 32+617.823 | 49540.946 | 43577.636 | 60 |
| 22 | 32+777.737 | 49375.396 | 43606.975 | 50 |
| 23 | 32+862.356 | 49358.675 | 43509.915 | 80 |
| 24 | 32+995.475 | 49299.02 | 43391.18 | 50 |
| 25 | 33+064.236 | 49303.709 | 43322.727 | 50 |
| 26 | 33+169.172 | 49227.594 | 43248.307 | 100 |
| 27 | 33+238.147 | 49192.186 | 43189.159 | 150 |
| 28 | 33+291.341 | 49169.490 | 43141.214 | 50 |
| 29 | 33+346.584 | 49121.063 | 43114.461 | 70 |
| 30 | 33+475.789 | 49041.788 | 43013.201 | 50 |
| 31 | 33+621.399 | 49155.613 | 42908.965 | 50 |
| 32 | 33+793.245 | 49142.852 | 42738.596 | 50 |
| 33 | 33+853.414 | 49174.716 | 42687.464 | 70 |
| 34 | 33+919.412 | 49185.959 | 42622.342 | 130 |

| SI. No. | HIPCH: | Easting | Northing | Radius |
|---------|------------|-----------|-----------|--------|
| | (m) | (m) | (m) | |
| 35 | 33+989.059 | 49205.982 | 42555.696 | 70 |
| 36 | 34+075.655 | 49160.743 | 42479.166 | 150 |
| 37 | 34+151.817 | 49148.545 | 42403.349 | 50 |
| 38 | 34+213.560 | 49106.269 | 42358.375 | 130 |
| 39 | 34+268.033 | 49073.564 | 42314.950 | 50 |
| 40 | 34+446.748 | 48908.848 | 42247.285 | 50 |
| 41 | 34+527.627 | 48955.796 | 42160.815 | 50 |
| 42 | 34+588.640 | 48951.676 | 42099.888 | 150 |
| 43 | 34+733.437 | 48957.758 | 41955.344 | 100 |
| 44 | 34+959.127 | 48771.463 | 41818.326 | 100 |
| 45 | 35+096.524 | 48775.683 | 41675.867 | 150 |
| 46 | 35+332.813 | 48823.891 | 41446.603 | 55 |
| 47 | 35+475.430 | 48673.258 | 41427.221 | 55 |
| 48 | 35+587.026 | 48661.842 | 41311.645 | 50 |
| 49 | 35+742.470 | 48542.877 | 41210.975 | 60 |
| 50 | 35+886.738 | 48690.164 | 41126.139 | 100 |
| 51 | 35+960.277 | 48742.963 | 41074.831 | 100 |
| 52 | 36+051.080 | 48825.983 | 41038.179 | 50 |
| 53 | 36+108.465 | 48852.038 | 40986.837 | 50 |
| 54 | 36+192.702 | 48917.908 | 40934.655 | 70 |
| 55 | 36+243.758 | 48967.549 | 40922.487 | 130 |
| 56 | 36+302.900 | 49021.204 | 40897.762 | 70 |
| 57 | 36+352.872 | 49055.906 | 40861.825 | 50 |
| 58 | 36+418.932 | 49115.525 | 40833.862 | 50 |
| 59 | 36+497.197 | 49133.429 | 40756.273 | 50 |
| 60 | 36+982.650 | 49530.481 | 40477.549 | 50 |
| 61 | 37+042.978 | 49590.700 | 40475.946 | 50 |
| 62 | 37+182.652 | 49702.340 | 40392.322 | 60 |
| 63 | 37+257.885 | 49775.851 | 40418.316 | 50 |
| 64 | 37+349.993 | 49863.903 | 40392.749 | 50 |
| 65 | 37+482.187 | 49923.347 | 40274.482 | 100 |
| 66 | 37+559.290 | 49980.157 | 40222.222 | 70 |
| 67 | 37+624.760 | 49989.146 | 40156.070 | 50 |
| 68 | 37+674.418 | 50013.233 | 40112.743 | 70 |
| 69 | 37+776.971 | 50024.276 | 40011.079 | 50 |
| 70 | 37+851.905 | 49979.158 | 39950.979 | 50 |
| 71 | 37+911.826 | 49988.067 | 39890.989 | 70 |
| 72 | 37+968.131 | 49981.152 | 39835.115 | 70 |
| 73 | 38+095.048 | 50028.921 | 39717.333 | 150 |
| 74 | 38+423.632 | 50245.777 | 39472.838 | 150 |
| 75 | 38+504.980 | 50307.009 | 39420.399 | 40 |
| 76 | 38+612.908 | 50240.226 | 39329.501 | 50 |
| 77 | 38+723.649 | 50273.876 | 39223.813 | 55 |
| 78 | 38+864.610 | 50419.837 | 39249.290 | 100 |
| 79 | 38+918.724 | 50466.801 | 39276.144 | 70 |
| 78 | 38+864.610 | 50419.837 | 39249.290 | 100 |

| SI. No. | HIPCH: | Easting | Northing | Radius |
|---------|-------------------|------------------|------------------|--------|
| 80 | (m) 39+021.940 | (m) 50568.914 | (m) 39280.851 | 40 |
| 81 | 39+102.669 | 50586.919 | 39198.777 | 50 |
| 82 | 39+155.586 | 50628.508 | 39165.313 | 70 |
| 83 | 39+223.193 | 50674.951 | 39116.268 | 100 |
| 84 | 39+299.321 | 50746.221 | 39088.716 | 100 |
| 85 | 39+383.312 | 50805.984 | 39030.144 | 70 |
| 86 | 39+453.280 | 50803.984 | 38961.286 | 150 |
| 87 | 39+539.140 | 50840.954 | 38878.656 | 70 |
| 88 | 39+633.377 | 50832.517 | 38784.609 | 50 |
| 89 | 39+719.402 | 50891.301 | 38720.615 | 50 |
| 90 | 39+929.591 | 50779.281 | 38537.617 | 100 |
| 91 | 40+191.049 | 50685.368 | 38294.209 | 100 |
| 92 | 40+270.212 | 50622.504 | 38245.844 | 130 |
| 93 | 40+327.171 | 50570.400 | 38222.829 | 100 |
| 93 | 40+327.171 | 50498.675 | 38156.701 | 70 |
| 95 | 40+424.739 | 50496.675 | 38127.687 | 100 |
| | 40+579.316 | | | |
| 96 | | 50385.092 | 38058.615 | 100 |
| 97 | 40+865.781 | 50132.529 | 37924.751 | 150 |
| 98 | 40+938.824 | 50062.015 | 37905.896 | 100 |
| 99 | 41+797.608 | 49343.684 | 37437.351 | 70 |
| 100 | 41+874.258 | 49312.603 | 37368.169 | 40 |
| 101 | 41+965.362 | 49377.987 | 37302.453 | 40 |
| 102 | 42+057.651 | 49320.771 | 37226.335 | 50 |
| 103 | 42+140.053 | 49238.358 | 37219.216 | 50 |
| 104 | 42+269.609 | 49183.942 | 37098.366 | 30 |
| 105 | 42+403.573 | 49135.729 | 37254.245 | 30 |
| 106 | 42+539.142 | 49058.602 | 37120.472 | 50 |
| 107 | 42+605.626 | 48995.921 | 37096.708 | 50 |
| 108 | 42+728.550 | 48902.516 | 37018.175 | 40 |
| 109 | 42+834.714 | 48905.718 | 37173.280 | 50 |
| 110 | 42+971.572 | 48798.730 | 37257.195 | 50 |
| 111 | 43+117.484 | 48682.970 | 37170.544 | 40 |
| 112 | 43+223.000 | 48678.992 | 37065.799 | 40 |
| 113 | 43+290.589 | 48623.234 | 37027.455 | 40 |
| 114 | 43+384.931 | 48601.999 | 36937.156 | 40 |
| 115 | 43+454.234 | 48670.449 | 36911.790 | 50 |
| 116 | 43+503.428 | 48709.566 | 36882.098 | 70 |
| 117 | 43+558.269 | 48761.103 | 36863.331 | 70 |
| 118 | 43+652.254 | 48821.303 | 36790.780 | 50 |
| 119 | 43+745.498 | 48906.282 | 36752.731 | 150 |
| 120 | 43+812.951 | 48971.603 | 36736.057 | 100 |
| 121 | 43+943.727 | 49068.524 | 36647.761 | 130 |
| 122 | 44+019.801 | 49141.505 | 36624.264 | 50 |
| 123 | 44+071.384 | 49175.425 | 36585.439 | 70 |
| 124 | 44+144.653 | 49234.688 | 36543.241 | 50 |

| SI. No. | HIPCH: (m) | Easting (m) | Northing (m) | Radius |
|---------|---------------|-------------|-----------------|--------|
| 125 | 44+265.077 | 49254.851 | 36425.197 | 100 |
| 126 | 44+405.594 | 49351.003 | 36321.419 | 50 |
| 127 | 44+510.370 | 49289.738 | 36227.844 | 50 |
| 128 | 44+632.723 | 49392.223 | 36144.735 | 70 |
| 129 | 44+694.989 | 49452.361 | 36128.673 | 70 |
| 130 | 44+747.320 | 49493.343 | 36095.934 | 70 |
| 131 | 44+940.206 | 49681.502 | 36055.158 | 130 |
| 132 | 45+175.934 | 49911.112 | 36100.335 | 40 |
| 133 | 45+267.484 | 49840.760 | 35987.651 | 50 |
| 134 | 45+344.422 | 49835.971 | 35911.087 | 80 |
| 135 | 45+444.594 | 49870.345 | 35817.169 | 100 |
| 136 | 45+506.317 | 49908.366 | 35768.568 | 100 |
| 137 | 45+666.792 | 49969.913 | 35621.530 | 50 |
| 138 | 45+756.732 | 50058.026 | 35606.709 | 100 |
| 139 | 45+821.370 | 50118.616 | 35584.251 | 100 |
| 140 | 45+905.707 | 50202.651 | 35579.067 | 50 |
| 141 | 46+010.185 | 50234.563 | 35476.698 | 70 |
| 142 | 46+190.924 | 50156.644 | 35316.978 | 35 |
| 143 | 46+391.994 | 50068.386 | 35526.230 | 40 |
| 144 | 46+450.680 | 50042.405 | 35341.744 | 50 |
| 145 | 46+619.188 | 49967.508 | 35191.300 | 50 |
| 146 | 46+688.545 | 49900.306 | 35170.857 | 50 |
| 147 | 46+802.003 | 49826.450 | 35084.838 | 100 |
| 148 | 46+878.456 | 49757.822 | 35050.848 | 50 |
| 149 | 47+008.116 | 49714.472 | 34921.664 | 40 |
| 150 | 47+120.809 | 49605.405 | 34987.630 | 40 |
| 151 | 47+249.007 | 49573.790 | 34851.156 | 40 |
| 152 | 47+359.409 | 49682.819 | 34817.754 | 40 |
| 153 | 47+454.738 | 49630.773 | 34719.415 | 40 |
| 154 | 47+598.179 | 49733.574 | 34618.938 | 50 |
| 155 | 47+740.573 | 49873.841 | 34632.305 | 50 |
| 156 | 47+830.761 | 49931.142 | 34563.319 | 50 |
| 157 | 47+972.419 | 50067.636 | 34525.481 | 100 |
| 158 | 48+050.780 | 50125.375 | 34472.961 | 50 |
| 159 | 48+131.890 | 50118.048 | 34391.029 | 50 |
| 160 | 48+312.865 | 50257.937 | 34275.591 | 50 |
| 161 | 48+443.890 | 50170.854 | 34172.003 | 50 |
| 162 | 48+544.922 | 50184.676 | 34073.004 | 80 |
| 163 | 48+690.417 | 50265.004 | 33952.318 | 50 |
| 164 | 48+779.550 | 50181.304 | 33899.297 | 50 |
| 165 | 48+845.934 | 50122.371 | 33933.655 | 50 |
| 166 | 48+902.380 | 50066.238 | 33938.517 | 50 |
| 167 | 48+959.228 | 50020.898 | 33972.846 | 100 |
| 168 | 49+040.970 | 49945.091 | 34001.936 | 40 |
| 169 | 49+111.171 | 49885.215 | 33966.488 | 50 |

| SI. No. | HIPCH: (m) | Easting (m) | Northing (m) | Radius |
|------------|--------------------------|------------------------|------------------------|----------|
| 170 | 49+187.379 | 49848.241 | 33900.408 | 40 |
| 171 | 49+273.655 | 49761.902 | 33926.689 | 50 |
| 172 | 49+361.366 | 49685.373 | 33880.911 | 40 |
| 173 | 49+448.177 | 49620.193 | 33943.093 | 40 |
| 174 | 49+554.959 | 49522.362 | 33903.781 | 40 |
| 175 | 49+656.918 | 49567.717 | 33806.495 | 50 |
| 176 | 49+790.747 | 49514.166 | 33686.301 | 50 |
| 177 | 49+995.996 | 49326.881 | 33782.872 | 50 |
| 178 | 50+092.774 | 49389.451 | 33589.212 | 50 |
| 179 | 50+175.094 | 49344.778 | 33518.331 | 50 |
| 180 | 50+287.870 | 49387.565 | 33412.944 | 80 |
| 181 | 50+385.167 | 49459.266 | 33347.416 | 50 |
| 182 | 50+514.533 | 49470.686 | 33218.702 | 100 |
| 183 | 50+625.012 | 49409.403 | 33126.580 | 50 |
| 184 | 50+696.325 | 49336.367 | 33133.262 | 50 |
| 185 | 50+758.223 | 49276.255 | 33119.329 | 50 |
| 186 | 50+830.311 | 49215.800 | 33160.334 | 50 |
| 187 | 50+890.763 | 49155.304 | 33153.210 | 50 |
| 188 | 50+944.060 | 49103.997 | 33167.133 | 50 |
| 189 | 51+029.802 | 49024.346 | 33137.422 | 50 |
| 190 | 51+124.499 | 49044.657 | 33036.318 | 30 |
| 191 | 51+204.163 | 48987.127 | 32983.095 | 30 |
| 192 | 51+308.219 | 49051.713 | 32903.654 | 50 |
| 193 194 | 51+461.003 51+527.482 | 49191.864 49162.851 | 32978.769 32860.772 | 40 50 |
| 194 | 51+527.462 | 49169.305 | 32803.736 | 50 |
| 196 | 51+663.129 | 49138.211 | 32732.123 | 50 50 |
| 197 | 51+744.101 | 49193.782 | 32667.738 | 50 |
| 198 | 51+832.569 | 49185.350 | 32578.714 | 50 |
| 199 | 51+958.166 | 49295.301 | 32512.074 | 50 |
| 200 | 52+022.087 | 49327.139 | 32456.800 | 50 |
| 201 | 52+109.268 | 49403.938 | 32415.664 | 50 |
| 202 | 52+301.723 | 49354.435 | 32222.943 | 60 |
| 203 | 52+512.001 | 49572.528 | 32194.062 | 50 |
| 204 | 52+586.659 | 49636.513 | 32156.741 | 50 |
| 205 | 52+663.447 | 49709.642 | 32178.221 | 100 |
| 206 | 52+787.701 | 49832.016 | 32172.963 | 50 |
| 207 | 52+885.129 | 49847.443 | 32075.474 | 100 |
| 208 | 52+990.253 | 49886.252 | 31978.273 | 70 |
| 209 | 53+097.299 | 49981.255 | 31929.561 | 50 |
| 210 | 53+177.820 | 49997.982 | 31851.335 | 50 |
| 211 | 53+246.695 | 50038.757 | 31795.998 | 50 |
| 212 | 53+336.630 | 50016.531 | 31707.636 | 50 |
| 213 | 53+530.839 | 50141.939 | 31558.167 | 50 |
| 214 | 53+616.202 | 50127.413 | 31473.415 | 50 |

| SI. No. | HIPCH: (m) | Easting (m) | Northing (m) | Radius |
|---------|---------------|-------------|-----------------|--------|
| 215 | 53+777.316 | 50214.321 | 31340.217 | 50 |
| 216 | 53+919.428 | 50103.573 | 31247.804 | 50 |
| 217 | 54+021.346 | 50107.116 | 31147.990 | 50 |
| 218 | 54+096.264 | 50164.918 | 31101.136 | 100 |
| 219 | 54+188.914 | 50220.505 | 31027.040 | 70 |
| 220 | 54+293.848 | 50323.610 | 31002.714 | 40 |
| 221 | 54+380.549 | 50311.527 | 30911.816 | 50 |
| 222 | 54+455.171 | 50352.268 | 30848.620 | 40 |
| 223 | 54+535.661 | 50315.505 | 30776.908 | 70 |
| 224 | 54+653.599 | 50220.871 | 30707.053 | 50 |
| 225 | 54+737.896 | 50250.013 | 30622.301 | 50 |
| 226 | 54+837.688 | 50207.405 | 30532.238 | 50 |
| 227 | 54+947.844 | 50101.499 | 30501.250 | 50 |
| 228 | 55+029.717 | 50060.060 | 30430.107 | 50 |
| 229 | 55+147.210 | 49940.567 | 30427.677 | 50 |
| 230 | 55+268.555 | 49887.721 | 30320.272 | 40 |
| 231 | 55+359.083 | 49926.217 | 30238.642 | 70 |

SCHEDULE - E (See Clauses 2.1 and 14.2)

MAINTENANCE REQUIREMENTS

1 Maintenance Requirements

- (i) The Contractor shall, at all times maintain the Project Highway in accordance with the provisions of this Agreement, Applicable Laws and Applicable Permits.
- (ii) The Contractor shall repair or rectify any Defect or deficiency set forth in Paragraph 2 of this Schedule-E within the time limit specified therein and any failure in this behalf shall constitute non-fulfillment of the Maintenance obligations by the Contractor. Upon occurrence of any breach hereunder, the Authority shall be entitled to effect reduction in monthly lump sum payment as set forth in Clause 14.6 of this Agreement, without prejudice to the rights of the Authority under this Agreement, including Termination thereof.
- (iii) All Materials, works and construction operations shall conform to the MORTH Specifications for Road and Bridge Works, and the relevant IRC publications. Where the specifications for a work are not given, Good Industry Practice shall be adopted.

[Specify all the relevant documents]

2. Repair/rectification of Defects and deficiencies

The obligations of the Contractor in respect of Maintenance Requirements shall include repair and rectification of the Defects and deficiencies specified in Annex - I of this Schedule-E within the time limit set forth therein.

3. Other Defects and deficiencies

In respect of any Defect or deficiency not specified in Annex - I of this Schedule-E, the Authority's Engineer may, in conformity with Good Industry Practice, specify the permissible limit of deviation or deterioration with reference to the Specifications and Standards, and any deviation or deterioration beyond the permissible limit shall be repaired or rectified by the Contractor within the time limit specified by the Authority's Engineer.

4. Extension of time limit

Notwithstanding anything to the contrary specified in this Schedule-E, if the nature and extent of any Defect or deficiency justifies more time for its repair or rectification than the time specified herein, the Contractor shall be entitled to additional time in conformity with Good Industry Practice. Such additional time

shall be determined by the Authority's Engineer and conveyed to the Contractor and the Authority with reasons thereof.

5. Emergency repairs/restoration

Notwithstanding anything to the contrary contained in this Schedule-E, if any Defect, deficiency or deterioration in the Project Highway poses a hazard to safety or risk of damage to property, the Contractor shall promptly take all reasonable measures for eliminating or minimizing such danger.

6. Daily inspection by the Contractor

The Contractor shall, through its engineer, undertake a daily visual inspection of the Project Highway and maintain a record thereof in a register to be kept in such form and manner as the Authority's Engineer may specify. Such record shall be kept in safe custody of the Contractor and shall be open to inspection by the Authority and the Authority's Engineer at any time during office hours.

7. Pre-monsoon inspection / Post-monsoon inspection

The Contractor shall carry out a detailed pre-monsoon inspection of all bridges, culverts and drainage system before [1st June] every year in accordance with the guidelines contained in IRC: SP35. Report of this inspection together with details of proposed maintenance works as required on the basis of this inspection shall be sent to the Authority's Engineer before the [10th June] every year. The Contractor shall complete the required repairs before the onset of the monsoon and send to the Authority's Engineer a compliance report. Post monsoon inspection shall be done by the [30th September] and the inspection report together with details of any damages observed and proposed action to remedy the same shall be sent to the Authority's Engineer.

8. Repairs on account of natural calamities

All damages occurring to the Project Highway on account of a Force Majeure Event or default or neglect of the Authority shall be undertaken by the Authority at its own cost. The Authority may instruct the Contractor to undertake the repairs at the rates agreed between the Parties.

| Asset Type | Performance | | f Service OS) | Frequency of | Tools/Equipment | Standards and References for | Time limit for Rectification/ | Maintenance |
|--|----------------------------------|---------------|--|-----------------|---|--|-------------------------------|-------------------------------------|
| | Parameter | Desirable | Acceptable | Inspection | | Inspection and Data Analysis | Repair | Specifications |
| | Potholes | Nil | < 0.1 % of area and subject to limit of 10 mm indepth | Daily | Length Measurement Unit like Scale, Tape, odometer etc. | | 24-48 hours | MORT&H Specification 3004.2 |
| Flexible Pavement | Cracking | Nil | < 5 % subject to limit of 0.5 sqm for any 50 m length | Daily | | IRC 82: 2015 and Distress Identification Manual for Long Term Pavement | 7-15 days | MORT&H Specification 3004.3 |
| (Pavement of MCW, Service | Rutting | Nil | < 5 mm | Daily | Straight Edge | Performance Program, FHWA 2003 (http://www.tfhrc.com/pavement/lttp/reports/03031/) | 15 -30 days | MORT&H Specification 3004.2 |
| Road, approaches of Grade | Corrugations and Shoving | Nil | < 0.1 % of area | Daily | Length Measurement Unit like | | 2-7 days | IRC:82- 2015 |
| structure, approaches of | Bleeding | Nil | < 0.1 % of area | Daily | Scale, Tape, odometer etc. | | 3-7 days | MORT&H Specification 3004.4 |
| connecting roads, slip | Raveling / Stripping | Nil | < 0.1 % of area | Daily | | | 7-15 days | IRC:82- 2015 read with IRC SP 81 |
| roads, lay byes etc. as applicable) | Edge Deformation/ Breaking | Nil | < 1 m for any 100 m section and width < 0.1 m at any location, restricted to 30 cm from the edge | Daily | Scale, Tape, odometer etc. | | | IRC:82- 2015 |
| | Roughness BI | 2000 mm/km | 2400 mm/km | Bi- Annually | Class I Profilometer | Class I Profilometer : ASTM E950 (98) :2004 –Standard Test Method for | 180 days | IRC:82-2015 |
| | Skid Number | 60SN | 50SN | Bi- | SCRIM | measuring Longitudinal Profile of | 180 days | BS: 7941-1: 2006 |

| | Pavement Condition Index | 3 | 2.1 | Annually Bi- Annually | (Sideway-force Coefficient Routine Investigation Machine or equivalent) | Travelled Surfaces with Accelerometer Established Inertial Profiling Reference ASTM E1656 -94: 2000- Standard Guide for Classification of Automatic Pavement Condition Survey Equipment | 180 days | IRC:82- 2015 |
|--|----------------------------------|--|---|-----------------------------|--|---|----------|----------------|
| | Other Pavement Distresses | | | Bi- Annually | | | 2-7 days | IRC:82- 2015 |
| | Deflection/ Remaining Life | | | Annually | Falling Weight Deflect meter | IRC 115: 2014 | 180 days | IRC:115-2014 |
| Rigid Pavement (Pavement of MCW, Service Road, Grade Structure, approaches of connecting roads, slip roads, lay byes etc. as applicable) | Roughness BI | 2200m m/km | 2400mm /km | Bi- Annually | Class I Profilometer | ASTM E950 (98) :2004 and ASTM E1656 - 94: 2000 | 180 days | IRC:SP:83-2008 |
| | Skid | Skid Resistan different spec Minimum SN 36 | ce no. at ed of vehicles Traffic Speed (Km/h) 50 65 80 | Bi- Annually | SCRIM (Sideway-force Coefficient Routine Investigation Machine or equivalent) | RC:SP:83-2008 | 180 days | IRC:SP:83-2008 |
| | | 31 31 | 95 110 | | 242 | | | |

| Embankment/ Slope | Edge drop at shoulders | Nil | 40 mm | Daily | Length Measurement Unit like Scale, Tape, odometer etc. | IRC | 7-15 days | MORT&H Specification 408.4 |
|----------------------|-----------------------------------|-----|---|---|--|-----|-----------|-------------------------------|
| | Slope of camber/cross fall | Nil | <2% variation in prescribed slope of camber /cross fall | Daily | | | 7-15 days | MORT&H Specification 408.4 |
| | Embankment Slopes | Nil | <15 % variation in prescribe side slope | Daily | | | 7-15 days | MORT&H Specification 408.4 |
| | Embankment Protection | Nil | Nil | Daily | NA | | 7-15 days | MORT&H Specification |
| | Rain Cuts/ Gullies in slope | Nil | Nil | Daily Specially During Rainy Season | NA | | 7-15 days | MORT&H Specification |

In addition to the above performance criterion, the contractor shall strictly maintain the rigid pavements as per requirements in the following table

Table -2: Maintenance Criteria for Rigid Pavements:

| S.No | | Magazirad | Degree | | Repair A | Action |
|------|--|---|----------|--|-------------------------------------|---|
| 2.NO | Type of Distress | Measured Parameter | of | Assessment Rating | For the case d < D/2 | For the case d > |
| • | | Parameter | Severity | | Short Term | D/2 Long Term |
| | | | CRAC | KING | | |
| 1. | Single Discrete Cracks Not | w = width of crack L = length of crack d = depth of crack D = depth of slab | 0 | Nil, not discernible | No Action | Not applicable |
| | intersecting with any joint | | 1 | w < 0.2 mm. hair cracks | | |
| | | | 2 | w = 0.2 - 0.5 mm, discernible from slow-moving car | | Seal, and stitch if L > Im. |
| | | | 3 | w = 0.5 - 1.5 mm, discernible from fast-moving car | Seal without delay | Within 7days |
| | | | 4 | w = 1.5 - 3.0 mm | Seal, and stitch if L > l m. | Staple or Dowel Bar Retrofit, FDR for affected portion. |
| | | | 5 | w > 3 mm. | Within 7 days | Within 15days |
| 2. | Single Transverse (or Diagonal) | w = width of crack | 0 | Nil, not discernible | No Action | |
| | Crack intersecting with one or more joints | L = length of crack d = depth of crack | 1 | w < 0.2 mm, hair cracks | Route and seal with epoxy. | Staple or Dowel Bar Retrofit. |
| | | D = depth of slab | 2 | w = 0.2 - 0.5 mm, discernible from slow vehicle | Within 7 days | Within 15 days |
| | | | 3 | w = 0.5 - 3.0 mm, discernible from fast vehicle | Route, seal and stitch, if L > 1 m. | |
| | | | | | Within 7 days | |

| | | | 5 | w = 3.0 - 6.0 mm w > 6 mm, usually associated with spelling, and/or slab rocking under traffic | Dowel Bar Retrofit. Within 15 days Not Applicable, as it may be full depth | Full Depth Repair Dismantle and reconstruct affected. Portion with norms and specifications - See Para 5.5 & 9.2 Within 15days |
|---|--------------------------------------|--|---|---|---|--|
| 3 | Single Longitudinal Crack | w = width of crack | 0 | Nil, not discernible | No Action | |
| | intersecting with one or more joints | L = length of crack d = depth of crack D = depth of slab | 1 | w < 0.5 mm, discernable from slow moving vehicle | Seal with epoxy, if L > 1 m. Within 7 days | Staple or dowel bar retrofit. Within 15days |
| | | | 2 | w = 0.5 - 3.0 mm, discernible from fast vehicle | Route seal and stitch, if L > I m. Within 15 days | |
| | | | 3 | w = 3.0 – 6.0 mm | Staple, if L > 1 m. Within 15 days | Partial Depth Repair with stapling. Within 15days |
| | | | 4 | w = 6.0 - 12.0 mm, usually associated with spalling | | , |
| | | | 5 | w > 12 mm, usually associated with spalling, and/or slab rocking under traffic | Not Applicable, as it may be full depth | Full Depth Repair Dismantle and reconstruct affected portion as per norms and specifications - See Para 5.6.4 |

| | | | | | | Within 15days |
|---|------------------------------|---|---|--|---|---|
| 4 | Multiple Cracks intersecting | w = width of crack | 0 | Nil, not discernible | No Action | |
| | with one or more joints | | 1 | w < 0.2 mm, hair cracks | Seal, and stitch if L > I m. | |
| | | | 2 | w = 0.2 - 0.5 mm. discernible from slow vehicle | Within 15 days | |
| | | | 3 | w = 0.5 - 3.0 mm, discernible from fast vehicle | Full depth repair within 15 days | Dismantle, Reinstate Sub-base, |
| | | | 4 | w = 3.0 - 6.0 mm panel broken into 2 or 3 pieces | | Reconstruct whole slab as per specifications within 30 days |
| | | | 5 | w > 6 mm and/or panel broken into more than 4 pieces | | , |
| 5 | Corner Break | w = width of crack L = length of crack | 0 | Nil, not discernible | No Action | |
| | | | 1 | w < 0.5 mm; only 1 corner broken | Seal with low viscosity epoxy to | Seal with epoxy seal with epoxy |
| | | | 2 | w < 1.5 mm; L < 0.6 m, only one corner broken | secure broken parts Within 7 days Partial Depth (Refer Figure 8.3 of IRC:SP: 83-2008) | Within 7 days |
| | | | 3 | w < 1.5 mm; L < 0.6 m, two corners broken | | Full depth repair |
| | | | 4 | w > 1.5 mm; L > 0.6 m or three corners broken | | |

| | | | 5 | three or four corners broken | Within 15 days | Reinstate sub-base, and reconstruct the slab as per norms and specifications within 30days |
|---|--|---|---|--|---|--|
| 6 | Punchout (Applicable to Continuous Reinforced Concrete Pavement (CRCP) only) | w = width of crack L = length (m/m2) | 0 | Nil, not discernible w < 0.5 mm; L < 3 m/m2 | Not Applicable, as it may be full depth | No Action Seal with low viscosity epoxy to secure broken parts. Within 15 days |
| | | | 2 | either w > 0.5 mm or L < 3 m/m2 | | |
| | | | 3 | w > 1.5 mm and L < 3 m/m2 | | |
| | | | 4 | w > 3 mm, L < 3 m/m2 and deformation | | Full depth repair - Cut out and replace damaged area taking |
| | | | 5 | w > 3 mm, L > 3 m/m2 and deformation | | care not to damage Reinforcement. Within 30days |
| 7 | Raveling or Honeycomb type surface | r = area damaged surface/total | 0 | Nil, not discernible | No Action | |
| | surface of slab (%) h = maximum depth of damage | <u> </u> | 1 | r < 2 % | Local repair of areas Damaged | |
| | | | 2 | r = 2 - 10 % | and liable to be damaged. | |
| | | | | | Within 15 days | |

| | | | 3 | r = 10-25% | Bonded Inlay, 2 or 3 slabs if | |
|---|----------|---|---|-----------------------|--|-----------|
| | | | 4 | r = 25 - 50 % | Affecting | |
| | | | | | Within 30 days | |
| | | | 5 | r > 50% and h > 25 mm | Reconstruct slabs, 4 or more slabs if affecting. | |
| | | | | | Within 30 days | |
| 8 | Scaling | r = damaged surface/total | 0 | Nil, not discernible | Short Term | Long Term |
| | | surface of slab (%) h = maximum depth of damage | | | No Action | |
| | | | 1 | r < 2 % | Local repair of areas Damaged | |
| | | | 2 | r = 2 - 10 % | and liable to be damaged. | |
| | | | | | Within 7days | |
| | | | 3 | r = 10 - 20% | Bonded Inlay within 15 Days | |
| | | | 4 | r = 10 - 30% | Reconstruct slab within | |
| | | | 5 | r>30 % and h> 25mm | 30 days | |
| 9 | Polished | t = texture depth, | 0 | | | |

| | Surface/Glazing | sand patch test | 1 | t > 1 mm | No action | |
|----|--|--|------------------|--|--|----------------|
| | | | 2 | t = 1 – 0.6 mm | | Not Applicable |
| | | | 3 | t = 0.6 – 0.3 mm | Monitor rate of deterioration | |
| | | | 4 | t = 0.3 – 0.1 mm | Diamond Grinding if Affecting 50% or more slabs in a | |
| | | | 5 | t < 0.1 mm | Continuous stretch of minimum 5 km. Within 30 days | |
| 10 | Popout (Small Hole), Pothole Refer Para 8.4 | n = number/m ₂ d = diameter h = maximum depth | 0 1 2 3 | d < 50 mm; h < 25 mm; n < 1 per 5 m ₂ d = 50 - 100 mm; h < 50 mm; n < 1 per 5 m ₂ d = 50 - 100 mm; h > 50 mm; n < 1 per 5 m ₂ d = 100 - 300 mm; h < 100 mm n < 1 per 5 m ₂ | No action. Partial depth repair 65 mm deep. Within 15 days Partial depth repair 110mm | Not Applicable |

| | | | 4 | d = 100 - 300 mm; h > 100 mm; n < 1 per 5 m ₂ | i.e.10 mm more than the depth of the hole. | |
|----|--------------------|---|---|--|--|----------------|
| | | | 5 | d > 300 mm; h > 100 mm: n > 1 per 5 m ₂ | Within 30 days Full depth repair. Within 30 days | |
| 11 | Joint Seal Defects | loss or damage L = Length as % total | 0 | Difficult to discern. | No action. | |
| | | joint length | 1 | Discernible, L< 25% but of little immediate consequence with regard to ingress of water or trapping incompressible material. | Clean joint, inspect later. | Not Applicable |
| | | | 2 | Notable. L > 25% insufficient protection against ingress of water and trapping incompressible material. | Clean and reapply sealant in Selected locations. Within 7 days | |
| | | | 4 | Severe; w > 3 mm negligible protection against ingress of water and trapping incompressible material. | Clean, widen and reseal the joint. Within 7 days | |
| | Spalling of Joints | w = width on either | 0 | Nil, not discernible | No action. | |

| 12 | | side of the joint L = length of spalled portion (as % joint length) | 1 | w < 10 mm | Apply low viscosity epoxy resin/ mortar in cracked portion. | |
|----|---|---|---|-------------------------|---|----------------------------------|
| | | | 2 | w = 10 - 20 mm, L < 25% | Within 7 days | |
| | | | 3 | w = 20 - 40 mm, L > 25% | Partial Depth Repair. | Not Applicable |
| | | | 3 | , , , , , | Within 15 days | |
| | | | 4 | w = 40 - 80 mm, L > 25% | 30 - 50 mm deep, h = w + 20% of w, within 30 days | |
| | | | 5 | w > 80 mm, and L > 25% | 50 - 100 mm deep repair. | |
| | | | | | H = w + 20% of w. | |
| | | | | | Within 30 days | |
| 13 | Faulting (or Stepping) in Cracks or Joints | f = difference of level | 0 | not discernible, < 1 mm | No action. | No action. |
| | | | 1 | f < 3 mm | | |
| | | | 2 | f = 3 - 6 mm | Determine cause and observe, take action for diamond grinding | Replace the slab as appropriate. |
| | | | 3 | f = 6 - 12 mm | Diamond Grinding | Within 30days |

| | | | 5 | f= 12 - 18 mm f> 18 mm | Raise sunken slab. Strengthen subgrade and sub-base by grouting and raising sunken slab | Replace the slab as appropriate. Within 30days |
|----|--------------------|-------------------|-------|---|--|---|
| 14 | Blowup or Buckling | l - | cal 0 | Nil, not discernible | No Action | |
| | | normal profile | 1 | h < 6 mm | | |
| | | | 2 | h = 6 - 12 mm | Install Signs to Warn Traffic | |
| | | | 3 | h = 12 - 25 mm | within 7 days | |
| | | | 4 | h > 25 mm | Full Depth Repair. | |
| | | | 5 | shattered slabs, ie 4 or more pieces | Within 30 days Replace broken slabs. Within 30 days | |
| 15 | Depression | h = negative vert | cal 0 | Not discernible, h < 5 mm | No action. | |

| | | displacement from | | | | |
|----|-------|--|---|---------------------------------|---|----------------|
| | | normal profile L =length | 1 | h = 5 - 15 mm | | |
| | | | 2 | h = 15-30 mm, Nos <20% joints | Install Signs to Warn Traffic within 7 days | Not Applicable |
| | | | 3 | h = 30 - 50 mm | | |
| | | | 4 | h > 50 mm or > 20% joints | Strengthen subgrade. | |
| | | | 5 | h > 100 mm | Reinstate pavement at normal level if L < 20 m. Within 30 days | |
| 16 | Heave | h = positive vertical displacement from | 0 | Not discernible. h < 5 mm | No action. | |
| | | normal profile. L = length | 1 | h = 5 - 15 mm | Follow up. | |
| | | | 2 | h = 15 - 30 mm, Nos <20% joints | Install Signs to Warn Traffic | |
| | | | 3 | h = 30 - 50 mm | within 7 days | scrabble |
| | | | 4 | h > 50 mm or > 20% joints | Stabilise subgrade. | |

| | | | 5 | h > 100 mm | Reinstate pavement at normal level if length < 20 m. Within 30 days | |
|----|--------------------------|---|---|---------------------------------|--|--|
| 17 | Bump | h = vertical displacement from normal profile | 0 | h < 4 mm h = 4 - 7 mm | No action Grind, in case of new construction within 7 days | Construction Limit for New Construction. |
| | | | 3 | h = 7 - 15 mm | Grind, in case of ongoing Maintenance within 15 days | Replace in case of new construction. Within 30days |
| | | | 4 | h > 15 mm | Full Depth Repair. Within 30 days | Full Depth Repair. Within 30days |
| | | | 0 | Nil, not discernible < 3mm | Short Term No Action | Long Term |
| | | | 0 | ivii, not discernible > Sillill | NO ACTION | |
| 18 | Lane to Shoulder Dropoff | f = difference of level | 1 | f = 3 - 10 mm | Spot repair of shoulder | |
| | | | 2 | f = 10 - 25 mm | within 7 days | |

| | | | 3 | f = 25 - 50 mm f = 50 - 75 mm | Fill up shoulder within 7 dayss | For any 100 m Stretch Reconstruct shoulder, if affecting 25% or more of stretch. |
|----|---------|--|--------|--------------------------------------|---|---|
| | | | 5 | f > 75 mm | | Within 30days |
| | | | Drair | nage | | |
| 19 | Pumping | quantity of fines and water expelled through open joints and cracks Nos | 0 | not discernible | No Action | |
| | | | 1 to 2 | slight/ occasional Nos < 10% | Repair cracks and joints Without delay. | Inspect and repair sub-drainage at distressed sections and upstream. |
| | | | 3 to 4 | appreciable/ Frequent 10 - 25% | Lift or jack slab within 30 days. | and upstream. |
| | | | 5 | abundant, crack development > 25% | Repair distressed pavement sections. Strengthen subgrade and subbase. Replace slab. Within 30 days | |

| 20 | Ponding | Ponding on slabs due to blockage of drains | 0-2 | No discernible problem | No action. | |
|----|---------|--|--------|---|---|--|
| | | | 3 to 4 | Blockages observed in drains, but water flowing | Clean drains etc within 7 days, Follow up | Action required to stop water damaging |
| | | | 5 | Ponding, accumulation of water observed | -do | foundation within 30 days. |

Table -3: Maintenance Criteria for Safety Related Items and Other Furniture Items:

| Asset Type | Performance Parameter | Level | of Service (| LOS) | Frequency of Measurement | Testing Method | Recommended Remedial measures | Time limit for Rectification | Specifications and Standards |
|---------------|---|--------------------------|----------------------------|--|-----------------------------|---|---|------------------------------------|------------------------------------|
| Highway | Availability of Safe Sight Distance | | of safe stop shall be | l-2014, a ping sight available Safe | | Manual | Removal of obst 24 hours, in cas affected by tem such as trees encroachments. | e of sight line porary objects | |
| | | Design Speed, kmph | Minimum Sight Distance (m) | Stopping Sight Distance (m) | Monthly | Measurement s with 0 dometer along with video/image | In case of permanent structure or design deficiency: Removal of obstruction/improvement of deficiency at the earliest Speed Restriction boards and suitable | | IRC:SP 84-2014 |
| | | 100 | 360 | 180 | | backup traffic calming measures such as transverse bar marking, | | | |
| | | 80 | 260 | 130 | | | blinkers, etc. sh during the rectification. | 0. | |

| Pavement Marking | Wear | <70% of marking remaining | Bi- Annually | Visual Assessment as per Annexure-F of IRC:35- 2015 | Re - painting | Cat-1 Defect – within 24 hours Cat-2 Defect - within 2 months | IRC:35- 2015 |
|---------------------|--------------------------|---|-----------------|--|---|---|-----------------|
| | Day time Visibility | During expected life Service Time Cement Road - 130mcd/m ₂ /lux Bituminous Road - 100mcd/m ₂ /lux | Monthly | As per Annexure-D of IRC:35-2015 | Re - painting | Cat-1 Defect – within 24 hours Cat-2 Defect – within 2 months | IRC:35- 2015 |
| | Night Time Visibility | InitialandMinimumPerformanceforDryRetroreflectivity during night time:Design Speed(RL) Reflectivity (mcd/m2/lux)RetroUp to 652008065-100250120Above 100350150Initial Performance for Night Visibility under wet condition (Retro reflectivity): | Bi-Annually | As per Annexure-E of IRC:35-2015 | Re - painting | Cat-1 Defect – within 24 hours Cat-2 Defect – within 2 months | IRC:35-2015 |
| Road Signs | Shape and Position | Shape and Position as per IRC:67-2012. Signboard should be clearly visible for the design speed of the section. | Daily | Visual with video/image backup | Improvement of shape, in case if shape is damaged. Relocation as Per | 48 hours in case of Mandatory Signs, Cautionary and Informatory | IRC:67-2012 |

| | | | | | requirement | Signs (Single and Dual post signs) 15 Days in case of Gantry/Cantile ver Sign boards | |
|----------------------------|--|--|-------------|---|------------------------|--|-------------------------------------|
| | Retro reflectivity | As per specifications in IRC:67- 2012 | Bi-Annually | Testing of Each signboard using Retro Reflectivity Measuring Device. In accordance with ASTM D 4956-09. | Change of signboard | 48 hours in case of Mandatory Signs, Cautionary and Informatory Signs (Single and Dual post signs) 1 Month in case of Gantry/ Cantilever Sign boards | IRC:67-2012 |
| Kerb | Kerb Height | As per IRC 86:1983 depending upon type of Kerb | Bi-Annually | Use of distance measuring tape | Raising Kerb Height | Within 1 Month | IRC 86:1983 |
| | Kerb Painting | Functionality: Functioning of Kerb painting as intended | Daily | Visual with video/image backup | Kerb Repainting | Within 7-days | IRC 35:2015 |
| Other Road Furniture | Reflective Pavement Markers (Road Studs) | Numbers and Functionality as per specifications in IRC:SP:84-2014 and IRC:35-2015, unless specified in Schedule-B. | Daily | Counting | New Installation | Within 2 months | IRC:SP:84- 2014, IRC:35- 2015 |
| | Pedestrian Guardrail | Functionality: Functioning of guardrail as intended | Daily | Visual with video/image | Rectification | Within 15 days | IRC:SP:84- 2014 |

| | | | | backup | | | |
|--------------------|---|---|---------|--|--------------------------------------|----------------|--------------------------------------|
| | Traffic Safety Barriers | Functionality: Functioning of Safety Barriers as intended | Daily | Visual with video/image backup | Rectification | Within 7 days | IRC:SP:84- 2014, IRC:119- 2015 |
| | End Treatment of Traffic Safety Barriers | Functionality: Functioning of End Treatment as intended | Daily | Visual with video/image backup | Rectification | Within 7 days | IRC:SP:84- 2014, IRC:119- 2015 |
| | Attenuators Functionality: Functioning of Attenuators as intended | | Daily | Visual with video/image backup | Rectification | Within 7 days | IRC:SP-2014, IRC:119- 2015 |
| | Guard Posts Functionality: Functioning of Guard Posts and Delineators as intended | | Daily | Visual with video/image backup | Rectification | Within 15 days | IRC: 79 - 1981 |
| | Overhead Sign Structure | Overhead sign structure shall be structurally adequate | Daily | Visual with video/image backup | Rectification | Within 15 days | IRC:67-2012 |
| | Traffic Blinkers | Functionality: Functioning of Traffic Blinkers as intended | Daily | Visual with video/image backup | Rectification | Within 7 days | IRC:SP:84- 2014 |
| Highway | Highway Lights | Illumination: Minimum 40 Lux illumination on the road surface | Daily | The illumination level shall be measured with luxmeter | Improvement in Lighting System | 24 hours | IRC:SP:84- 2014 |
| Lighting System | | No major failure in the lighting system | Daily | - | Rectification of failure | 24 hours | IRC:SP:84- 2014 |
| | | No minor failure in the lighting system | Monthly | - | Rectification of failure | 8 hours | IRC:SP:84- 2014 |
| | Toll Plaza Canopy Lights | Minimum 40 Lux illumination on the road surface | Daily | The illumination level shall be measured | Improvement in Lighting System | 24 hours | IRC:SP:84- 2014 |

| | | | | with luxmeter | | | |
|--|--|---|---------|--------------------------------------|--|----------------|--------------------|
| | | No major/minor failure in the lighting system | Daily | - | Rectification of failure | 8 hours | IRC:SP:84- 2014 |
| Trees and Plantatio n including median plantatio n | Obstruction in a minimum head-room of 5.5 m above carriageway or obstruction in visibility of road signs | No obstruction due to trees | Monthly | Visual with video/image backup | Removal of trees | Immediate | IRC:SP:84- 2014 |
| | Deterioration in health of trees and bushes | Health of plantation shall be as per requirement of specifications & instructions issued by Authority from time to time | Daily | Visual with video/image backup | Timely watering and treatment. Or Replacement of Trees and Bushes. | Within 90 days | IRC:SP:84- 2014 |
| | Vegetation affecting sight line and road structures | Sight line shall be free from obstruction by vegetation | Daily | Visual with video/image backup | Removal of trees | Immediate | IRC:SP 84- 2014 |
| Rest Areas | Cleaning of toilets | - | Daily | - | - | Every 4 hours | |
| | Defects in electrical, water and sanitary installations | - | Daily | - | Rectification | 24 hours | |
| Other Project Facilities | pedestrian fac | eterioration in Approach Roads, cilities, truck lay-bys, bus-bays, attle crossings, Traffic Aid Posts, | Daily | - | Rectification | 15 days | IRC:SP 84- 2014 |

| and | Medical Aid Posts and other works | | | |
|---------|-----------------------------------|--|--|--|
| Approac | | | | |
| h roads | | | | |

| Asset Type | Performance Parameter | Level of Service (LOS) | Frequency of Measurement | Testing Method | Recommended Remedial measures | Time limit for Rectification | Specifications and Standards |
|---------------------------|--|--|--|--|--|---|--|
| Pipe/box/slab culverts | Free waterway/ unobstructed flow section | 85% of culvert normal flow area to available. | 2 times in a year (before and after rainy season) | Inspection by Bridge Engineer as per IRC SP: 35-1990 and recording of depth of silting and area of vegetation. | Cleaning silt up soils and debris in culvert barrel after rainy season, removal of bushes and vegetation, U/s of barrel, under barrel and D/s of barrel before rainy season. | 15 days before onset of monsoon and within 30 days after end of rainy season. | IRC 5-2015, IRC SP:40- 1993 and IRC SP:13- 2004 |
| | Leak-proof expansion joints if any | No leakage through expansion joints | Bi-Annually | Physical inspection of expansion joints as per IRC SP: 35-1990 if any, for leakage strains on walls at joints. | Fixing with sealant suitably | 30 days or before onset of rains whichever comes earlier | IRC SP:40- 1993 and IRC SP:69-2011 |
| | Structurally sound | Spalling of concrete not more than 0.25 sqm Delamination of concrete not more than 0.25 | Bi-Annually | Detailed inspection of all components of culvert as per IRC SP:35-1990 and recording | Repairs to spalling, cracking, delamination, rusting shall be followed as per IRC:SP:40-1993. | 15 days | IRC SP 40- 1993 and MORTH Specification s clause 2800 |

| | Protection works in good condition | sq.m. Cracks wider than 0.3 mm not more than 1m aggregatelength Damaged of rough stone apron or bank revetment not more than 3 sqm, damage to solid apron (concreteapron) not more than 1 sqm | 2 times in a year (before and after rainy season) | Condition survey as per IRC SP:35- 1990 | Repairs to damaged aprons and pitching | 30 days after defect observation or 2 weeks before onset of rainy season whichever is earlier. | IRC: SP 40- 1993 and IRC:SP:13- 2004. |
|---|--|---|--|--|---|---|---|
| Bridges including ROBs Flyover etc. as applicable | Riding quality or user comfort | No pothole in wearing coat on bridge deck | Daily | Visual inspection as per IRC SP:35- 1990 | Repairs to BC or wearing coat | 15 days | MORT&H Specification 2811 |
| Bridge -Super Structure | Bumps | No bump at expansion joint | Daily | Visual inspection as per IRC SP:35- 1990 | Repairs to BC on either side of expansion joints, profile correction course on approach slab in case of settlement to approach embankment | 15 days | MORT&H Specification 3004.2 & 2811. |
| | User safety (condition of crash barrier and guard rail) | No damaged or missing stretch of crash barrier or pedestrian hand railing | Daily | Visual inspection and detailed condition survey as per IRC SP: 35- | Repairs and replacement of safety barriers as the case may be | 3 days | IRC: 5-1998, IRC SP: 84- 2014 and IRC SP: 40- 1993. |

| | | | 1990. | | | |
|--|---|---------------------------------------|--|--|----------|--|
| Rusted reinforcement Spalling of concrete Delamination | Not more than 0.25 sq.m Not more than 0.50 sq.m Not more than 0.50 sq.m | Bi- Annually | Detailed condition survey as per IRC SP: 35-1990 using Mobile Bridge Inspection Unit | All the corroded reinforcement shall need to be thoroughly cleaned from rusting and applied with anticorrosive coating before carrying out the repairs to affected concrete portion with | 15 days | IRC SP: 40- 1993 and MORTH Specification 1600. |
| Cracks | Not more than | Bi- | Detailed | epoxy mortar / concrete. Grouting with | 48 Hours | IRC SP: 40- |
| wider than 0.30 mm | 1m total length | Annually | condition survey as per IRC SP: 35-1990 using Mobile Bridge Inspection Unit | epoxy mortar, investigating causes for cracks development and carry out necessary rehabilitation | | 1993 and MORTH Specification 2800. |
| Rainwater seepage through deck slab | Leakage - nil | Quarterly | Detailed condition survey as per IRC SP: 35-1990 using Mobile Bridge Inspection Unit | Grouting of deck slab at leakage areas, waterproofing, repairs to drainage spouts | 1 months | MORTH specifications 2600 & 2700 |
| Deflection due to permanent loads and live | Within design limits. | Once in every 10 years for spans more | Load test method | Carry out major rehabilitation works on bridge to retain original | 6 months | IRC SP: 51- 1999. |

| loads | | than 40 m | | design loads capacity | | |
|---|---------------------------|---|---|---|----------|--|
| Vibrat in brid deck d movin | lge vibrations shall | Once in every 5 years for spans more than 30m and every 10 years for spans between 15 to 30 m | Laser displacement sensors or laser vibro-meters | Strengthening of super structure | 4 months | AASHTO LRFD specifications |
| Leaka; Expan joints | 9 | | Detailed condition survey as per IRC SP:35-1990 using Mobile Bridge Inspection Unit | Replace of seal in expansion joint | 15 days | MORTH specifications 2600 and IRC SP: 40-1993. |
| Debris dust in strip s expan- joint | debris in expansion joint | Monthly | Detailed condition survey as per IRC SP:35-1990 using Mobile Bridge Inspection Unit | Cleaning of expansion joint gaps thoroughly | 3 days | MORTH specification s 2600 and IRC SP: 40- 1993. |
| Draina | | Bi- Annually | Detailed condition survey as per IRC SP: 35-1990 | Cleaning of drainage spouts thoroughly. Replacement of missing/broken | 3 days | MORTH specification 2700. |

| | | No silt, debris, clogging of drainage spout collection chamber. | | using Mobile Bridge Inspection Unit | down take pipes with a minimum pipe extension of 500mm below soffit of slab. Providing sealant around the drainage spout if any leakages observed | | |
|-------------------------|--|---|-------------|--|--|----------|--|
| Bridge- substructure | Cracks/ spalling of concrete/ Rusted steel | No cracks, spalling of concrete and rusted steel | Bi-Annually | Detailed condition survey as per IRC SP: 35-1990 using Mobile Bridge Inspection Unit | All the corroded reinforcement shall need to be thoroughly cleaned from rusting and applied with anticorrosive coating before carrying out repairs to substructure by grouting/guniting and micro concreting depending on type of defect noticed | 30 days | IRC SP: 40- 1993 and MORTH specification 2800. |
| | Bearings | Delaminating of bearing reinforcement not more than 5%, cracking or tearing of rubber not more than 2 | Bi-Annually | Detailed condition survey as per IRC SP: 35-1990 using Mobile Bridge Inspection Unit | In case of failure of even one bearing on any pier/abutment, all the bearings on that pier/abutment shall be replaced, in order | 3 months | MORTH specificatio n 2810 and IRC SP: 40- 199. |

| | | locations per side, no rupture of reinforcement or rubber | | | to get uniform load transfer on to bearings. | | |
|-----------------------|--|--|---|---|---|--|--|
| Bridge Foundations | Scouring around foundations | Scouring shall not be lower than maximum scour level for the bridge | Bi-Annually | Condition survey and visual Inspection as per IRC SP:35- 1990 using Mobile Bridge Inspection Unit. In case of oubt, use Underwater camera for inspection of deep wells in major Rivers. | suitable protection works around pier/abutment | 1 months | IRC SP: 40- 1993, IRC 83-2014, MORTH specification 2500 |
| | Protection works in good condition | Damaged of rough stone apron or bank revetment not more than 3 sq.m, damage to solid apron (concrete apron) not more than 1 sq.m | 2 times in a year (before and after rainy season) | Condition survey as per IRC SP:35-1990 | Repairs to damaged aprons and pitching. | 30 days After defect observation or 2 weeks before onset of rainy season whichever is earlier. | IRC: SP 40- 1993 and IRC:SP:13-2004. |

Note: Any Structure during the entire contract period which is found that does not complies with all requirements of this Table will be prepared, rehabilitated or even reconstructed under the scope of the contractor.

Table 4: Maintenance Criteria for Structures and Culverts:

Table 5: Maintenance Criteria for Hill Roads

In addition to above, for hill roads the following provisions for maintenance is also to done.

| Hill Roads | | | | |
|------------|---------------------------------------|------------------------|--|--|
| (i) | Damage to Retaining wall/ Breast wall | 7 (Seven) days | | |
| (ii) | Landslides requiring clearance | 12 (Twelve) hours | | |
| (iii) | Snow requiring clearance | 24 (Twenty Four) hours | | |

Note: For all tables 1 to 5 above, latest BIS & IRC standards (even those not indicated herewith)

along with MoRTH specifications shall be binding for all maintenance activities.

A. Flexible Pavement

| | Nature of Defect or deficiency | Time limit for repair/ rectification | | |
|---------|---|---|--|--|
| (b) Gr | anular earth shoulders, side slopes, drains and c | | | |
| (i) | Variation by more than 1 % in the prescribed slope of camber/cross fall (shall not be less than the camber on the main carriageway) | 7 (seven) days | | |
| (ii) | Edge drop at shoulders exceeding 40 mm | 7 (seven) days | | |
| (iii) | Variation by more than 15% in the prescribed side (embankment) slopes | 30 (thirty) days | | |
| (iv) | Rain cuts/gullies in slope | 7 (seven) days | | |
| (v) | Damage to or silting of culverts and side drains | 7 (seven) days | | |
| (vi) | Desilting of drains in urban/semi- urban areas | 24 (twenty four) hours | | |
| (vii) | Railing, parapets, crash barriers | 7 (seven) days (Restore immediately if causing safety hazard) | | |
| (c) Roa | d side furniture including road sign and paveme | ent marking | | |
| (i) | Damage to shape or position, poor visibility or loss of retro- reflectivity | 48 (forty eight) hours | | |
| (ii) | Painting of km stone, railing, parapets, crash barriers | As and when required/ Once every year | | |
| (iii) | Damaged/missing signs road requiring replacement | 7 (seven) days | | |
| (vi) | Damage to road mark ups | 7 (seven) days | | |
| (d) Roa | nd lighting | | | |
| (i) | Any major failure of the system | 24 (twenty four) hours | | |
| (ii) | Faults and minor failures | 8 (eight) hours | | |
| (e) Tre | es and plantation | | | |
| (i) | Obstruction in a minimum head- room of 5 m above carriageway or obstruction in visibility of road signs | 24 (twenty four)hours | | |
| (ii) | Removal of fallen trees from carriageway | 4 (four) hours | | |
| (iii) | Deterioration in health of trees and bushes | Timely watering and treatment | | |
| (vi) | Trees and bushes requiring replacement | 30 (thirty) days | | |
| (v) | Removal of vegetation affecting sight line and road structures | 15 (fifteen) days | | |
| (f) Res | | | | |
| (i) | Cleaning of toilets | Every 4 (four) hours | | |

| (ii) | Defects in electrical, water and sanitary | 24 (twenty four) hours |
|----------|--|--|
| (11) | installations | 24 (twenty lour) nours |
| (σ) [Το | ll Plaza] | |
| (h) | Other Project Facilities and Approach roads | |
| (i) | Damage in approach roads, pedestrian facilities, | 15 (fifteen) days |
| (-) | truck lay- byes, bus-bays, bus-shelters, cattle | |
| | crossings, [Traffic Aid Posts, Medical Aid Posts] | |
| | and service roads | |
| (ii) | Damaged vehicles or debris on the road | 4 (four) hours |
| (iii) | Malfunctioning of the mobile crane | 4 (four) hours |
| Bridge | | |
| | erstructure | |
| (i) | Any damage, cracks, spalling/ scaling | within 48 (forty eight) hours |
| | Temporary measures Permanent measures | within 15 (fifteen) days or as |
| | | specified by the Authority's |
| | | Engineer |
| (b) For | indations | |
| (i) | Scouring and/or cavitation | 15 (fifteen) days |
| (c) Pie | rs, abutments, return walls and wing walls | |
| (i) | Cracks and damages including settlement and | 30 (thirty) days |
| | tilting, spalling, scaling | |
| | rings (metallic) of bridges | |
| (i) | Deformation, damages, tilting or shifting of | 15 (fifteen) days Greasing of metallic |
| | bearings | bearings once in a year |
| (e) Joir | | |
| (i) | Malfunctioning of joints | 15 (fifteen) days |
| | er items | |
| (i) | Deforming of pads in elastomeric bearings | 7 (seven) days |
| (ii) | Gathering of dirt in bearings and joints; or | 3 (three) days |
| | clogging of spouts, weep holes and vent-holes | |
| (iii) | Damage or deterioration in kerbs, parapets, | 3 (three) days (immediately within |
| | handrails and crash barriers | 24 hours if posing danger to safety) |
| (vi) | Rain-cuts or erosion of banks of the side slopes of | 7 (seven) days |
| | approaches | 17 (22 |
| (v) | Damage to wearing coat | 15 (fifteen) days |
| (vi) | Damage or deterioration in approach slabs, | 30 (thirty) days |
| 6 113 | pitching, apron, toes, floor or guide bunds | 17 (22 |
| (vii) | Growth of vegetation affecting the structure or | 15 (fifteen) days |
| () *** | obstructing the waterway | |
| (g) Hill | | |
| (i) | Damage to retaining wall/breast wall | 7 (seven) days |
| (ii) | Landslides requiring clearance | 12 (twelve) hours |
| (iii) | Snow requiring clearance Where necessary, the Authority may modify the t | 24 (twenty four) hours |

[Note: Where necessary, the Authority may modify the time limit for repair/rectification, or add to the nature of Defect or deficiency before issuing the bidding document, with the approval of the competent authority.]

SCHEDULE - F (See Clause 3.1.7(a))

APPLICABLE PERMITS

1 Applicable Permits

- (i) The Contractor shall obtain, as required under the Applicable Laws, the following Applicable Permits:
- (a) Permission of the State Government for extraction of boulders from quarry;
- (b) Permission of Village Panchayats and Pollution Control Board for installation of crushers;
- (c) License for use of explosives;
- (d) Permission of the State Government for drawing water from river/reservoir;
- (e) License from inspector of factories or other competent Authority for setting up batching plant;
- (f) Clearance of Pollution Control Board for setting up batching plant;
- (g) Clearance of Village Panchayats and Pollution Control Board for setting up asphalt plant;
- (h) Permission of Village Panchayats and State Government for borrow earth; and
- (i) Any other permits or clearances required under Applicable Laws.
- (ii) Applicable Permits, as required, relating to environmental protection and conservation shall have been procured by the Authority in accordance with the provisions of this Agreement.

SCHEDULE - G

(See Clauses 7.1 and 19.2)

FORM OF BANK GUARANTEE

Annex-I (See Clause 7.1)

[Performance Security/Additional Performance Security] IDG(RD)&SS.

[DG(RD)&SS, Ministry of Road Transport & Highways Transport Bhawan, New Delhi] WHEREAS: (A) [name and address of contractor] (hereinafter called the "Contractor") and [name and address of the authority], (hereinafter called the "Authority") have entered into an agreement (hereinafter called the "Agreement") for the construction of the "Improvement/widening to two-lanning of stretch from km 55.525 to km 79.680 of Ranikhor- Baghmara Project in the state of Meghalaya under "SARDP-NE" Phase-A on EPC mode (Package-III)", subject to and in accordance with the provisions of the Agreement The Agreement requires the Contractor to furnish a Performance Security for due and faithful (B) performance of its obligations, under and in accordance with the Agreement, during the {Construction Period/ Defects Liability Period and Maintenance Period} (as defined in the Agreement) in a sum of Rs.... cr. (Rupees crore) (the "Guarantee Amount"). We, (the "Bank") have agreed to (C) furnish this bank guarantee (hereinafter called the "Guarantee") by way of Performance Security. NOW, THEREFORE, the Bank hereby, unconditionally and irrevocably, guarantees and affirms as follows:

1. The Bank hereby unconditionally and irrevocably guarantees the due and faithful performance of the Contractor's obligations during the {Construction Period/ Defects Liability Period and Maintenance Period} under and in accordance with the Agreement, and agrees and undertakes to pay to the Authority, upon its mere first written demand, and without any demur, reservation, recourse, contest or protest, and without any reference to the Contractor, such sum or sums up to an aggregate sum of the Guarantee Amount as the Authority shall claim, without the Authority being required to prove or to show grounds or reasons for its demand and/or for the sum specified therein.

- 2. A letter from the Authority, under the hand of an officer not below the rank of [General Manager in the National Highways Authority of India], that the Contractor has committed default in the due and faithful performance of all or any of its obligations under and in accordance with the Agreement shall be conclusive, final and binding on the Bank. The Bank further agrees that the Authority shall be the sole judge as to whether the Contractor is in default in due and faithful performance of its obligations during and under the Agreement and its decision that the Contractor is in default shall be final and binding on the Bank, notwithstanding any differences between the Authority and the Contractor, or any dispute between them pending before any court, tribunal, arbitrators or any other authority or body, or by the discharge of the Contractor for any reason whatsoever.
- 3. In order to give effect to this Guarantee, the Authority shall be entitled to act as if the Bank were the principal debtor and any change in the constitution of the Contractor and/or the Bank, whether by their absorption with any other body or corporation or otherwise, shall not in any way or manner affect the liability or obligation of the Bank under this Guarantee.
- 4. It shall not be necessary, and the Bank hereby waives any necessity, for the Authority to proceed against the Contractor before presenting to the Bank its demand under this Guarantee.
- 5. The Authority shall have the liberty, without affecting in any manner the liability of the Bank under this Guarantee, to vary at any time, the terms and conditions of the Agreement or to extend the time or period for the compliance with, fulfillment and/ or performance of all or any of the obligations of the Contractor contained in the Agreement or to postpone for any time, and from time to time, any of the rights and powers exercisable by the Authority against the Contractor, and either to enforce or forbear from enforcing any of the terms and conditions contained in the Agreement and/or the securities available to the Authority, and the Bank shall not be released from its liability and obligation under these presents by any exercise by the Authority of the liberty with reference to the matters aforesaid or by reason of time being given to the Contractor or any other forbearance, indulgence, act or omission on the part of the Authority or of any other matter or thing whatsoever which under any law relating to sureties and guarantors would but for this provision have the effect of releasing the Bank from its liability and obligation under this Guarantee and the Bank hereby waives all of its rights under any such law.
- 6. This Guarantee is in addition to and not in substitution of any other guarantee or security now or which may hereafter be held by the Authority in respect of or relating to the Agreement or for the fulfillment, compliance and/or performance of all or any of the obligations of the Contractor under the Agreement.
- 7. Notwithstanding anything contained hereinbefore, the liability of the Bank under this Guarantee is restricted to the Guarantee Amount and this Guarantee will remain in force for

the period specified in paragraph 8 below and unless a demand or claim in writing is made by the Authority on the Bank under this Guarantee all rights of the Authority under this Guarantee shall be forfeited and the Bank shall be relieved from its liabilities hereunder.

- 8. The Guarantee shall cease to be in force and effect on ****s. Unless a demand or claim under this Guarantee is made in writing before expiry of the Guarantee, the Bank shall be discharged from its liabilities hereunder.
- 9. The Bank undertakes not to revoke this Guarantee during its currency, except with the previous express consent of the Authority in writing, and declares and warrants that it has the power to issue this Guarantee and the undersigned has full powers to do so on behalf of the Bank.
- 10. Any notice by way of request, demand or otherwise hereunder may be sent by post addressed to the Bank at its above referred branch, which shall be deemed to have been duly authorized to receive such notice and to effect payment thereof forthwith, and if sent by post it shall be deemed to have been given at the time when it ought to have been delivered in due course of post and in proving such notice, when given by post, it shall be sufficient to prove that the envelope containing the notice was posted and a certificate signed by an officer of the Authority that the envelope was posted shall be conclusive.
- 11. This Guarantee shall come into force with immediate effect and shall remain in force and effect for up to the date specified in paragraph 8 above or until it is released earlier by the Authority pursuant to the provisions of the Agreement.

 - 13. Intimation regarding issuance of this Bank Guarantee shall be sent to Authority's Bank through SFMS gateway as per the details below:

| S | Particulars | Details |
|--------|-------------|---------|
| · N | | |
| 0 | | |

| • | | |
|---|---------------------------------|--------------------------------------|
| 1 | Name of Beneficiary | National Highways & Infrastructure |
| | | Development Corporation Limited |
| 2 | Beneficiary Bank Account No. | 90621010002659 |
| 3 | Beneficiary Bank Branch | IFSC SYNB0009062 |
| 4 | Beneficiary Bank Branch | Transport Bhawan, New Delhi |
| | Name | |
| 5 | Beneficiary Bank Address | Syndicate Bank transport Bhawan, 1st |
| | | Parliament Street, New Delhi-110001 |

Signed and sealed this day of 20....... at

SIGNED, SEALED AND DELIVERED

For and on behalf of the Bank by: (Signature) (Name) (Designation) (Code Number) (Address)

NOTES:

- (i) The bank guarantee should contain the name, designation and code number of the officer(s) signing the guarantee.
- (ii) The address, telephone number and other details of the head office of the Bank as well as of issuing branch should be mentioned on the covering letter of issuing branch.

Annex – II (Schedule - G) (See Clause 19.2)

Form for Guarantee for Withdrawal of Retention Money

[DG(RD)&SS,

Ministry of Road Transport & Highways Transport Bhawan, New Delhi]

WHEREAS:

- (A) [name and address of contractor] (hereinafter called the "Contractor") has executed an agreement (hereinafter called the "Agreement") with the NHIDCL, (hereinafter called the "Authority") for the construction of the "Improvement/widening to two-lanning of stretch from km 55.525 to km 79.680 of Ranikhor- Baghmara Project in the state of Meghalaya under "SARDP-NE" Phase-A on EPC mode (Package-III) subject to and in accordance with the provisions of the Agreement.
- (B) In accordance with Clause 19.2 of the Agreement, the Authority shall make to the Contractor an interest bearing @Bank Rate + 3% advance payment (herein after called "Advance Payment") equal to 10% (ten per cent) of the Contract Price; and that the Advance Payment shall be made in two installments subject to the Contractor furnishing an irrevocable and unconditional guarantee by a scheduled bank for an amount equivalent to 110% (one hundred and ten percent) of such installment to remain effective till the complete and full repayment of the installment of the Advance Payment as security for compliance with its obligations in accordance with the Agreement. The amount of {first/second} installment of the Advance Payment is Rs. ----- cr. (Rupees ----- crore) and the amount of this Guarantee is Rs. ----- cr. (Rupees ----- crore) (the "Guarantee Amount")\$.
- (C) We, through our branch at (the "Bank") have agreed to furnish this bank guarantee (hereinafter called the "Guarantee") for the Guarantee Amount.
- NOW, THEREFORE, the Bank hereby unconditionally and irrevocably guarantees and affirms as follows:
- 1. The Bank hereby unconditionally and irrevocably guarantees the due and faithful repayment on time of the aforesaid instalment of the Advance Payment under and in accordance with the Agreement, and agrees and undertakes to pay to the Authority, upon its mere first written demand, and without any demur, reservation, recourse, contest or protest, and without any reference to the Contractor, such sum or sums up to an aggregate sum of the Guarantee Amount as the Authority shall claim, without the Authority being required to prove or to show grounds or reasons for its demand and/or for the sum specified therein.
 - A letter from the Authority, under the hand of an officer not below the rank of [General Manager in the National Highways Authority of India], that the Contractor has committed

default in the due and faithful performance of all or any of its obligations for under and in accordance with the Agreement shall be conclusive, final and binding on the Bank. The Bank further agrees that the Authority shall be the sole judge as to whether the Contractor is in default in due and faithful performance of its obligations during and under the Agreement and its decision that the Contractor is in default shall be final, and binding on the Bank, notwithstanding any differences between the Authority and the Contractor, or any dispute between them pending before any court, tribunal, arbitrators or any other authority or body, or by the discharge of the Contractor for any reason whatsoever.

- 2. In order to give effect to this Guarantee, the Authority shall be entitled to act as if the Bank were the principal debtor and any change in the constitution of the Contractor and/or the Bank, whether by their absorption with any other body or corporation or otherwise, shall not in any way or manner affect the liability or obligation of the Bank under this Guarantee.
- 3. It shall not be necessary, and the Bank hereby waives any necessity, for the Authority to proceed against the Contractor before presenting to the Bank its demand under this Guarantee.
- 4. The Authority shall have the liberty, without affecting in any manner the liability of the Bank under this Guarantee, to vary at any time, the terms and conditions of the Advance Payment or to extend the time or period of its repayment or to postpone for any time, and from time to time, any of the rights and powers exercisable by the Authority against the Contractor, and either to enforce or forbear from enforcing any of the terms and conditions contained in the Agreement and/or the securities available to the Authority, and the Bank shall not be released from its liability and obligation under these presents by any exercise by the Authority of the liberty with reference to the matters aforesaid or by reason of time being given to the Contractor or any other forbearance, indulgence, act or omission on the part of the Authority or of any other matter or thing whatsoever which under any law relating to sureties and guarantors would but for this provision have the effect of releasing the Bank from its liability and obligation under this Guarantee and the Bank hereby waives all of its rights under any such law.
- 5. This Guarantee is in addition to and not in substitution of any other guarantee or security now or which may hereafter be held by the Authority in respect of or relating to the Retention Money.
- 6. Notwithstanding anything contained hereinbefore, the liability of the Bank under this Guarantee is restricted to the Guarantee Amount and this Guarantee will remain in force for the period specified in paragraph 8 below and unless a demand or claim in writing is made by the Authority on the Bank under this Guarantee all rights of the Authority under this Guarantee shall be forfeited and the Bank shall be relieved from its liabilities hereunder.
- The Guarantee shall cease to be in force and effect on ****.\$ Unless a demand or claim under this Guarantee is made in writing on or before the aforesaid date, the Bank shall be discharged from its liabilities hereunder.
- 8. The Bank undertakes not to revoke this Guarantee during its currency, except with the previous express consent of the Authority in writing, and declares and warrants that it has the

45

- power to issue this Guarantee and the undersigned has full powers to do so on behalf of the Bank.
- 9. Any notice by way of request, demand or otherwise hereunder may be sent by post addressed to the Bank at its above referred branch, which shall be deemed to have been duly authorised to receive such notice and to effect payment thereof forthwith, and if sent by post it shall be deemed to have been given at the time when it ought to have been delivered in due course of post and in proving such notice, when given by post, it shall be sufficient to prove that the envelope containing the notice was posted and a certificate signed by an officer of the Authority that the envelope was so posted shall be conclusive.
- 10. This Guarantee shall come into force with immediate effect and shall remain in force and effect up to the date specified in paragraph 8 above or until it is released earlier by the Authority pursuant to the provisions of the Agreement.
- 12. Intimation regarding issuance of this Bank Guarantee shall be sent to Authority's Bank through SFMS gateway as per the details below:

| S | Particulars | Details |
|---|---------------------------------|------------------------------------|
| N | | |
| 0 | | |
| • | | |
| 1 | Name of Beneficiary | National Highways & Infrastructure |
| | | Development Corporation Limited |
| 2 | Beneficiary Bank Account No. | 90621010002659 |
| 3 | Beneficiary Bank Branch | IFSC SYNB0009062 |
| 4 | Beneficiary Bank Branch | Transport Bhawan, New Delhi |
| | Name | |

| 5 | Beneficiary Bank | Syndicate Bank transport Bhawan, 1st |
|---|------------------|--------------------------------------|
| | Address | Parliament Street, New Delhi-110001 |

Signed and sealed this day of, 20....... at

SIGNED, SEALED AND DELIVERED

For and on behalf of the Bank by:

(Signature)

(Name)

(Designation)

(Code Number)

(Address)

NOTES:

- (i) The bank guarantee should contain the name, designation and code number of the officer(s) signing the guarantee.
- (ii) The address, telephone number and other details of the head office of the Bank as well as of issuing branch should be mentioned on the covering letter of issuing branch.

Schedule-H

(See Clauses 10.1 (iv) and 19.3)

Contract Price Weightages

- 1.1 The Contract Price for this Agreement is Rs _____
- 1.2 Proportions of the Contract Price for different stages of Construction of the Project Highway shall be as specified below:

| Item | Weightage in percentage to the Contract Price | Stage for Payment | Percentage weightage |
|---|---|---|-------------------------|
| 1 | 2 | 3 | 4 |
| Road works including culverts, widening and | 59.55% | A- Widening and strengthening of existing road (1) Earthwork up to top of the subgrade | 18.14% |
| repair of | | (2) Sub-base Course | 6.41% |
| culverts. | | (3) Non Bituminous Base Course | 3.94% |
| | | (4) Bituminous Base Course | 0.83% |
| | | (5) Wearing Coat | 3.41% |
| | | (6) Widening and repair of culvert | 0.00% |
| | | B1- Reconstruction/ New 2- Lane realignment/bypass (Flexible Pavement) | |
| | | (1) Earthwork up to top of the subgrade | 33.69% |
| | | (2) Sub-base Course | 9.61% |
| | | (3) Non Bituminous Base Course | 5.91% |
| | | (4) Bituminous Base Course | 1.01% |
| | | (5) Wearing Coat | 4.17% |
| | | B2- Reconstruction/ New 2- Lane realignment/bypass (Rigid Pavement) | |
| | | (1) Earthwork up to top of the subgrade | 0.00% |
| | | (2) Sub-base Course | 0.00% |
| | | (3) Dry Lean Concrete (DLC) Course | 0.00% |
| | | (4) Pavement Quality Control (PQC) Course | 0.00% |
| | | | |

| | | C1- Reconstruction/ New Service Road (Flexible Pavement) | |
|--|--------|---|--------|
| | | (1) Earthwork up to top of the subgrade | 0.00% |
| | | (2) Sub-base Course | 0.00% |
| | | (3) Non Bituminous Base Course | 0.00% |
| | | (4) Bituminous Base Course | 0.00% |
| | | (5) Wearing Coat | 0.00% |
| | | C2- Reconstruction/ New Service Road (Rigid Pavement) | |
| | | (1) Earthwork up to top of the subgrade | 0.00% |
| | | (2) Sub-base Course | 0.00% |
| | | (3) Dry Lean Concrete (DLC) Course | 0.00% |
| | | (4) Pavement Quality Control (PQC) Course | 0.00% |
| | | D - Re-Construction and new culverts on existing road, realignments on existing road, realignments, by passes: | |
| | | Culverts(Length<6m) | 12.90% |
| Minor Bridges/Underp asses/Overpasse | 10.70% | A1-Widening and Repairs of Minor Bridges (Length>6m and <60m) | |
| S | | Minor bridges | 0.00% |
| | | A2-New Minor Bridges (Length>6m and <60m) | |
| | | (1) Foundation+Sub Structure: On completion of the foundation work including foundations for wing and return walls ,abutments,piers upto the abutment/pier cap | 62.00% |
| | | (2) Super Structure: On completion of the super structure in all respect includong wearing coat, bearings, expansion joints, hand rails, crash barriers,road sign & markings, tests on completion etc. complete in all respect, | 33.00% |

| | | (3) Approaches: | |
|--------------|-------|---|-------|
| | | On completion of approaches including Retaining walls, stone pitching, protection works complete in all respect and fit for use | 5.00% |
| | | (4) Guide Bund and River Training Works: On completion of Guide Bund and River Training Works complete in all respect. | 0.00% |
| | | B.1- Widening and repair of Underpasses/overpasses | |
| | | Underpasses/Overpasses | 0.00% |
| | | B.2- New Underpasses/overpasses | |
| | | (1) Foundation+Sub Structure: On completion of the foundation work including foundations for wing and return walls ,abutments,piers upto the abutment/pier cap | 0.00% |
| | | (2) Super Structure: On completion of the super structure in | |
| | | all respect including wearing coat, bearings, expansion joints, hand rails, crash barriers, road sign & markings, tests on completion etc. complete in all respect. | 0.00% |
| | | Wearing Coat (a) in case of Overpass- wearing coat including expansion joint complete in all respect as specified and (b) in case of underpass rigid pavement including drainage facility complete in all respects as specified. | |
| | | (3) Approaches: On completion of approaches including Retaining Walls, stone pitching, protection works complete in all respect and fit for use | 0.00% |
| Major Bridge | 2.82% | A.1 -Widening and repairs of Major | |

| (length>60m) | Bridges | |
|---------------------------------|--|--------|
| works and | (1) Foundation | 0.00% |
| RUB/ROB/elev | (2) Sub-structure | 0.00% |
| ated | (3) Super-structure (including bearings) | 0.00% |
| sections/flyover s including | (4) Wearing coat including expansion | |
| viaducts, if any | joints | 0.00% |
| | (5) Miscellaneous items like hand rails, crash barriers, road markings etc. | 0.00% |
| | (6) Wing walls/Return Walls | 0.00% |
| | (7) Guide bunds, River Training Works etc | 0.00% |
| | (8) Approaches (including retaining walls, stone pitching and protection works) | 0.00% |
| | A.2 -New <u>Major Bridges</u> | |
| | (1) Foundation | 40.00% |
| | (2) Sub-structure | 17.00% |
| | (3) Super-structure (including bearings) | 33.00% |
| | (4) Wearing Coat including expansion joints | 5.00% |
| | (5) Miscellaneous items like hand rails, crash barriers, road markings etc. | 5.00% |
| | (6) Wing walls/Return Walls | 0.00% |
| | (7) Guide bunds, River Training Works etc | 0.00% |
| | (8) Approaches (including retaining walls, stone pitching and protection works) | 0.00% |
| | B.1-Widening and repair of (a) ROB | |
| | (b) RUB | |
| | (1) Foundation | 0.00% |
| | (2) Sub-structure | 0.00% |
| | (3) Super-structure (including bearings) | 0.00% |
| | (4) Wearing Coat (a) in case of ROB - wearing coat including expansion joint complete in all respect as specified and (b) in case of RUB rigid pavement under RUB including drainage facility complete in all respects as specified. | 0.00% |
| | (5) Miscellaneous items like hand rails, crash barriers, road markings etc. | 0.00% |
| | (6) Wing walls/Return Walls | 0.00% |

| (7) Approaches (including retaining walls, stone pitching and protection works) | 0.00% |
|--|-------|
| B.2-New ROB/RUB (a) ROB | |
| (b) RUB | |
| (1) Foundation | 0.00% |
| (2) Sub-structure | 0.00% |
| (3) Super-structure (including bearings) | 0.00% |
| (4) Wearing Coat (a) in case of ROB - wearing coat including expansion joint complete in all respect as specified and (b) in case of RUB rigid pavement under RUB including drainage facility complete in all respects as specified. | 0.00% |
| (5) Miscellaneous items like hand rails, crash barriers, road markings etc. | 0.00% |
| (6) Wing walls/Return Walls | 0.00% |
| (7) Approaches (including retaining walls, stone pitching and protection works) | 0.00% |
| C.1- Widening and repair of Elevated Sections/Flyovers/Grade Separators | |
| (1) Foundation | 0.00% |
| (2) Sub-structure | 0.00% |
| (3) Super-structure (including bearings) | 0.00% |
| (4) Wearing Coat including expansion joints. | 0.00% |
| (5) Miscellaneous items like hand rails, crash barriers, road markings etc. | 0.00% |
| (6) Wing walls/Return Walls | 0.00% |
| (7) Approaches (including retaining walls, stone pitching and protection works) | 0.00% |
| C.2- New Elevated Sections/Flyovers/Grade Separators | |
| (1) Foundation | 0.00% |
| (2) Sub-structure | 0.00% |
| (3) Super-structure (including bearings) | 0.00% |
| (4) Wearing Coat including expansion joints. | 0.00% |
| (5) Miscellaneous items like hand rails, crash barriers, road markings etc. | 0.00% |

| | | (6) Wing walls/Return Walls | 0.00% |
|------------------|--------|--|--------|
| | | (7) Approaches (including retaining walls, stone pitching and protection works) | 0.00% |
| Other works | 26.23% | (i) Toll Plaza | 0.00% |
| | | (ii)Road side drains | 8.75% |
| | | (iii)Road signs, markings, km stones, safety devices, | 14.50% |
| | | (iv)Project facilities | 0.00% |
| | | a) Bus bays | 1.06% |
| | | b) Truck lay bye | 0.00% |
| | | c) Rest Areas | 0.00% |
| | | d) Others(Junction and Site Clearance) | 4.53% |
| | | (v)Road side plantation | 0.00% |
| | | (vi) Repair of protection works other than approaches to the bridges, elevated sections/ flyovers/grade separators and ROBs/RUBs | 0.00% |
| | | (vii)Safety and traffic management during construction | 0.00% |
| | | (viii)Protection works(Includes retaining wall and breast wall) | 71.16% |
| Utiltiy Shifting | 0.71% | PHED | 73.71% |
| | | Electric Shifting | 26.29% |
| | | Others | |

1.3 Procedure of estimating the value of work done.

1.3.1 Road works

Procedure for estimating the value of road work done shall be as follows:

Table 1.3.1

| Stage of Payment | Percentage - weightage | Payment Procedure |
|--|------------------------|--|
| A- Widening and strengthening of existing road | | Unit of measurement is linear length. Payment of each stage shall be made on pro rata basis on completion of a stage |
| (1) Earthwork up to top of the sub-grade | 18.14% | in a length of not less than 5 (five) percent of the total length. |
| (2) Sub-base Course | 6.41% | |
| (3) Non Bituminous Base Course | 3.94% | |
| (4) Bituminous Base Course | 0.83% | |

| (6) Widening and repair of culvert 0.00% Cost of ten completed culverts shall be determined pro rate with respect to the total number of culverts. Payment shall be made on the completion of atleast one culverts. B1- Reconstruction/ New 2-Lane realignment/bypass (Flexible Pavement) (1) Earthwork up to top of the sub-grade (2) Sub-base Course (3) Non Bituminous Base Course (4) Bituminous Base (5) Wearing Coat (2) Sub-base Course (3) Non-Bituminous Base (1) Earthwork up to top of the sub-grade (2) Sub-base Course (3) Dry Lean Concrete (DLC) Course (4) Pavement Quality Control (PQC) Course (4) Pavement Quality Control (PQC) Course (5) Wearing Coat (6) Sub-base Course (7) Sub-base Course (8) Dry Lean Concrete (DLC) Course (9) Sub-base Course (10) Earthwork up to top of the sub-grade (11) Earthwork up to top of the sub-grade (12) Sub-base Course (13) Non Bituminous Base (14) Pavement Quality Control (PQC) Course (15) Wearing Coat (16) Earthwork up to top of the sub-grade (17) Earthwork up to top of the sub-grade (18) Sub-base Course (19) Sub-base Course (19) Sub-base Course (20) Sub-base Course (30) Non Bituminous Base (21) Sub-base Course (31) Non Bituminous Base (22) Sub-base Course (33) Non Bituminous Base (24) Bituminous Base (25) Wearing Coat (26) Reconstruction/ New Service Road (Rigid Pavement) (11) Earthwork up to top of the sub-grade (22) Sub-base Course (33) Non Bituminous Base (34) Rituminous Base (35) Wearing Coat (41) Earthwork up to top of the sub-grade (42) Sub-base Course (43) Rituminous Base (44) Bituminous Base (45) Wearing Coat (46) Wearing Coat (47) Course (48) Wearing Coat (49) Wearing Coat (40) Wearing Coat (40) Wearing Coat (41) Earthwork up to top of the sub-grade (42) Sub-base Course (43) Wearing Coat (44) Earthwork up to top of the sub-grade (45) Wearing Coat (46) Wearing Coat (47) Wearing Coat (48) Wearing Coat (49) Wearing Coat (40) Wearing Coat (40) Wearing Coat (40) Wearing Coat (41) Wearing Coat (42) Wearing Coat (43) Wearing Coat (44) Wearing Coat (45) Wearing Coat (46) Wearing Co | (5) Wearing Coat | 3.41% | |
|--|---|--------|---|
| New 2-Lane realignment/bypass (Flexible Pavement) 23.69% 2 | . , | 0.00% | determined pro rate with respect to the total number of culverts. Payment shall be made on the completion of atleast |
| of the sub-grade (2) Sub-base Course (3) Non Bituminous Base Course (4) Bituminous Base Course (5) Wearing Coat B2- Reconstruction/ New 2-Lane realignment/bypass (Flexible Pavement) (1) Earthwork up to top of the sub-grade (2) Sub-base Course (3) Dry Lean Concrete (DLC) Course (4) Pavement Quality Control (PQC) Course (2) Sub-base Course (3) Non Bituminous Base Course (4) Pavement Quality Control (PQC) Course (2) Sub-base Course (3) Non Bituminous Base Course (4) Pavement Quality Control (PQC) Course (5) Wearing Coat (6) Bituminous Base Course (7) Sub-base Course (8) Non Bituminous Base Course (9) Sub-base Course (1) Earthwork up to top of the sub-grade (1) Earthwork up to top of the sub-grade (2) Sub-base Course (3) Non Bituminous Base Course (4) Bituminous Base Course (5) Wearing Coat (6) Wearing Coat (7) Reconstruction/ New Service Road (Rigid Payement) (8) Wearing Coat (9) Wearing Coat (1) Earthwork up to top of the sub-grade (1) Earthwork up to top of the sub-grade (1) Earthwork up to top of the sub-grade (2) Sub-base Course (3) Non Bituminous Base Course (4) Bituminous Base Course (5) Wearing Coat (1) Earthwork up to top of the sub-grade (1) Earthwork up to t | New 2-Lane realignment/bypass | | Payment of each stage shall be made on pro rata basis on completion of a stage |
| (3) Non Bituminous Base Course (4) Bituminous Base Course (5) Wearing Coat B2- Reconstruction/ New 2-Lane realignment/bypass (Flexible Pavement) (1) Earthwork up to top of the sub-grade (3) Dry Lean Concrete (DLC) Course (4) Pavement Quality Control (PQC) Course C1- Reconstruction/ New Service Road (Flexible Pavement) (1) Earthwork up to top of the sub-grade (4) Pavement Quality Control (PQC) Course C1- Reconstruction/ New Service Road (Flexible Pavement) (1) Earthwork up to top of the sub-grade (2) Sub-base Course (3) Non Bituminous Base (2) Sub-base Course (3) Non Bituminous Base Course (4) Bituminous Base Course (5) Wearing Coat (6) Wearing Coat (7) Reconstruction/ New Service Road (Rigid Pavement) (8) Bituminous Base Course (9) Wearing Coat (1) Earthwork up to top of the sub-grade (1) Earthwork up to top of the sub-grade (1) Earthwork up to top of the sub-grade (2) Sub-base Course (3) Non Bituminous Base Course (4) Bituminous Base Course (5) Wearing Coat (1) Earthwork up to top of the sub-grade (2) Sub-base Course (3) Non Bituminous Base Course (4) Bituminous Base Course (5) Wearing Coat (1) Earthwork up to top of the sub-grade (2) Sub-grade (3) Non Bituminous Base (4) Bituminous Base (5) Wearing Coat (6) Wearing Coat (7) Reconstruction/ New Service Road (Rigid Pavement) (1) Earthwork up to top of the sub-grade (1) Earth | 1 1 1 | 33.69% | length whichever is less. |
| Course (4) Bituminous Base Course (5) Wearing Coat B2- Reconstruction/ New 2-Lane realignment/bypass (Flexible Pavement) (1) Earthwork up to top of the sub-grade (2) Sub-base Course (3) Dry Lean Concrete (DLC) Course C1- Reconstruction/ New Service Road (Flexible Pavement) (1) Earthwork up to top of the sub-grade C1- Reconstruction/ New Service Road (Flexible Pavement) (1) Earthwork up to top of the sub-grade C1- Reconstruction/ New Service Road (Flexible Pavement) (1) Earthwork up to top of the sub-grade (2) Sub-base Course (3) Non Bituminous Base Course (4) Pavement Quality (2) Sub-base Course (3) Non Bituminous Base Course (4) Bituminous Base Course (5) Wearing Coat C2- Reconstruction/ New Service Road (Rigid Pavement) (1) Earthwork up to top of the sub-grade (2) Sub-base Course (3) Non Bituminous Base Course (4) Bituminous Base Course (5) Wearing Coat C1- Reconstruction/ New Service Road (Rigid Pavement) (1) Earthwork up to top of the sub-grade (2) Sub-base Course (3) Non Bituminous Base Course (4) Bituminous Base Course (5) Wearing Coat C1- Reconstruction/ New Service Road (Rigid Pavement) (1) Earthwork up to top of the sub-grade Unit of measurement is linear length. Payment of each stage shall be made on pro rata basis on completion of a stage in full length or 0.5 (zero point five) km length whichever is less. | (2) Sub-base Course | 9.61% | |
| Course C | Course | 5.91% | |
| B2- Reconstruction/New 2-Lane realignment/bypass (Flexible Pavement) Payment of each stage shall be made on pro rata basis on completion of a stage in full length or 0.5 (zero point five) km length whichever is less. | ` ' | 1.01% | |
| Payment of each stage shall be made on pro rata basis on completion of a stage in full length or 0.5 (zero point five) km length whichever is less. | ` ' | 4.17% | |
| of the sub-grade (2) Sub-base Course (3) Dry Lean Concrete (DLC) Course (4) Pavement Quality Control (PQC) Course C1- Reconstruction/ New Service Road (Flexible Pavement) (1) Earthwork up to top of the sub-grade (2) Sub-base Course (3) Non Bituminous Base Course (4) Bituminous Base Course (5) Wearing Coat C2- Reconstruction/ New Service Road (Rigid Pavement) (1) Earthwork up to top of the sub-grade (2) Sub-base Course (3) Non Bituminous Base Course (4) Bituminous Base Course (5) Wearing Coat C2- Reconstruction/ New Service Road (Rigid Pavement) (1) Earthwork up to top of the sub-grade (1) Earthwork up to top of the sub-grade (2) Sub-base Course (3) Non Bituminous Base Course (4) Bituminous Base Course (5) Wearing Coat Unit of measurement is linear length. Payment of each stage shall be made on pro rata basis on completion of a stage in full length or 0.5 (zero point five) km length whichever is less. | New 2-Lane realignment/bypass (Flexible Pavement) | | Payment of each stage shall be made on pro rata basis on completion of a stage in full length or 0.5 (zero point five) km |
| (3) Dry Lean Concrete (DLC) Course (4) Pavement Quality Control (PQC) Course C1- Reconstruction/ New Service Road (Flexible Pavement) (1) Earthwork up to top of the sub-grade (2) Sub-base Course (3) Non Bituminous Base Course (4) Bituminous Base Course (5) Wearing Coat C2- Reconstruction/ New Service Road (Rigid Pavement) (1) Earthwork up to top of the sub-grade (1) Earthwork up to top of the sub-grade (2) Sub-base Course (3) Non Bituminous Base Course (4) Bituminous Base Course (5) Wearing Coat C2- Reconstruction/ New Service Road (Rigid Pavement) (1) Earthwork up to top of the sub-grade (1) Earthwork up to top of the sub-grade (2) Sub-base Course (3) Non Bituminous Base Course (4) Bituminous Base Course (5) Wearing Coat (6) Wearing Coat (7) Unit of measurement is linear length. Payment of each stage shall be made on pro rata basis on completion of a stage in full length or 0.5 (zero point five) km length whichever is less. | ` ' | 0.00% | length whichever is less. |
| (4) Pavement Quality Control (PQC) Course C1- Reconstruction/ New Service Road (Flexible Pavement) (1) Earthwork up to top of the sub-grade (2) Sub-base Course (3) Non Bituminous Base Course (4) Bituminous Base Course (5) Wearing Coat C2- Reconstruction/ New Service Road (Rigid Pavement) (1) Earthwork up to top of the sub-grade (1) Earthwork up to top of the sub-grade (2) Sub-base Course (3) Non Bituminous Base Course (4) Bituminous Base Course (5) Wearing Coat C2- Reconstruction/ New Service Road (Rigid Pavement) (1) Earthwork up to top of the sub-grade (2) Course (3) Non Bituminous Base Course (4) Bituminous Base Course (5) Wearing Coat (6) Wearing Coat (7) Very Service Road (Rigid Pavement) (8) Very Care Point five) km length or 0.5 (zero point five) km length whichever is less. | (2) Sub-base Course | 0.00% | |
| Control (PQC) Course C1- Reconstruction/ New Service Road (Flexible Pavement) (1) Earthwork up to top of the sub-grade (2) Sub-base Course (3) Non Bituminous Base Course (4) Bituminous Base Course (5) Wearing Coat C2- Reconstruction/ New Service Road (Rigid Pavement) (1) Earthwork up to top of the sub-grade (2) Sub-base Course (3) Non Bituminous Base Course (4) Bituminous Base Course (5) Wearing Coat C2- Reconstruction/ New Service Road (Rigid Pavement) (1) Earthwork up to top of the sub-grade (2) Sub-base Course (3) Non Bituminous Base O.00% (4) Bituminous Base O.00% (5) Wearing Coat (6) Wearing Coat (7) Very Service Road (Rigid Pavement) (8) Very Service Road (Rigid Pavement) (9) Very Service Road (Rigid Pavement) (1) Earthwork up to top of the sub-grade (1) Earthwork up to top of the sub-grade | 1 | 0.00% | |
| New Service Road (Flexible Pavement)Payment of each stage shall be made on pro rata basis on completion of a stage in full length or 0.5 (zero point five) km length whichever is less.(2) Sub-base Course0.00%(3) Non Bituminous Base Course0.00%(4) Bituminous Base Course0.00%(5) Wearing Coat0.00%C2- Reconstruction/New Service Road (Rigid Pavement)Unit of measurement is linear length. Payment of each stage shall be made on pro rata basis on completion of a stage in full length or 0.5 (zero point five) km length whichever is less. | | 0.00% | |
| of the sub-grade (2) Sub-base Course (3) Non Bituminous Base Course (4) Bituminous Base Course (5) Wearing Coat C2- Reconstruction/ New Service Road (Rigid Pavement) (1) Earthwork up to top of the sub-grade O.00% length whichever is less. length whichever is less. Unit of measurement is linear length. Payment of each stage shall be made on pro rata basis on completion of a stage in full length or 0.5 (zero point five) km length whichever is less. | New Service Road (Flexible Pavement) | | Payment of each stage shall be made on pro rata basis on completion of a stage |
| (3) Non Bituminous Base Course (4) Bituminous Base Course (5) Wearing Coat C2- Reconstruction/ New Service Road (Rigid Pavement) (1) Earthwork up to top of the sub-grade O.00% Unit of measurement is linear length. Payment of each stage shall be made on pro rata basis on completion of a stage in full length or 0.5 (zero point five) km length whichever is less. | 1 1 | 0.00% | |
| Course (4) Bituminous Base Course (5) Wearing Coat C2- Reconstruction/ New Service Road (Rigid Pavement) (1) Earthwork up to top of the sub-grade O.00% Unit of measurement is linear length. Payment of each stage shall be made on pro rata basis on completion of a stage in full length or 0.5 (zero point five) km length whichever is less. | (2) Sub-base Course | 0.00% | |
| Course (5) Wearing Coat C2- Reconstruction/ New Service Road (Rigid Pavement) (1) Earthwork up to top of the sub-grade Unit of measurement is linear length. Payment of each stage shall be made on pro rata basis on completion of a stage in full length or 0.5 (zero point five) km length whichever is less. | Course | 0.00% | |
| C2- Reconstruction/ New Service Road (Rigid Pavement) (1) Earthwork up to top of the sub-grade Unit of measurement is linear length. Payment of each stage shall be made on pro rata basis on completion of a stage in full length or 0.5 (zero point five) km length whichever is less. | Course | 0.00% | |
| New Service Road (Rigid Pavement)Payment of each stage shall be made on pro rata basis on completion of a stage in full length or 0.5 (zero point five) km length whichever is less. | (5) Wearing Coat | 0.00% | |
| of the sub-grade 0.00% length whichever is less. | New Service Road (Rigid Payr | | Payment of each stage shall be made on pro rata basis on completion of a stage |
| (2) Sub-base Course 0.00% | | 0.00% | |
| | (2) Sub-base Course | 0.00% | |

| (3) Dry Lean Concrete (DLC) Course | 0.00% | |
|--|--------|--|
| (4) Pavement Quality Control (PQC) Course | 0.00% | |
| D - Re-Construction and new culverts on existing road, realignments on existing road, realignments,bypasses: | | Cost of ten completed culverts shall be determined pro rate with respect to the total number of culverts. Payment shall be made on the completion of atleast one culverts. |
| Culverts(Length<6m) | 12.90% | |

@ For calculation of payment stage for main carriageway the project length shall be converted into equivalent 2 lane length . For example, if the total length of 4 lane main carriageway is 100 km, then the equivalent length for calculation of payment stage will be 2 x 100 km. Now, if the total length of bituminous work to be done is 100 km, the cost per km of bituminous work shall be determined as follows:

Cost per km = P x weightage for road work x weightage for bituminous work x (1/L) Where P = Contract Price

L = Total equivalent 2-Lane length in km as defined above.

Similarly, the rates per km for other stages shall be worked out accordingly.

Note: The length affected due to law and order problems or litigation during execution including the length not handed over to contractor under clause 8.3 of this Contract Agreement due to which the contractor is unable to execute the work, may be deducted from the total project length for payment purpose. The total length calculated here is only for payment purpose and will not affect and referred in other clauses of the contract agreement.

1.3.2 Minor Bridge and Underpasses/Overpasses

Procedure for estimating the value of Minor Bridge works and Underpasses/Overpasses shall be stated in table 1.3.2

Table 1.3.2

| | Table 1.3.2 | | | |
|--|------------------------|--|--|--|
| Stage of Payment | Percentage - weightage | Payment Procedure | | |
| 1 | 2 | 3 | | |
| A1-Widening and Repairs of Minor Bridges (Length>6m and <60m) | 0.00% | Cost of each minor bridge shall be determined on pro rata basis with respect to the total linear length of the minor bridges. Payment shall be made on the completion of widening and repair works of a minor bridge. | | |
| A2-New Minor Bridges | | | | |
| (i) Foundation+Sub Structure: On completion of the foundation work including foundations for wing and return walls ,abutments,piers upto the abutment/pier cap (ii) Super Structure: | 62.00% | (i) Foundation+Sub Structure: Cost of each minor bridge shall be determined on pro rata basis with respect to the total linear length (m) of the minor bridges. Payment against foundation+sub structure shall be made on pro rata basis on copletion of a stage i.e. not less than 25% of the scope of foundation+ sub structure of each bridge subject to completion of atleast two foundations along with sub structure upto abutment/pier cap level of each bridge. In case where load testing is required for foundation, the trigger of first payment shall include load testing also where specified. (ii) Super Structure: | | |
| On completion of the super structure in all respect including wearing coat, bearings, expansion joints, hand rails, crash barriers, road sign & markings, tests on completion etc. complete in | 33.00% | Payment shall be made on pro rata basis on completion of a stage i.e. completion of super structure of atleast one span in all respect as specified in the column of "Stage of Payment" in this sub clause. | | |

| all rasport | | <u> </u> |
|---|---------------|--|
| all respect, | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| (iii) Approaches: | | (iii) Approaches: |
| On completion of approaches | | Payment shall be made on pro rata basis on |
| including Retaining walls, | - 000/ | completion of a stage i.e. completion of |
| stone pitching, protection | 5.00% | approaches in all respect as specified in the |
| works complete in all respect | | column of " Stage of Payment" in this sub |
| and fit for use | | clause. |
| (iv) Guide Bund and River | | (iv) Guide Bund and River Training Works: |
| Training Works: | | |
| On completion of Guide | | Payment shall be made on pro rata basis on |
| Bund and River Training Works complete in all | 0.00% | completion of a stage i.e. completion of |
| * | | Guide Bunds and River Training Works in all respect as specified. |
| respect. B.1- Widening and repair of | | Cost of each overpass/underpass shall be |
| Underpasses/overpasses | | determined on pro rata basis with respect |
| Chuci passes/over passes | | to the total linear length of the |
| | | underpass/overpass. |
| | | Payment shall be made on the completion |
| | 0.00% | of wiening & repair works of a |
| | | underpass/overpass. |
| B.2- New | | - |
| Underpasses/overpasses | | |
| (i) Foundation+Sub | | (i) Foundation+Sub Structure: Cost of |
| Structure: | | each Underpass/Overpass shall be |
| On completion of the | | determined on pro rata basis with respect |
| foundation work including | | to the total linear length (m) of the |
| foundations for wing and | | Underpass/Overpass. Payment |
| return walls ,abutments,piers | | against foundation+sub structure shall be |
| upto the abutment/pier cap | 0.000/ | made on pro rata basis on copletion of a |
| | 0.00% | stage i.e. not less than 25% of the scope of |
| | | foundation+ sub structure of each |
| | | Underpass/Overpass subject to completion of atleast two foundations along with sub |
| | | structure upto abutment/pier cap level of |
| | | each Underpass/Overpass. |
| | | In case where load testing is required for |
| | | foundation, the trigger of first payment |
| | | shall include load testing also where |
| | | specified. |
| (ii) Super Structure: | | (ii) Super Structure: |
| , · · · - | | , · · · - · · · · · · · · · · · · · · · |

| On completion of the super structure in all respect including wearing coat, bearings, expansion joints, hand rails, crash barriers,road sign & markings, tests on completion etc. complete in all respect. Wearing Coat (a) in case of Overpass- wearing coat including expansion joint complete in all respect as specified and (b) in case of underpass rigid pavement including drainage facility complete in all respects as specified. | 0.00% | Payment shall be made on pro rata basis on completion of a stage i.e. completion of super structure of atleast one span in all respect as specified in the column of "Stage of Payment" in this sub clause. |
|--|-------|---|
| (iii) Approaches: On completion of approaches including Retaining Walls, stone pitching, protection works complete in all respect and fit for use | 0.00% | (iii) Approaches: Payment shall be made on pro rata basis on completion of a stage i.e. completion of approaches in all respect as specified in the column of "Stage of Payment" in this sub clause. |

Major Bridge Works, ROB/RUB and Structures

| Stage of Payment | Percentage - weightage | Payment Procedure |
|---|------------------------|---|
| 1 | 2 | 3 |
| A1-Widening and Repairs of Major Bridges | | |
| (i) Foundation: | 0.00% | (i) Foundation: Cost of each Major bridge shall be determined on pro rata basis with respect to the total linear length (m) of the Major bridges. Payment against foundation shall be made on pro rata basis on copletion of a stage i.e. not less than 25% of the scope of foundation of Major Bridge subject to completion of atleast two foundationsof the Major Bridge. In case where load testing is required for foundation, the trigger of first payment shall include load testing also where specified. |
| (ii) Sub Structure: | | (ii) Sub Structure: |

| (iii) Super Structure | 0.00% | Payment against sub structure shall be made on pro rata basis on copletion of a stage i.e. not less than 25% of the scope of sub structure of Major Bridge subject to completion of atleast two sub structure of the abutment/pier upto abutment/pier cap level of the major bridge. (iii) Super Structure: |
|--|-------|--|
| (including bearings) | 0.00% | Payment shall be made on pro rata basis on completion of a stage i.e. completion of super structure including bearings of atleast one span in all respect as specified. |
| (iv) Wearing Coat including | | Wearing Coat |
| expansion joints. | 0.00% | Payment shall be made on completion of wearing coat including expansion joints complete in all respect as specified. |
| (v) Miscellaneous items like hand rails, crash barriers, road markings etc. | | (v) Miscellaneous |
| | 0.00% | Payment shall be made on completion of all Miscellaneous works like hand rails, crash barriers, road markings etc.complete in all respect as specified. |
| (vi) Wing walls/Return Walls | | (vi) Wing walls/Return Walls |
| wans | 0.00% | Payment shall be made on completion of all Wing walls/Return Walls complete in all respect as specified. |
| (vii) Guide bunds, River Training Works etc | | (vii) Guide bunds, River Training Works etc |
| Training works etc | 0.00% | Payment shall be made on completion of all Guide bunds/River Training Works etc. complete in all respect as specified. |
| (viii) Approaches (including retaining walls, stone pitching and protection works) | | (viii) Approaches: |
| 52.20) | 0.00% | Payment shall be made on completion of both approaches including stone pitching, protection works, etc. complete in all respects as specified. |

1.3.3 Major Bridge Works, ROB/RUB and Structures.

Procedure for estimating the value of Major Bridge Works, ROB/RUB and Structures work shall be

as stated in table 1.3.3:

| Stage of Payment | Percentage weightage | e 1.3.3 - Payment Procedure |
|---|----------------------|---|
| 1 | 2 | 3 |
| (i) Foundation: | 40.00% | (i) Foundation: Cost of each Major bridge shall be determined on pro rata basis with respect to the total linear length (m) of the Major bridges. Payment against foundation shall be made on pro rata basis on copletion of a stage i.e. not less than 25% of the scope of foundation of Major Bridge subject to completion of atleast two foundationsof the Major Bridge. |
| (ii) Sub Structure: | 17.00% | In case where load testing is required for foundation, the trigger of first payment shall include load testing also where specified. (ii) Sub Structure: Payment against sub structure shall be made on pro rata basis on copletion of a stage i.e. not less than 25% of the scope of sub structure of Major Bridge subject to completion of atleast two sub structure of the abutment/pier upto abutment/pier cap level of the major bridge. |
| (iii) Super Structure (including bearings) | | (iii) Super Structure: |
| | 33.00% | Payment shall be made on pro rata basis on completion of a stage i.e. completion of super structure including bearings of atleast one span in all respect as specified. |
| (iv) Wearing Coat including expansion | | Wearing Coat |
| joints. | 5.00% | Payment shall be made on completion of wearing coat including expansion joints complete in all respect as specified. |
| (v) Miscellaneous items like hand rails, crash barriers, road | | (v) Miscellaneous |
| markings etc. | 5.00% | Payment shall be made on completion of all Miscellaneous works like hand rails, crash barriers, road markings etc.complete in all respect as specified. |
| (vi) Wing | | (vi) Wing walls/Return Walls |
| walls/Return Walls | 0.00% | Payment shall be made on completion of all Wing walls/Return Walls complete in all respect as specified. |

| (vii) Guide bunds, | | (vii) Guide bunds, River Training Works etc |
|--|-------|---|
| River Training Works | | (vii) Guide builds, Miver Training Works etc |
| etc | | Downant shall be used an assembly as a fall C 11 |
| | 0.00% | Payment shall be made on completion of all Guide bunds/River Training Works etc. complete in all respect as specified. |
| (viii) Approaches | | (viii) Approaches: |
| (including retaining walls, stone pitching | | |
| and protection works) | | |
| | | Payment shall be made on completion of both |
| | 0.00% | approaches including stone pitching, protection works, etc. complete in all respects as specified. |
| B1 - Widening and | | |
| repairs of | | |
| (a) ROB (b) RUB | | |
| (b) KO | | |
| (i) Foundation: | 0.00% | (i) Foundation: Cost of each ROB/RUB shall be determined on pro rata basis with respect to the total linear length (m) of the ROB/RUB. Payment against foundation shall be made on pro rata basis on copletion of a stage i.e. not less than 25% of the scope of foundation of ROB/RUB subject to completion of atleast two foundations of the ROB/RUB. |
| (ii) Sub Structure: | 0.00% | In case where load testing is required for foundation, the trigger of first payment shall include load testing also where specified. (ii) Sub Structure: Payment against sub structure shall be made on pro rata basis on copletion of a stage i.e. not less than 25% of the scope of sub structure of ROB/RUB subject to completion of atleast two sub structure of the abutment/pier upto abutment/pier cap level of the ROB/RUB. |
| (iii) Super Structure | | (iii) Super Structure: |
| (including bearings) | | () 2 P 2 2 2 2 2 2 2 2 |
| | 0.00% | Payment shall be made on pro rata basis on completion of a stage i.e. completion of super structure including bearings of atleast one span in all respect as specified. |
| (iv) Wearing Coat | | (iv) Wearing Coat: |
| including expansion joints in case of ROB. | | |
| In case of RUB, rigid | | |
| pavement under RUB | | |
| including drainage | | |

| facility as specified. | | |
|---|-------|---|
| facility as specifica. | | |
| | | |
| | | |
| (v) Miscellaneous items like hand rails, crash barriers, road | 0.00% | Payment shall be made on completion of (a) in case of ROB - wearing coat including expansion joint complete in all respect as specified and (b) in case of RUB rigid pavement under RUB including drainage facility complete in all respects as specified. (v) Miscellaneous |
| markings etc. | 0.00% | Payment shall be made on completion of all Miscellaneous works like hand rails, crash barriers, road markings etc.complete in all respect as specified. |
| (vi) Wing | | (vi) Wing walls/Return Walls |
| walls/Return Walls | 0.00% | Payment shall be made on completion of all Wing walls/Return Walls complete in all respect as specified. |
| (vii) Approaches | | (viii) Approaches: |
| (including retaining walls, stone pitching and protection works) | | |
| | 0.00% | Payment shall be made on completion of both approaches including stone pitching, protection works, etc. complete in all respects as specified. |
| B2 - New (a) ROB (b) RUB | | |
| (i) Foundation: | 0.00% | (i) Foundation: Cost of each ROB/RUB shall be determined on pro rata basis with respect to the total linear length (m) of the ROB/RUB. Payment against foundation shall be made on pro rata basis on copletion of a stage i.e. not less than 25% of the scope of foundation of ROB/RUB subject to completion of atleast two foundations of the ROB/RUB. |
| (ii) Sub Structure: | | In case where load testing is required for foundation, the trigger of first payment shall include load testing also where specified. (ii) Sub Structure: |

| | 0.00% | Payment against sub structure shall be made on pro rata basis on copletion of a stage i.e. not less than 25% of the scope of sub structure of ROB/RUB subject to completion of atleast two sub structure of the abutment/pier upto abutment/pier cap level of the ROB/RUB. |
|---|-------|---|
| (iii) Super Structure | | (iii) Super Structure: |
| (including bearings) | 0.00% | Payment shall be made on pro rata basis on completion of a stage i.e. completion of super structure including bearings of atleast one span in all respect as specified. |
| (iv) Wearing Coat | | (iv) Wearing Coat: |
| including expansion joints in case of ROB. In case of RUB, rigid pavement under RUB including drainage facility as specified. | | |
| (v) Miscellaneous | 0.00% | Payment shall be made on completion of (a) in case of ROB - wearing coat including expansion joint complete in all respect as specified and (b) in case of RUB rigid pavement under RUB including drainage facility complete in all respects as specified. (v) Miscellaneous |
| items like hand rails, crash barriers, road markings etc. | | Doymont shall be made on completion of all |
| | 0.00% | Payment shall be made on completion of all Miscellaneous works like hand rails, crash barriers, road markings etc.complete in all respect as specified. |
| (vi) Wing | | (vi) Wing walls/Return Walls |
| walls/Return Walls | 0.00% | Payment shall be made on completion of all Wing walls/Return Walls complete in all respect as specified. |
| (vii) Approaches (including retaining walls, stone pitching | | (viii) Approaches: |
| and protection works) | 0.00% | Payment shall be made on completion of both approaches including stone pitching, protection works, etc. complete in all respects as specified. |
| C1 - Widening and repairs of Elevated Section/Flyovers/ | | |

| Grade Separators | | |
|---|-------|---|
| (i) Foundation: | 0.00% | (i) Foundation: Cost of each Structure shall be determined on pro rata basis with respect to the total linear length (m) of the structures. Payment against foundation shall be made on pro rata basis on copletion of a stage i.e. not less than 25% of the scope of foundation of structures subject to completion of atleast two foundations of the structures. |
| (ii) Sub Structure: | 0.00% | In case where load testing is required for foundation, the trigger of first payment shall include load testing also where specified. (ii) Sub Structure: Payment against sub structure shall be made on pro rata basis on copletion of a stage i.e. not less than 25% of the scope of sub structure of structures subject to completion of atleast two sub structure of the abutment/pier upto abutment/pier cap level of the structures. |
| (iii) Super Structure (including bearings) | | (iii) Super Structure: |
| (====================================== | 0.00% | Payment shall be made on pro rata basis on completion of a stage i.e. completion of super structure including bearings of atleast one span in all respect as specified. |
| (iv) Wearing Coat including expansion | | Wearing Coat |
| joints. | 0.00% | Payment shall be made on completion of wearing coat including expansion joints complete in all respect as specified. |
| (v) Miscellaneous items like hand rails, crash barriers, road | | (v) Miscellaneous |
| markings etc. | 0.00% | Payment shall be made on completion of all Miscellaneous works like hand rails, crash barriers, road markings etc.complete in all respect as specified. (vi) Wing walls/Poturn Walls |
| (vi) Wing walls/Return Walls | | (vi) Wing walls/Return Walls Payment shall be made on completion of all Wing |
| | 0.00% | walls/Return Walls complete in all respect as specified. |

| (vii) Annuaches | | (viii) Approaches |
|--|-------|---|
| (vii) Approaches (including retaining walls, stone pitching and protection works) | | (viii) Approaches: |
| | 0.00% | Payment shall be made on completion of both approaches including stone pitching, protection works, etc. complete in all respects as specified. |
| C2 - New Elevated Section/Flyovers/ Grade Separators | | |
| (i) Foundation: | 0.00% | (i) Foundation: Cost of each Structure shall be determined on pro rata basis with respect to the total linear length (m) of the structures. Payment against foundation shall be made on pro rata basis on copletion of a stage i.e. not less than 25% of the scope of foundation of structures subject to completion of atleast two foundations of the structures. |
| (ii) Sub Structure: | 0.00% | In case where load testing is required for foundation, the trigger of first payment shall include load testing also where specified. (ii) Sub Structure: Payment against sub structure shall be made on pro rata basis on copletion of a stage i.e. not less than 25% of the scope of sub structure of structures subject to completion of atleast two sub structure of the abutment/pier upto abutment/pier cap level of the structures. |
| (iii) Super Structure | | (iii) Super Structure: |
| (including bearings) | 0.00% | Payment shall be made on pro rata basis on completion of a stage i.e. completion of super structure including bearings of atleast one span in all respect as specified. |
| (iv) Wearing Coat including expansion | | Wearing Coat |
| joints. | 0.00% | Payment shall be made on completion of wearing coat including expansion joints complete in all respect as specified. |
| (v) Miscellaneous items like hand rails, crash barriers, road markings etc. | | (v) Miscellaneous |

| | 0.00% | Payment shall be made on completion of all Miscellaneous works like hand rails, crash barriers, road markings etc.complete in all respect as specified. |
|---|-------|---|
| (vi) Wing walls/Return Walls | 0.00% | (vi) Wing walls/Return Walls Payment shall be made on completion of all Wing walls/Return Walls complete in all respect as specified. |
| (vii) Approaches (including retaining walls, stone pitching and protection works) | | (viii) Approaches: |
| | 0.00% | Payment shall be made on completion of both approaches including stone pitching, protection works, etc. complete in all respects as specified. |

Note: (1) In case of innovative major bridge projects like cable suspension/cable stayed/Extra dozed and exceptionally long span bridges , the schedule may be modified as per site requirement before bidding with due approval of DG(RD)&SS, MoRT&H.

(2) The Schedule for exclusive tunnel projects may be prepared as per site requirement before bidding with due approval of DG(RD)&SS ,MoRT&H.

1.3.4 Other works.

Procedure for estimating the value of other works done shall be as stated in table 1.3.4:

Table 1.3.4

| 1 abit 1.3.4 | | |
|--|-----------|---|
| Stage of Payment | Weightage | Payment Procedure |
| (i) Toll Plaza | 0.00% | Unit of measurement is each completed toll plaza. Payment of each toll plaza shall be made on pro rata basis with respect to the total of all toll plazas. |
| (ii)Road side drains | 8.75% | Unit of measurement is linear length in km. |
| (iii)Road signs, markings, km stones, safety devices, etc. | 14.50% | Payment shall be made on pro rata basis on completion of a stage in a length of not less than 05% (five per cent) of the total length. |
| (iv)Project facilities | 0.00% | Payment shall be made on pro rata basis for |
| a) Bus Bays | 1.06% | completed facilities. |
| b) Truck Lay Bye | 0.00% | |
| c) Rest Areas | 0.00% | |
| d) Others(Junctions and site clearance) | 4.53% | |
| (v)Road side plantation | 0.00% | Unit of measurement is linear length. Payment shall be made on pro rata basis on completion of a |

| (vi) Repair of Protection works other than approaches to the bridges, elevated sections/flyovers/ grade separators and ROBs/RUBs. | 0.00% | stage in a length of not less than 05% (five per cent) of the total length. |
|---|--------|---|
| (vii) Safety and traffic management during construction | 0.00% | Payment shall be made on prorate basis every six month. |
| (viii)Protection works(Includes retaining wall, breast wall and gabion structure for muck disposal) | 71.16% | Unit of measurement is linear length. Payment shall be made on pro rata basis on completion of a stage in a length of not less than 5% (five per cent) of the total length. |

1.3.5 Utility Shifting

Procedure for estimating the value of Utility shifting works done shall be as stated in table 1.3.5:

| Stage of | Weightage | Payment Procedure | | |
|------------------------------|-----------|---|--|--|
| Payment PHED | 73.71% | Payment is divided in following activities and Payment of each activity shall be made on pro rata basis on completion of 5km of linear project length. Removal of existing utility 30% Erection/Laying 30% Commissioning 40% | | |
| Electric Utility Shifting | 26.29% | Dismantling will include proper listing and stocking of usable and non-usable | | |
| Water resource shifting | 0.00% | items. Commissioning will be completed on furnishing the commissioning certificate from concerned utility owning department. | | |

2. Procedure for payment for Maintenance

- 2.1 The cost for maintenance shall be as stated in Clause 14.1(v).
- 2.2 Payment for Maintenance shall be made in Monthly basis in accordance with the provisions of Clause 19.6 & 19.7 of the Contract Agreement.

SCHEDULE - J (See Clause 10.3(ii))

PROJECT COMPLETION SCHEDULE

1 Project Completion Schedule

During Construction period, the Contractor shall comply with the requirements set forth in this Schedule-J for each of the Project Milestones and the **Scheduled Completion Date**. Within 15 (fifteen) days of the date of each Project Milestone, the Contractor shall notify the Authority of such compliance along with necessary particulars thereof.

2 Project Milestone-I

- (i) Project Milestone-I shall occur on the date falling on the 192nd (One hundred and ninety second) day from the Appointed Date (the "**Project Milestone-I**").
- (ii) Prior to the occurrence of Project Milestone-I, the Contractor shall have commenced construction of the Project Highway and submitted to the Authority duly and validly prepared Stage Payment Statements for an amount not less than 10% (ten per cent) of the Contract Price.

3 Project Milestone-II

- (i) Project Milestone-II shall occur on the date falling on the 329th (Three hundred and Twenty Ninth) day from the Appointed Date (the "**Project Milestone-II**").
- (ii) Prior to the occurrence of Project Milestone-II, the Contractor shall have continued with construction of the Project Highway and submitted to the Authority duly and validly prepared Stage Payment Statements for an amount not less than 35% (thirty per cent) of the Contract Price and should have started construction of all bridges.

4 Project Milestone-III

- (i) Project Milestone-III shall occur on the date falling on the 466th (Four hundred and sixty sixth) day from the Appointed Date (the "**Project Milestone-III**").
- (ii) Prior to the occurrence of Project Milestone-III, the Contractor shall have continued with construction of the Project Highway and submitted to the Authority duly and validly prepared Stage Payment Statements for an amount not less than 70% (sixty per cent) of the Contract Price and should have started construction of all project facilities.

5 Scheduled Completion Date

- (i) The Scheduled Completion Date shall occur on the 548th (Five Hundred and forty eighth) day from the Appointed Date.
- (ii) On or before the Scheduled Completion Date, the Contractor shall have completed construction in accordance with this Agreement.

6 Extension of time

Upon extension of any or all of the aforesaid Project Milestones or the Scheduled Completion Date, as the case may be, under and in accordance with the provisions of this Agreement, the Project Completion Schedule shall be deemed to have been amended accordingly.

SCHEDULE - K (See Clause 12.1 (ii))

Tests on Completion

1 Schedule for Tests

- (i) The Contractor shall, no later than 30 (thirty) days prior to the likely completion of construction, notify the Authority's Engineer and the Authority of its intent to subject the Project Highway to Tests, and no later than 10 (ten) days prior to the actual date of Tests, furnish to the Authority's Engineer and the Authority detailed inventory and particulars of all works and equipment forming part of Works.
- (ii) The Contractor shall notify the Authority's Engineer of its readiness to subject the Project Highway to Tests at any time after 10 (ten) days from the date of such notice, and upon receipt of such notice, the Authority's Engineer shall, in consultation with the Contractor, determine the date and time for each Test and notify the same to the Authority who may designate its representative to witness the Tests. The Authority's Engineer shall thereupon conduct the Tests itself or cause any of the Tests to be conducted in accordance with Article 12 and this Schedule-K.

2 Tests

- (i) Visual and physical test: The Authority's Engineer shall conduct a visual and physical check of construction to determine that all works and equipment forming part thereof conform to the provisions of this Agreement. The physical tests shall include [***].
- (ii) Riding quality test: Riding quality of each lane of the carriageway shall be checked with the help of a Network Survey Vehicle (NSV) fitted with latest equipments and the maximum permissible roughness for purposes of this Test shall be [2,000 (two thousand)] mm for each kilometer.
- (iii) Tests for bridges: All major and minor bridges shall be subjected to the rebound hammer and ultrasonic pulse velocity tests, to be conducted in accordance with the procedure described in Special Report No. 17: 1996 of the IRC Highway Research Board on Nondestructive Testing Techniques, at two spots in every span, to be chosen at random by the Authority's Engineer. Bridges with a span of 15 (fifteen) metres or more shall also be subjected to load testing.
- (iv) Other tests: The Authority's Engineer may require the Contractor to carry out or cause to be carried additional tests, in accordance with Good Industry Practice, for determining the compliance of the Project Highway with Specifications and standards, except tests as specified in clause 5,but shall include measuring the reflectivity of road markings and road signs; and measuring the illumination level (lux) of lighting using requisite testing equipment.
- (v) Environmental audit: The Authority's Engineer shall carry out a check to determine conformity of the Project Highway with the environmental requirements set forth in Applicable Laws and Applicable Permits.

(vi) Safety Audit: The Authority's Engineer shall carry out, or cause to be carried out, a safety audit to determine conformity of the Project Highway with the safety requirements and Good Industry Practice.

3 Agency for conducting Tests

All Tests set forth in this Schedule-K shall be conducted by the Authority's Engineer or such other agency or person as it may specify in consultation with the Authority.

4 Completion Certificate

Upon successful completion of Tests, the Authority's Engineer shall issue the Completion Certificate in accordance with the provisions of Article 12.

5. The Authority Engineer will carry out tests with following equipment at his own cost in the presence of contractor's representative.

| S.No. | Key metrics of Asset | Equipment to be used | Frequency of condition survey |
|-------|-------------------------|-----------------------|------------------------------------|
| 1 | Surface | Network Survey | At least twice a year (As per |
| | defects of | Vehicle (NSV) | survey |
| | pavement | | months defined for the state basis |
| | | | rainy season) |
| 2 | Roughness of | Network Survey | At least twice a year (As per |
| | pavement | Vehicle (NSV) | survey |
| | | | months defined for the state basis |
| | | | rainy season) |
| 3 | Strength of | Falling Weight | At least once a year |
| | pavement | Deflectometer (FWD) | |
| 4 | Bridges | Mobile Bridge | At least twice a year (As per |
| | | Inspection Unit (MBU) | survey |
| | | | months defined for the state basis |
| | | | rainy season) |
| 5 | Road signs | Retro-reflectometer | At least twice a year (As per |
| | | | survey |
| | | | months defined for the state basis |
| | | | rainy season) |

The first testing with the help of NSV shall be conducted at the time of issue of Completion Certificate.

Schedule – L (See Clause 12.2)

Completion Certificate

| 1 | I, |
|---|---|
| 2 | It is certified that, in terms of the aforesaid Agreement, all works forming part of Project Highway have been completed, and the Project Highway is hereby declared fit for entry into operation on this the day of 20 |
| | SIGNED, SEALED AND DELIVERED |
| | For and on behalf of |
| | the Authority's Engineer by: |
| | (Signature) |
| | (Name) |
| | (Designation) |
| | (Address) |

SCHEDULE - M

(See Clauses 14.6, 15.2 and 19.7)

PAYMENT REDUCTION FOR NON-COMPLIANCE

1. Payment reduction for non-compliance with the Maintenance Requirements

- (i) Monthly lump sum payments for maintenance shall be reduced in the case of non-compliance with the Maintenance Requirements set forth in Schedule-E.
- (ii) Any deduction made on account of non-compliance with the Maintenance Requirements shall not be paid even after compliance subsequently. The deductions shall continue to be made every month until compliance is done.
- (iii) The Authority's Engineer shall calculate the amount of payment reduction on the basis of weightage in percentage assigned to non-conforming items as given in Paragraph 2.

2. Percentage reductions in lump sum payments

• The following percentages shall govern the payment reduction:

| S. No. | Item/Defect/Deficiency | Percentage | |
|------------|--|------------|--|
| (a) | Carriageway/Pavement | | |
| (i) | Potholes, cracks, other surface defects | 15% | |
| (ii) | Repairs of Edges, Rutting | 5% | |
| (b) | Road, Embankment, Cuttings, Shoulders | | |
| (i) | Edge drop, inadequate crossfall, undulations, settlement, potholes, ponding, obstructions | 10% | |
| (ii) | Deficient slopes, raincuts, disturbed pitching, vegetation growth, pruning of trees | 5% | |
| (c) | Bridges and Culverts | | |
| (i) | Desilting, cleaning. vegetation growth, damaged pitching, flooring, parapets, wearing course, footpaths, any damage to foundations | 20% | |
| (ii) | Any Defects in superstructures, bearings and sub-structures | 10% | |
| S. No. | Item/Defect/Deficiency | Percentage | |
| (iii) | Painting, repairs/replacement kerbs, railings, parapets, guideposts/crash barriers | 5% | |
| (d) | Roadside Drains | | |
| (i) | Cleaning and repair of drains | 5% | |

| (e) | Road Furniture | |
|------------|--|-----|
| (i) | Cleaning, painting, replacement of road signs, delineators, road markings, 200 | 5% |
| | m/km/5th km stones | |
| (f) | Miscellaneous Items | |
| (i) | Removal of dead animals, broken down/accidented vehicles, fallen trees, road blockades or malfunctioning of mobile | 10% |
| (ii) | Any other Defects in accordance with | 5% |
| , | paragraph 1. | |
| (g) | Defects in Other Project Facilities | 5% |

(ii) The amount to be deducted from monthly lump-sum payment for non compliance of particular item shall be calculated as under:

$$R=P/100 x (M_1 \text{ or } M_2) x L1/L$$

Where P = Percentage of particular item/Defect/deficiency for deduction

M = Monthly lump-sum payment in accordance with the Bid

L1 = Non-complying length

L = Total length of the road,

 $R = Reduction \ (the \ amount \ to \ be \ deducted \ for \ non \ compliance \ for \ a \ particular \\ item/Defect/deficiency$

The total amount of reduction shall be arrived at by summation of reductions for such items/Defects/deficiency or non compliance.

For any Defect in a part of one kilometer, the non-conforming length shall be taken as one kilometer.

SCHEDULE - N (See Clause 18.1.1)

SELECTION OF AUTHORITY'S ENGINEER

1 Selection of Authority's Engineer

- 1.1 The provisions of the Model Request for Proposal for Selection of Technical Consultants, issued by the Ministry of Finance in May 2009, or any substitute thereof shall apply for selection of an experienced firm to discharge the functions and duties of an Authority's Engineer.
- 1.2 In the event of termination of the Technical Consultants appointed in accordance with the provisions of Paragraph 1.1, the Authority shall appoint another firm of Technical Consultants forthwith and may engage a government-owned entity in accordance with the provisions of Paragraph 3 of this Schedule-N.

2 Terms of Reference

The Terms of Reference for the Authority's Engineer (the "**TOR**") shall substantially conform with Annex 1 to this Schedule N.

3 Appointment of Government entity as Authority's Engineer

Notwithstanding anything to the contrary contained in this Schedule, the Authority may in its discretion appoint a government-owned entity as the Authority's Engineer; provided that such entity shall be a body corporate having as one of its primary functions the provision of consulting, advisory and supervisory services for engineering projects; provided further that a government-owned entity which is owned or controlled by the Authority shall not be eligible for appointment as Authority's Engineer.

Annex -I (Schedule - N)

TERMS OF REFERENCE FOR AUTHORITY'S ENGINEER

1 Scope

- - # In case the bid of Authority's Engineer is invited simultaneously with the bid of EPC project, then the status of bidding of EPC project only to be indicated
- (ii) The TOR shall apply to construction and maintenance of the Project Highway.

2 Definitions and interpretation

- (i) The words and expressions beginning with or in capital letters and not defined herein but defined in the Agreement shall have, unless repugnant to the context, the meaning respectively assigned to them in the Agreement.
- (ii) References to Articles, Clauses and Schedules in this TOR shall, except where the context otherwise requires, be deemed to be references to the Articles, Clauses and Schedules of the Agreement, and references to Paragraphs shall be deemed to be references to Paragraphs of this TOR.
- (iii) The rules of interpretation stated in Article 1 of the Agreement shall apply, mutatis mutandis, to this TOR.

3. General

- (i) The Authority's Engineer shall discharge its duties in a fair, impartial and efficient manner, consistent with the highest standards of professional integrity and Good Industry Practice.
- (ii) The Authority's Engineer shall perform the duties and exercise the authority in accordance with the provisions of this Agreement, but subject to obtaining prior written approval of the Authority before determining:
 - (a) any Time Extension;
 - (b) any additional cost to be paid by the Authority to the Contractor;
 - (c) the Termination Payment; or
 - (d) any other matter which is not specified in (a), (b) or (c) above and which creates an obligation or liability on either Party for a sum exceeding Rs. 5,000,000 (Rs. fifty lakh).
- (iii) The Authority's Engineer shall submit regular periodic reports, at least once every month, to the Authority in respect of its duties and functions under this Agreement. Such reports shall be submitted by the Authority's Engineer within 10 (ten) days of the beginning of every month.
- (iv) The Authority's Engineer shall inform the Contractor of any delegation of its duties and

- responsibilities to its suitably qualified and experienced personnel; provided, however, that it shall not delegate the authority to refer any matter for the Authority's prior approval in accordance with the provisions of Clause 18.2.
- (v) The Authority's Engineer shall aid and advise the Authority on any proposal for Change of Scope under Article 13.
- (vi) In the event of any disagreement between the Parties regarding the meaning, scope and nature of Good Industry Practice, as set forth in any provision of the Agreement, the Authority's Engineer shall specify such meaning, scope and nature by issuing a reasoned written statement relying on good industry practice and authentic literature.

4 Construction Period

- During the Construction Period, the Authority's Engineer shall review and approve the Drawings furnished by the Contractor along with supporting data, including the geotechnical and hydrological investigations, characteristics of materials from borrow areas and quarry sites, topographical surveys, and the recommendations of the Safety Consultant in accordance with the provisions of Clause 10.1 (vi). The Authority's Engineer shall complete such review and approval and send its observations to the Authority and the Contractor within 15 (fifteen) days of receipt of such Drawings; provided, however that in case of a Major Bridge or Structure, the aforesaid period of 15 (fifteen) days may be extended upto 30 (thirty) days. In particular, such comments shall specify the conformity or otherwise of such Drawings with the Scope of the Project and Specifications and Standards.
- (ii) The Authority's Engineer shall review any revised Drawings sent to it by the Contractor and furnish its comments within 10 (ten) days of receiving such Drawings.
- (iii) The Authority's Engineer shall review the Quality Assurance Plan submitted by the Contractor and shall convey its comments to the Contractor within a period of 21 (twenty-one) days stating the modifications, if any, required thereto.
- (iv) The Authority's Engineer shall complete the review and approve of the methodology proposed to be adopted by the Contractor for executing the Works, and convey its comments to the Contractor within a period of 10 (ten) days from the date of receipt of the proposed methodology from the Contractor.
- (v) The Authority's Engineer shall grant written approval to the Contractor, where necessary, for interruption and diversion of the flow of traffic in the existing lane(s) of the Project Highway for purposes of maintenance during the Construction Period in accordance with the provisions of Clause 10.4.
- (vi) The Authority's Engineer shall review the monthly progress report furnished by the Contractor and send its comments thereon to the Authority and the Contractor within 7 (seven) days of receipt of such report.
- (vii) The Authority's Engineer shall inspect the Construction Works and the Project Highway and shall submit a monthly Inspection Report bringing out the results of inspections and the remedial action taken by the Contractor in respect of Defects or deficiencies. In particular, the Authority's Engineer shall include in its Inspection Report, the compliance of the recommendations made by the Safety Consultant.
- (viii) The Authority's Engineer shall conduct the pre-construction review of manufacturer's test reports and standard samples of manufactured Materials, and such other Materials as the Authority's Engineer may require.
- (ix) For determining that the Works conform to Specifications and Standards, the Authority's Engineer shall require the Contractor to carry out, or cause to be carried out, tests at such

time and frequency and in such manner as specified in the Agreement and in accordance with Good Industry Practice for quality assurance. For purposes of this Paragraph 4.9, the tests specified in the IRC Special Publication-11 (Handbook of Quality Control for Construction of Roads and Runways) and the Specifications for Road and Bridge Works issued by MORTH (the "Quality Control Manuals") or any modification/substitution thereof shall be deemed to be tests conforming to Good Industry Practice for quality assurance.

- (x) The Authority's Engineer shall test check at least 20 (twenty) percent of the quantity or number of tests prescribed for each category or type of test for quality control by the Contractor.
- (xi) The timing of tests referred to in Paragraph 4.9, and the criteria for acceptance/ rejection of their results shall be determined by the Authority's Engineer in accordance with the Quality Control Manuals. The tests shall be undertaken on a random sample basis and shall be in addition to, and independent of, the tests that may be carried out by the Contractor for its own quality assurance in accordance with Good Industry Practice.
- (xii) In the event that results of any tests conducted under Clause 11.10 establish any Defects or deficiencies in the Works, the Authority's Engineer shall require the Contractor to carry out remedial measures.
- (xiii) The Authority's Engineer may instruct the Contractor to execute any work which is urgently required for the safety of the Project Highway, whether because of an accident, unforeseeable event or otherwise; provided that in case of any work required on account of a Force Majeure Event, the provisions of Clause 21.6 shall apply.
- (xiv) In the event that the Contractor fails to achieve any of the Project Milestones, the Authority's Engineer shall undertake a review of the progress of construction and identify potential delays, if any. If the Authority's Engineer shall determine that completion of the Project Highway is not feasible within the time specified in the Agreement, it shall require the Contractor to indicate within 15 (fifteen) days the steps proposed to be taken to expedite progress, and the period within which the Project Completion Date shall be achieved. Upon receipt of a report from the Contractor, the Authority's Engineer shall review the same and send its comments to the Authority and the Contractor forthwith.
- (xv) The Authority's Engineer shall obtain from the Contractor a copy of all the Contractor's quality control records and documents before the Completion Certificate is issued pursuant to Clause 12.4.
- (xvi) Authority's Engineer may recommend to the Authority suspension of the whole or part of the Works if the work threatens the safety of the Users and pedestrians. After the Contractor has carried out remedial measure, the Authority's Engineer shall inspect such remedial measures forthwith and make a report to the Authority recommending whether or not the suspension hereunder may be revoked.
- (xvii) In the event that the Contractor carries out any remedial measures to secure the safety of suspended works and Users, and requires the Authority's Engineer to inspect such works, the Authority's Engineer shall inspect the suspended works within 3 (three) days of receiving such notice, and make a report to the Authority forthwith, recommending whether or not such suspension may be revoked by the Authority.

(xviii) The Authority's Engineer shall carry out, or cause to be carried out, all the Tests specified in Schedule-K and issue a Completion Certificate or Provisional Certificate, as the case may be. For carrying out its functions under this Paragraph 4.18 and all matters incidental thereto, the Authority's Engineer shall act under and in accordance with the provisions of Article 12 and Schedule-K.

5. Maintenance Period

- (i) The Authority's Engineer shall aid and advise the Contractor in the preparation of its monthly Maintenance Programme and for this purpose carry out a joint monthly inspection with the Contractor.
- (ii) The Authority's Engineer shall undertake regular inspections, at least once every month, to evaluate compliance with the Maintenance Requirements and submit a Maintenance Inspection Report to the Authority and the Contractor.
- (iii) The Authority's Engineer shall specify the tests, if any, that the Contractor shall carry out, or cause to be carried out, for the purpose of determining that the Project Highway is in conformity with the Maintenance Requirements. It shall monitor and review the results of such tests and the remedial measures, if any, taken by the Contractor in this behalf.
- (iv) In respect of any defect or deficiency referred to in Paragraph 3 of Schedule-E, the Authority's Engineer shall, in conformity with Good Industry Practice, specify the permissible limit of deviation or deterioration with reference to the Specifications and Standards and shall also specify the time limit for repair or rectification of any deviation or deterioration beyond the permissible limit.
- (v) The Authority's Engineer shall examine the request of the Contractor for closure of any lane(s) of the Project Highway for undertaking maintenance/repair thereof, and shall grant permission with such modifications, as it may deem necessary, within 5 (five) days of receiving a request from the Contractor. Upon expiry of the permitted period of closure, the Authority's Engineer shall monitor the reopening of such lane(s), and in case of delay, determine the Damages payable by the Contractor to the Authority under Clause 14.5.

6 Determination of costs and time

- (i) The Authority's Engineer shall determine the costs, and/or their reasonableness, that are required to be determined by it under the Agreement.
- (ii) The Authority's Engineer shall determine the period of Time Extension that is required to be determined by it under the Agreement.
- (iii) The Authority's Engineer shall consult each Party in every case of determination in accordance with the provisions of Clause 18.5.

7. Payments

(i) The Authority's Engineer shall withhold payments for the affected works for which the Contractor fails to revise and resubmit the Drawings to the Authority's Engineer in accordance with the provisions of Clause 10.2.4 (d).

- (ii) Authority's Engineer shall –
- (a) within 10 (ten) days of receipt of the Stage Payment Statement from the Contractor pursuant to Clause 19.4, determine the amount due to the Contractor and recommend the release of 90 (ninety) percent of the amount so determined as part payment, pending issue of the Interim Payment Certificate; and
- (b) within 15 (fifteen) days of the receipt of the Stage Payment Statement referred to in Clause 19.4, deliver to the Authority and the Contractor an Interim Payment Certificate certifying the amount due and payable to the Contractor, after adjustments in accordance with the provisions of Clause 19.10.
- (iii) The Authority's Engineer shall, within 15 (fifteen) days of receipt of the Monthly Maintenance Statement from the Contractor pursuant to Clause 19.6, verify the Contractor's monthly statement and certify the amount to be paid to the Contractor in accordance with the provisions of the Agreement.
- (iv) The Authority's Engineer shall certify final payment within 30 (thirty) days of the receipt of the final payment statement of Maintenance in accordance with the provisions of Clause 19.16.

8. Other duties and functions

The Authority's Engineer shall perform all other duties and functions as specified in the Agreement.

9 Miscellaneous

- (i) A copy of all communications, comments, instructions, Drawings or Documents sent by the Authority's Engineer to the Contractor pursuant to this TOR, and a copy of all the test results with comments of the Authority's Engineer thereon, shall be furnished by the Authority's Engineer to the Authority forthwith.
- (ii) The Authority's Engineer shall retain at least one copy each of all Drawings and Documents received by it, including "as-built" Drawings, and keep them in its safe custody.
- (iii) Within 90 (ninety) days of the Project Completion Date, the Authority's Engineer shall obtain a complete set of as-built Drawings, in 2 (two) hard copies and in micro film form or in such other medium as may be acceptable to the Authority, reflecting the Project Highway as actually designed, engineered and constructed, including an asbuilt survey illustrating the layout of the Project Highway and setback lines, if any, of the buildings and structures forming part of Project Facilities; and shall hand them over to the Authority against receipt thereof.
- (iv) The Authority's Engineer, if called upon by the Authority or the Contractor or both, shall mediate and assist the Parties in arriving at an amicable settlement of any Dispute between the Parties.

| T C | ne Authority's lontractor's Def | Engineer shall ault within on | inform the | Authority a | nd the Contre. | actor of any | event of |
|--------|---------------------------------|----------------------------------|------------|-------------|----------------|--------------|----------|
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

SCHEDULE - O

(See Clauses 19.4.1, 19.6.1, and 19.8.1)

Forms of Payment Statements

1. Stage Payment Statement for Works

The Stage Payment Statement for Works shall state:

- (a) the estimated amount for the Works executed in accordance with Clause 19.3(i) subsequent to the last claim;
- (b) amounts reflecting adjustments in price for the aforesaid claim;
- (c) the estimated amount of each Change of Scope Order executed subsequent to the last claim;
- (d) amounts reflecting adjustment in price, if any, for (c) above in accordance with the provisions of Clause 13.2(iii) (a);
- (e) total of (a), (b), (c) and (d) above;
- (f) Deductions:
 - Any amount to be deducted in accordance with the provisions of the Agreement except taxes;
 - (ii) Any amount towards deduction of taxes; and
 - (iii) Total of (i) and (ii) above.
- (g) Net claim: (e) (f) (iii);
- (h) The amounts received by the Contractor upto the last claim:
 - (i) For the Works executed (excluding Change of Scope orders);
 - (ii) For Change of Scope Orders, and
 - (iii) Taxes deducted

2. Monthly Maintenance Payment Statement

The monthly Statement for Maintenance Payment shall state:

- (a) the monthly payment admissible in accordance with the provisions of the Agreement;
- (b) the deductions for maintenance work not done:
- (c) net payment for maintenance due, (a) minus (b);
- (d) amounts reflecting adjustments in price under Clause 19.12; and
- (e) amount towards deduction of taxes.

3. Contractor's claim for Damages

Note: The Contractor shall submit its claims in a form acceptable to the Authority.

SCHEDULE - P

(See Clause 20.1)

INSURANCE

1. Insurance during Construction Period

- (i) The Contractor shall effect and maintain at its own cost, from the Appointed Date till the date of issue of the Completion Certificate, the following insurances for any loss or damage occurring on account of Non Political Event of Force Majeure, malicious act, accidental damage, explosion, fire and terrorism:
 - (a) insurance of Works, Plant and Materials and an additional sum of [15 (fifteen)] per cent of such replacement cost to cover any additional costs of and incidental to the rectification of loss or damage including professional fees and the cost of demolishing and removing any part of the Works and of removing debris of whatsoever nature; and
 - (b) insurance for the Contractor's equipment and Documents brought onto the Site by the Contractor, for a sum sufficient to provide for their replacement at the Site.
- (ii) The insurance under sub para (a) and (b) of paragraph 1(i) above shall cover the Authority and the Contractor against all loss or damage from any cause arising under paragraph 1.1 other than risks which are not insurable at commercial terms.

2. Insurance for Contractor's Defects Liability

The Contractor shall effect and maintain insurance cover of not less than 15% of the Contract Price for the Works from the date of issue of the Completion Certificate until the end of the Defects Liability Period for any loss or damage for which the Contractor is liable and which arises from a cause occurring prior to the issue of the Completion Certificate. The Contractor shall also maintain other insurances for maximum sums as may be required under the Applicable Laws and in accordance with Good Industry Practice.

3. Insurance against injury to persons and damage to property

(i) The Contractor shall insure against its liability for any loss, damage, death or bodily injury, or damage to any property (except things insured under Paragraphs 1 and 2 of this Schedule or to any person (except persons insured under Clause 20.9), which may arise out of the Contractor's performance of this Agreement. This insurance shall be for a limit per occurrence of not less than the amount stated below with no limit on the number of occurrences.

The insurance cover shall be not less than: Rs. [*****]

- (ii) The insurance shall be extended to cover liability for all loss and damage to the Authority's property arising out of the Contractor's performance of this Agreement excluding:
 - (a) the Authority's right to have the construction works executed on, over, under, in or through any land, and to occupy this land for the Works; and
 - (b) damage which is an unavoidable result of the Contractor's obligations to execute the Works.

4. Insurance to be in joint names

The insurance under paragraphs 1 to 3 above shall be in the joint names of the Contractor

and the Authority.

Schedule-Q

(See Clause 14.10)

Tests on Completion of Maintenance Period

1. Riding Quality test:

Riding quality test: Riding quality of each lane of the carriageway shall be checked with the help of a calibrated bump integrator and the maximum permissible roughness for purposes of this Test shall be [2,200 (two thousand and two hundred only)] mm for each kilometre.

2. Visual and physical test:

The Authority's Engineer shall conduct a visual and physical check of construction to determine that all works and equipment forming part thereof conform to the provisions of this Agreement. The physical tests shall include measurement of cracking, rutting, stripping and potholes and shall be as per the requirement of maintenance mentioned in Schedule-E.

Schedule-R

(See Clause 14.10)

Taking Over Certificate

| I, (Name and designation of the Authority's Representative) under and in |
|---|
| accordance with the Agreement dated (the "Agreement"), for |
| "Improvement/widening to Two-laning with earthen shoulder of Nongjri (Design Ch. |
| 30.00km) to Maheshkola (Design Ch. 55.525km)[R-M-B Package-II] on SH-4 section of |
| Ranikor- Maheshkhola-Baghmara Project in the state of Meghalaya on EPC basis" (the |
| "Project Highway") on Engineering, Procurement and Construction (EPC) basis through |
| (Name of Contractor), hereby certify that the Tests on completion of |
| Maintenance Period in accordance with Article 14 of the Agreement have been successfully |
| undertaken to determine compliance of the Project Highway with the provisions of the |
| Agreement and I hereby certify that the Authority has taken over the Project highway from |
| the Contractor on this day |
| the contractor on this day |
| |
| |
| |
| |
| |
| |
| |
| CICNED CEALED AND DELIVEDED |
| SIGNED, SEALED AND DELIVERED |
| |
| |
| |
| |
| (Signature) |
| (Name and designation of Authority's Representative) |
| |
| (Address) |

**** End of the Document ****